

A. N. 734
11-2-17

CALL No...534...5...
LAN



HYDRODYNAMICS

CAMBRIDGE UNIVERSITY PRESS WAREHOUSE,

C. F. CLAY, MANAGER

London: FETTER LANE, E C.

Glasgow. 50, WELLINGTON STREET.



Leipzig F A BROCKHAUS.

New York THE MACMILLAN COMPANY

Bombay and Calcutta MACMILLAN AND CO, LTD.

[*All Rights reserved*]


HYDRODYNAMICS

BY

HORACE LAMB, M.A., LL.D., D.Sc., F.R.S.

PROFESSOR OF MATHEMATICS IN THE VICTORIA UNIVERSITY OF MANCHESTER;
FORMERLY FELLOW OF TRINITY COLLEGE, CAMBRIDGE

THIRD EDITION



CAMBRIDGE
AT THE UNIVERSITY PRESS

1906

IIA Lib.



First Edition 1879
Second Edition 1895
Third Edition 1906

TO

HENRY MARTYN TAYLOR

THIS BOOK IS INSCRIBED BY HIS FRIEND
THE AUTHOR

PREFACE.

THIS book may be regarded as a third edition of a "Treatise on the Mathematical Theory of the Motion of Fluids," which was published in 1879. The second edition, largely remodelled and extended, appeared under the present title in 1895. In this issue no further change has been made in the general plan and arrangement, but the work has been carefully revised, occasional passages have been rewritten, and many interpolations and additions have been made, amounting in all to about one-fifth of the whole. The numbering of the sections has consequently been somewhat disturbed. The more important extensions will be found in the latter half of the book, which deals mainly with physical applications.

One or two points from the preface of 1895 may be repeated.

I have persisted in the use of the reversed sign of the velocity-potential, writing $u = -\partial\phi/\partial x$, &c, in place of $u = \partial\phi/\partial x$, &c. The physical interpretation of the function is thereby greatly improved, and the far-reaching analogy with the magnetic potential is at the same time made more complete. It should be remembered that the prevalent usage had a purely analytical origin, in connection with the notion of 'perfect differentials'. From a physical point of view it is so much more natural to regard the state of motion of a dynamical system, in any given configuration, as specified by the impulses which would start it, rather than by those which would stop it, that the change here advocated would seem to require no further justification. It is, moreover, not wholly an innovation, for it may claim authority in the writings of Cauchy. If he, instead of Poisson, had happened to write a text-book of Mechanics, the convention would, I think, have been different.

Pains have been taken to give full and accurate references in the foot-notes, but it will be understood that the original methods have not always been followed in the text.

In the preceding edition I endeavoured, in the spirit of Poincaré's warning, "*Gardons nous de croire qu'une science soit faite quand on l'a réduite à des formules analytiques*," to render the analytical results as intelligible as

possible, by numerical calculations, and by the insertion of a number of diagrams of stream-lines and other curves, drawn to scale. This process of illustration has been continued. For facilities in reproducing some of the new diagrams I am indebted to the Councils of the London Mathematical Society and the Manchester Literary and Philosophical Society, in whose publications they first appeared.

I have had recourse to Professor A. E. H. Love's kind advice on various points, and have to thank him for several valuable suggestions.

The officers and staff of the University Press have placed me under great obligation by the constant consideration shewn in matters connected with the printing.

I have ventured to inscribe on the fly-leaf the name of Mr H. M. Taylor, whose kindly encouragement first led me to write on the subject, and whose help in revision I had gratefully to record on the former occasions. I feel that this edition is the poorer for want of the vigilant censorship which has so often been exercised for the benefit of his friends, but which is unfortunately no longer within his power.

HORACE LAMB

January, 1906

CONTENTS

CHAPTER I.

THE EQUATIONS OF MOTION

ART		PAGE
1, 2	Fundamental property of a fluid	1
3-12	'Eulerian' form of the equations of motion Dynamical equations Equation of continuity Physical equations Surface conditions Equation of energy Impulsive generation of motion	3
13-16	'Lagrangian' forms of the dynamical equations and of the equation of continuity Weber's transformation Extension of the Lagrangian notation	12

CHAPTER II.

INTEGRATION OF THE EQUATIONS IN SPECIAL CASES.

17-20	Velocity-potential Lagrange's theorem Physical meaning of ϕ . Geometrical properties Integration of the equations when a velocity-potential exists, pressure-equation	15
21-25	Steady motion Deduction of the pressure-equation from the principle of energy Limit to the velocity Efflux of liquids; vena contracta. Efflux of gases	18
26-29	Examples of rotating fluid Uniform rotation. Rankine's 'combined vortex' Electromagnetic rotation	24

CHAPTER III.

IRROTATIONAL MOTION

30-33	Analysis of the motion of a fluid element 'Flow' and 'circulation.' Stokes' theorem Constancy of circulation in a moving circuit	28
34-46	Irrotational motion in simply-connected spaces, ϕ single-valued Case of an incompressible fluid, tubes of flow ϕ cannot be a maximum or minimum Mean value of ϕ over a spherical surface Conditions of determinateness of ϕ (Green's theorem; dynamical interpreta- tion, formula for kinetic energy Kelvin's theorem of minimum energy	34

ART		PAGE
47-55	Multiply-connected regions Irrotational motion, cyclic constants Conditions of determinateness Kelvin's extension of Green's theorem, dynamical interpretation, energy of an irrotationally moving liquid in a cyclic space	47
56-58	'Sources' and 'sinks' Double sources Surface-distributions of simple and double sources	55

CHAPTER IV

MOTION OF A LIQUID IN TWO DIMENSIONS.

59-62	Lagrange's stream-function Connection with the theory of the complex variable; conjugate functions	60
63-70	Simple types of motion, acyclic and cyclic General formulæ, Fourier method Motion of a circular cylinder, without and with circula- tion of the fluid round it	66
71, 72	Inverse methods Motion due to the translation of a solid, elliptic cylinder Flow past an oblique lamina, couple-resultant of fluid pressures Motion due to a rotating solid, rotating prismatic vessel, rotating elliptic cylinder in infinite liquid	77
73-78	Steady motions with a free surface Schwarz' method Investigations of Helmholtz, Kirchhoff, etc Applications to Borda's mouthpiece, the vena contracta, the impact of a stream on a lamina, Bobyleff's problem	85
79	Discontinuous motions	97
80	Flow in a curved stratum	100

CHAPTER V.

IRROTATIONAL MOTION OF A LIQUID PROBLEMS IN THREE DIMENSIONS

81-89	Spherical harmonics, Maxwell's theory, poles Transformation to polar coordinates Zonal harmonics Hypergeometric series Legendre's functions Functions 'of the second kind' Tesseral and sectorial harmonics Conjugate property of surface harmonics Expansions Other symbolical solutions of $\nabla^2\phi=0$, definite- integral forms of the zonal harmonic	102
90-93.	Hydrodynamical applications, impulsive pressure over a sphere, pre- scribed normal velocity over a sphere, energy Motion of a solid sphere in an infinite liquid, the effect is on the <i>inertia</i> of the sphere Sphere in a liquid with concentric spherical boundary	113
94-97.	Stokes' stream-function, general formulæ in terms of spherical harmonics Stream-lines of a sphere. Image of a double source in a sphere Rankine's method	117
98, 99	Motion of two spheres in an infinite liquid, kinematical formulæ	122
100-102	Cylindrical harmonics Bessel's functions Definite-integral expression of an arbitrary function in terms of the function J_0 Hydro- dynamical applications	126

ART		PAGE
103-109	Ellipsoidal harmonics for ovary and planetary ellipsoids Motion of a liquid due to translation and rotation of an ellipsoid of revolution Flow through a circular aperture Stream-lines of a circular disk	132
110-115	Motion of a fluid in ellipsoidal envelope General expression of $\nabla^2\phi$ in orthogonal curvilinear coordinates Confocal quadrics, ellipsoidal coordinates Motion of fluid due to a varying ellipsoidal boundary Flow through an elliptic aperture Translation and rotation of an ellipsoid	140
116	References to other researches	149

CHAPTER VI

ON THE MOTION OF SOLIDS THROUGH A LIQUID · DYNAMICAL THEORY

117-125	Motion due to a single solid in an infinite liquid, kinematical formulae Theory of 'impulse' Dynamical equations relative to axes fixed in the solid Kinetic energy, coefficients of inertia. Components of impulse Reciprocal formulae Components of fluid pressure on moving solid The three permanent translations, stability The possible steady motions Motion due to an impulsive couple	150
126-131	Hydrokinetic symmetry Motion of a solid of revolution, stability or instability of steady translation, without and with rotation. Motion of a 'helicoid' Inertia-coefficients of liquid contained in a rigid envelope	161
132-134	Case of a perforated solid with cyclic motion through the apertures Steady motion of a ring, condition of stability	170
135-138	Equations of motion in generalized coordinates. Lagrange's equations Hamiltonian principle Adaptation to Hydrodynamics Motion of a sphere near a rigid boundary, motion of two spheres in the line of centres	174
139-144	Modification of Lagrange's equations, ignorance of coordinates Equations of motion of a 'gyrostatic' system Kinetostatics Motion of a sphere in a cyclic region Circulation round thin cores or through tubes, comparison with electromagnetic phenomena	182

CHAPTER VII.

VORTEX MOTION

145-153	'Vortex-lines' and 'vortex-filaments', kinematical properties. Persistence of vortices Conditions of determinateness of vortex-motion Component velocities expressed in terms of expansion and rotation, electromagnetic analogy Velocity-potential due to a vortex 'Vortex-shoets' Impulse and energy of a vortex-system	193
154-159	Rectilinear vortices, vortex-pair Kirchhoff's theory Stability of a cylindrical vortex Kirchhoff's elliptic vortex. Vortices in a curved stratum of fluid	211

ART		PAGE
160-163	Circular vortices, energy and impulse, stream-function Isolated vortex-ring, stream-lines, velocity of translation Mutual influence of vortex-rings Image of a vortex in a sphere	221
164	General conditions for steady motion of a fluid Cylindrical and spherical vortices	229
165	References to further researches	232
166	Clebsch's transformation of the hydrodynamical equations	233

CHAPTER VIII

TIDAL WAVES

167	General theory of small oscillations, normal modes, forced oscillations	235
168-178.	Free waves in uniform canal, wave-velocity, effect of initial conditions, physical meaning of the various approximations, energy of a wave-system Artifice of steady motion Superposition of wave-systems, reflection Effect of disturbing forces Free and forced oscillations in a finite canal	239
179-182	Canal theory of the tides, disturbing potential. Tides in an equatorial canal, and in a canal parallel to the equator, diurnal tides Canal coincident with a meridian, change of mean level, fortnightly tide	252
183, 184	Waves in a canal of variable section Examples of free and forced oscillations, exaggeration of tides in shallow seas and estuaries	257
185, 186	Waves of finite amplitude, Riemann's method Change of type; tides of the second order	261
187-196	Wave motion in two horizontal dimensions Oscillations of rectangular and circular sheets of water Bessel's functions Case of variable depth; example Propagation of disturbances outwards from a centre, Bessel's function of the second kind Waves due to a variable local pressure General formula for diverging waves Effect of a transient source of disturbance	265
197-200	Oscillations of a spherical sheet of water, free and forced waves. Effect of the mutual attraction of the liquid Oscillations of a sea bounded by meridians and parallels	286
201-211	Equations of motion relative to rotating axes, free and forced oscillations, stability, 'ordinary' and 'secular' Application to hydrodynamics, tidal oscillations of a rotating sheet of water Plane problems straight canal, circular sheet of uniform depth, circular sheet of variable depth	293
212-223	Tidal oscillations on a rotating globe, Laplace's kinetic theory Tides of long period Diurnal tides Semi-diurnal tides Numerical results Hough's investigations Modifications of the kinetic theory due to the actual shape of the ocean, questions of phase	312
224, 225	Stability of the ocean Remarks on the general theory of kinetic stability	336
APPENDIX	On Tide-generating Forces	339

CHAPTER IX

SURFACE-WAVES

ART		PAGE
226-235	Statement of the two-dimensional problem, surface conditions Standing waves Progressive waves, numerical illustrations Energy of a simple-harmonic wave-train Artifice of steady motion Waves in superposed liquids Waves on the boundary of two currents, instability. Theory of 'group-velocity'	344
236-245	Waves on deep water due to a localized disturbance, the Cauchy-Poisson problem Effect of a periodic local disturbance Surface-disturbance of a stream Case of finite depth Effect of slight irregularities in the bed of a stream Theory of wave-resistance	364
246-250	Waves of finite amplitude Stokes' waves of permanent type, Gerstner's rotational waves, Scott Russell's solitary wave, investigations of Korteweg and De Vries Helmholtz' dynamical condition for waves of permanent type	392
251-253	Wave-propagation in two horizontal dimensions. Effect of a localized initial disturbance Local periodic pressure Effect of a pressure-disturbance advancing over the surface of water, ship-waves	406
254-258	Standing waves in limited masses of water; case of uniform depth Transverse oscillations in a canal, triangular section, semicircular section Longitudinal oscillations, 'edge-waves'	418
259-261	Oscillations of a liquid globe Ocean of uniform depth on spherical nucleus	428
262-268	Capillarity, surface-condition Capillary waves, group-velocity. Waves subject to gravity and capillarity, minimum wave-velocity Waves on the common boundary of two currents. Surface-disturbance of a stream, waves and ripples Effect of a pressure-point advancing over the surface, wave-patterns	433
269-271	Vibrations of a cylindrical column of liquid, instability of a jet Oscillations of a liquid globule, and of a bubble	448

CHAPTER X

WAVES OF EXPANSION.

272-276	Plane waves, velocity of sound Energy of a wave-system	451
277-280	Waves of finite amplitude, methods of Riemann and Earnshaw Condition for permanence of type, Rankine's investigation Question as to the possibility of waves of discontinuity	459
281, 282	Symmetrical spherical waves Sources of sound Solution in terms of initial conditions	466
283, 284	General equation of sound-waves, Poisson's integral Equation of energy Determinateness of solutions	470
285, 286	Simple-harmonic vibrations, periodic sources General theory, extension of Green's theorem Kirchhoff's formula	473

ART		PAGE
287-292	Applications of spherical harmonics Vibrations of air in spherical envelope, oscillations of a spherical sheet of air Propagation of waves outwards from a spherical surface, effect of lateral motion. Theory of the ball-pendulum, correction for inertia, dissipation-coefficient Impact of waves on a fixed, and on a moveable sphere, case of synchronism .	478
293, 294	Approximate treatment of diffraction problems when the wave-length is relatively large Diffraction by a flat disk, by an aperture in a thin screen, and by an obstacle of any form .	491
295	Solution of the equation $\phi = c^2 \nabla^2 \phi$ in spherical harmonics Conditions at the front of an advancing wave .	496
296-301	Sound-waves in two dimensions, effect of a transient source, comparison with the case of three dimensions Simple-harmonic motion, solutions in Bessel's functions Scattering of waves by a cylindrical obstacle Approximate theory of diffraction in two dimensions Diffraction by a flat blade, and by an aperture in a thin screen Reflection and transmission of air waves by a grating .	499
302-304	Atmospheric oscillations, general equations Plane waves travelling vertically Slow horizontal oscillations of the atmosphere of a globe, atmospheric tides .	516

CHAPTER XI

VISCOSITY

305-310	General theory of dissipative forces One degree of freedom, free oscillations, forced oscillations, effect of friction on phase Application to tides in equatorial canal, tidal lagging, and tidal friction Dissipative systems in general, frictional and gyrostatic terms Dissipation Function Oscillations of a dissipative system about a configuration of absolute equilibrium Effect of gyrostatic terms Two degrees of freedom, disturbance of long period .	521
311-317	Viscosity of fluids, specification of stress, formulæ of transformation. Expression of the stresses as linear functions of rates of strain Coefficient of viscosity Boundary conditions, question of slipping Dynamical equations, interpretation Rate of dissipation in a liquid .	532
318-322	Problems of steady motion Flow of a liquid between parallel planes, Héc Shaw's experiments Flow through a pipe of circular section, Poiseuille's laws Other forms of section Steady rotation of a cylinder, and of a sphere Meaning of the approximations employed .	542
323-326	General solution of the problem of steady motion in terms of spherical harmonics Rectilinear motion of a sphere, resistance, terminal velocity, stream-lines Extensions to ellipsoid .	548
327	Theorems of Helmholtz and Korteweg, minimum dissipation .	556
328-330	Problems of periodic motion Laminar motion, diffusion of angular velocity Oscillating plane Periodic tidal force, feeble influence of viscosity on 'regular' oscillations .	558

Contents

XV

ART.		PAGE
331-334	Effect of viscosity on gravity-waves Effect of surface-forces, generation and maintenance of waves by wind, Scott Russell's observations Calming effect of oil on water-waves	563
335-339	Periodic motion with a spherical boundary, general solution in spherical harmonics Applications, decay of motion in a fixed spherical vessel, torsional oscillations of a hollow sphere containing liquid, effect of viscosity on a ball-pendulum	571
340	Notes on two-dimensional problems	584
341-343	* Viscosity in gases, dissipation Damping of sound-waves by viscosity, combined effect of viscosity and thermal conduction	586
344-346	Turbulent Motion, critical velocity of water in a pipe, law of resistance, Reynolds' experiments Theoretical investigations of Rayleigh, Kelvin, and Reynolds	591

CHAPTER XII.

ROTATING MASSES OF LIQUID.

347-349	Formulae relating to the attraction of ellipsoids Maclaurin's and Jacobi's ellipsoids Linear series of ellipsoidal forms of equilibrium; numerical results	602
350	Other special forms of relative equilibrium Rotating annulus	610
351-354	General conditions of relative equilibrium, linear series of equilibrium forms, limiting forms and forms of bifurcation; exchange of stabilities Secular stability of Maclaurin's and Jacobi's ellipsoids The pear-shaped figure of equilibrium	612
355	Small oscillations of a rotating ellipsoidal mass, Poincaré's method; references	619
356, 357	Dirichlet's ellipsoids, references Motion of a liquid ellipsoid with its axes fixed in direction Rotating ellipsoid of revolution, finite oscillations about the spherical form Dedekind's ellipsoid. The irrotational ellipsoid Rotating elliptic cylinder	621
LIST OF AUTHORS CITED		627
INDEX		630

ADDITIONS AND CORRECTIONS

Page 149, Art 116 A reference to the researches of C. A. Bjerknes on pulsating spheres has unfortunately been omitted. A full account of these is given by V. Bjerknes, *Vorlesungen über hydrodynamische Fernkräfte*, Leipzig, 1900–1902.

Page 261, first footnote Add a reference to Chrystal, "On the Hydrodynamical Theory of Seiches, with a Bibliographical Sketch," *Trans. R. S. Edin.*, t. xli p. 599 (1905).

Page 286, equation (36), for ' $d\xi$ ' read ' $d\phi$ ', for ' $\frac{1}{4}\pi - \frac{1}{2}\eta$ ' read ' $\frac{1}{4}\pi - \frac{1}{4}\eta$ '

„ 405, line 5, for 'minimum' read 'stationary'

„ 413, footnote A paper by Lord Kelvin on "Deep Sea Ship-Waves," *Proc. R. S. Edin.*, t. xxv p. 1060 (1905), has appeared since this chapter was printed.

Page 418, first footnote Reference should also have been made to papers by A. Rasmussen and G. Rota, respectively, *Trans. Inst. Nav. Arch.*, t. xli p. 12 (1899), and t. xlii p. 239 (1900).

Page 512, equation (8), for ' Σ ' read ' \sum_{1}^{∞} '

„ 513, equations (18), insert a comma after ' $\log \mu$ '

HYDRODYNAMICS.

CHAPTER I.


THE EQUATIONS OF MOTION.

1. THE following investigations proceed on the assumption that the matter with which we deal may be treated as practically continuous and homogeneous in structure, *i.e.* we assume that the properties of the smallest portions into which we can conceive it to be divided are the same as those of the substance in bulk.

The fundamental property of a fluid is that it cannot be in equilibrium in a state of stress such that the mutual action between two adjacent parts is oblique to the common surface. This property is the basis of Hydrostatics, and is verified by the complete agreement of the deductions of that science with experiment. Very slight observation is enough, however, to convince us that oblique stresses may exist in fluids *in motion*. Let us suppose for instance that a vessel in the form of a circular cylinder, containing water (or other liquid), is made to rotate about its axis, which is vertical. If the motion of the vessel be uniform, the fluid is soon found to be rotating with the vessel as one solid body. If the vessel be now brought to rest, the motion of the fluid continues for some time, but gradually subsides, and at length ceases altogether, and it is found that during this process the portions of fluid which are further from the axis lag behind those which are nearer, and have their motion more rapidly checked. These phenomena point to the existence of mutual actions between contiguous elements which are partly tangential to the common surface. For if the mutual action were everywhere wholly normal, it is obvious that the moment of momentum, about the axis of the vessel, of any portion of fluid bounded by a surface of revolution about this axis, would be constant. We infer, moreover, that these tangential stresses are not called into play so long as the fluid moves as a solid body, but only whilst a change of shape of some portion of the mass is going on, and that their tendency is to oppose this change of shape.

2 It is usual, however, in the first instance to neglect the tangential stresses altogether. Their effect is in many practical cases small, and independently of this, it is convenient to divide the not inconsiderable difficulties of our subject by investigating first the effects of purely normal stress. The further consideration of the laws of tangential stress is accordingly deferred till Chapter xi.

If the stress exerted across any small plane area situate at a point P of the fluid be wholly normal, its intensity (per unit area) is the same for all aspects of the plane. The following proof of this theorem is given here for purposes of reference. Through P draw three straight lines PA , PB , PC mutually at right angles, and let a plane whose direction-cosines relatively to these lines are l , m , n , passing infinitely close to P , meet them in A , B , C . Let p , p_1 , p_2 , p_3 denote the intensities of the stresses* across the faces ABC , PBC , PCA , PAB , respectively, of the tetrahedron $PABC$. If Δ be the area of the first-mentioned face, the areas of the others are, in order, $l\Delta$, $m\Delta$, $n\Delta$. Hence if we form the equation of motion of the tetrahedron parallel to PA we have $p_1 l\Delta = pl \cdot \Delta$, where we have omitted the terms which express the rate of change of momentum, and the component of the extraneous forces, because they are ultimately proportional to the mass of the tetrahedron, and therefore of the third order of small linear quantities, whilst the terms retained are of the second. We have then, ultimately, $p = p_1$, and similarly $p = p_2 = p_3$, which proves the theorem.



3 The equations of motion of a fluid have been obtained in two different forms, corresponding to the two ways in which the problem of determining the motion of a fluid mass, acted on by given forces and subject to given conditions, may be viewed. We may either regard as the object of our investigations a knowledge of the velocity, the pressure, and the density, at all points of space occupied by the fluid, for all instants, or we may seek to determine the history of every particle. The equations obtained on these two plans are conveniently designated, as by German mathematicians, the 'Eulerian' and the 'Lagrangian' forms of the hydrokinetic equations, although both forms are in reality due to Euler†

* Reckoned positive when pressures, negative when tensions. Most fluids are, however, incapable under ordinary conditions of supporting more than an exceedingly slight degree of tension, so that p is nearly always positive.

† "Principes généraux du mouvement des fluides" *Hist. de l'Acad. de Berlin*, 1755.

"De principis motus fluidorum" *Novi Comm. Acad. Petrop.* t. xiv. p. 1 (1759).

Lagrange gave three investigations of the equations of motion, first, incidentally, in

The Eulerian Equations

4 Let u, v, w be the components, parallel to the co-ordinate axes, of the velocity at the point (x, y, z) at the time t . These quantities are then functions of the independent variables x, y, z, t . For any particular value of t they express the motion at that instant at all points of space occupied by the fluid, whilst for particular values of x, y, z they give the history of what goes on at a particular place.

We shall suppose, for the most part, not only that u, v, w are finite and continuous functions of x, y, z , but that their space-derivatives of the first order ($\partial u/\partial x, \partial v/\partial x, \partial w/\partial x$, &c) are everywhere finite*, we shall understand by the term 'continuous motion,' a motion subject to these restrictions. Cases of exception, if they present themselves, will require separate examination. In continuous motion, as thus defined, the relative velocity of any two neighbouring particles P, P' will always be infinitely small, so that the line PP' will always remain of the same order of magnitude. It follows that if we imagine a small closed surface to be drawn, surrounding P , and suppose it to move with the fluid, it will always enclose the same matter. And *any* surface whatever, which moves with the fluid, completely and permanently separates the matter on the two sides of it.

5. The values of u, v, w for successive values of t give as it were a series of pictures of consecutive stages of the motion, in which however there is no immediate means of tracing the identity of any one particle.

To calculate the rate at which any function $F(x, y, z, t)$ varies for a moving particle, we remark that at the time $t + \delta t$ the particle which was originally in the position (x, y, z) is in the position $(x + u\delta t, y + v\delta t, z + w\delta t)$, so that the corresponding value of F is

$$F(x + u\delta t, y + v\delta t, z + w\delta t, t + \delta t) = F + u\delta t \frac{\partial F}{\partial x} + v\delta t \frac{\partial F}{\partial y} + w\delta t \frac{\partial F}{\partial z} + \delta t \frac{\partial F}{\partial t}.$$

If, after Stokes, we introduce the symbol D/Dt to denote a differentiation following the motion of the fluid, the new value of F is also expressed by $F + DF/Dt \delta t$, whence

$$\frac{DF}{Dt} = \frac{\partial F}{\partial t} + u \frac{\partial F}{\partial x} + v \frac{\partial F}{\partial y} + w \frac{\partial F}{\partial z} \dots \dots \dots (1)$$

connection with the principle of Least Action, in the *Miscellanea Taurinensia*, t. II (1760), *Oeuvres*, Paris, 1867-92, t. I., secondly in his "Mémoire sur la Théorie du Mouvement des Fluides," *Nouv. mém. de l'Acad. de Berlin*, 1781, *Oeuvres*, t. IV, and thirdly in the *Mécanique Analytique*. In this last exposition he starts with the second form of the equations (Art. 13, below), but translates them at once into the 'Eulerian' notation.

* It is important to bear in mind, with a view to some later developments under the head of Vortex Motion, that these derivatives need not be assumed to be continuous.

6 To form the dynamical equations, let p be the pressure, ρ the density, X, Y, Z the components of the extraneous forces per unit mass, at the point (x, y, z) at the time t . Let us take an element having its centre at (x, y, z) , and its edges $\delta x, \delta y, \delta z$ parallel to the rectangular co-ordinate axes. The rate at which the x -component of the momentum of this element is increasing is $\rho \delta x \delta y \delta z Du/Dt$; and this must be equal to the x -component of the forces acting on the element. Of these the extraneous forces give $\rho \delta x \delta y \delta z X$. The pressure on the yz -face which is nearest the origin will be ultimately

$$(p - \frac{1}{2} \partial p / \partial x \cdot \delta x) \delta y \delta z^*,$$

that on the opposite face

$$(p + \frac{1}{2} \partial p / \partial x \cdot \delta x) \delta y \delta z$$

The difference of these gives a resultant $-\partial p / \partial x \cdot \delta x \delta y \delta z$ in the direction of x -positive. The pressures on the remaining faces are perpendicular to x . We have then

$$\rho \delta x \delta y \delta z \frac{Du}{Dt} = \rho \delta x \delta y \delta z X - \frac{\partial p}{\partial x} \delta x \delta y \delta z.$$

Substituting the value of Du/Dt from (1), and writing down the symmetrical equations, we have

$$\left. \begin{aligned} \frac{\partial u}{\partial t} + u \frac{\partial u}{\partial x} + v \frac{\partial u}{\partial y} + w \frac{\partial u}{\partial z} &= X - \frac{1}{\rho} \frac{\partial p}{\partial x}, \\ \frac{\partial v}{\partial t} + u \frac{\partial v}{\partial x} + v \frac{\partial v}{\partial y} + w \frac{\partial v}{\partial z} &= Y - \frac{1}{\rho} \frac{\partial p}{\partial y}, \\ \frac{\partial w}{\partial t} + u \frac{\partial w}{\partial x} + v \frac{\partial w}{\partial y} + w \frac{\partial w}{\partial z} &= Z - \frac{1}{\rho} \frac{\partial p}{\partial z}. \end{aligned} \right\} \dots \dots \dots (2)$$

7. To these dynamical equations we must join, in the first place, a certain kinematical relation between u, v, w, ρ , obtained as follows.

If \mathbf{v} be the volume of a moving element, we have, on account of the constancy of mass,

$$\frac{D}{Dt} \rho \mathbf{v} = 0,$$

or
$$\frac{1}{\rho} \frac{D\rho}{Dt} + \frac{1}{\mathbf{v}} \frac{D\mathbf{v}}{Dt} = 0. \dots \dots \dots (1)$$

To calculate the value of $1/\mathbf{v} D\mathbf{v}/Dt$, let the element in question be that which at time t fills the rectangular space $\delta x \delta y \delta z$ having one corner P at (x, y, z) , and the edges PL, PM, PN (say) parallel to the co-ordinate axes. At time $t + \delta t$ the same element will form an oblique parallelepiped, and since

* It is easily seen, by Taylor's theorem, that the mean pressure over any face of the element $\delta x \delta y \delta z$ may be taken to be equal to the pressure at the centre of that face.

the velocities of the particle L relative to the particle P are $\partial u/\partial x \cdot \delta x$, $\partial v/\partial x \cdot \delta x$, $\partial w/\partial x \cdot \delta x$, the projections of the edge PL become, after the time δt ,

$$\left(1 + \frac{\partial u}{\partial x} \delta t\right) \delta x, \quad \frac{\partial v}{\partial x} \delta t \delta x, \quad \frac{\partial w}{\partial x} \delta t \delta x,$$

respectively. To the first order in δt , the length of this edge is now

$$= \left(1 + \frac{\partial u}{\partial x} \delta t\right) \delta x,$$

and similarly for the remaining edges. Since the angles of the parallelepiped differ infinitely little from right angles, the volume is still given, to the first order in δt , by the product of the three edges, *i.e.* we have

$$\mathbf{v} + \frac{D\mathbf{v}}{Dt} \delta t = \left\{1 + \left(\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z}\right) \delta t\right\} \delta x \delta y \delta z,$$

$$\text{or} \quad \frac{1}{\mathbf{v}} \frac{D\mathbf{v}}{Dt} = \frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} \quad \dots \dots \dots (2)$$

Hence (1) becomes

$$\frac{D\rho}{Dt} + \rho \left(\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z}\right) = 0 \quad \dots \dots \dots (3)$$

This is called the 'equation of continuity.'

The expression $\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z}$,

which, as we have seen, measures the rate of increase of volume of the fluid at the point (x, y, z) , is conveniently called the 'expansion' at that point.

8. Another, and now more usual, method of obtaining the above equation is, instead of following the motion of a fluid element, to fix the attention on an element $\delta x \delta y \delta z$ of space, and to calculate the change produced in the included mass by the flux across the boundary. If the centre of the element be at (x, y, z) , the amount of matter which per unit time enters it across the yz -face nearest the origin is

$$\left(\rho u - \frac{1}{2} \frac{\partial}{\partial x} \rho u \delta x\right) \delta y \delta z,$$

and the amount which leaves it by the opposite face is

$$\left(\rho u + \frac{1}{2} \frac{\partial}{\partial x} \rho u \delta x\right) \delta y \delta z$$

The two faces together give a gain

$$- \frac{\partial}{\partial x} \rho u \delta x \delta y \delta z,$$

per unit time. Calculating in the same way the effect of the flux across the

remaining faces, we have for the total gain of mass, per unit time, in the space $\delta x \delta y \delta z$, the formula

$$-\left(\frac{\partial \rho u}{\partial x} + \frac{\partial \rho v}{\partial y} + \frac{\partial \rho w}{\partial z}\right) \delta x \delta y \delta z.$$

Since the quantity of matter in any region can vary only in consequence of the flux across the boundary, this must be equal to

$$\frac{\partial}{\partial t}(\rho \delta x \delta y \delta z),$$

whence we get the equation of continuity in the form

$$\frac{\partial \rho}{\partial t} + \frac{\partial \rho u}{\partial x} + \frac{\partial \rho v}{\partial y} + \frac{\partial \rho w}{\partial z} = 0. \dots \dots \dots (4)$$

9 It remains to put in evidence the physical properties of the fluid, so far as these affect the quantities which occur in our equations

In an 'incompressible' fluid, or liquid, we have $D\rho/Dt = 0$, in which case the equation of continuity takes the simple form

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 0 \dots \dots \dots (1)$$

It is not assumed here that the fluid is of *uniform* density, though this is of course by far the most important case.

If we wished to take account of the slight compressibility of actual liquids, we should have a relation of the form

$$p = \kappa(\rho - \rho_0)/\rho_0, \dots \dots \dots (2)$$

or

$$\rho/\rho_0 = 1 + p/\kappa, \dots \dots \dots (3)$$

where κ denotes what is called the 'elasticity of volume.'

In the case of a gas whose temperature is uniform and constant we have the 'isothermal' relation

$$p/p_0 = \rho/\rho_0, \dots \dots \dots (4)$$

where p_0, ρ_0 are any pair of corresponding values for the temperature in question

In most cases of motion of gases, however, the temperature is not constant, but rises and falls, for each element, as the gas is compressed or rarefied. When the changes are so rapid that we can ignore the gain or loss of heat by an element due to conduction and radiation, we have the 'adiabatic' relation

$$p/p_0 = (\rho/\rho_0)^\gamma, \dots \dots \dots (5)$$

where p_0 and ρ_0 are any pair of corresponding values for the element considered. The constant γ is the ratio of the two specific heats of the gas, for atmospheric air, and some other gases, its value is 1.408

10 At the boundaries (if any) of the fluid, the equation of continuity is replaced by a special surface-condition. Thus at a *fixed* boundary, the velocity of the fluid perpendicular to the surface must be zero, *i.e.* if l, m, n be the direction-cosines of the normal,

$$lu + mv + nw = 0 \quad \dots \dots \dots (1)$$

Again at a surface of discontinuity, *i.e.* a surface at which the values of u, v, w change abruptly as we pass from one side to the other, we must have

$$l(u_1 - u_2) + m(v_1 - v_2) + n(w_1 - w_2) = 0, \quad \dots \dots \dots (2)$$

where the suffixes are used to distinguish the values on the two sides. The same relation must hold at the common surface of a fluid and a moving solid

The general surface-condition, of which these are particular cases, is that if $F(x, y, z, t) = 0$ be the equation of a bounding surface, we must have at every point of it

$$DF/Dt = 0 \quad \dots \dots \dots (3)$$

For the velocity relative to the surface of a particle lying in it must be wholly tangential (or zero), otherwise we should have a finite flow of fluid across it. It follows that the instantaneous rate of variation of F for a surface-particle must be zero

A fuller proof, given by Lord Kelvin*, is as follows. To find the rate of motion (\dot{v}) of the surface $F(x, y, z, t) = 0$, normal to itself, we write

$$F(x + l\nu\delta t, y + m\dot{v}\delta t, z + n\dot{v}\delta t, t + \delta t) = 0,$$

where l, m, n are the direction-cosines of the normal at (x, y, z) , whence

$$\dot{v} \left(l \frac{\partial F}{\partial x} + m \frac{\partial F}{\partial y} + n \frac{\partial F}{\partial z} \right) + \frac{\partial F}{\partial t} = 0$$

Since

$$(l, m, n) = \left(\frac{\partial F}{\partial x}, \frac{\partial F}{\partial y}, \frac{\partial F}{\partial z} \right) - R,$$

where

$$R = \left\{ \left(\frac{\partial F}{\partial x} \right)^2 + \left(\frac{\partial F}{\partial y} \right)^2 + \left(\frac{\partial F}{\partial z} \right)^2 \right\}^{\frac{1}{2}},$$

we have

$$\dot{v} = - \frac{1}{R} \frac{\partial F}{\partial t} \quad \dots \dots \dots (4)$$

At every point of the surface we must have

$$v = lu + mv + nw,$$

which leads, on substitution of the above values of l, m, n , to the equation (3).

The partial differential equation (3) is also satisfied by any surface moving with the fluid. This follows at once from the meaning of the operator

* (W. Thomson) "Notes on Hydrodynamics," *Camb. and Dub. Math. Journ.* Feb. 1848
Mathematical and Physical Papers, Cambridge, 1882, t. i. p. 83

D/Dt . A question arises as to whether the converse necessarily holds, *viz* whether a moving surface whose equation $F=0$ satisfies (3) will always consist of the same particles. Considering any such surface, let us fix our attention on a particle P situate on it at time t . The equation (3) expresses that the rate at which P is separating from the surface is at this instant zero, and it is easily seen that *if the motion be continuous* (according to the definition of Art 4), the normal velocity, relative to the moving surface F , of a particle at an infinitesimal distance ζ from it is of the order ζ , *viz* it is equal to $G\zeta$ where G is finite. Hence the equation of motion of the particle P relative to the surface may be written

$$D\zeta/Dt = G\zeta.$$

This shews that $\log \zeta$ increases at a finite rate, and since it is negative infinite to begin with (when $\zeta=0$), it remains so throughout, *viz* ζ remains zero for the particle P .

The same result follows from the nature of the solution of

$$\frac{\partial F}{\partial t} + u \frac{\partial F}{\partial x} + v \frac{\partial F}{\partial y} + w \frac{\partial F}{\partial z} = 0, \quad \dots \quad (5)$$

considered as a partial differential equation in F^* . The subsidiary system of ordinary differential equations is

$$dt = \frac{dx}{u} = \frac{dy}{v} = \frac{dz}{w}, \quad \dots \quad (6)$$

in which x, y, z are regarded as functions of the independent variable t . These are evidently the equations to find the paths of the particles, and their integrals may be supposed put in the forms

$$x=f_1(\alpha, b, c, t), \quad y=f_2(\alpha, b, c, t), \quad z=f_3(\alpha, b, c, t), \quad \dots \quad (7)$$

where the arbitrary constants α, b, c are any three quantities serving to identify a particle, for instance they may be the initial co-ordinates. The general solution of (5) is then found by elimination of α, b, c between (7) and

$$F=\psi(\alpha, b, c), \quad \dots \quad (8)$$

where ψ is an arbitrary function. This shews that a particle once in the surface $F=0$ remains in it throughout the motion.

Equation of Energy

11 In most cases which we shall have occasion to consider the extraneous forces have a potential, *viz* we have

$$X, Y, Z = -\frac{\partial \Omega}{\partial x}, -\frac{\partial \Omega}{\partial y}, -\frac{\partial \Omega}{\partial z} \quad \dots \dots \dots (1)$$

The physical meaning of Ω is that it denotes the potential energy, per unit mass, at the point (x, y, z) , in respect of forces acting at a distance. It will

* Lagrange, *Oeuvres*, t. iv. p. 706

be sufficient for the present to consider the case where the field of extraneous force is constant with respect to the time, *i.e.* $\partial\Omega/\partial t = 0$. If we now multiply the equations (2) of Art. 6 by u, v, w , in order, and add, we obtain a result which may be written

$$\frac{1}{2}\rho \frac{D}{Dt}(u^2 + v^2 + w^2) + \rho \frac{D\Omega}{Dt} = - \left(u \frac{\partial p}{\partial x} + v \frac{\partial p}{\partial y} + w \frac{\partial p}{\partial z} \right).$$

If we multiply this by $\delta x \delta y \delta z$, and integrate over any region, we find

$$\frac{D}{Dt}(T + V) = - \iiint \left(u \frac{\partial p}{\partial x} + v \frac{\partial p}{\partial y} + w \frac{\partial p}{\partial z} \right) dx dy dz, \quad \dots \quad (2)$$

$$\text{where} \quad T = \frac{1}{2} \iiint \rho (u^2 + v^2 + w^2) dx dy dz, \quad V = \iiint \Omega \rho dx dy dz, \dots \dots (3)$$

i.e. T and V denote the kinetic energy, and the potential energy in relation to the field of extraneous force, of the fluid which at the moment occupies the region in question. The triple integral on the right-hand side of (2) may be transformed by a process which will often recur in our subject. Thus, by a partial integration,

$$\iiint u \frac{\partial p}{\partial x} dx dy dz = \iint [pu] dy dz - \iiint p \frac{\partial u}{\partial x} dx dy dz,$$

where $[pu]$ is used to indicate that the values of pu at the points where the boundary of the region is met by a line parallel to x are to be taken, with proper signs. If l, m, n be the direction-cosines of the *inwardly* directed normal to any element δS of this boundary, we have $\delta y \delta z = \pm l \delta S$, the signs alternating at the successive intersections referred to. We thus find that

$$\iint [pu] dy dz = - \iint p u l \delta S,$$

where the integration extends over the whole bounding surface. Transforming the remaining terms in a similar manner, we obtain

$$\frac{D}{Dt}(T + V) = \iint p (lu + mv + nw) \delta S + \iiint p \left(\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} \right) dx dy dz \dots (4)$$

In the case of an incompressible fluid this reduces to the form

$$\frac{D}{Dt}(T + V) = \iint (lu + mv + nw) p \delta S. \dots \dots \dots (5)$$

Since $lu + mv + nw$ denotes the velocity of a fluid particle in the direction of the normal, the latter integral expresses the rate at which the pressures $p \delta S$ exerted from without on the various elements δS of the boundary are doing work. Hence the total increase of energy, kinetic and potential, of any portion of the liquid, is equal to the work done by the pressures on its surface.

In particular, if the fluid be bounded on all sides by fixed walls, we have

$$lu + mv + nw = 0$$

over the boundary, and therefore

$$T + V = \text{const} \quad \dots \quad \dots \quad (6)$$

A similar interpretation can be given to the more general equation (4), provided p be a function of ρ only. If we write

$$E = - \int p d\left(\frac{1}{\rho}\right), \dots \dots \dots (7)$$

then E measures the work done by unit mass of the fluid against external pressure, as it passes, under the supposed relation between p and ρ , from its actual volume to some standard volume. For example, if the unit mass were enclosed in a cylinder with a sliding piston of area A , then when the piston is pushed outwards through a space δx , the work done is $pA \delta x$, of which the factor $A\delta x$ denotes the increment of volume, *i.e.* of ρ^{-1} . In the case of the adiabatic relation we find

$$E = \frac{1}{\gamma - 1} \left(\frac{p}{\rho} - \frac{p_0}{\rho_0} \right). \dots \dots \dots (8)$$

We may call E the intrinsic energy of the fluid, per unit mass. Now, recalling the interpretation of the expression

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z}$$

given in Art. 7, we see that the volume-integral in (4) measures the rate at which the various elements of the fluid are losing intrinsic energy by expansion*, it is therefore equal to $-DW/Dt$,

where

$$W = \iiint E \rho \, dx \, dy \, dz \quad \dots \quad \dots \quad (9)$$

Hence

$$\frac{D}{Dt}(T + V + W) = \iint p(lu + mv + nw) \, dS. \quad \dots \quad (10)$$

The total energy, which is now partly kinetic, partly potential in relation to a constant field of force, and partly intrinsic, is therefore increasing at a rate equal to that at which work is being done on the boundary by pressure from without

* Otherwise,

$$\begin{aligned} & p \left(\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} \right) \delta x \, \delta y \, \delta z \\ &= -p \, \frac{1}{\rho} \frac{D\rho}{Dt} \, \delta x \, \delta y \, \delta z = p \, \frac{D}{Dt} \left(\frac{1}{\rho} \right) \rho \, \delta x \, \delta y \, \delta z = - \frac{DE}{Dt} \rho \, \delta x \, \delta y \, \delta z. \end{aligned}$$

Impulsive Generation of Motion

12 If at any instant impulsive forces act bodily on the fluid, or if the boundary conditions suddenly change, a sudden alteration in the motion may take place. The latter case may arise, for instance, when a solid immersed in the fluid is suddenly set in motion

Let ρ be the density, u, v, w the component velocities immediately before, u', v', w' those immediately after the impulse, X', Y', Z' the components of the extraneous impulsive forces per unit mass, ϖ the impulsive pressure, at the point (x, y, z) . The change of momentum parallel to x of the element defined in Art. 6 is then $\rho \delta x \delta y \delta z (u' - u)$, the x -component of the extraneous impulsive forces is $\rho \delta x \delta y \delta z X'$, and the resultant impulsive pressure in the same direction is $-\partial \varpi / \partial x \delta x \delta y \delta z$. Since an impulse is to be regarded as an infinitely great force acting for an infinitely short time (τ , say), the effects of all finite forces during this interval are neglected

$$\text{Hence,} \quad \rho \delta x \delta y \delta z (u' - u) = \rho \delta x \delta y \delta z X' - \frac{\partial \varpi}{\partial x} \delta x \delta y \delta z,$$

$$\left. \begin{array}{l} \text{or} \\ \text{Similarly,} \end{array} \quad \begin{array}{l} u' - u = X' - \frac{1}{\rho} \frac{\partial \varpi}{\partial x} \\ v' - v = Y' - \frac{1}{\rho} \frac{\partial \varpi}{\partial y} \\ w' - w = Z' - \frac{1}{\rho} \frac{\partial \varpi}{\partial z} \end{array} \right\} \dots \dots \dots (1)$$

These equations might also have been deduced from (2) of Art. 6, by multiplying the latter by δt , integrating between the limits 0 and τ , putting

$$X' = \int_0^\tau X dt, \quad Y' = \int_0^\tau Y dt, \quad Z' = \int_0^\tau Z dt, \quad \varpi = \int_0^\tau p dt,$$

and then making τ vanish

In a liquid an instantaneous change of motion can be produced by the action of impulsive pressures only, even when no impulsive forces act bodily on the mass. In this case we have $X', Y', Z' = 0$, so that

$$\left. \begin{array}{l} u' - u = -\frac{1}{\rho} \frac{\partial \varpi}{\partial x} \\ v' - v = -\frac{1}{\rho} \frac{\partial \varpi}{\partial y} \\ w' - w = -\frac{1}{\rho} \frac{\partial \varpi}{\partial z} \end{array} \right\} \dots \dots \dots (2)$$

If we differentiate these equations with respect to x, y, z , respectively, and

add, and if we further suppose the density to be uniform, we find by Art. 9 (1) that

$$\frac{\partial^2 \varpi}{\partial x^2} + \frac{\partial^2 \varpi}{\partial y^2} + \frac{\partial^2 \varpi}{\partial z^2} = 0$$

The problem then, in any given case, is to determine a value of ϖ satisfying this equation and the proper boundary conditions*; the instantaneous change of motion is then given by (2)

The Lagrangian Equations

13. Let a, b, c be the initial co-ordinates of any particle of fluid, x, y, z its co-ordinates at time t . We here consider x, y, z as functions of the independent variables a, b, c, t , their values in terms of these quantities give the whole history of every particle of the fluid. The velocities parallel to the axes of co-ordinates of the particle (a, b, c) at time t are $\partial x/\partial t, \partial y/\partial t, \partial z/\partial t$, and the component accelerations in the same directions are $\partial^2 x/\partial t^2, \partial^2 y/\partial t^2, \partial^2 z/\partial t^2$. Let p be the pressure and ρ the density in the neighbourhood of this particle at time t , X, Y, Z the components of the extraneous forces per unit mass acting there. Considering the motion of the mass of fluid which at time t occupies the differential element of volume $\delta x \delta y \delta z$, we find by the same reasoning as in Art. 6,

$$\frac{\partial^2 x}{\partial t^2} = X - \frac{1}{\rho} \frac{\partial p}{\partial x},$$

$$\frac{\partial^2 y}{\partial t^2} = Y - \frac{1}{\rho} \frac{\partial p}{\partial y},$$

$$\frac{\partial^2 z}{\partial t^2} = Z - \frac{1}{\rho} \frac{\partial p}{\partial z}.$$

These equations contain differential coefficients with respect to x, y, z , whereas our independent variables are a, b, c, t . To eliminate these differential coefficients, we multiply the above equations by $\partial x/\partial a, \partial y/\partial a, \partial z/\partial a$, respectively, and add; a second time by $\partial x/\partial b, \partial y/\partial b, \partial z/\partial b$, and add, and again a third time by $\partial x/\partial c, \partial y/\partial c, \partial z/\partial c$, and add. We thus get the three equations

$$\left(\frac{\partial^2 x}{\partial t^2} - X\right) \frac{\partial x}{\partial a} + \left(\frac{\partial^2 y}{\partial t^2} - Y\right) \frac{\partial y}{\partial a} + \left(\frac{\partial^2 z}{\partial t^2} - Z\right) \frac{\partial z}{\partial a} + \frac{1}{\rho} \frac{\partial p}{\partial a} = 0,$$

$$\left(\frac{\partial^2 x}{\partial t^2} - X\right) \frac{\partial x}{\partial b} + \left(\frac{\partial^2 y}{\partial t^2} - Y\right) \frac{\partial y}{\partial b} + \left(\frac{\partial^2 z}{\partial t^2} - Z\right) \frac{\partial z}{\partial b} + \frac{1}{\rho} \frac{\partial p}{\partial b} = 0,$$

$$\left(\frac{\partial^2 x}{\partial t^2} - X\right) \frac{\partial x}{\partial c} + \left(\frac{\partial^2 y}{\partial t^2} - Y\right) \frac{\partial y}{\partial c} + \left(\frac{\partial^2 z}{\partial t^2} - Z\right) \frac{\partial z}{\partial c} + \frac{1}{\rho} \frac{\partial p}{\partial c} = 0.$$

These are the 'Lagrangian' forms of the dynamical equations

* It will appear in Chapter III. that the value of ϖ is thus determinate, save as to an additive constant

14 To find the form which the equation of continuity assumes in terms of our present variables, we consider the element of fluid which originally occupied a rectangular parallelepiped having its centre at the point (a, b, c) , and its edges $\delta a, \delta b, \delta c$ parallel to the axes. At the time t the same element forms an oblique parallelepiped. The centre now has for its co-ordinates x, y, z ; and the projections of the edges on the co-ordinate axes are respectively

$$\begin{aligned} \frac{\partial x}{\partial a} \delta a, \quad \frac{\partial y}{\partial a} \delta a, \quad \frac{\partial z}{\partial a} \delta a, \\ \frac{\partial x}{\partial b} \delta b, \quad \frac{\partial y}{\partial b} \delta b, \quad \frac{\partial z}{\partial b} \delta b, \\ \frac{\partial x}{\partial c} \delta c, \quad \frac{\partial y}{\partial c} \delta c, \quad \frac{\partial z}{\partial c} \delta c. \end{aligned}$$

The volume of the parallelepiped is therefore

$$\begin{vmatrix} \frac{\partial x}{\partial a} & \frac{\partial y}{\partial a} & \frac{\partial z}{\partial a} \\ \frac{\partial x}{\partial b} & \frac{\partial y}{\partial b} & \frac{\partial z}{\partial b} \\ \frac{\partial x}{\partial c} & \frac{\partial y}{\partial c} & \frac{\partial z}{\partial c} \end{vmatrix} \delta a \delta b \delta c,$$

or, as it is often written, $\frac{\partial (x, y, z)}{\partial (a, b, c)} \delta a \delta b \delta c$

Hence, since the mass of the element is unchanged, we have

$$\rho \frac{\partial (x, y, z)}{\partial (a, b, c)} = \rho_0, \quad \dots \dots \dots (1)$$

where ρ_0 is the initial density at (a, b, c)

In the case of an incompressible fluid $\rho = \rho_0$, so that (1) becomes

$$\frac{\partial (x, y, z)}{\partial (a, b, c)} = 1. \dots \dots \dots (2)$$

Weber's Transformation

15 If as in Art 11 the forces X, Y, Z have a potential Ω , the dynamical equations of Art 13 may be written

$$\frac{\partial^2 x}{\partial t^2} \frac{\partial x}{\partial a} + \frac{\partial^2 y}{\partial t^2} \frac{\partial y}{\partial a} + \frac{\partial^2 z}{\partial t^2} \frac{\partial z}{\partial a} = - \frac{\partial \Omega}{\partial a} - \frac{1}{\rho} \frac{\partial p}{\partial a}, \text{ \&c, \&c}$$

Let us integrate these equations with respect to t between the limits 0 and t . We remark that

$$\begin{aligned} \int_0^t \frac{\partial^2 x}{\partial t^2} \frac{\partial x}{\partial a} dt &= \left[\frac{\partial x}{\partial t} \frac{\partial x}{\partial a} \right]_0^t - \int_0^t \frac{\partial x}{\partial t} \frac{\partial^2 x}{\partial a \partial t} dt \\ &= \frac{\partial x}{\partial t} \frac{\partial x}{\partial a} - u_0 - \frac{1}{2} \frac{\partial}{\partial a} \int_0^t \left(\frac{\partial x}{\partial t} \right)^2 dt, \end{aligned}$$

where u_0 is the initial value of the x -component of velocity of the particle (a, b, c) Hence if we write

$$\chi = \int_0^t \left[\int \frac{dp}{\rho} + \Omega - \frac{1}{2} \left\{ \left(\frac{\partial x}{\partial t} \right)^2 + \left(\frac{\partial y}{\partial t} \right)^2 + \left(\frac{\partial z}{\partial t} \right)^2 \right\} \right] dt, \dots \quad (1)$$

we find*

$$\left. \begin{aligned} \frac{\partial x}{\partial t} \frac{\partial x}{\partial a} + \frac{\partial y}{\partial t} \frac{\partial y}{\partial a} + \frac{\partial z}{\partial t} \frac{\partial z}{\partial a} - u_0 &= -\frac{\partial \chi}{\partial a}, \\ \frac{\partial x}{\partial t} \frac{\partial x}{\partial b} + \frac{\partial y}{\partial t} \frac{\partial y}{\partial b} + \frac{\partial z}{\partial t} \frac{\partial z}{\partial b} - v_0 &= -\frac{\partial \chi}{\partial b}, \\ \frac{\partial x}{\partial t} \frac{\partial x}{\partial c} + \frac{\partial y}{\partial t} \frac{\partial y}{\partial c} + \frac{\partial z}{\partial t} \frac{\partial z}{\partial c} - w_0 &= -\frac{\partial \chi}{\partial c} \end{aligned} \right\} \dots \dots \dots (2)$$

These three equations, together with

$$\frac{\partial \chi}{\partial t} = \int \frac{dp}{\rho} + \Omega - \frac{1}{2} \left\{ \left(\frac{\partial x}{\partial t} \right)^2 + \left(\frac{\partial y}{\partial t} \right)^2 + \left(\frac{\partial z}{\partial t} \right)^2 \right\}, \dots \dots (3)$$

and the equation of continuity, are the partial differential equations to be satisfied by the five unknown quantities x, y, z, p, χ, ρ being supposed already eliminated by means of one of the relations of Art. 9

The initial conditions to be satisfied are

$$x = a, \quad y = b, \quad z = c, \quad \chi = 0$$

16 It is to be remarked that the quantities a, b, c need not be restricted to mean the initial co-ordinates of a particle, they may be any three quantities which serve to identify a particle, and which vary continuously from one particle to another. If we thus generalise the meanings of a, b, c , the form of the dynamical equations of Art. 13 is not altered, to find the form which the equation of continuity assumes, let x_0, y_0, z_0 now denote the initial co-ordinates of the particle to which a, b, c refer. The initial volume of the parallelepiped, whose centre is at (x_0, y_0, z_0) and whose edges correspond to variations $\delta a, \delta b, \delta c$ of the parameters, a, b, c , is

$$\frac{\partial (x_0, y_0, z_0)}{\partial (a, b, c)} \delta a \delta b \delta c,$$

$$\text{so that we have} \quad \rho \frac{\partial (x, y, z)}{\partial (a, b, c)} = \rho_0 \frac{\partial (x_0, y_0, z_0)}{\partial (a, b, c)}, \quad \dots \quad (1)$$

or, for an incompressible fluid,

$$\frac{\partial (x, y, z)}{\partial (a, b, c)} = \frac{\partial (x_0, y_0, z_0)}{\partial (a, b, c)} \quad \dots \quad (2)$$

* H. Weber, "Ueber eine Transformation der hydrodynamischen Gleichungen," *Crelle*, t. lxxviii (1868)

CHAPTER II

INTEGRATION OF THE EQUATIONS IN SPECIAL CASES

17. In a large and important class of cases the component velocities u, v, w can be expressed in terms of a single function ϕ , as follows

$$u, v, w = -\frac{\partial\phi}{\partial x}, -\frac{\partial\phi}{\partial y}, -\frac{\partial\phi}{\partial z}. \quad \dots\dots\dots (1)^*$$

Such a function is called a 'velocity-potential,' from its analogy with the potential function which occurs in the theories of Attractions, Electrostatics, &c. The general theory of the velocity-potential is reserved for the next chapter, but we give at once a proof of the following important theorem.

If a velocity-potential exist, at any one instant, for any finite portion of a perfect fluid in motion under the action of forces which have a potential, then, provided the density of the fluid be either constant or a function of the pressure only, a velocity-potential exists for the same portion of the fluid at all instants before or after†.

In the equations of Art. 15, let the instant at which the velocity-potential ϕ_0 exists be taken as the origin of time, we have then

$$u_0 da + v_0 db + w_0 dc = -d\phi_0,$$

throughout the portion of the mass in question. Multiplying the equations (2) of Art. 15 in order by da, db, dc , and adding we get

$$\frac{\partial x}{\partial t} dx + \frac{\partial y}{\partial t} dy + \frac{\partial z}{\partial t} dz - (u_0 da + v_0 db + w_0 dc) = -d\chi,$$

* The reasons for the introduction of the *minus* sign are stated in the Preface

| Lagrange, "Mémoire sur la Théorie du Mouvement des Fluides," *Nouv. mém. de l'Acad. de Berlin*, 1781, *Oeuvres*, t. iv p. 714. The argument is reproduced in the *Mécanique Analytique*.

Lagrange's statement and proof were alike imperfect, the first rigorous demonstration is due to Cauchy, "Mémoire sur la Théorie des Ondes," *Mém. de l'Acad. roy. des Sciences*, t. i (1827), *Oeuvres Complètes*, Paris, 1882, 1^{re} Série, t. i p. 38, the date of the memoir is 1815. Another proof is given by Stokes, *Camb. Trans.* t. viii (1845) (see also *Math. and Phys. Papers*, Cambridge, 1880, t. i. pp. 106, 158, and t. ii. p. 36), together with an excellent historical and critical account of the whole matter.

or, in the 'Eulerian' notation,

$$u dx + v dy + w dz = -d(\phi_0 + \chi) = -d\phi, \text{ say}$$

Since the upper limit of t in Art 15 (1) may be positive or negative, this proves the theorem

It is to be particularly noticed that this continued existence of a velocity-potential is predicated, not of regions of space, but of portions of matter. A portion of matter for which a velocity-potential exists moves about and carries this property with it, but the part of space which it originally occupied may, in the course of time, come to be occupied by matter which did not originally possess the property, and which therefore cannot have acquired it.

The class of cases in which a velocity-potential exists includes all those where the motion has originated from rest under the action of forces of the kind here supposed, for then we have, initially,

$$u_0 da + v_0 db + w_0 dc = 0,$$

or

$$\phi_0 = \text{const.}$$

The restrictions under which the above theorem has been proved must be carefully remembered. It is assumed not only that the extraneous forces X , Y , Z , estimated at per unit mass, have a potential, but that the density ρ is either uniform or a function of p only. The latter condition is violated for example, in the case of the convection currents generated by the unequal application of heat to a fluid, and again, in the wave-motion of a heterogeneous but incompressible fluid arranged originally in horizontal layers of equal density. Another case of exception is that of 'electro-magnetic rotations', see Art 29.

18 A comparison of the formulae (1) with the equations (2) of Art 12 leads to a simple physical interpretation of ϕ

Any actual state of motion of a liquid, for which a (single-valued) velocity-potential exists, could be produced instantaneously from rest by the application of a properly chosen system of impulsive pressures. This is evident from the equations cited, which shew, moreover, that $\phi = \varpi/\rho + \text{const}$, so that $\varpi = \rho\phi + C$ gives the requisite system. In the same way $\varpi = -\rho\phi + C$ gives the system of impulsive pressures which would completely stop the motion. The occurrence of an arbitrary constant in these expressions shews, what is otherwise evident, that a pressure uniform throughout a liquid mass produces no effect on this motion*.

In the case of a gas, ϕ may be interpreted as the potential of the extraneous impulsive forces by which the actual motion at any instant could be produced instantaneously from rest.

* This interpretation was given by Cauchy, *loc cit*, and by Poisson, *Mém de l'Acad. roy. des Sciences*, t 1 (1816)

A state of motion for which a velocity-potential does not exist cannot be generated or destroyed by the action of impulsive pressures, or of extraneous impulsive forces having a potential.

19 The existence of a velocity-potential indicates, besides, certain *kinematical* properties of the motion.

A 'line of motion' or 'stream-line'* is defined to be a line drawn from point to point, so that its direction is everywhere that of the motion of the fluid. The differential equations of the system of such lines are

$$\frac{dx}{u} = \frac{dy}{v} = \frac{dz}{w}. \quad \dots \dots \dots (2)$$

The relations (1) shew that when a velocity-potential exists the lines of motion are everywhere perpendicular to a system of surfaces, viz the 'equipotential' surfaces $\phi = \text{const}$

Again, if from the point (x, y, z) we draw a linear element δs in the direction (l, m, n) , the velocity resolved in this direction is $lu + mv + nw$, or

$$-\frac{\partial \phi}{\partial x} \frac{dx}{\delta s} - \frac{\partial \phi}{\partial y} \frac{dy}{\delta s} - \frac{\partial \phi}{\partial z} \frac{dz}{\delta s}, \text{ which } = -\frac{\partial \phi}{\partial s}$$

The velocity in any direction is therefore equal to the rate of decrease of ϕ in that direction

Taking δs in the direction of the normal to the surface $\phi = \text{const}$, we see that if a series of such surfaces be drawn corresponding to equidistant values of ϕ , the common difference being infinitely small, the velocity at any point will be inversely proportional to the distance between two consecutive surfaces in the neighbourhood of the point.

Hence, if any equipotential surface intersect itself, the velocity is zero at the intersection. The intersection of two *distinct* equipotential surfaces would imply an infinite velocity

20. Under the circumstances stated in Art. 17, the equations of motion are at once integrable throughout that portion of the fluid mass for which a velocity-potential exists. For in virtue of the relations

$$\frac{\partial v}{\partial z} = \frac{\partial w}{\partial y}, \quad \frac{\partial w}{\partial x} = \frac{\partial u}{\partial z}, \quad \frac{\partial u}{\partial y} = \frac{\partial v}{\partial x},$$

which are implied in (1), the equations of Art. 6 may be written

$$-\frac{\partial^2 \phi}{\partial x \partial t} + u \frac{\partial u}{\partial x} + v \frac{\partial v}{\partial x} + w \frac{\partial w}{\partial x} = -\frac{\partial \Omega}{\partial x} - \frac{1}{\rho} \frac{\partial p}{\partial x}, \quad \&c, \quad \&c.$$

* Some writers prefer to restrict the use of the term 'stream-line' to the case of steady motion, as defined in Art. 21.

These have the integral

$$\int \frac{dp}{\rho} = \frac{\partial \phi}{\partial t} - \Omega - \frac{1}{2} q^2 + F(t), \quad \dots \dots \dots (3)$$

where q denotes the resultant velocity $(u^2 + v^2 + w^2)^{\frac{1}{2}}$, and $F(t)$ is an arbitrary function of t . It is often convenient to suppose this arbitrary function to be incorporated in the value of $\partial \phi / \partial t$, this is permissible since, by (1), the values of u, v, w are not thereby affected

Our equations take a specially simple form in the case of an incompressible fluid, viz we then have

$$\frac{p}{\rho} = \frac{\partial \phi}{\partial t} - \Omega - \frac{1}{2} q^2 + F(t), \quad \dots \dots \dots (4)$$

with the equation of continuity

$$\frac{\partial^2 \phi}{\partial x^2} + \frac{\partial^2 \phi}{\partial y^2} + \frac{\partial^2 \phi}{\partial z^2} = 0, \quad \dots \dots \dots (5)$$

which is the equivalent of Art 9 (1) When, as in many cases which we shall have to consider, the boundary conditions are purely kinematical, the process of solution consists in finding a function which shall satisfy (5) and the prescribed surface-conditions The pressure p is then given by (4), and is thus far indeterminate to the extent of an additive function of t It becomes determinate when the value of p at some point of the fluid is given for all values of t

Suppose, for example, that we have a solid or solids moving through a liquid completely enclosed by fixed boundaries, and that it is possible (*e.g.* by means of a piston) to apply an arbitrary pressure at some point of the boundary Whatever variations are made in the magnitude of the force applied to the piston, the motion of the fluid and of the solids will be absolutely unaffected, the pressure at all points instantaneously rising or falling by equal amounts Physically, the origin of the paradox (such as it is) is that the fluid is treated as absolutely incompressible In actual liquids changes of pressure are propagated with very great, but not infinite, velocity.

Steady Motion

21 When at every point the velocity is constant in magnitude and direction, *i.e.* when

$$\frac{\partial u}{\partial t} = 0, \quad \frac{\partial v}{\partial t} = 0, \quad \frac{\partial w}{\partial t} = 0, \quad \dots \dots \dots (1)$$

everywhere, the motion is said to be 'steady'

In steady motion the lines of motion coincide with the paths of the particles. For if P, Q be two consecutive points on a line of motion, a particle which is at any instant at P is moving in the direction of the tangent at P , and will, therefore, after an infinitely short time arrive at Q The motion being steady, the lines of motion remain the same Hence the

direction of motion at Q is along the tangent to the same line of motion, & the particle continues to describe the line.

In steady motion the equation (3) of the last Art becomes

$$\int \frac{dp}{\rho} = -\Omega - \frac{1}{2}q^2 + \text{constant} \quad \dots \quad (2)$$

The law of variation of pressure *along a stream-line* can however in this case be found without assuming the existence of a velocity-potential. For if δs denote an element of a stream-line, the acceleration in the direction of motion is $q \partial q / \partial s$, and we have

$$q \frac{\partial q}{\partial s} = -\frac{\partial \Omega}{\partial s} - \frac{1}{\rho} \frac{\partial p}{\partial s},$$

whence, integrating along the stream-line,

$$\int \frac{dp}{\rho} = -\Omega - \frac{1}{2}q^2 + C. \quad \dots \quad (3)$$

This is similar in form to (2), but is more general in that it does not assume the existence of a velocity-potential. It must however be carefully noticed that the 'constant' of equation (2) and the 'C' of equation (3) have different meanings, the former being an absolute constant, while the latter is constant along any particular stream-line, but may vary as we pass from one stream-line to another.

22 The theorem (3) stands in close relation to the principle of energy. If this be assumed independently, the formula may be deduced as follows*. Taking first the particular case of a liquid, let us consider the portion of an infinitely narrow tube, whose boundary follows the stream-lines, included between two cross sections A and B , the direction of motion being from A to B . Let p be the pressure, q the velocity, Ω the potential of the extraneous forces, σ the area of the cross section, at A , and let the values of the same quantities at B be distinguished by accents. In each unit of time a mass $\rho q \sigma$ at A enters the portion of the tube considered, whilst an equal mass $\rho q' \sigma'$ leaves it at B . Hence $q \sigma = q' \sigma'$. Again, the work done on the mass entering at A is $p q \sigma$ per unit time, whilst the loss of work at B is $p' q' \sigma'$. The former mass brings with it the energy $\rho q \sigma (\frac{1}{2} q^2 + \Omega)$, whilst the latter carries off energy to the amount $\rho q' \sigma' (\frac{1}{2} q'^2 + \Omega')$. The motion being steady, the portion of the tube considered neither gains nor loses energy on the whole, so that

$$p q \sigma + \rho q \sigma (\frac{1}{2} q^2 + \Omega) = p' q' \sigma' + \rho q' \sigma' (\frac{1}{2} q'^2 + \Omega')$$

Dividing by $\rho q \sigma (= \rho q' \sigma')$, we have

$$\frac{p}{\rho} + \frac{1}{2} q^2 + \Omega = \frac{p'}{\rho} + \frac{1}{2} q'^2 + \Omega',$$

* This is really a reversion to the methods of Daniel Bernoulli, *Hydrodynamica*, Argentorati, 1738.

or, using C in the same sense as before,

$$\frac{p}{\rho} = -\Omega - \frac{1}{2}q^2 + C, \dots\dots\dots (4)$$

which is what the equation (3) becomes when ρ is constant

To prove the corresponding formula for compressible fluids, we remark that the fluid entering at A now brings with it, in addition to its energies of motion and position, the intrinsic energy

$$- \int p d\left(\frac{1}{\rho}\right), \quad \text{or} \quad -\frac{p}{\rho} + \int \frac{dp}{\rho},$$

per unit mass The addition of these terms to (4) gives the equation (3)

The motion of a gas is as a rule subject to the adiabatic law

$$p/p_0 = (\rho/\rho_0)^\gamma, \dots\dots\dots (5)$$

and the equation (3) then takes the form

$$\frac{\gamma}{\gamma-1} \frac{p}{\rho} = -\Omega - \frac{1}{2}q^2 + C. \dots\dots\dots (6)$$

23 The preceding equations shew that, in steady motion, and for points along any one stream-line*, the pressure is, *cæteris paribus*, greatest where the velocity is least, and *vice versa*†. This statement, though opposed to popular notions, becomes evident when we reflect that a particle passing from a place of higher to one of lower pressure must have its motion accelerated, and *vice versa*‡.

It follows that in any case to which the equations of the last Art apply there is a limit which the velocity cannot exceed‡. For instance, let us suppose that we have a liquid flowing from a reservoir where the velocity may be neglected, and the pressure is p_0 , and that we may neglect extraneous forces. We have then, in (4), $C = p_0/\rho$, and therefore

$$p = p_0 - \frac{1}{2}\rho q^2. \dots\dots\dots (7)$$

Now although it is found that a liquid from which all traces of air or other dissolved gas have been eliminated can sustain a negative pressure, or tension, of considerable magnitude§, this is not the case with fluids such as we find them under ordinary conditions. Practically, then, the equation (7) shews that q cannot exceed $(2p_0/\rho)^{\frac{1}{2}}$. This limiting velocity is of course that with which the fluid would escape from the reservoir into a vacuum. In the case of water at atmospheric pressure it is the velocity 'due to' the height of the water-barometer, or about 45 feet per second.

* This restriction is unnecessary when a velocity-potential exists

† Some interesting practical illustrations of this principle are given by Froude, *Nature*, t. xiii, 1875

‡ Cf. Helmholtz, "Ueber discontinuirliche Flüssigkeitsbewegungen," *Berl. Monatsber.*, April, 1868, *Phil. Mag.*, Nov. 1868, *Gesammelte Abhandlungen*, Leipzig, 1882-3, t. i. p. 146

§ O. Reynolds, *Manch. Mem.*, t. vi. (1877); *Scientific Papers*, Cambridge, 1900, t. i. p. 281

If in any case of fluid motion of which we have succeeded in obtaining the analytical expression, we suppose the motion to be gradually accelerated until the velocity at some point reaches the limit here indicated, a cavity will be formed there, and the conditions of the problem are more or less changed.

It will be shewn, in the next chapter (Art 44), that in irrotational motion of a liquid, whether 'steady' or not, the place of least pressure is always at some point of the boundary, provided the extraneous forces have a potential Ω satisfying the equation

$$\frac{\partial^2 \Omega}{\partial x^2} + \frac{\partial^2 \Omega}{\partial y^2} + \frac{\partial^2 \Omega}{\partial z^2} = 0.$$

This includes, of course, the case of gravity.

In the general case of a fluid in which p is a given function of ρ we have, putting $\Omega = 0$ in (3),

$$q^2 = 2 \int_p^{p_0} \frac{dp}{\rho} \dots \dots \dots (8)$$

For a gas subject to the adiabatic law, this gives

$$q^2 = \frac{2\gamma}{\gamma-1} \frac{p_0}{\rho_0} \left\{ 1 - \left(\frac{p}{p_0} \right)^{\frac{\gamma-1}{\gamma}} \right\} \dots \dots \dots (9)$$

$$= \frac{2}{\gamma-1} (c_0^2 - c^2), \dots \dots \dots (10)$$

if $c = (\gamma p / \rho)^{\frac{1}{2}} = (dp/d\rho)^{\frac{1}{2}}$, denote the velocity of sound in the gas when at pressure p and density ρ , and c_0 the corresponding velocity for gas under the conditions which obtain in the reservoir (See Chap. x.) Hence the limiting velocity is

$$\left(\frac{2}{\gamma-1} \right)^{\frac{1}{2}} \cdot c_0,$$

or, $2.214 c_0$, if $\gamma = 1.408$.

24 We conclude this chapter with a few simple applications of the equations.

Efflux of Liquids.

Let us take in the first instance the problem of the efflux of a liquid from a small orifice in the walls of a vessel which is kept filled up to a constant level, so that the motion may be regarded as steady.

The origin being taken in the upper surface, let the axis of z be vertical, and its positive direction downwards, so that $\Omega = -gz$. If we suppose the area of the upper surface large compared with that of the orifice, the velocity at the former may be neglected. Hence, determining the value of C in Art. 22 (4) so that $p = P$ (the atmospheric pressure), when $z = 0$, we have*

$$\frac{p}{\rho} = \frac{P}{\rho} + gz - \frac{1}{2} q^2 \dots \dots \dots (1)$$

* This result is due to D. Bernoulli, *l. c. ante*, p. 19.

At the surface of the issuing jet we have $p = P$, and therefore

$$q^2 = 2gz, \dots \dots \dots (2)$$

i.e. the velocity is that due to the depth below the upper surface. This is known as *Torricelli's Theorem* *.

We cannot however at once apply this result to calculate the rate of efflux of the fluid, for two reasons. In the first place, the issuing fluid must be regarded as made up of a great number of elementary streams converging from all sides towards the orifice. Its motion is not, therefore, throughout the area of the orifice, everywhere perpendicular to this area, but becomes more and more oblique as we pass from the centre to the sides. Again, the converging motion of the elementary streams must make the pressure at the orifice somewhat greater in the interior of the jet than at the surface, where it is equal to the atmospheric pressure. The velocity, therefore, in the interior of the jet will be somewhat less than that given by (2)

Experiment shews however that the converging motion above spoken of ceases at a short distance beyond the orifice, and that (in the case of a circular orifice) the jet then becomes approximately cylindrical. The ratio of the area of the section S' of the jet at this point (called the 'vena contracta') to the area S of the orifice is called the 'coefficient of contraction'. If the orifice be simply a hole in a thin wall, this coefficient is found experimentally to be about .62

The paths of the particles at the vena contracta being nearly straight, there is little or no variation of pressure as we pass from the axis to the outer surface of the jet. We may therefore assume the velocity there to be uniform throughout the section, and to have the value given by (2), where z now denotes the depth of the vena contracta below the surface of the liquid in the vessel. The rate of efflux is therefore

$$(2gz)^{\frac{1}{2}} \cdot \rho S' \dots \dots \dots (3)$$

The calculation of the form of the issuing jet presents difficulties which have only been overcome in a few ideal cases of motion in two dimensions (See Chapter IV.) It may however be shewn that the coefficient of contraction must, in general, lie between $\frac{1}{2}$ and 1. To put the argument in its simplest form, let us first take the case of liquid issuing from a vessel the pressure in which, at a distance from the orifice, exceeds that of the external space by the amount P , gravity being neglected. When the orifice is closed by a plate, the resultant pressure of the fluid on the containing vessel is of course *nil*. If when the plate is removed, we assume (for the moment) that the pressure on the walls remains sensibly equal to P , there will be an unbalanced pressure PS acting on the vessel in the direction opposite to that of

* "De motu gravium naturaliter accelerato," Firenze 1643

the jet, and tending to make it recoil. The equal and contrary reaction on the fluid produces in unit time the velocity q in the mass $\rho q S'$ flowing through the 'vena contracta,' whence

$$PS = \rho q^2 S'. \quad \dots \dots \dots (4)$$

The principle of energy gives, as in Art 22,

$$P = \frac{1}{2} \rho q^2, \dots \dots \dots (5)$$

so that, comparing, we have $S' = \frac{1}{2} S$. The formula (1) shows that the pressure on the walls, especially in the neighbourhood of the orifice, will in reality fall somewhat below the static pressure P , so that the left-hand side of (4) is an under-estimate. The ratio S'/S will therefore in general be $> \frac{1}{2}$.

In one particular case, viz where a short cylindrical tube, projecting inwards, is attached to the orifice, the assumption above made is sufficiently exact, and the consequent value $\frac{1}{2}$ for the coefficient then agrees with experiment.

The reasoning is easily modified so as to take account of gravity (or other conservative forces). We have only to substitute for P the excess of the static pressure at the level of the orifice over the pressure outside. The difference of level between the orifice and the 'vena contracta' is here neglected*.

Efflux of Gases.

25 We consider next the efflux of a gas, supposed to flow through a small orifice from a vessel in which the pressure is p_0 and density ρ_0 into a space where the pressure is p_1 . We assume that the motion has become steady, and that the expansion takes place according to the adiabatic law.

If the ratio p_0/p_1 of the pressures inside and outside the vessel do not exceed a certain limit, to be indicated presently, the flow will take place in much the same manner as in the case of a liquid, and the rate of discharge may be found by putting $p=p_1$ in Art 23 (9), and multiplying the resulting value of q by the area S' of the vena contracta. Thus gives for the rate of discharge of mass †

$$G_1 \rho_1 S' = \left(\frac{2}{\gamma - 1} \right)^{\frac{1}{2}} c_0 \rho_0 \left\{ \left(\frac{p_1}{p_0} \right)^{\frac{2}{\gamma}} - \left(\frac{p_1}{p_0} \right)^{\frac{\gamma+1}{\gamma}} \right\}^{\frac{1}{2}} S' \dots \dots \dots (1)$$

It is plain, however, that there must be a limit to the applicability of this result; for otherwise we should be led to the paradoxical conclusion that when $p_1 = 0$, i.e. the discharge is into a vacuum, the flux of matter is *nil*. The elucidation of this point is due to

* The above theory is due to Borda (*Mém de l'Acad des Sciences*, 1766), who also made experiments with the special form of mouth-piece referred to, and found $S/S' = 1.942$. It was re-discovered by Hanlon, *Proc. Lond Math Soc*, t. iii. p. 4 (1869); the question is further elucidated in a note appended to this paper by Maxwell. See also Froude and J. Thomson, *Proc. Glasgow Phil Soc.*, t. x (1876).

† A result equivalent to this was given by Saint Venant and Wantzel, *Journ. de l'École Polyt.*, t. xvi. p. 92 (1839).

Prof. Osborne Reynolds*. It is easily found by means of Art 23 (8), that $q\rho$ is a maximum, *i.e.* the section of an elementary stream is a minimum, when $q^2 = dp/d\rho$, that is, the velocity of the stream is equal to the velocity of sound in gas of the pressure and density which prevail there. On the adiabatic hypothesis this gives, by Art 23 (10),

$$\frac{c}{c_0} = \left(\frac{2}{\gamma+1} \right)^{\frac{1}{2}}, \quad \dots \quad \dots \quad \dots \quad (2)$$

and therefore, since $c^2 \propto \rho^{\gamma-1}$,

$$\frac{\rho}{\rho_0} = \left(\frac{2}{\gamma+1} \right)^{\frac{1}{\gamma-1}}, \quad \frac{p}{p_0} = \left(\frac{2}{\gamma+1} \right)^{\frac{\gamma}{\gamma-1}}, \quad \dots \quad \dots \quad \dots \quad (3)$$

or, if $\gamma = 1.408$,

$$\rho = 634\rho_0, \quad p = 527p_0 \quad \dots \quad \dots \quad \dots \quad (4)$$

If p_1 be less than this value, the stream after passing the point in question widens out again, until it is lost at a distance in the eddies due to viscosity. The minimum sections of the elementary streams will be situated in the neighbourhood of the orifice, and their sum S may be called the virtual area of the latter. The velocity of efflux, as found from (2), is

$$q = 911c_0$$

The rate of discharge is then $= q\rho S$, where q and ρ have the values just found, and is therefore approximately independent of the external pressure p_1 so long as this falls below $527p_0$. The physical reason of this is (as pointed out by Reynolds) that, so long as the velocity at any point exceeds the velocity of sound under the conditions which obtain there, no change of pressure can be propagated backwards beyond this point so as to affect the motion higher up the stream.

These conclusions appear to be in good agreement with experimental results.

Under similar circumstances as to pressure, the velocities of efflux of different gases are (so far as γ can be assumed to have the same value for each) proportional to the corresponding velocities of sound. Hence (as we shall see in Chap. x) the velocity of efflux will vary inversely, and the rate of discharge of mass will vary directly, as the square root of the density†

Rotating Liquid.

26 Let us next take the case of a mass of liquid rotating, under the action of gravity only, with constant and uniform angular velocity ω about the axis of z , supposed drawn vertically upwards.

By hypothesis,

$$\begin{aligned} u, v, w &= -\omega y, \omega x, 0, \\ X, Y, Z &= 0, 0, -g. \end{aligned}$$

The equation of continuity is satisfied identically, and the dynamical equations obviously are

$$-\omega^2 x = -\frac{1}{\rho} \frac{\partial p}{\partial x}, \quad -\omega^2 y = -\frac{1}{\rho} \frac{\partial p}{\partial y}, \quad 0 = -\frac{1}{\rho} \frac{\partial p}{\partial z} - g \quad \dots (1)$$

* "On the Flow of Gases," *Proc Manch. Lit and Phil Soc.*, Nov. 17, 1885, *Phil Mag.*, March, 1886. A similar explanation was given by Hugoniot, *Comptes Rendus*, June 28, July 26, and Dec 13, 1886. I have attempted, above, to condense the reasoning of these writers

† Cf Graham, *Phil Trans.*, 1846.

These have the common integral

$$\frac{p}{\rho} = \frac{1}{2}\omega^2(x^2 + y^2) - gz + \text{const.} \dots \dots \dots (2)$$

The free surface, $p = \text{const.}$, is therefore a paraboloid of revolution about the axis of z , having its concavity upwards, and its latus rectum $= 2g/\omega^2$.

Since
$$\frac{\partial v}{\partial x} - \frac{\partial u}{\partial y} = 2\omega,$$

a velocity-potential does not exist. A motion of this kind could not therefore be generated in a 'perfect' fluid, *i.e.* in one unable to sustain tangential stress.

27. Instead of supposing the angular velocity ω to be uniform, let us suppose it to be a function of the distance r from the axis, and let us inquire what form must be assigned to this function in order that a velocity-potential may exist for the motion. We find

$$\frac{\partial v}{\partial x} - \frac{\partial u}{\partial y} = 2\omega + r \frac{d\omega}{dr},$$

and in order that this may vanish we must have $\omega r^2 = \mu$, a constant. The velocity at any point is then $= \mu/r$, so that the equation (2) of Art 21 becomes

$$\frac{p}{\rho} = \text{const} - \frac{1}{2} \frac{\mu^2}{r^2}, \dots \dots \dots (1)$$

if no extraneous forces act. To find the value of ϕ we have, using polar co-ordinates,

$$\frac{\partial \phi}{\partial r} = 0, \quad \frac{\partial \phi}{r \partial \theta} = -\frac{\mu}{r},$$

whence
$$\phi = -\mu \theta + \text{const} = -\mu \tan^{-1} \frac{y}{x} + \text{const} \dots \dots \dots (2)$$

We have here an instance of a 'cyclic' function. A function is said to be 'single-valued' throughout any region of space when we can assign to every point of that region a definite value of the function in such a way that these values shall form a continuous system. This is not possible with the function (2); for the value of ϕ , if it vary continuously, changes by $-2\pi\mu$ as the point to which it refers describes a complete circuit round the origin. The general theory of cyclic velocity-potentials will be given in the next chapter.

If gravity act, and if the axis of z be drawn vertically upwards, we must add to (1) the term $-gz$. The form of the free surface is therefore that generated by the revolution of the hyperbolic curve $x^2z = \text{const.}$ about the axis of z .

By properly fitting together the two preceding solutions we obtain the case of Rankine's 'combined vortex.' Thus the motion being everywhere in


coaxial circles, let us suppose the velocity to be equal to ωr from $r=0$ to $r=a$, and to $\omega a^2/r$ for $r>a$. The corresponding forms of the free surface are then given by

$$z = \frac{\omega^2}{2g} (r^2 - a^2) + C,$$

and

$$z = \frac{\omega^2}{2g} \left(a^2 - \frac{a^4}{r^2} \right) + C,$$

these being continuous when $r=a$. The depth of the central depression below the general level of the surface is therefore $\omega^2 a^2/g$.



28. To illustrate, by way of contrast, the case of extraneous forces not having a potential, let us suppose that a mass of liquid filling a right circular cylinder moves from rest under the action of the forces

$$X = Ax + By, \quad Y = B'x + Cy, \quad Z = 0,$$

the axis of z being that of the cylinder

If we assume $u = -\omega y$, $v = \omega x$, $w = 0$, where ω is a function of t only, these values satisfy the equation of continuity and the boundary conditions. The dynamical equations are evidently

$$\left. \begin{aligned} -y \frac{d\omega}{dt} - \omega^2 x &= Ax + By - \frac{1}{\rho} \frac{\partial p}{\partial x}, \\ x \frac{d\omega}{dt} - \omega^2 y &= B'x + Cy - \frac{1}{\rho} \frac{\partial p}{\partial y} \end{aligned} \right\} \dots \dots \dots (1)$$

Differentiating the first of these with respect to y , and the second with respect to x and subtracting, we eliminate p , and find

$$\frac{d\omega}{dt} = \frac{1}{2} (B' - B) \dots \dots \dots (2)$$

The fluid therefore rotates as a whole about the axis of z with constantly accelerated angular velocity, except in the particular case when $B=B'$. To find p , we substitute the value of $d\omega/dt$ in (1) and integrate; we thus get

$$\frac{p}{\rho} = \frac{1}{2} \omega^2 (x^2 + y^2) + \frac{1}{2} (Ax^2 + 2\beta xy + Cy^2) + \text{const.},$$

where $2\beta = B + B'$.

29 As a final example, we will take one suggested by the theory of 'electro-magnetic rotations'

If an electric current be made to pass radially from an axial wire, through a conducting liquid, to the walls of a metallic containing cylinder, in a uniform magnetic field, the extraneous forces will be of the type*

$$X, Y, Z = -\frac{\mu y}{r^2}, \frac{\mu x}{r^2}, 0$$

Assuming $u = -\omega y$, $v = \omega x$, $w = 0$, where ω is a function of r and t only, we have

$$\left. \begin{aligned} -y \frac{\partial \omega}{\partial t} - \omega^2 x &= -\frac{\mu y}{r^2} - \frac{1}{\rho} \frac{\partial p}{\partial x}, \\ x \frac{\partial \omega}{\partial t} - \omega^2 y &= \frac{\mu x}{r^2} - \frac{1}{\rho} \frac{\partial p}{\partial y} \end{aligned} \right\} \dots \dots \dots (1)$$

Eliminating p , we obtain

$$2 \frac{\partial \omega}{\partial t} + r \frac{\partial^2 \omega}{\partial r^2} = 0.$$

The solution of this is

$$\omega = F'(t)/r^2 + f(r),$$

where F' and f denote arbitrary functions. Since $\omega = 0$ when $t = 0$, we have

$$F'(0)/r^2 + f(r) = 0,$$

and therefore

$$\omega = -\frac{F'(t) - F'(0)}{r^2} = \frac{\lambda}{r^2}, \dots \dots \dots (2)$$

where λ is a function of t which vanishes for $t = 0$. Substituting in (1), and integrating, we find

$$\frac{p}{\rho} = \left(\mu - \frac{d\lambda}{dt} \right) \tan^{-1} \frac{y}{x} - \frac{1}{2} \omega^2 r^2 + \chi(t)$$

Since p is essentially a single-valued function, we must have $d\lambda/dt = \mu$, or $\lambda = \mu t$. Hence the fluid rotates with an angular velocity which varies inversely as the square of the distance from the axis, and increases constantly with the time

* If C denote the total flux of electricity outwards, per unit length of the axis, and γ the component of the magnetic force parallel to the axis, we have $\mu = \gamma C / 2\pi\rho$. For the history of such experiments see Winkelmann, *Handbuch d. Physik*, t. iii (2), p. 315. The above case is specially simple, in that the forces X, Y, Z , have a potential ($\Omega = -\mu \tan^{-1} y/x$), though a 'cyclic' one. As a rule, in electro-magnetic rotations, the mechanical forces X, Y, Z have not a potential at all.

CHAPTER III.

IRROTATIONAL MOTION

30. THE present chapter is devoted mainly to an exposition of some general theorems relating to the kinds of motion already considered in Arts. 17—20, viz. those in which $u dx + v dy + w dz$ is an exact differential throughout a finite mass of fluid. It is convenient to begin with the following analysis, due to Stokes*, of the motion of a fluid element in the most general case.

The component velocities at the point (x, y, z) being u, v, w , the relative velocities at an infinitely near point $(x + \delta x, y + \delta y, z + \delta z)$ are

$$\left. \begin{aligned} \delta u &= \frac{\partial u}{\partial x} \delta x + \frac{\partial u}{\partial y} \delta y + \frac{\partial u}{\partial z} \delta z, \\ \delta v &= \frac{\partial v}{\partial x} \delta x + \frac{\partial v}{\partial y} \delta y + \frac{\partial v}{\partial z} \delta z, \\ \delta w &= \frac{\partial w}{\partial x} \delta x + \frac{\partial w}{\partial y} \delta y + \frac{\partial w}{\partial z} \delta z \end{aligned} \right\} \dots \dots \dots (1)$$

If we write $a = \frac{\partial u}{\partial x}, \quad b = \frac{\partial v}{\partial y}, \quad c = \frac{\partial w}{\partial z},$

$$f = \frac{1}{2} \left(\frac{\partial w}{\partial y} + \frac{\partial v}{\partial z} \right), \quad g = \frac{1}{2} \left(\frac{\partial u}{\partial z} + \frac{\partial w}{\partial x} \right), \quad h = \frac{1}{2} \left(\frac{\partial v}{\partial x} + \frac{\partial u}{\partial y} \right),$$

$$\xi = \frac{1}{2} \left(\frac{\partial w}{\partial y} - \frac{\partial v}{\partial z} \right), \quad \eta = \frac{1}{2} \left(\frac{\partial u}{\partial z} - \frac{\partial w}{\partial x} \right), \quad \zeta = \frac{1}{2} \left(\frac{\partial v}{\partial x} - \frac{\partial u}{\partial y} \right),$$

equations (1) may be written

$$\left. \begin{aligned} \delta u &= a \delta x + h \delta y + g \delta z + \eta \delta z - \xi \delta y, \\ \delta v &= h \delta x + b \delta y + f \delta z + \xi \delta x - \zeta \delta z, \\ \delta w &= g \delta x + f \delta y + c \delta z + \xi \delta y - \eta \delta x. \end{aligned} \right\} \dots \dots \dots (2)$$

Hence the motion of a small element having the point (x, y, z) for its centre may be conceived as made up of three parts

* "On the Theories of the Internal Friction of Fluids in Motion, &c." *Camb. Phil. Trans.*, t viii (1845), *Math. and Phys. Papers*, t 1 p. 80.

The first part, whose components are u, v, w , is a motion of *translation* of the element as a whole.

The second part, expressed by the first three terms on the right-hand sides of the equations (2), is a motion such that, if $\delta x, \delta y, \delta z$ be regarded as current co-ordinates, every point is moving in the direction of the normal to that quadric of the system

$$a(\delta x)^2 + b(\delta y)^2 + c(\delta z)^2 + 2f\delta y\delta z + 2g\delta z\delta x + 2h\delta x\delta y = \text{const}, \dots (3)$$

on which it lies. If we refer these quadrics to their principal axes, the corresponding parts of the velocities parallel to these axes will be

$$\delta u' = a'\delta x', \quad \delta v' = b'\delta y', \quad \delta w' = c'\delta z', \quad \dots \dots \dots (4)$$

if

$$a'(\delta x')^2 + b'(\delta y')^2 + c'(\delta z')^2 = \text{const}$$

is what (3) becomes by the transformation. The formulae (4) express that the length of every line in the element parallel to x' is being elongated at the (positive or negative) rate a' , whilst lines parallel to y' and z' are being elongated in like manner at the rates b' and c' respectively. Such a motion is called one of *pure strain* and the principal axes of the quadrics (3) are called the axes of the strain.

The last two terms on the right-hand sides of the equations (2) express a *rotation* of the element as a whole about an instantaneous axis; the component angular velocities of the rotation being ξ, η, ζ^* .


This analysis may be illustrated by the so-called ‘laminar’ motion of a liquid in which

$$u = 2\mu y, \quad v = 0, \quad w = 0,$$

so that

$$a, b, c, f, g, \xi, \eta = 0, \quad h = \mu, \quad \zeta = -\mu$$

If A represent a rectangular fluid element bounded by planes parallel to the co-ordinate planes, then B represents the change produced in this in a short time by the strain, and C that due to the strain *plus* the rotation.



It is easily seen that the above resolution of the motion is unique. If we assume that the motion relative to the point (x, y, z) can be made up of a strain and a rotation in which the axes and coefficients of the strain and the

* The quantities corresponding to ξ, η, ζ in the theory of the infinitely small *displacements* of a continuous medium had been interpreted by Cauchy as expressing the ‘mean rotations’ of an element, *Exercices d’Analyse et de Physique*, t. II. (Paris, 1841), p. 302.

axis and angular velocity of the rotation are arbitrary, then calculating the relative velocities $\delta u, \delta v, \delta w$, we get expressions similar to those on the right-hand sides of (2), but with arbitrary values of $a, b, c, f, g, h, \xi, \eta, \zeta$. Equating coefficients of $\delta x, \delta y, \delta z$, however, we find that a, b, c , &c. must have respectively the same values as before. Hence the directions of the axes of the strain, the rates of extension or contraction along them, and the axis and the angular velocity of rotation, at any point of the fluid, depend only on the state of relative motion at that point, and not on the position of the axes of reference.

When throughout a finite portion of a fluid mass we have ξ, η, ζ all zero, the relative motion of any element of that portion consists of a pure strain only, and is called 'irrotational.'

31 The value of the integral

$$\int (u dx + v dy + w dz),$$

or

$$\int \left(u \frac{dx}{ds} + v \frac{dy}{ds} + w \frac{dz}{ds} \right) ds,$$

taken along any line $ABCD$, is called* the 'flow' of the fluid from A to D along that line. We shall denote it for shortness by $I(ABCD)$


If A and D coincide, so that the line forms a closed curve, or circuit, the value of the integral is called the 'circulation' in that circuit. We denote it by $I(ABCA)$. If in either case the integration be taken in the opposite direction, the signs of $dx/ds, dy/ds, dz/ds$ will be reversed, so that we have

$$I(AD) = -I(DA), \text{ and } I(ABCA) = -I(ACBA)$$

It is also plain that

$$I(ABCD) = I(AB) + I(BC) + I(CD)$$

Again, any surface may be divided, by a double series of lines crossing it, into infinitely small elements. The sum of the circulations round the boundaries of these elements, taken all in the same sense, is equal to the circulation round the original boundary of the surface (supposed for the moment to consist of a single closed curve). For, in the sum in question, the flow along each side common to two elements comes in twice, once for each element, but with opposite signs, and therefore disappears from the result. There remain then only the flows along those sides which are parts of the original boundary; whence the truth of the above statement




From this it follows, by considerations of continuity, that the circulation

* Sir W. Thomson, "On Vortex Motion" *Edin Trans*, t xxv (1869)

round the boundary of any surface-element δS , having a given position and aspect, is ultimately proportional to the area of the element

If the element be a rectangle $\delta y \delta z$ having its centre at the point (x, y, z) , then calculating the circulation round it in the direction shewn by the arrows in the annexed figure, we have



$$\begin{aligned} I(AB) &= \{v - \tfrac{1}{2}(\partial v / \partial z) \delta z\} \delta y, & I(BC) &= \{w + \tfrac{1}{2}(\partial w / \partial y) \delta y\} \delta z, \\ I(CD) &= -\{v + \tfrac{1}{2}(\partial v / \partial z) \delta z\} \delta y, & I(DA) &= -\{w - \tfrac{1}{2}(\partial w / \partial y) \delta y\} \delta z, \end{aligned}$$

and therefore

$$I(ABCD A) = \left(\frac{\partial w}{\partial y} - \frac{\partial v}{\partial z}\right) \delta y \delta z$$

In this way we infer that the circulations round the boundaries of any infinitely small areas $\delta S_1, \delta S_2, \delta S_3$, having their planes parallel to the co-ordinate planes, are

$$2\xi \delta S_1, \quad 2\eta \delta S_2, \quad 2\zeta \delta S_3, \dots \dots \dots (1)$$

respectively.

Again, referring to the figure and the notations of Art. 2, we have

$$\begin{aligned} I(ABCA) &= I(PBCP) + I(PCAP) + I(PABP) \\ &= 2\xi . l\Delta + 2\eta . m\Delta + 2\zeta . n\Delta, \end{aligned}$$

whence we infer that the circulation round the boundary of *any* infinitely small area δS is

$$2(l\xi + m\eta + n\zeta) \delta S \dots \dots \dots (2)$$

We have here an independent proof that the quantities ξ, η, ζ may be regarded as the components of a vector.

It will be observed that some convention is implied as to the relation between the sense in which the circulation round the boundary of δS is estimated, and the sense of the normal (l, m, n) . In order to have a clear understanding on this point, we shall suppose in this book that the axes of

co-ordinates form a *right-handed* system; thus if the axes of x and y point E. and N. respectively, that of z will point vertically upwards*. The sense in which the circulation, as given by (2) is estimated, is then related to the direction of the normal (l, m, n) in the manner typified by a right-handed screw†.

A distinction is now generally recognized between two classes of vectors. If we transform to another system of rectangular axes Ox', Oy', Oz' whose positions are indicated in the usual manner by the annexed scheme of direction-cosines, we have

$$\begin{array}{c|ccc} & x & y & z \\ \hline x' & l_1, m_1, n_1, \\ y' & l_2, m_2, n_2, \\ z' & l_3, m_3, n_3 \end{array} \quad \left. \begin{array}{l} u' = l_1 u + m_1 v + n_1 w, \\ v' = l_2 u + m_2 v + n_2 w, \\ w' = l_3 u + m_3 v + n_3 w, \end{array} \right\} \quad \dots \quad (3)$$

in all cases. On the other hand we find

$$\left. \begin{array}{l} \xi' = \pm (l_1 \xi + m_1 \eta + n_1 \zeta), \\ \eta' = \pm (l_2 \xi + m_2 \eta + n_2 \zeta), \\ \zeta' = \pm (l_3 \xi + m_3 \eta + n_3 \zeta), \end{array} \right\} \quad \dots \quad (4)$$

where the upper or lower signs are to be taken according as the two systems of axes are congruent or not‡. A vector which, like the velocity (u, v, w) , is transformed by formulae of the type (3) is called 'polar', whilst one which, like (ξ, η, ζ) , is transformed by (4) is distinguished as 'axial'§.

32 Expressing now that the circulation round the edge of any finite surface is equal to the sum of the circulations round the boundaries of the infinitely small elements into which the surface may be divided, we have, by (2),

$$\int (u dx + v dy + w dz) = 2 \iint (l \xi + m \eta + n \zeta) dS, \dots \dots \dots (5)$$

or, substituting the values of ξ, η, ζ from Art. 30,

$$\int (u dx + v dy + w dz) = \iiint \left\{ l \left(\frac{\partial w}{\partial y} - \frac{\partial v}{\partial z} \right) + m \left(\frac{\partial u}{\partial z} - \frac{\partial w}{\partial x} \right) + n \left(\frac{\partial v}{\partial x} - \frac{\partial u}{\partial y} \right) \right\} dS, \dots (6)$$

where the single-integral is taken along the bounding curve, and the double-integral over the surface||. In these formulae the quantities l, m, n are the direction-cosines of the normal drawn always on one side of the surface,

* Maxwell, *Proc Lond Math. Soc*, t. III. pp. 279, 280. Thus in the fig. of p 31 the axis of z is supposed drawn towards the reader.

† See Maxwell, *Electricity and Magnetism*, Oxford, 1873, Art 23


‡ Two right-handed systems, or two left-handed systems are 'congruent,' whilst a right-handed and a left-handed system are not

§ For references see M Abraham, "Geometrische Grundbegriffe d Mechanik deformirbarer Körper," *Encyclopaedie d math Wissenschaften*, t IV (Leipzig, 1901)

|| This theorem is due to Stokes, *Smith's Prize Examination Papers* for 1854. The first published proof appears to have been given by Hankel, *Zur allgem. Theorie der Bewegung der Flüssigkeiten*, Göttingen, 1861, p 35. That given above is due to Lord Kelvin, *l c. ante*, p. 30. See also Thomson and Tait, *Natural Philosophy*, Art 190 (j), and Maxwell, *Electricity and Magnetism*, Art 24

which we may term the positive side; the direction of integration in the first member is then that in which a man walking on the surface, on the positive side of it, and close to the edge, must proceed so as to have the surface always on his left hand.

The theorem (5) or (6) may evidently be extended to a surface whose boundary consists of two or more closed curves, provided the integration in the first member be taken round each of these in the proper direction, according to the rule just given. Thus, if the surface integral in (6) extend over the shaded portion of the annexed figure, the directions in which the circulations in the several parts of the boundary are to be taken are shewn by the arrows, the positive side of the surface being that which faces the reader.



The value of the surface-integral taken over a closed surface is zero

It should be noticed that (6) is a theorem of pure mathematics, and is true whatever functions u, v, w may be of x, y, z , provided only they be continuous and differentiable at all points of the surface*.

33 The rest of this chapter is devoted to a study of the kinematical properties of irrotational motion in general, as defined by the equations

$$\xi, \eta, \zeta = 0, \quad \dots \dots \dots (1)$$

i.e. the circulation in every *infinitely small* circuit is assumed to be zero. The existence and properties of the velocity-potential in the various cases that may arise will appear as consequences of this definition.

The physical importance of the subject rests on the fact that if the motion of any portion of a fluid mass be irrotational at any one instant it will under certain very general conditions continue to be irrotational. Practically, as will be seen, this has already been established by Lagrange's theorem, proved in Art 17, but the importance of the matter warrants a repetition of the investigation, in the Eulerian notation, in the form given by Lord Kelvin†

Consider first any terminated line AB drawn in the fluid, and suppose every point of this line to move always with the velocity of the fluid at that point. Let us calculate the rate at which the flow along this line, from A to B , is increasing. If $\delta x, \delta y, \delta z$ be the projections on the co-ordinate axes of an element of the line, we have

$$\frac{D}{Dt}(u\delta x) = \frac{Du}{Dt}\delta x + u\frac{D\delta x}{Dt}$$

* It is not necessary that their differential coefficients should be continuous.

† *l.c. ante*, p 30

Now $D\delta x/Dt$, the rate at which δx is increasing in consequence of the motion of the fluid, is equal to the difference of the velocities parallel to x at its two ends, *i.e.* to δu ; and the value of Du/Dt is given in Art. 6. Hence, and by similar considerations, we find, if ρ be a function of p only, and if the extraneous forces X, Y, Z have a potential Ω ,

$$\frac{D}{Dt}(u\delta x + v\delta y + w\delta z) = -\frac{\delta p}{\rho} - \delta\Omega + u\delta u + v\delta v + w\delta w$$

Integrating along the line, from A to B , we get

$$\frac{D}{Dt} \int_A^B (u\delta x + v\delta y + w\delta z) = \left[-\int \frac{dp}{\rho} - \Omega + \frac{1}{2}q^2 \right]_A^B, \quad \dots \dots (2)$$

or, the rate at which the flow from A to B is increasing is equal to the excess of the value which $-\int dp/\rho - \Omega + \frac{1}{2}q^2$ has at B over that which it has at A . This theorem comprehends the whole of the dynamics of a perfect fluid. For instance, equations (2) of Art 15 may be derived from it by taking as the line AB the infinitely short line whose projections were originally $\delta\alpha, \delta b, \delta c$, and equating separately to zero the coefficients of these infinitesimals

If Ω be single-valued, the expression within brackets on the right-hand side of (2) is a single-valued function of x, y, z . Hence if the integration on the left-hand be taken round a closed curve, so that B coincides with A , we have

$$\frac{D}{Dt} \int (u\delta x + v\delta y + w\delta z) = 0, \quad \dots \dots (3)$$

or, the circulation in any circuit moving with the fluid does not alter with the time

It follows that if the motion of any portion of a fluid mass be initially irrotational it will always retain this property, for otherwise the circulation in every infinitely small circuit would not continue to be zero, as it is initially by virtue of Art. 32 (5)

34. Considering now any region occupied by irrotationally-moving fluid, we see from Art. 32 (5) that the circulation is zero in every circuit which can be filled up by a continuous surface lying wholly in the region, or which in other words is capable of being contracted to a point without passing out of the region. Such a circuit is said to be 'reducible'

Again, let us consider two paths ACB, ADB , connecting two points A, B of the region, and such that either may by continuous variation be made to coincide with the other, without ever passing out of the region. Such paths are called 'mutually reconcilable'. Since the circuit $ACBDA$ is reducible, we have $I(ACBDA) = 0$, or since $I(BDA) = -I(ADB)$,

$$I(ACB) = I(ADB),$$

i.e. the flow is the same along any two reconcilable paths

A region such that *all* paths joining any two points of it are mutually reconcilable is said to be 'simply-connected'. Such a region is that enclosed within a sphere, or that included between two concentric spheres. In what follows, as far as Art 46, we contemplate only simply-connected regions.

35 The irrotational motion of a fluid within a simply-connected region is characterized by the existence of a single-valued velocity-potential. Let us denote by $-\phi$ the flow to a variable point P from some fixed point A , viz

$$\phi = - \int_A^P (u dx + v dy + w dz). \quad \dots \dots \dots (1)$$

The value of ϕ has been shewn to be independent of the path along which the integration is effected, provided it lie wholly within the region. Hence ϕ is a single-valued function of the position of P , let us suppose it expressed in terms of the co-ordinates (x, y, z) of that point. By displacing P through an infinitely short space parallel to each of the axes of co-ordinates in succession, we find

$$u = - \frac{\partial \phi}{\partial x}, \quad v = - \frac{\partial \phi}{\partial y}, \quad w = - \frac{\partial \phi}{\partial z}, \quad \dots \dots \dots (2)$$

i.e. ϕ is a velocity-potential, according to the definition of Art 17.

The substitution of any other point B for A , as the lower limit of the integral in (1), simply adds an arbitrary constant to the value of ϕ , viz the flow from A to B . The original definition of ϕ in Art 17, and the physical interpretation in Art 18, alike leave the function indeterminate to the extent of an additive constant.

As we follow the course of any line of motion the value of ϕ continually decreases, hence in a simply-connected region the lines of motion cannot form closed curves.

36. The function ϕ with which we have here to do is, together with its first differential coefficients, by the nature of the case, finite, continuous, and single-valued at all points of the region considered. In the case of incompressible fluids, which we now proceed to consider more particularly, ϕ must also satisfy the equation of continuity, (5) of Art 20, or as we shall in future write it, for shortness,

$$\nabla^2 \phi = 0, \quad \dots \dots \dots (1)$$

at every point of the region. Hence ϕ is now subject to mathematical conditions identical with those satisfied by the potential of masses attracting or repelling according to the law of the inverse square of the distance, at all points external to such masses, so that many of the results proved in the theories of Attractions, Electrostatics, Magnetism, and the Steady Flow of Heat, have also a hydrodynamical application. We proceed to develop those which are most important from this point of view.

In any case of motion of an incompressible fluid the surface-integral of the normal velocity taken over any surface, open or closed, is conveniently called the 'flux' across that surface. It is of course equal to the volume of fluid crossing the surface per unit time.

When the motion is irrotational, the flux is given by

$$-\iint \frac{\partial \phi}{\partial n} dS,$$

where δS is an element of the surface, and δn an element of the normal to it, drawn in the proper direction. In any region occupied wholly by liquid, the total flux across the boundary is zero, *i.e.*

$$\iint \frac{\partial \phi}{\partial n} dS = 0, \quad \dots \dots \dots (2)$$

the element δn of the normal being drawn always on one side (say inwards), and the integration extending over the whole boundary. This may be regarded as a generalized form of the equation of continuity (1).

The lines of motion drawn through the various points of an infinitesimal circuit define a tube, which may be called a tube of flow. The product of the velocity (q) into the cross-section (σ , say) is the same at all points of such a tube.

We may, if we choose, regard the whole space occupied by the fluid as made up of tubes of flow, and suppose the size of the tubes so adjusted that the product $q\sigma$ is the same for each. The flux across any surface is then proportional to the number of tubes which cross it. If the surface be closed, the equation (2) expresses the fact that as many tubes cross the surface inwards as outwards. Hence a line of motion cannot begin or end at a point of the fluid.

37. The function ϕ cannot be a maximum or minimum at a point in the interior of the fluid. for, if it were, we should have $\partial \phi / \partial n$ everywhere positive, or everywhere negative, over a small closed surface surrounding the point in question. Either of these suppositions is inconsistent with (2).

Further, the square of the velocity cannot be a *maximum* at a point in the interior of the fluid. For let the axis of x be taken parallel to the direction of the velocity at any point P . The equation (1), and therefore also the equation (2), is satisfied if we write $\partial \phi / \partial x$ for ϕ . The above argument then shews that $\partial \phi / \partial x$ cannot be a maximum or a minimum at P . Hence there must be points in the immediate neighbourhood of P at which $(\partial \phi / \partial x)^2$ and therefore *a fortiori*

$$\left(\frac{\partial \phi}{\partial x}\right)^2 + \left(\frac{\partial \phi}{\partial y}\right)^2 + \left(\frac{\partial \phi}{\partial z}\right)^2$$

is greater than the square of the velocity at P^* .

* This theorem was enunciated, in another connection, by Lord Kelvin, *Phil Mag*, Oct.

On the other hand, the square of the velocity may be a *minimum* at some point of the fluid. The simplest case is that of a *zero* velocity; see, for example, the figure of Art 69, below

38. Let us apply (2) to the boundary of a finite spherical portion of the liquid. If r denote the distance of any point from the centre of the sphere, $\delta\omega$ the elementary solid angle subtended at the centre by an element δS of the surface, we have

$$\partial\phi/\partial n = -\partial\phi/\partial r,$$

and $\delta S = r^2\delta\omega$. Omitting the factor r^2 , (2) becomes

$$\iint \frac{\partial\phi}{\partial r} d\omega = 0,$$

or

$$\frac{\partial}{\partial r} \iint \phi d\omega = 0. \quad \dots \dots \dots (3)$$

Since $1/4\pi \cdot \iint \phi d\omega$ or $1/4\pi r^2 \iint \phi dS$ measures the mean value of ϕ over the surface of the sphere, (3) shews that this mean value is independent of the radius. It is therefore the same for any sphere, concentric with the former one, which can be made to coincide with it by gradual variation of the radius, without ever passing out of the region occupied by the irrotationally moving liquid. We may therefore suppose the sphere contracted to a point, and so obtain a simple proof of the theorem, first given by Gauss in his memoir* on the theory of Attractions, that the mean value of ϕ over any spherical surface throughout the interior of which (1) is satisfied, is equal to its value at the centre

The theorem, proved in Art 37, that ϕ cannot be a maximum or a minimum at a point in the interior of the fluid, is an obvious consequence of the above

The above proof appears to be due, in principle, to Frost†. Another demonstration, somewhat different in form, has been given by Lord Rayleigh‡. The equation (1), being linear, will be satisfied by the arithmetic mean of any number of separate solutions $\phi_1, \phi_2, \phi_3, \dots$. Let us suppose an infinite number of systems of rectangular axes to be arranged uniformly about any point P as origin, and let $\phi_1, \phi_2, \phi_3, \dots$ be the velocity-potentials of motions which are the same with respect to these systems as the original motion ϕ is with

1850 [*Reprint of Papers on Electrostatics, &c*, London, 1872, Art 665] The above demonstration is due to Kirchhoff, *Vorlesungen über mathematische Physik, Mechanik*, Leipzig, 1876, p. 186. For another proof see Art 44 below

* "Allgemeine Lehrsätze, u s w," *Resultate aus den Beobachtungen des magnetischen Vereins*, 1839 [*Werke*, Göttingen, 1870-80, t. v p 199]

† *Quarterly Journal of Mathematics*, t. xii (1873)

‡ *Messenger of Mathematics*, t. vii p 69 (1878); *Sc. Papers*, t. i. p. 347.

respect to the system x, y, z . In this case the arithmetic mean ($\bar{\phi}$, say) of the functions $\phi_1, \phi_2, \phi_3, \dots$ will be a function of r , the distance from P , only. Expressing that in the motion (if any) represented by $\bar{\phi}$, the flux across any spherical surface which can be contracted to a point, without passing out of the region occupied by the fluid, would be zero, we have

$$4\pi r^2 \frac{\partial \bar{\phi}}{\partial r} = 0,$$

or $\bar{\phi} = \text{const}$

39 Again, let us suppose that the region occupied by the irrotationally moving fluid is ‘periphractic,’* *i.e.* that it is limited internally by one or more closed surfaces, and let us apply (2) to the space included between one (or more) of these internal boundaries, and a spherical surface completely enclosing it (or them) and lying wholly in the fluid. If M denote the total flux into this region, across the internal boundary, we find, with the same notation as before,

$$\iint \frac{\partial \phi}{\partial r} dS = -M,$$

the surface-integral extending over the sphere only. This may be written

$$\frac{1}{4\pi} \frac{\partial}{\partial r} \iint \phi d\omega = -\frac{M}{4\pi r^2},$$

whence

$$\frac{1}{4\pi r^2} \iint \phi dS = \frac{1}{4\pi} \iint \phi d\omega = \frac{M}{4\pi r} + C \quad \dots \dots \dots (4)$$

That is, the mean value of ϕ over any spherical surface drawn under the above-mentioned conditions is equal to $M/4\pi r + C$, where r is the radius, M an absolute constant, and C a quantity which is independent of the radius but may vary with the position of the centre†

If however the original region throughout which the irrotational motion holds be unlimited externally, and if the first derivative (and therefore all the higher derivatives) of ϕ vanish at infinity, then C is the same for *all* spherical surfaces enclosing the whole of the internal boundaries. For if such a sphere be displaced parallel to x^\dagger , without alteration of size, the rate at which C varies in consequence of this displacement is, by (4), equal to the mean value of $\partial\phi/\partial x$ over the surface. Since $\partial\phi/\partial x$ vanishes at infinity, we can by taking the sphere large enough make the latter mean value as small as we please.

* See Maxwell, *Electricity and Magnetism*, Arts. 18, 22. A region is said to be ‘aperiphractic’ when every closed surface drawn in it can be contracted to a point without passing out of the region.

† It is understood, of course, that the spherical surfaces to which this statement applies are reconcilable with one another, in a sense analogous to that of Art. 34.

‡ Kirchhoff, *Mechanik*, p. 191.

Hence C is not altered by a displacement of the centre of the sphere parallel to x . In the same way we see that C is not altered by a displacement parallel to y or z , i.e. it is absolutely constant.

If the internal boundaries of the region considered be such that the total flux across them is zero, *e.g.* if they be the surfaces of solids, or of portions of incompressible fluid whose motion is rotational, we have $M = 0$, so that the mean value of ϕ over *any* spherical surface enclosing them all is the same.

40 (α) If ϕ be constant over the boundary of any simply-connected region occupied by liquid moving irrotationally, it has the same constant value throughout the interior of that region. For if not constant it would necessarily have a maximum or a minimum value at some point of the region.

Otherwise we have seen in Arts. 35, 36 that the lines of motion cannot begin or end at any point of the region, and that they cannot form closed curves lying wholly within it. They must therefore traverse the region, beginning and ending on its boundary. In our case however this is impossible, for such a line always proceeds from places where ϕ is greater to places where it is less. Hence there can be no motion, i.e.

$$\frac{\partial \phi}{\partial x}, \frac{\partial \phi}{\partial y}, \frac{\partial \phi}{\partial z} = 0,$$

and therefore ϕ is constant and equal to its value at the boundary.

(β) Again, if $\partial \phi / \partial n$ be zero at every point of the boundary of such a region as is above described, ϕ will be constant throughout the interior. For the condition $\partial \phi / \partial n = 0$ expresses that no lines of motion enter or leave the region, but that they are all contained within it. This is however, as we have seen, inconsistent with the other conditions which the lines must conform to. Hence, as before, there can be no motion, and ϕ is constant.

This theorem may be otherwise stated as follows: no continuous irrotational motion of a liquid can take place in a simply-connected region bounded entirely by fixed rigid walls.

(γ) Again, let the boundary of the region considered consist partly of surfaces S over which ϕ has a given constant value, and partly of other surfaces Σ over which $\partial \phi / \partial n = 0$. By the previous argument, no lines of motion can pass from one point to another of S , and none can cross Σ . Hence no such lines exist, ϕ is therefore constant as before, and equal to its value at S .

It follows from these theorems that the irrotational motion of a liquid in a simply-connected region is determinate when either the value of ϕ , or the value of the inward normal velocity $-\partial \phi / \partial n$, is prescribed at all points of the boundary, or (again) when the value of ϕ is given over part of the boundary,

and the value of $-\partial\phi/\partial n$ over the remainder. For if ϕ_1, ϕ_2 be the velocity-potentials of two motions each of which satisfies the prescribed boundary-conditions, in any one of these cases, the function $\phi_1 - \phi_2$ satisfies the condition (α) or (β) or (γ) of the present Article, and must therefore be constant throughout the region

41 A class of cases of great importance, but not strictly included in the scope of the foregoing theorems, occurs when the region occupied by the irrotationally moving liquid extends to infinity, but is bounded internally by one or more closed surfaces. We assume, for the present, that this region is simply-connected, and that ϕ is therefore single-valued

If ϕ be constant over the internal boundary of the region, and tend everywhere to the same constant value at an infinite distance from the internal boundary, it is constant throughout the region. For otherwise ϕ would be a maximum or a minimum at some point.

We infer, exactly as in Art. 40, that if ϕ be given arbitrarily over the internal boundary, and have a given constant value at infinity, its value is everywhere determinate

Of more importance in our present subject is the theorem that, if the normal velocity be zero at every point of the internal boundary, and if the fluid be at rest at infinity, then ϕ is everywhere constant. We cannot however infer this at once from the proof of the corresponding theorem in Art. 40. It is true that we may suppose the region limited externally by an infinitely large surface at every point of which $\partial\phi/\partial n$ is infinitely small, but it is conceivable that the integral $\iint \partial\phi/\partial n \cdot dS$, taken over a portion of this surface, might still be finite, in which case the investigation referred to would fail. We proceed therefore as follows.

Since the velocity tends to the limit zero at an infinite distance from the internal boundary (S , say), it must be possible to draw a closed surface Σ , completely enclosing S , beyond which the velocity is everywhere less than a certain value ϵ , which value may, by making Σ large enough, be made as small as we please. Now in any direction from S let us take a point P at such a distance beyond Σ that the solid angle which Σ subtends at it is infinitely small, and with P as centre let us describe two spheres, one just excluding, the other just including S . We shall prove that the mean value of ϕ over each of these spheres is, within an infinitely small amount, the same. For if Q, Q' be points of these spheres on a common radius PQ, PQ' , then if Q, Q' fall within Σ the corresponding values of ϕ may differ by a finite amount, but since the portion of either spherical surface which falls within Σ is an infinitely small fraction of the whole, no finite difference in the mean values can arise from this cause. On the other hand, when Q, Q' fall without Σ , the corresponding values of ϕ cannot differ by so much as ϵ , for ϵ is

by definition a superior limit to the rate of variation of ϕ . Hence, the mean values of ϕ over the two spherical surfaces must differ by less than $\epsilon.QQ'$. Since QQ' is finite, whilst ϵ may by taking Σ large enough be made as small as we please, the difference of the mean values may, by taking P sufficiently distant, be made infinitely small.

Now we have seen in Arts 38, 39 that the mean value of ϕ over the inner sphere is equal to its value at P , and that the mean value over the outer sphere is (since $M=0$) equal to a constant quantity C . Hence, ultimately, the value of ϕ at infinity tends everywhere to the constant value C .

The same result holds even if the normal velocity be not zero over the internal boundary, for in the theorem of Art 39 M is divided by r , which is in our case infinite.

It follows that if $\partial\phi/\partial n = 0$ at all points of the internal boundary, and if the fluid be at rest at infinity, it must be everywhere at rest. For no lines of motion can begin or end on the internal boundary. Hence such lines, if they existed, must come from an infinite distance, traverse the region occupied by the fluid, and pass off again to infinity; i.e. they must form infinitely long courses between places where ϕ has, within an infinitely small amount, the same value C , which is impossible.

The theorem that, if the fluid be at rest at infinity, the motion is determinate when the value of $-\partial\phi/\partial n$ is given over the internal boundary, follows by the same argument as in Art 40

Green's Theorem.

42 In treatises on Electrostatics, &c, many important properties of the potential are usually proved by means of a certain theorem due to Green. Of these the most important from our present point of view have already been given; but as the theorem in question leads, amongst other things, to a useful expression for the kinetic energy in any case of irrotational motion, some account of it will properly find a place here

Let U, V, W be any three functions which are finite, single-valued and differentiable at all points of a connected region completely bounded by one or more closed surfaces S , let δS be an element of any one of these surfaces, and l, m, n the direction-cosines of the normals to it drawn inwards. We shall prove in the first place that

$$\iint (lU + mV + nW) dS = - \iiint \left(\frac{\partial U}{\partial x} + \frac{\partial V}{\partial y} + \frac{\partial W}{\partial z} \right) dx dy dz, \quad \dots\dots(1)$$

where the triple-integral is taken throughout the region, and the double-integral over its boundary.

If we conceive a series of surfaces drawn so as to divide the region into any number of separate parts, the integral

$$\iint (lU + mV + nW) dS, \dots\dots\dots (2)$$

taken over the original boundary, is equal to the sum of the similar integrals each taken over the whole boundary of one of these parts. For, for every element $\delta\sigma$ of a dividing surface, we have, in the integrals corresponding to the parts lying on the two sides of this surface, elements $(lU + mV + nW)\delta\sigma$, and $(l'U + m'V + n'W)\delta\sigma$, respectively. But the normals to which l, m, n , and l', m', n' refer being drawn inwards in each case, we have $l' = -l, m' = -m, n' = -n$, so that, in forming the sum of the integrals spoken of, the elements due to the dividing surfaces disappear, and we have left only those due to the original boundary of the region.

Now let us suppose the dividing surfaces to consist of three systems of planes, drawn at infinitesimal intervals, parallel to yz, zx, xy , respectively. If x, y, z be the co-ordinates of the centre of one of the rectangular spaces thus formed, and $\delta x, \delta y, \delta z$ the lengths of its edges, the part of the integral (2) due to the yz -face nearest the origin is

$$\left(U - \frac{1}{2} \frac{\partial U}{\partial x} \delta x \right) \delta y \delta z,$$

and that due to the opposite face is

$$- \left(U + \frac{1}{2} \frac{\partial U}{\partial x} \delta x \right) \delta y \delta z.$$

The sum of these is $-\partial U / \partial x \delta x \delta y \delta z$. Calculating in the same way the parts of the integral due to the remaining pairs of faces, we get for the final result

$$- \left(\frac{\partial U}{\partial x} + \frac{\partial V}{\partial y} + \frac{\partial W}{\partial z} \right) \delta x \delta y \delta z.$$

Hence (1) simply expresses the fact that the surface-integral (2), taken over the boundary of the region, is equal to the sum of the similar integrals taken over the boundaries of the elementary spaces of which we have supposed it built up.

It is evident from (1), or it may be proved directly by transformation of co-ordinates, that if (U, V, W) be a *polar* vector, the expression

$$\frac{\partial U}{\partial x} + \frac{\partial V}{\partial y} + \frac{\partial W}{\partial z}$$

is a 'scalar' quantity, i.e. its value is unaffected by any such transformation. It is now usually called the 'divergence' of the vector-field at the point (x, y, z) .

The interpretation, when (U, V, W) is the velocity of a continuous substance, is obvious. In the particular case of irrotational motion we obtain

$$\iint \frac{\partial \phi}{\partial n} dS = - \iiint \nabla^2 \phi dx dy dz, \quad \dots \dots \dots (3)$$

where δn denotes an element of the inwardly-directed normal to the surface S .

Again, if we put $U, V, W = \rho u, \rho v, \rho w$, respectively, we reproduce in substance the investigation of Art. 8.

Another useful result is obtained by putting $U, V, W = u\phi, v\phi, w\phi$, respectively, where u, v, w satisfy the relation

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 0$$

throughout the region, and make

$$lu + mv + nw = 0$$

over the boundary. We find

$$\iiint \left(u \frac{\partial \phi}{\partial x} + v \frac{\partial \phi}{\partial y} + w \frac{\partial \phi}{\partial z} \right) dx dy dz = 0. \quad \dots \dots (4)$$

The function ϕ is here merely restricted to be finite, single-valued, and continuous, and to have its first differential coefficients finite, throughout the region.

43. Now let ϕ, ϕ' be any two functions which, together with their first and second derivatives, are finite and single-valued throughout the region considered; and let us put

$$U, V, W = \phi \frac{\partial \phi'}{\partial x}, \phi \frac{\partial \phi'}{\partial y}, \phi \frac{\partial \phi'}{\partial z},$$

respectively, so that $lU + mV + nW = \phi \frac{\partial \phi'}{\partial n}$.

Substituting in (1) we find

$$\iint \phi \frac{\partial \phi'}{\partial n} dS = - \iiint \left(\frac{\partial \phi}{\partial x} \frac{\partial \phi'}{\partial x} + \frac{\partial \phi}{\partial y} \frac{\partial \phi'}{\partial y} + \frac{\partial \phi}{\partial z} \frac{\partial \phi'}{\partial z} \right) dx dy dz \\ - \iiint \phi \nabla^2 \phi' dx dy dz \quad \dots (5)$$

By interchanging ϕ and ϕ' we obtain

$$\iint \phi' \frac{\partial \phi}{\partial n} dS = - \iiint \left(\frac{\partial \phi}{\partial x} \frac{\partial \phi'}{\partial x} + \frac{\partial \phi}{\partial y} \frac{\partial \phi'}{\partial y} + \frac{\partial \phi}{\partial z} \frac{\partial \phi'}{\partial z} \right) dx dy dz \\ - \iiint \phi' \nabla^2 \phi dx dy dz. \quad \dots (6)$$

Equations (5) and (6) together constitute Green's theorem*.

* G. Green, *Essay on Electricity and Magnetism*, Nottingham, 1828, Art. 3 [*Mathematical Papers* (ed. Ferrers), Cambridge, 1871, p. 23]

44. If ϕ, ϕ' be the velocity-potentials of two distinct modes of irrotational motion of a liquid, so that

$$\nabla^2 \phi = 0, \quad \nabla^2 \phi' = 0, \quad \dots \dots \dots (1)$$

we obtain

$$\iint \phi \frac{\partial \phi'}{\partial n} dS = \iint \phi' \frac{\partial \phi}{\partial n} dS. \quad \dots \dots \dots (2)$$

If we recall the physical interpretation of the velocity-potential, given in Art. 18, then, regarding the motion as generated in each case impulsively from rest, we recognize this equation as a particular case of the dynamical theorem that

$$\Sigma p_r q_r' = \Sigma p_r' q_r,$$

where p_r, q_r and p_r', q_r' are generalized components of impulse and velocity, in any two possible motions of a system*.

Again, in Art. 43 (6) let $\phi' = \phi$, and let ϕ be the velocity-potential of a liquid. We obtain

$$\iiint \left\{ \left(\frac{\partial \phi}{\partial x} \right)^2 + \left(\frac{\partial \phi}{\partial y} \right)^2 + \left(\frac{\partial \phi}{\partial z} \right)^2 \right\} dx dy dz = - \iint \phi \frac{\partial \phi}{\partial n} dS. \quad \dots \dots (3)$$

To interpret this we multiply both sides by $\frac{1}{2} \rho$. Then on the right-hand side $-\partial \phi / \partial n$ denotes the normal velocity of the fluid inwards, whilst $\rho \phi$ is, by Art. 18, the impulsive pressure necessary to generate the motion. It is a proposition in Dynamics† that the work done by an impulse is measured by the product of the impulse into half the sum of the initial and final velocities, resolved in the direction of the impulse, of the point to which it is applied. Hence the right-hand side of (3), when modified as described, expresses the work done by the system of impulsive pressures which, applied to the surface S , would generate the actual motion; whilst the left-hand side gives the kinetic energy of this motion. The formula asserts that these two quantities are equal. Hence if T denote the total kinetic energy of the liquid, we have the very important result

$$2T = - \rho \iint \phi \frac{\partial \phi}{\partial n} dS. \quad \dots \dots \dots (4)$$

If in (3), in place of ϕ , we write $\partial \phi / \partial x$, which will of course satisfy $\nabla^2 \partial \phi / \partial x = 0$, and apply the resulting theorem to the region included within a spherical surface of radius r having any point (x, y, z) as centre, then with the same notation as in Art. 39, we have

$$\begin{aligned} \frac{1}{2} r^3 \frac{\partial}{\partial r} \iint w^2 d\omega &= \iint u \frac{\partial u}{\partial r} dS = - \iint \frac{\partial \phi}{\partial x} \frac{\partial}{\partial n} \left(\frac{\partial \phi}{\partial x} \right) dS \\ &= \iint \left\{ \left(\frac{\partial^2 \phi}{\partial x^2} \right)^2 + \left(\frac{\partial^2 \phi}{\partial x \partial y} \right)^2 + \left(\frac{\partial^2 \phi}{\partial x \partial z} \right)^2 \right\} dx dy dz \end{aligned}$$

* Thomson and Tait, *Natural Philosophy*, Art. 313, equation (11)

† *Ibid.*, Art. 303

Hence, writing $q^2 = u^2 + v^2 + w^2$,

$$\frac{1}{2} \rho^2 \frac{\partial}{\partial r} \int \int q^2 d\omega = \int \int \int \left\{ \left(\frac{\partial^2 \phi}{\partial x^2} \right)^2 + \left(\frac{\partial^2 \phi}{\partial y^2} \right)^2 + \left(\frac{\partial^2 \phi}{\partial z^2} \right)^2 + 2 \left(\frac{\partial^2 \phi}{\partial y \partial z} \right)^2 + 2 \left(\frac{\partial^2 \phi}{\partial z \partial x} \right)^2 + 2 \left(\frac{\partial^2 \phi}{\partial x \partial y} \right)^2 \right\} dx dy dz \quad \dots \dots (5)$$

Since this latter expression is essentially positive, the mean value of q^2 , taken over a sphere having any given point as centre, increases with the radius of the sphere. Hence q^2 cannot be a maximum at any point of the fluid, as was proved otherwise in Art. 37

Moreover, recalling the formula for the pressure in any case of irrotational motion of a liquid, viz

$$\frac{p}{\rho} = \frac{\partial \phi}{\partial t} - \Omega - \frac{1}{2} q^2 + F(t), \quad \dots \dots \dots (6)$$

we infer that, provided the potential Ω of the external forces satisfy the condition

$$\nabla^2 \Omega = 0, \quad \dots \dots \dots (7)$$

the mean value of p over a sphere described with any point in the interior of the fluid as centre will diminish as the radius increases. The place of least pressure will therefore be somewhere on the boundary of the fluid. This has a bearing on the point discussed in Art. 23

45 In this connection we may note a remarkable theorem discovered by Lord Kelvin*, and afterwards generalized by him into an universal property of dynamical systems started impulsively from rest under prescribed velocity-conditions†

The irrotational motion of a liquid occupying a simply-connected region has less kinetic energy than any other motion consistent with the same normal motion of the boundary

Let T be the kinetic energy of the irrotational motion to which the velocity-potential ϕ refers, and T_1 that of another motion given by

$$u = -\frac{\partial \phi}{\partial x} + u_0, \quad v = -\frac{\partial \phi}{\partial y} + v_0, \quad w = -\frac{\partial \phi}{\partial z} + w_0, \quad \dots \dots (8)$$

where, in virtue of the equation of continuity, and the prescribed boundary-condition, we must have

$$\frac{\partial u_0}{\partial x} + \frac{\partial v_0}{\partial y} + \frac{\partial w_0}{\partial z} = 0$$

throughout the region, and $lu_0 + mv_0 + nw_0 = 0$

over the boundary. Further let us write

$$T_0 = \frac{1}{2} \rho \iiint (u_0^2 + v_0^2 + w_0^2) dx dy dz. \quad \dots \dots \dots (9)$$

* (W. Thomson) "On the Vis-Viva of a Liquid in Motion," *Camb and Dub Math. Journ.*, 1849 [*Mathematical and Physical Papers*, t. i. p. 107].

† Thomson and Tait, *Natural Philosophy*, Art. 312.

We find
$$T_1 = T + T_0 - \rho \iiint \left(v_0 \frac{\partial \phi}{\partial x} + v_0 \frac{\partial \phi}{\partial y} + w_0 \frac{\partial \phi}{\partial z} \right) dx dy dz.$$

Since the last integral vanishes, by Art. 42 (4), we have

$$T_1 = T + T_0, \quad \dots \dots \dots (10)$$

which proves the theorem

46. We shall require to know, hereafter, the form assumed by the expression (4) for the kinetic energy when the fluid extends to infinity and is at rest there, being limited internally by one or more closed surfaces S . Let us suppose a large closed surface Σ described so as to enclose the whole of S . The energy of the fluid included between S and Σ is

$$-\frac{1}{2}\rho \iint \phi \frac{\partial \phi}{\partial n} dS - \frac{1}{2}\rho \iint \phi \frac{\partial \phi}{\partial n} d\Sigma, \quad \dots \dots \dots (11)$$

where the integration in the first term extends over S , that in the second over Σ . Since we have, by the equation of continuity,

$$\iint \frac{\partial \phi}{\partial n} dS + \iint \frac{\partial \phi}{\partial n} d\Sigma = 0,$$

(8) may be written

$$-\frac{1}{2}\rho \iint (\phi - C) \frac{\partial \phi}{\partial n} dS - \frac{1}{2}\rho \iint (\phi - C) \frac{\partial \phi}{\partial n} d\Sigma, \quad \dots \dots (12)$$

where C may be any constant, but is here supposed to be the constant value to which ϕ was shewn in Art 39 to tend at an infinite distance from S . Now the whole region occupied by the fluid may be supposed made up of tubes of flow, each of which must pass either from one point of the internal boundary to another, or from that boundary to infinity. Hence the value of the integral

$$\iint \frac{\partial \phi}{\partial n} d\Sigma,$$

taken over any surface, open or closed, finite or infinite, drawn within the region, must be finite. Hence ultimately, when Σ is taken infinitely large and infinitely distant all round from S , the second term of (12) vanishes, and we have

$$2T = -\rho \iint (\phi - C) \frac{\partial \phi}{\partial n} dS, \quad \dots \dots \dots (13)$$

where the integration extends over the internal boundary only

If the total flux across the internal boundary be zero, we have

$$\iint \frac{\partial \phi}{\partial n} dS = 0,$$

so that (13) may be written
$$2T = -\rho \iint \phi \frac{\partial \phi}{\partial n} dS, \quad \dots \dots \dots (14)$$

simply

On Multiply-connected Regions.

47 Before discussing the properties of irrotational motion in multiply-connected regions we must examine more in detail the nature and classification of such regions. In the following synopsis of this branch of the geometry of position we recapitulate for the sake of completeness one or two definitions already given.

We consider any connected region of space, enclosed by boundaries. A region is 'connected' when it is possible to pass from any one point of it to any other by an infinity of paths, each of which lies wholly in the region.

Any two such paths, or any two circuits, which can by continuous variation be made to coincide without ever passing out of the region, are said to be 'mutually reconcilable'. Any circuit which can be contracted to a point without passing out of the region is said to be 'reducible.' Two reconcilable paths, combined, form a reducible circuit. If two paths or two circuits be reconcilable, it must be possible to connect them by a continuous surface, which lies wholly within the region, and of which they form the complete boundary; and conversely.

It is further convenient to distinguish between 'simple' and 'multiple' irreducible circuits. A 'multiple' circuit is one which can by continuous variation be made to appear, in whole or in part, as the repetition of another circuit a certain number of times. A 'simple' circuit is one with which this is not possible.

A 'barrier,' or 'diaphragm,' is a surface drawn across the region, and limited by the line or lines in which it meets the boundary. Hence a barrier is necessarily a connected surface, and cannot consist of two or more detached portions.

A 'simply-connected' region is one such that all paths joining any two points of it are reconcilable, or such that all circuits drawn within it are reducible.

A 'doubly-connected' region is one such that two irreconcilable paths, and no more, can be drawn between any two points A, B of it, viz any other path joining AB is reconcilable with one of these, or with a combination of the two taken each a certain number of times. In other words, the region is such that one (simple) irreducible circuit can be drawn in it, whilst all other circuits are either reconcilable with this (repeated, if necessary), or are reducible. As an example of a doubly-connected region we may take that enclosed by the surface of an anchor-ring, or that external to such a ring and extending to infinity.

Generally, a region such that n irreconcilable paths, and no more, can be drawn between any two points of it, or such that $n - 1$ (simple) irreducible

and irreconcilable circuits, and no more, can be drawn in it, is said to be '*n*-ply-connected.'

The shaded portion of the figure on p. 33 is a triply-connected space of two dimensions.

It may be shewn that the above definition of an *n*-ply-connected space is self-consistent. In such simple cases as $n=2$, $n=3$, this is sufficiently evident without demonstration.

48 Let us suppose, now, that we have an *n*-ply-connected region, with $n-1$ simple independent irreducible circuits drawn in it. It is possible to draw a barrier meeting any one of these circuits in one point only, and not meeting any of the $n-2$ remaining circuits. A barrier drawn in this manner does not destroy the continuity of the region, for the interrupted circuit remains as a path leading round from one side to the other. The order of connection of the region is however diminished by unity, for every circuit drawn in the modified region must be reconcilable with one or more of the $n-2$ circuits not met by the barrier.

A second barrier, drawn in the same manner, will reduce the order of connection again by one, and so on, so that by drawing $n-1$ barriers we can reduce the region to a simply-connected one.

A simply-connected region is divided by a barrier into two separate parts, for otherwise it would be possible to pass from a point on one side the barrier to an adjacent point on the other side by a path lying wholly within the region, which path would in the original region form an irreducible circuit.

Hence in an *n*-ply-connected region it is possible to draw $n-1$ barriers, and no more, without destroying the continuity of the region. This property is sometimes adopted as the definition of an *n*-ply-connected space.

Irrotational Motion in Multiply-connected Spaces.

49. The circulation is the same in any two reconcilable circuits $ABCA$, $A'B'C'A'$ drawn in a region occupied by fluid moving irrotationally. For the two circuits may be connected by a continuous surface lying wholly within the region; and if we apply the theorem of Art 32 to this surface, we have, remembering the rule as to the direction of integration round the boundary,

$$I(ABCA) + I(A'C'B'A') = 0,$$

or

$$I(ABCA) = I(A'B'C'A').$$

If a circuit $ABCA$ be reconcilable with two or more circuits $A'B'C'A'$, $A''B''C''A''$, &c, combined, we can connect all these circuits by a continuous

surface which lies wholly within the region, and of which they form the complete boundary Hence

$I(ABCA) + I(A'C'B'A') + I(A''C''B''A'') + \&c = 0,$

or $I(ABCA) = I(A'B'C'A') + I(A''B''C''A'') + \&c.,$

i.e the circulation in any circuit is equal to the sum of the circulations in the several members of any set of circuits with which it is reconcilable

Let the order of connection of the region be $n + 1$, so that n independent simple irreducible circuits $a_1, a_2, \dots a_n$ can be drawn in it, and let the circulations in these be $\kappa_1, \kappa_2, \dots \kappa_n$, respectively The sign of any κ will of course depend on the direction of integration round the corresponding circuit, let the direction in which κ is estimated be called the positive direction in the circuit. The value of the circulation in any other circuit can now be found at once For the given circuit is necessarily reconcilable with some combination of the circuits $a_1, a_2, \dots a_n$, say with a_1 taken p_1 times, a_2 taken p_2 times and so on, where of course any p is negative when the corresponding circuit is taken in the negative direction. The required circulation then is

$p_1\kappa_1 + p_2\kappa_2 + \dots + p_n\kappa_n \dots \dots \dots (1)$

Since any two paths joining two points A, B of the region together form a circuit, it follows that the values of the flow in the two paths differ by a quantity of the form (1), where, of course, in particular cases some or all of the p 's may be zero

50. Let us denote by $-\phi$ the flow to a variable point P from a fixed point A , viz

$\phi = - \int_A^P (u dx + v dy + w dz) \dots \dots \dots (2)$

So long as the path of integration from A to P is not specified, ϕ is indeterminate to the extent of a quantity of the form (1).

If however n barriers be drawn in the manner explained in Art 48, so as to reduce the region to a simply-connected one, and if the path of integration in (2) be restricted to lie within the region as thus modified (i.e it is not to cross any of the barriers), then ϕ becomes a single-valued function, as in Art 35 It is continuous throughout the modified region, but its values at two adjacent points on opposite sides of a barrier differ by $\pm \kappa$ To derive the value of ϕ when the integration is taken along any path in the unmodified region we must *subtract* the quantity (1), where any p denotes the number of times this path crosses the corresponding barrier. A crossing in the positive direction of the circuits interrupted by the barrier is here counted as positive, a crossing in the opposite direction as negative

By displacing P through an infinitely short space parallel to each co-ordinate axis in succession, we find

$$u, v, w = -\frac{\partial \phi}{\partial x}, -\frac{\partial \phi}{\partial y}, -\frac{\partial \phi}{\partial z},$$


so that ϕ satisfies the definition of a velocity-potential (Art. 17). It is now however a many-valued or cyclic function, i.e. it is not possible to assign to every point of the original region a unique and definite value of ϕ , such values forming a continuous system. On the contrary, whenever P describes an irreducible circuit, ϕ will not, in general, return to its original value, but will differ from it by a quantity of the form (1). The quantities $\kappa_1, \kappa_2, \dots, \kappa_n$, which specify the amounts by which ϕ *decreases* as P describes the several independent circuits of the region, may be called the 'cyclic constants' of ϕ .

It is an immediate consequence of the 'circulation-theorem' of Art. 33 that under the conditions there presupposed the cyclic constants do not alter with the time. The necessity for these conditions is exemplified in the problem of Art. 29, where the potential of the extraneous forces is itself a cyclic function.

The foregoing theory may be illustrated by the case of Art. 27 (2), where the region (as limited by the exclusion of the origin, where the formula would give an infinite velocity) is doubly-connected, since we can connect any two points A, B of it by two irreconcilable paths passing on opposite sides of the axis of z , e.g. ACB, ADB in the figure. The portion of the plane zx for which x is positive may be taken as a barrier, and the region is thus made simply-connected. The circulation in any circuit meeting this barrier once only, e.g. in $ACBDA$, is

$$\int_0^{2\pi} \mu/r \cdot r d\theta, \text{ or } 2\pi\mu$$

That in any circuit not meeting the barrier is zero. In the modified region ϕ may be put equal to a single-valued function, viz $-\mu\theta$, but its value on the positive side of the barrier is zero, that at an adjacent point on the negative side is $-2\pi\mu$.



More complex illustrations of irrotational motion in multiply-connected spaces of two dimensions will present themselves in the next chapter.

51. Before proceeding further we may briefly indicate a somewhat different method of presenting the above theory.

Starting from the existence of a velocity-potential as the characteristic of the class of motions which we propose to study, and adopting the second definition of an $n+1$ -ply-connected region, indicated in Art. 48, we remark that in a simply-connected region every equipotential surface must either be a closed surface, or else form a barrier dividing the region into two separate parts. Hence, supposing the whole system of such surfaces drawn, we see that if a closed curve cross any given equipotential surface once it must cross

it again, and in the opposite direction. Hence, corresponding to any element of the curve, included between two consecutive equipotential surfaces, we have a second element such that the flow along it, being equal to the difference between the corresponding values of ϕ , is equal and opposite to that along the former, so that the circulation in the whole circuit is zero.

If however the region be multiply-connected, an equipotential surface may form a barrier without dividing it into two separate parts. Let as many such surfaces be drawn as is possible without destroying the continuity of the region. The number of these cannot, by definition, be greater than n . Every other equipotential surface which is not closed will be reconcilable (in an obvious sense) with one or more of these barriers. A curve drawn from one side of a barrier round to the other, without meeting any of the remaining barriers, will cross every equipotential surface reconcilable with the first barrier an odd number of times, and every other equipotential surface an even number of times. Hence the circulation in the circuit thus formed will not vanish, and ϕ will be a cyclic function.

In the method adopted above we have based the whole theory on the equations

$$\frac{\partial w}{\partial y} - \frac{\partial v}{\partial z} = 0, \quad \frac{\partial u}{\partial z} - \frac{\partial w}{\partial x} = 0, \quad \frac{\partial v}{\partial x} - \frac{\partial u}{\partial y} = 0, \quad \dots\dots (3)$$

and have deduced the existence and properties of the velocity-potential in the various cases as necessary consequences of these. In fact, Arts. 34, 35, and 49, 50 may be regarded as a treatise on the integration of this system of differential equations.

The integration of (3), when we have, on the right-hand side, instead of zero, known functions of x, y, z , will be treated in Chapter VII

52 Proceeding now, as in Art 36, to the particular case of an incompressible fluid, we remark that whether ϕ be cyclic or not, its first derivatives $\partial\phi/\partial x, \partial\phi/\partial y, \partial\phi/\partial z$, and therefore all the higher derivatives, are essentially single-valued functions, so that ϕ will still satisfy the equation of continuity

$$\nabla^2\phi = 0, \quad \dots\dots\dots (1)$$

or the equivalent form
$$\iint \frac{\partial\phi}{\partial n} dS = 0, \quad \dots\dots\dots (2)$$

where the surface-integration extends over the whole boundary of any portion of the fluid.

The theorem (α) of Art 40, viz that ϕ must be constant throughout the interior of any region at every point of which (1) is satisfied, if it be constant over the boundary, still holds when the region is multiply-connected. For ϕ , being constant over the boundary, is necessarily single-valued.

The remaining theorems of Art. 40, being based on the assumption that the stream-lines cannot form closed curves, will require modification. We must introduce the additional condition that the circulation is to be zero in each circuit of the region

Removing this restriction, we have the theorem that the irrotational motion of a liquid occupying an n -ply-connected region is determinate when the normal velocity at every point of the boundary is prescribed, as well as the value of the circulation in each of the n independent and irreducible circuits which can be drawn in the region. For if ϕ_1, ϕ_2 be the (cyclic) velocity-potentials of two motions satisfying the above conditions, then $\phi = \phi_1 - \phi_2$ is a single-valued function which satisfies (1) at every point of the region, and makes $\partial\phi/\partial n = 0$ at every point of the boundary. Hence by Art 40, ϕ is constant, and the motions determined by ϕ_1 and ϕ_2 are identical

The theory of multiple connectivity seems to have been first developed by Riemann* for spaces of two dimensions, à propos of his researches on the theory of functions of a complex variable, in which connection also cyclic functions, satisfying the equation

$$\frac{\partial^2 \phi}{\partial x^2} + \frac{\partial^2 \phi}{\partial y^2} = 0$$

through multiply-connected regions, present themselves.

The bearing of the theory on Hydrodynamics, and the existence in certain cases of many-valued velocity-potentials were first pointed out by von Helmholtz† The subject of cyclic irrotational motion in multiply-connected regions was afterwards taken up and fully investigated by Lord Kelvin in the paper on vortex-motion already referred to‡

Lord Kelvin's Extension of Green's Theorem.

53 It was assumed in the proof of Green's Theorem that ϕ and ϕ' were both single-valued functions. If either be a cyclic function, as may be the case when the region to which the integrations in Art 43 refer is multiply-connected, the statement of the theorem must be modified. Let us suppose, for instance, that ϕ is cyclic, the surface-integral on the left-hand side of Art. 43 (5), and the second volume-integral on the right-hand side, are then indeterminate, on account of the indeterminateness in the value of ϕ itself. To remove this indeterminateness, let the barriers necessary to reduce the region to a simply-connected one be drawn, as explained in Art. 48. We may now suppose ϕ to be continuous and single-valued throughout the

* *Grundlagen für eine allgemeine Theorie der Functionen einer veränderlichen complexen Grösse*, Göttingen, 1851 [*Mathematische Werke*, Leipzig, 1876, p 3]. Also "Lehrsätze aus der Analysis Situs," *Crelle*, t liv (1857) [*Werke*, p 84]

† *Crelle*, t lv, 1858

‡ See also Kirchhoff, "Ueber die Kräfte welche zwei unendlich dünne starre Ringe in einer Flüssigkeit scheinbar auf einander ausüben können," *Crelle*, t lxxi (1869) [*Ges Abh.*, p 404].

region thus modified, and the equation referred to will then hold, provided the two sides of each barrier be reckoned as part of the boundary of the region, and therefore included in the surface-integral on the left-hand side. Let $\delta\sigma_1$ be an element of one of the barriers, κ_1 the cyclic constant corresponding to that barrier, $\partial\phi'/\partial n$ the rate of variation of ϕ' in the positive direction of the normal to $\delta\sigma_1$. Since, in the parts of the surface-integral due to the two sides of $\delta\sigma_1$, $\partial\phi'/\partial n$ is to be taken with opposite signs, whilst the value of ϕ on the positive side exceeds that on the negative side by κ_1 , we get finally for the element of the integral due to $\delta\sigma_1$, the value $\kappa_1\partial\phi'/\partial n \delta\sigma_1$. Hence Art 43 (5) becomes, in the altered circumstances,

$$\begin{aligned} & \iint \phi \frac{\partial\phi'}{\partial n} dS + \kappa_1 \iint \frac{\partial\phi'}{\partial n} d\sigma_1 + \kappa_2 \iint \frac{\partial\phi'}{\partial n} d\sigma_2 + \&c. \\ &= - \iiint \left(\frac{\partial\phi}{\partial x} \frac{\partial\phi'}{\partial x} + \frac{\partial\phi}{\partial y} \frac{\partial\phi'}{\partial y} + \frac{\partial\phi}{\partial z} \frac{\partial\phi'}{\partial z} \right) dx dy dz - \iiint \phi \nabla^2 \phi' dx dy dz, \quad (1) \end{aligned}$$

where the surface-integrations indicated on the left-hand side extend, the first over the original boundary of the region only, and the rest over the several barriers. The coefficient of any κ is evidently *minus* the total flux across the corresponding barrier, in a motion of which ϕ' is the velocity-potential. The values of ϕ in the first and last terms of the equation are to be assigned in the manner indicated in Art 50.

If ϕ' also be a cyclic function, having the cyclic constants $\kappa'_1, \kappa'_2, \&c.$, then Art. 43 (6) becomes in the same way

$$\begin{aligned} & \iint \phi' \frac{\partial\phi}{\partial n} dS + \kappa'_1 \iint \frac{\partial\phi}{\partial n} d\sigma_1 + \kappa'_2 \iint \frac{\partial\phi}{\partial n} d\sigma_2 + \dots \\ &= - \iiint \left(\frac{\partial\phi}{\partial x} \frac{\partial\phi'}{\partial x} + \frac{\partial\phi}{\partial y} \frac{\partial\phi'}{\partial y} + \frac{\partial\phi}{\partial z} \frac{\partial\phi'}{\partial z} \right) dx dy dz - \iiint \phi' \nabla^2 \phi dx dy dz. \quad (2) \end{aligned}$$

Equations (1) and (2) together constitute Lord Kelvin's extension of Green's theorem

54 If ϕ, ϕ' are both velocity-potentials of a liquid, we have

$$\nabla^2 \phi = 0, \quad \nabla^2 \phi' = 0, \quad \dots \dots \dots (3)$$

and therefore $\iint \phi \frac{\partial\phi'}{\partial n} dS + \kappa_1 \iint \frac{\partial\phi'}{\partial n} d\sigma_1 + \kappa_2 \iint \frac{\partial\phi'}{\partial n} d\sigma_2 + \dots$

$$= \iint \phi' \frac{\partial\phi}{\partial n} dS + \kappa'_1 \iint \frac{\partial\phi}{\partial n} d\sigma_1 + \kappa'_2 \iint \frac{\partial\phi}{\partial n} d\sigma_2 + \dots \dots \dots (4)$$

To obtain a physical interpretation of this theorem it is necessary to explain in the first place a method, imagined by Lord Kelvin, of generating any given cyclic irrotational motion of a liquid in a multiply-connected space

Let us suppose the fluid to be enclosed in a perfectly smooth and flexible membrane occupying the position of the boundary. Further, let n barriers be drawn, as in Art 48, so as to convert the region into a simply-connected one, and let their places be occupied by similar membranes, infinitely thin, and destitute of inertia. The fluid being initially at rest, let each element of the first-mentioned membrane be suddenly moved inwards with the given (positive or negative) normal velocity $-\partial\phi/\partial n$, whilst uniform impulsive pressures $\kappa_1\rho, \kappa_2\rho, \dots \kappa_n\rho$ are simultaneously applied to the negative sides of the respective barrier-membranes. The motion generated will be characterized by the following properties. It will be irrotational, being generated from rest, the normal velocity at every point of the original boundary will have the prescribed value; the values of the impulsive pressure at two adjacent points on opposite sides of a membrane will differ by the corresponding value of $\kappa\rho$, and the values of the velocity-potential will therefore differ by the corresponding value of κ , finally, the motion on one side of a barrier will be continuous with that on the other. To prove the last statement we remark, first, that the velocities normal to the barrier at two adjacent points on opposite sides of it are the same, being each equal to the normal velocity of the adjacent portion of the membrane. Again, if P, Q be two consecutive points on a barrier, and if the corresponding values of ϕ be on the positive side ϕ_P, ϕ_Q , and on the negative side ϕ'_P, ϕ'_Q , we have

$$\phi_P - \phi'_P = \kappa = \phi_Q - \phi'_Q,$$

and therefore

$$\phi_Q - \phi_P = \phi'_Q - \phi'_P,$$

i.e., if $PQ = \delta s$,

$$\partial\phi/\partial s = \partial\phi'/\partial s$$

Hence the tangential velocities at two adjacent points on opposite sides of the barrier also agree. If then we suppose the barrier-membranes to be liquefied immediately after the impulse, we obtain the irrotational motion in question.

The physical interpretation of (4), when multiplied by $-\rho$, now follows as in Art. 44. The values of $\rho\kappa$ are additional components of momentum, and those of $-\iint \partial\phi/\partial n \, d\sigma$, the fluxes through the various apertures of the region, are the corresponding generalized velocities.

55. If in (2) we put $\phi' = \phi$, and suppose ϕ to be the velocity-potential of an incompressible fluid, we find

$$\begin{aligned} 2T &= \rho \iiint \left\{ \left(\frac{\partial\phi}{\partial x} \right)^2 + \left(\frac{\partial\phi}{\partial y} \right)^2 + \left(\frac{\partial\phi}{\partial z} \right)^2 \right\} dx dy dz \\ &= -\rho \iint \phi \frac{\partial\phi}{\partial n} dS - \rho\kappa_1 \iint \frac{\partial\phi}{\partial n} d\sigma_1 - \rho\kappa_2 \iint \frac{\partial\phi}{\partial n} d\sigma_2 - \dots \quad \dots \quad (5) \end{aligned}$$

The last member of this formula has a simple interpretation in terms of the artificial method of generating cyclic irrotational motion just explained. The

first term has already been recognized as equal to twice the work done by the impulsive pressure $\rho\phi$ applied to every part of the original boundary of the fluid. Again, $\rho\kappa_1$ is the impulsive pressure applied, in the positive direction, to the infinitely thin massless membrane by which the place of the first barrier was supposed to be occupied; so that the expression

$$-\frac{1}{2} \iint \rho\kappa_1 \frac{\partial\phi}{\partial n} d\sigma_1$$

denotes the work done by the impulsive forces applied to that membrane, and so on. Hence (5) expresses the fact that the energy of the motion is equal to the work done by the whole system of impulsive forces by which we may suppose it generated.

In applying (5) to the case where the fluid extends to infinity and is at rest there, we may replace the first term of the third member by

$$-\rho \iint (\phi - C) \frac{\partial\phi}{\partial n} dS, \quad \dots\dots\dots (6)$$

where the integration extends over the internal boundary only. The proof is the same as in Art 46. When the total flux across this boundary is zero, this reduces to

$$-\rho \iint \phi \frac{\partial\phi}{\partial n} dS. \quad \dots\dots\dots (7)$$

The minimum theorem of Lord Kelvin, given in Art. 45, may now be extended as follows

The irrotational motion of a liquid in a multiply-connected region has less kinetic energy than any other motion consistent with the same normal motion of the boundary and the same value of the total flux through each of the several independent channels of the region

The proof is left to the reader.

Sources and Sinks.

56. The analogy with the theories of Electrostatics, the Steady Flow of Heat, &c., may be carried further by means of the conception of sources and sinks.

A 'simple source' is a point from which fluid is imagined to flow out uniformly in all directions. If the total flux outwards across a small closed surface surrounding the point be m , then m is called the 'strength' of the source. A negative source is called a 'sink.' The continued existence of a source or a sink would postulate of course a continual creation or annihilation of fluid at the point in question.

The velocity-potential at any point P , due to a simple source, in a liquid at rest at infinity, is

$$\phi = m/4\pi r, \quad \dots \dots \dots (1)$$

where r denotes the distance of P from the source. For this gives a radial flow from the point, and if $\delta S = r^2 \delta \omega$, be an element of a spherical surface having its centre at the source, we have

$$-\iint \frac{\partial \phi}{\partial r} dS = m,$$

a constant, so that the equation of continuity is satisfied, and the flux outwards has the value appropriate to the strength of the source

A combination of two equal and opposite sources $\pm m'$, at a distance δs apart, where, in the limit, δs is taken to be infinitely small, and m' infinitely great, but so that the product $m'\delta s$ is finite and equal to μ (say), is called a 'double source' of strength μ , and the line δs , considered as drawn in the direction from $-m'$ to $+m'$, is called its axis

To find the velocity-potential at any point (x, y, z) due to a double source μ situate at (x', y', z') , and having its axis in the direction (l, m, n) , we remark that, f being any continuous function,

$$\begin{aligned} & f(x' + l\delta s, y' + m\delta s, z' + n\delta s) - f(x', y', z') \\ &= \left(l \frac{\partial}{\partial x'} + m \frac{\partial}{\partial y'} + n \frac{\partial}{\partial z'} \right) f(x', y', z') \delta s, \end{aligned}$$

ultimately Hence, putting $f(x', y', z') = m'/4\pi r$, where

$$r = \{(x - x')^2 + (y - y')^2 + (z - z')^2\}^{\frac{1}{2}},$$

we find

$$\phi = \frac{\mu}{4\pi} \left(l \frac{\partial}{\partial x'} + m \frac{\partial}{\partial y'} + n \frac{\partial}{\partial z'} \right) \frac{1}{r}, \quad \dots \dots \dots (2)$$

$$= -\frac{\mu}{4\pi} \left(l \frac{\partial}{\partial x} + m \frac{\partial}{\partial y} + n \frac{\partial}{\partial z} \right) \frac{1}{r}, \quad \dots \dots \dots (3)$$

$$= \frac{\mu \cos \mathfrak{S}}{4\pi r^2}, \quad \dots \dots \dots (4)$$

where, in the latter form, \mathfrak{S} denotes the angle which the line r , considered as drawn from (x', y', z') to (x, y, z) , makes with the axis (l, m, n)

We might proceed, in a similar manner (see Art 83), to build up sources of higher degrees of complexity, but the above is sufficient for our immediate purpose.

Finally, we may imagine simple or double sources, instead of existing at isolated points, to be distributed continuously over lines, surfaces, or volumes.

57. We can now prove that any continuous acyclic irrotational motion of a liquid mass may be regarded as due to a distribution of simple and double sources over the boundary.

This depends on the theorem, proved in Art 44, that if ϕ, ϕ' be any two single-valued functions which satisfy $\nabla^2\phi = 0, \nabla^2\phi' = 0$ throughout a given region, then

$$\iint \phi \frac{\partial \phi'}{\partial n} dS = \iint \phi' \frac{\partial \phi}{\partial n} dS, \dots\dots\dots (5)$$

where the integration extends over the whole boundary. In the present application, we take ϕ to be the velocity-potential of the motion in question, and put $\phi' = 1/r$, the reciprocal of the distance of any point of the fluid from a fixed point P

We will first suppose that P is in the space occupied by the fluid. Since ϕ' then becomes infinite at P , it is necessary to exclude this point from the region to which the formula (5) applies; this may be done by describing a small spherical surface about P as centre. If we now suppose $\delta\Sigma$ to refer to this surface, and δS to the original boundary, the formula gives

$$\iint \phi \frac{\partial}{\partial n} \left(\frac{1}{r} \right) d\Sigma + \iint \phi \frac{\partial}{\partial n} \left(\frac{1}{r} \right) dS = \iint \frac{1}{r} \frac{\partial \phi}{\partial n} d\Sigma + \iint \frac{1}{r} \frac{\partial \phi}{\partial n} dS. \dots (6)$$

At the surface Σ we have $\partial/\partial n (1/r) = -1/r^2$, hence if we put $\delta\Sigma = r^2 d\omega$, and finally make $r = 0$, the first integral on the left-hand becomes $-4\pi\phi_P$, where ϕ_P denotes the value of ϕ at P , whilst the first integral on the right vanishes. Hence

$$\phi_P = -\frac{1}{4\pi} \iint \frac{1}{r} \frac{\partial \phi}{\partial n} dS + \frac{1}{4\pi} \iint \phi \frac{\partial}{\partial n} \left(\frac{1}{r} \right) dS. \dots\dots\dots (7)$$

This gives the value of ϕ at any point P of the fluid in terms of the values of ϕ and $\partial\phi/\partial n$ at the boundary. Comparing with the formulae (1) and (2) we see that the first term is the velocity-potential due to a surface distribution of simple sources, with a density $-\partial\phi/\partial n$ per unit area, whilst the second term is the velocity-potential of a distribution of double sources, with axes normal to the surface, the density being ϕ . It will appear from equation (10), below, that this is only one out of an infinite number of surface-distributions which will give the same value of ϕ throughout the interior.

When the fluid extends to infinity and is at rest there, the surface-integrals in (7) may, on a certain understanding, be taken to refer to the internal boundary alone. To see this, we may take as external boundary an infinite sphere having the point P as centre. The corresponding part of the first integral in (7) vanishes, whilst that of the second is equal to C , the constant value to which, as we have seen in Art 41, ϕ tends at infinity. It is convenient, for facility of statement, to suppose $C = 0$, this is legitimate since we may always add an arbitrary constant to ϕ .

When the point P is external to the surface, ϕ' is finite throughout the original region, and the formula (5) gives at once

$$0 = -\frac{1}{4\pi} \iint \frac{1}{r} \frac{\partial \phi}{\partial n} dS + \frac{1}{4\pi} \iint \phi \frac{\partial}{\partial n} \left(\frac{1}{r} \right) dS \dots\dots\dots (8)$$

where, again, in the case of a liquid extending to infinity, and at rest there the terms due to the infinitely distant part of the boundary may be omitted.

58. The distribution expressed by (7) can, further, be replaced by one of simple sources only, or of double sources only, over the boundary

Let ϕ be the velocity-potential of the fluid occupying a certain region, and let ϕ' now denote the velocity-potential of any possible acyclic irrotational motion through the rest of infinite space, with the condition that ϕ , or ϕ' , as the case may be, vanishes at infinity. Then, if the point P be internal to the first region, and therefore external to the second, we have

$$\left. \begin{aligned} \phi_P &= -\frac{1}{4\pi} \iint \frac{1}{r} \frac{\partial \phi}{\partial n} dS + \frac{1}{4\pi} \iint \phi \frac{\partial}{\partial n} \left(\frac{1}{r} \right) dS, \\ 0 &= -\frac{1}{4\pi} \iint \frac{1}{r} \frac{\partial \phi'}{\partial n'} dS + \frac{1}{4\pi} \iint \phi' \frac{\partial}{\partial n'} \left(\frac{1}{r} \right) dS, \end{aligned} \right\} \dots \dots \dots (9)$$

where δn , $\delta n'$ denote elements of the normal to dS , drawn inwards to the first and second regions respectively, so that $\partial/\partial n' = -\partial/\partial n$. By addition, we have

$$\phi_P = -\frac{1}{4\pi} \iint \frac{1}{r} \left(\frac{\partial \phi}{\partial n} + \frac{\partial \phi'}{\partial n'} \right) dS + \frac{1}{4\pi} \iint (\phi - \phi') \frac{\partial}{\partial n} \left(\frac{1}{r} \right) dS. \quad \dots (10)$$

The function ϕ' will be determined by the surface-values of ϕ' or $\partial\phi'/\partial n'$ which are as yet at our disposal

Let us in the first place make $\phi' = \phi$. The tangential velocities on the two sides of the boundary are then continuous, but the normal velocities are discontinuous. To assist the ideas, we may imagine a liquid to fill infinite space, and to be divided into two portions by an infinitely thin vacuum sheet within which an impulsive pressure $\rho\phi$ is applied, so as to generate the given motion from rest. The last term of (10) disappears, so that

$$\phi_P = -\frac{1}{4\pi} \iint \frac{1}{r} \left(\frac{\partial \phi}{\partial n} + \frac{\partial \phi}{\partial n'} \right) dS, \quad \dots \dots (11)$$

that is, the motion (on either side) is that due to a surface-distribution of simple sources, of density

$$-\left(\frac{\partial \phi}{\partial n} + \frac{\partial \phi}{\partial n'} \right)^*.$$

Secondly, we may suppose that $\partial\phi'/\partial n = \partial\phi/\partial n$. This gives continuous normal velocity, but discontinuous tangential velocity, over the original boundary. The motion may in this case be imagined to be generated by giving the prescribed normal velocity $-\partial\phi/\partial n$ to every point of an infinitely thin membrane coincident in position with the boundary. The first term of (10) now vanishes, and we have

$$\phi_P = \frac{1}{4\pi} \iint (\phi - \phi') \frac{\partial}{\partial n} \left(\frac{1}{r} \right) dS, \quad \dots \dots (12)$$

* This investigation was first given by Green, from the point of view of Electrostatics *l.c. ante*, p. 43

shewing that the motion on either side may be conceived as due to a surface-distribution of double sources, with density

$$\phi - \phi'$$

It may be shewn that the above representations of ϕ in terms of simple sources alone, or of double sources alone, are unique, whereas the representation of Art. 57 is indeterminate*.

It is obvious that *cyclic* irrotational motion of a liquid cannot be reproduced by any arrangement of simple sources. It is easily seen, however, that it may be represented by a certain distribution of double sources over the boundary, together with a uniform distribution of double sources over each of the barriers necessary to render the region occupied by the fluid simply-connected. In fact, with the same notation as in Art. 53, we find

$$\phi_r = \frac{1}{4\pi} \iint (\phi - \phi') \frac{\partial}{\partial n} \left(\frac{1}{r} \right) dS + \frac{\kappa_1}{4\pi} \iint \frac{\partial}{\partial n} \left(\frac{1}{r} \right) d\sigma_1 + \frac{\kappa_2}{4\pi} \iint \frac{\partial}{\partial n} \left(\frac{1}{r} \right) d\sigma_2 + \dots \quad (13)$$

where ϕ is the single-valued velocity-potential which obtains in the modified region, and ϕ' is the velocity-potential of the acyclic motion which is generated in the external space when the proper normal velocity $-\partial\phi/\partial n$ is given to each element δS of a membrane coincident in position with the original boundary

Another mode of representing the irrotational motion of a liquid, whether cyclic or not, will present itself in the chapter on Vortex Motion.

We here close this account of the theory of irrotational motion. The mathematical reader will doubtless have noticed the absence of some important links in the chain of our propositions. For example, apart from physical considerations, no proof has been offered that a function ϕ exists which satisfies the conditions of Art. 36 throughout any given simply-connected region, and has arbitrarily prescribed values over the boundary. The formal proof of 'existence-theorems' of this kind is not attempted in the present treatise. For a review of the literature of this part of the subject the reader may consult the authors cited below†

* Cf Larmor, "On the Mathematical Expression of the Principle of Huyghens," *Proc Lond. Math Soc.* (2) t. 1 p. 1 (1903)

† H Burkhardt and W F Meyer, "Potentialtheorie," and A. Sommerfeld, "Randwerth-aufgaben in der Theorie d. part Diff-Gleichungen," *Encycl d. math. Wiss.*, t. II. (1900)

CHAPTER IV.

MOTION OF A LIQUID IN TWO DIMENSIONS

59 IF the velocities u, v be functions of x, y only, whilst w is zero, the motion takes place in a series of planes parallel to xy , and is the same in each of these planes. The investigation of the motion of a liquid under these circumstances is characterized by certain analytical peculiarities, and the solutions of several problems of great interest are readily obtained.

Since the whole motion is known when we know that in the plane $z = 0$, we may confine our attention to that plane. When we speak of points and lines drawn in it, we shall understand them to represent respectively the straight lines parallel to the axis of z , and the cylindrical surfaces having their generating lines parallel to the axis of z , of which they are the traces

By the flux across any curve we shall understand the volume of fluid which in unit time crosses that portion of the cylindrical surface, having the curve as base, which is included between the planes $z = 0, z = 1$

Let A, P be any two points in the plane xy . The flux across any two lines joining AP is the same, provided they can be reconciled without passing out of the region occupied by the moving liquid, for otherwise the space included between these two lines would be gaining or losing matter. Hence if A be fixed, and P variable, the flux across any line AP is a function of the position of P . Let ψ be this function; more precisely, let ψ denote the flux across AP *from right to left*, as regards an observer placed on the curve, and looking along it from A in the direction of P . Analytically, if l, m be the direction-cosines of the normal (drawn to the left) to any element δs of the curve, we have

$$\psi = \int_A^P (lu + mv) ds. \dots\dots\dots (1)$$

If the region occupied by the liquid be aperiphractic (see p 38), ψ is necessarily a single-valued function, but in periphractic regions the value of ψ may depend on the nature of the path AP . For spaces of two dimensions, however, periphraxy and multiple-connectivity become the same thing, so that

the properties of ψ , when it is a many-valued function, in relation to the nature of the region occupied by the moving liquid, may be inferred from Art. 50, where we have discussed the same question with regard to ϕ . The cyclic constants of ψ , when the region is periphractic, are the values of the flux across the closed curves forming the several parts of the internal boundary.

A change, say from A to B , of the point from which ψ is reckoned has merely the effect of adding a constant, viz the flux across a line BA , to the value of ψ , so that we may, if we please, regard ψ as indeterminate to the extent of an additive constant.

If P move about in such a manner that the value of ψ does not alter, it will trace out a curve such that no fluid anywhere crosses it, i.e a stream-line. Hence the curves $\psi = \text{const.}$ are the stream-lines, and ψ is called the 'stream-function.'

If P receive an infinitesimal displacement $PQ (= \delta y)$ parallel to y , the increment of ψ is the flux across PQ from right to left, i.e $\delta\psi = -u \cdot PQ$, or

$$u = -\frac{\partial\psi}{\partial y}. \dots \dots \dots (2)$$

Again, displacing P parallel to x , we find in the same way

$$v = \frac{\partial\psi}{\partial x}. \dots \dots \dots (3)$$

The existence of a function ψ related to u and v in this manner might also have been inferred from the form which the equation of continuity takes in this case, viz

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0, \dots \dots \dots (4)$$

which is the analytical condition that $udy - vdx$ should be an exact differential*

The foregoing considerations apply whether the motion be rotational or irrotational. The formulae for the component angular velocities, given in Art 30, become

$$\xi = 0, \quad \eta = 0, \quad \zeta = \frac{1}{2} \left(\frac{\partial^2\psi}{\partial x^2} + \frac{\partial^2\psi}{\partial y^2} \right), \dots \dots \dots (5)$$

so that in irrotational motion we have

$$\frac{\partial^2\psi}{\partial x^2} + \frac{\partial^2\psi}{\partial y^2} = 0 \dots \dots \dots (6)$$

* The function ψ was introduced in this way by Lagrange, *Nouv m  m de l'Acad de Berlin*, 1781 [*Oeuvres*, t iv p 720]. The kinematical interpretation is due to Rankine, "On Plane Water-Lines in Two Dimensions," *Phil. Trans* 1864 [*Miscellaneous Scientific Papers*, London, 1881, p 495]

60 In what follows we confine ourselves to the case of irrotational motion, which is, as we have already seen, characterized by the existence, in addition, of a velocity-potential ϕ , connected with u, v by the relations

$$u = -\frac{\partial \phi}{\partial x}, \quad v = -\frac{\partial \phi}{\partial y}, \quad \dots \dots \dots (1)$$

and, since we are considering the motion of incompressible fluids only, satisfying the equation of continuity

$$\frac{\partial^2 \phi}{\partial x^2} + \frac{\partial^2 \phi}{\partial y^2} = 0 \quad \dots \dots \dots (2)$$

The theory of the function ϕ , and the relation between its properties and the nature of the two-dimensional space through which the irrotational motion holds, may be readily inferred from the corresponding theorems in three dimensions proved in the last chapter. The alterations, whether of enunciation or of proof, which are requisite to adapt these to the case of two dimensions are for the most part purely verbal.

An exception, which we will briefly examine, occurs however in the case of the theorem of Art. 38 and of those which depend on it.

If δs be an element of the boundary of any portion of the plane xy which is occupied wholly by moving liquid, and if δn be an element of the normal to δs drawn inwards, we have, by Art. 36,

$$\int \frac{\partial \phi}{\partial n} ds = 0, \quad \dots \dots \dots (3)$$

the integration extending round the whole boundary. If this boundary be a circle, and if r, θ be polar co-ordinates referred to the centre P of this circle as origin, the last equation may be written

$$\int_0^{2\pi} \frac{\partial \phi}{\partial r} \cdot r d\theta = 0, \quad \text{or} \quad \frac{\partial}{\partial r} \int_0^{2\pi} \phi d\theta = 0.$$

Hence the integral

$$\frac{1}{2\pi} \int_0^{2\pi} \phi d\theta,$$

i.e. the mean value of ϕ over a circle of centre P and radius r , is independent of the value of r , and therefore remains unaltered when r is diminished without limit, in which case it becomes the value of ϕ at P .

If the region occupied by the fluid be periphractic, and if we apply (3) to the space enclosed between one of the internal boundaries and a circle with centre P and radius r surrounding this boundary, and lying wholly in the fluid, we have

$$\int_0^{2\pi} \frac{\partial \phi}{\partial r} \cdot r d\theta = -M, \quad \dots \dots \dots (4)$$

where the integration in the first member extends over the circle only, and M denotes the flux into the region across the internal boundary. Hence

$$\frac{\partial}{\partial r} \frac{1}{2\pi} \int_0^{2\pi} \phi d\theta = -\frac{M}{2\pi r},$$

which gives on integration $\frac{1}{2\pi} \int_0^{2\pi} \phi d\theta = -\frac{M}{2\pi} \log r + C, \quad \dots \dots \dots (5)$

i.e. the mean value of ϕ over a circle with centre P and radius r is equal to $-M/2\pi \cdot \log r + C$,

where C is independent of r but may vary with the position of P . This formula holds of course only so far as the circle embraces the same internal boundary, and lies itself wholly in the fluid.

If the region be unlimited externally, and if the circle embrace the whole of the internal boundaries, and if further the velocity be everywhere zero at infinity, then C is an absolute constant, as is seen by reasoning similar to that of Art. 41. It may then be shewn that the value of ϕ at a very great distance r from the internal boundary tends to the value $-M/2\pi \log r + C$. In the particular case of $M=0$ the limit to which ϕ tends at infinity is finite, in all other cases it is infinite, and of the opposite sign to M . We infer, as before, that there is only one single-valued function ϕ which 1° satisfies the equation (2) at every point of the plane xy external to a given system of closed curves, 2° makes the value of $\partial\phi/\partial n$ equal to an arbitrarily given quantity at every point of these curves, and 3° has its first differential coefficients all zero at infinity.

If we imagine point-sources, of the type explained in Art. 56, to be distributed uniformly along the axis of z , it is readily found that the velocity at a distance r from this axis will be in the direction of r , and equal to $m/2\pi r$, where m is a certain constant. This arrangement constitutes what may be called a 'line-source,' and its velocity-potential may be taken to be

$$\phi = -\frac{m}{2\pi} \log r. \quad \dots \dots \dots (6)$$

The reader who is interested in the matter will have no difficulty in working out a theory of two-dimensional sources and sinks, similar to that of Arts. 56-58*.

61 The kinetic energy T of a portion of fluid bounded by a cylindrical surface whose generating lines are parallel to the axis of z , and by two planes perpendicular to the axis of z at unit distance apart, is given by the formula

$$2T = \rho \iint \left\{ \left(\frac{\partial \phi}{\partial x} \right)^2 + \left(\frac{\partial \phi}{\partial y} \right)^2 \right\} dx dy = -\rho \int \phi \frac{\partial \phi}{\partial n} ds, \quad \dots \dots (1)$$

where the surface-integral is taken over the portion of the plane xy cut off by the cylindrical surface, and the line-integral round the boundary of this portion. Since $\partial\phi/\partial n = -\partial\psi/\partial s$, the formula (1) may be written

$$2T = \rho \int \phi d\psi, \quad \dots \dots \dots (2)$$

the integration being carried in the positive direction round the boundary.

If we attempt by a process similar to that of Art. 46 to calculate the energy in the case where the region extends to infinity, we find that its value is infinite, except when the total flux outwards (M) is zero. For if we introduce a circle of great radius r as the external boundary of the portion of the plane xy considered, we find that the corresponding part of the integral on the right-hand side of (1) increases indefinitely with r . The only exception is when $M=0$, in which case we may suppose the line-integral in (1) to extend over the internal boundary only.

If the cylindrical part of the boundary consist of two or more separate portions one of which embraces all the rest, the enclosed region is multiply-

* This subject has been treated very fully by C. Neumann, *Ueber das logarithmische und Newton'sche Potential*, Leipzig, 1877.

connected, and the equation (1) needs a correction, which may be applied exactly as in Art 55.

62. The functions ϕ and ψ are connected by the relations

$$\frac{\partial \phi}{\partial x} = \frac{\partial \psi}{\partial y}, \quad \frac{\partial \phi}{\partial y} = -\frac{\partial \psi}{\partial x} \quad \dots \dots \dots (1)$$

These conditions are fulfilled by equating $\phi + i\psi$, where i stands as usual for $\sqrt{-1}$, to any ordinary algebraic or transcendental function of $x + iy$, say

$$\phi + i\psi = f(x + iy) \quad \dots \dots \dots (2)$$

For then
$$\frac{\partial}{\partial y} (\phi + i\psi) = if'(x + iy) = i \frac{\partial}{\partial x} (\phi + i\psi), \quad \dots \dots \dots (3)$$

whence, equating separately the real and the imaginary parts, we see that the equations (1) are satisfied.

Hence any assumption of the form (2) gives a possible case of irrotational motion. The curves $\phi = \text{const.}$ are the curves of equal velocity-potential, and the curves $\psi = \text{const.}$ are the stream-lines. Since, by (1),

$$\frac{\partial \phi}{\partial x} \frac{\partial \psi}{\partial x} + \frac{\partial \phi}{\partial y} \frac{\partial \psi}{\partial y} = 0,$$

we see that these two systems of curves cut one another at right angles, as already proved. Since the relations (1) are unaltered when we write $-\psi$ for ϕ , and ϕ for ψ , we may, if we choose, look upon the curves $\psi = \text{const.}$ as the equipotential curves, and the curves $\phi = \text{const.}$ as the stream-lines, so that every assumption of the kind indicated gives us *two* possible cases of irrotational motion.

For shortness, we shall through the rest of this chapter follow the usual notation of the Theory of Functions, and write

$$z = x + iy, \quad \dots \dots \dots (4)$$

$$w = \phi + i\psi \quad \dots \dots \dots (5)$$

From a modern point of view, the fundamental property of a *function* of a complex variable is that it has a definite differential coefficient with respect to that variable*. If ϕ, ψ denote any functions whatever of x and y , then corresponding to every value of $x + iy$ there must be one or more definite values of $\phi + i\psi$; but the ratio of the differential of this function to that of $x + iy$, viz.

$$\frac{\delta \phi + i \delta \psi}{\delta x + i \delta y}, \quad \text{or} \quad \frac{\left(\frac{\partial \phi}{\partial x} + i \frac{\partial \psi}{\partial x} \right) \delta x + \left(\frac{\partial \phi}{\partial y} + i \frac{\partial \psi}{\partial y} \right) \delta y}{\delta x + i \delta y},$$

* See, for example, Forsyth, *Theory of Functions*, 2nd ed., Cambridge, 1900, cc. i, ii

depends in general on the ratio $\delta x \cdot \delta y$. The condition that it should be the same for all values of the latter ratio is

$$\frac{\partial \phi}{\partial y} + i \frac{\partial \psi}{\partial y} = i \left(\frac{\partial \phi}{\partial x} + i \frac{\partial \psi}{\partial x} \right), \quad \dots \dots \dots (6)$$

which is equivalent to (1) above. This property was adopted by Riemann as the definition of a function of the complex variable $x + iy$; viz such a function must have, for every assigned value of the variable, not only a definite value or system of values, but also for each of these values a definite differential coefficient. The advantage of this definition is that it is quite independent of the existence of an analytical expression for the function.

If the complex quantities z and w be represented geometrically after the manner of Argand and Gauss, the differential coefficient dw/dz may be interpreted as the operator which transforms an infinitesimal vector δz into the corresponding vector δw . It follows then, from the above property, that corresponding figures in the planes of z and w are similar in their infinitely small parts.

For instance, in the plane of w the straight lines $\phi = \text{const}$, $\psi = \text{const}$., where the constants have assigned to them a series of values in arithmetical progression, the common difference being infinitesimal and the same in each case, form two systems of straight lines at right angles, dividing the plane into infinitely small squares. Hence in the plane xy the corresponding curves $\phi = \text{const}$, $\psi = \text{const}$, the values of the constants being assigned as before, cut one another at right angles (as has already been proved otherwise) and divide the plane into infinitely small squares.

Conversely, if ϕ, ψ be any two functions of x, y such that the curves $\phi = m\epsilon$, $\psi = n\epsilon$, where ϵ is infinitesimal, and m, n are any integers, divide the plane xy into elementary squares, it is evident geometrically that

$$\frac{\partial x}{\partial \phi} = \pm \frac{\partial y}{\partial \psi}, \quad \frac{\partial x}{\partial \psi} = \mp \frac{\partial y}{\partial \phi}.$$

If we take the upper signs, these are the conditions that $x + iy$ should be a function of $\phi + i\psi$. The case of the lower signs is reduced to this by reversing the sign of ψ . Hence the equation (2) contains the *complete* solution of the problem of orthomorphic projection from one plane to another*.

The similarity of corresponding infinitely small portions of the planes w and z breaks down at points where the differential coefficient dw/dz is zero or infinite. Since

$$\frac{dw}{dz} = \frac{\partial \phi}{\partial x} + i \frac{\partial \psi}{\partial x}, \quad \dots \dots \dots (7)$$

the corresponding value of the velocity, in the hydrodynamical application, is zero or infinite.

* Lagrange, "Sur la construction des cartes géographiques," *Nouv. mém. de l'Acad. de Berlin*, 1779 [*Oeuvres*, t. iv. p. 636]. For the further history of the problem, see Forsyth, *Theory of Functions*, c. xix.

In all physical applications, w must be a single-valued, or at most a cyclic function of z , in the sense of Art 50, throughout the region with which we are concerned. Hence in the case of a 'multiform' function, this region must be confined to a single sheet of the corresponding Riemann's surface, and 'branch-points' therefore must not occur in its interior.

63. We can now proceed to some applications of the foregoing method.

First let us assume $w = Az^n$,

A being real. Introducing polar co-ordinates r, θ , we have

$$\left. \begin{aligned} \phi &= Ar^n \cos n\theta, \\ \psi &= Ar^n \sin n\theta \end{aligned} \right\} \dots \dots \dots (1)$$

The following cases may be noticed

1°. If $n=1$, the stream-lines are a system of straight lines parallel to x , and the equipotential curves are a similar system parallel to y . In this case any corresponding figures in the planes of w and z are similar, whether they be finite or infinitesimal.

2°. If $n=2$, the curves $\phi = \text{const.}$ are a system of rectangular hyperbolas having the axes of co-ordinates as their principal axes, and the curves $\psi = \text{const.}$ are a similar system, having the co-ordinate axes as asymptotes. The lines $\theta = 0, \theta = \frac{1}{2}\pi$ are parts of the same stream-line $\psi = 0$, so that we may take the positive parts of the axes of x, y as fixed boundaries, and thus obtain the case of a fluid in motion in the angle between two perpendicular walls.

3°. If $n=-1$, we get two systems of circles touching the axes of co-ordinates at the origin. Since now $\phi = A/r \cos \theta$, the velocity at the origin is infinite, we must therefore suppose the region to which our formulae apply to be limited internally by a closed curve.

4°. If $n=-2$, each system of curves is composed of a double system of lemniscates. The axes of the system $\phi = \text{const.}$ coincide with x or y , those of the system $\psi = \text{const.}$ bisect the angles between these axes.

5°. By properly choosing the value of n we get a case of irrotational motion in which the boundary is composed of two rigid walls inclined at any angle α . The equation of the stream-lines being

$$r^n \sin n\theta = \text{const.}, \quad \dots \dots \dots (2)$$

we see that the lines $\theta = 0, \theta = \pi/n$ are parts of the same stream-line. Hence if we put $n = \pi/\alpha$, we obtain the required solution in the form

$$\phi = Ar^{\frac{\pi}{\alpha}} \cos \frac{\pi\theta}{\alpha}, \quad \psi = Ar^{\frac{\pi}{\alpha}} \sin \frac{\pi\theta}{\alpha} \quad \dots \dots \dots (3)$$

The component velocities along and perpendicular to r , are

$$-A \frac{\pi}{\alpha} r^{\frac{\pi}{\alpha}-1} \cos \frac{\pi\theta}{\alpha}, \quad \text{and} \quad A \frac{\pi}{\alpha} r^{\frac{\pi}{\alpha}-1} \sin \frac{\pi\theta}{\alpha},$$

and are therefore zero, finite, or infinite at the origin, according as α is less than, equal to, or greater than π .

64. We take next some cases of cyclic functions.

1°. The assumption $w = -\mu \log z$, (1)

where μ is real, gives $\phi = -\mu \log r$, $\psi = -\mu\theta$.. (2)

The velocity at a distance r from the origin is μ/r , this point must therefore be isolated by drawing a closed curve round it

If we take the radii $\theta = \text{const.}$ as the stream-lines we get the case of a (two-dimensional) source at the origin (See Art 60)

If the circles $r = \text{const.}$ be taken as stream-lines we have the case of Art 27; the motion is now cyclic, the circulation in any circuit embracing the origin being $2\pi\mu$.

2° Let us take $w = -\mu \log \frac{z-a}{z+a}$ (3)

If we denote by r_1, r_2 the distances of any point in the plane xy from the points $(\pm a, 0)$, and by θ_1, θ_2 , the angles which these distances make with the positive direction of the axis of x , we have

$$z - a = r_1 e^{i\theta_1}, \quad z + a = r_2 e^{i\theta_2},$$

whence $\phi = -\mu \log r_1/r_2$, $\psi = -\mu(\theta_1 - \theta_2)$... (4)


The curves $\phi = \text{const.}$, $\psi = \text{const.}$ form two orthogonal systems of 'coaxial' circles.

Either of these systems may be taken as the equipotential curves, and the other system will then form the stream-lines. In either case the velocity at the points $(\pm a, 0)$ will be infinite. If these points be accordingly isolated by drawing closed curves round them, the rest of the plane xy becomes a triply-connected region.

If the circles $\theta_1 - \theta_2 = \text{const.}$ be taken as the stream-lines we have the case of a source and a sink, of equal intensities, situate at the points $(\pm a, 0)$. If a is diminished indefinitely, whilst μa remains finite, we reproduce the assumption of Art. 63, 3°, which therefore corresponds to the case of a double line-source at the origin (See the first diagram of Art 68)

If, on the other hand, we take the circles $r_1/r_2 = \text{const.}$ as the stream-lines we get a case of cyclic motion, viz the circulation in any circuit embracing the first (only) of the above points is $2\pi\mu$, that in a circuit embracing the

second is $-2\pi\mu$, whilst that in a circuit embracing both is zero. This example will have additional interest for us when in Chap VII we come to treat of 'Rectilinear Vortices'.



65. If w be a function of z , it follows at once from the definition of Art 62 that z is a function of w . The latter form of assumption is sometimes more convenient analytically than the former.

The relations (1) of Art 62 are then replaced by

$$\frac{\partial x}{\partial \phi} = \frac{\partial y}{\partial \psi}, \quad \frac{\partial x}{\partial \psi} = -\frac{\partial y}{\partial \phi} \quad \dots \dots \dots (1)$$

Also since

$$\frac{dw}{dz} = \frac{\partial \phi}{\partial x} + i \frac{\partial \psi}{\partial x} = -u + iv,$$

we have

$$-\frac{dz}{dw} = \frac{1}{u - iv} = \frac{1}{q} \left(\frac{u}{q} + i \frac{v}{q} \right),$$

where q is the resultant velocity at (x, y) . Hence if we write

$$\zeta = -\frac{dz}{dw}, \quad \dots \dots \dots (2)$$

and imagine the properties of the function ζ to be exhibited graphically in the manner already explained, the vector drawn from the origin to any point in the plane of ζ will agree in direction with, and be in magnitude the reciprocal of, the velocity at the corresponding point of the plane of z .

Again, since $1/q$ is the modulus of dz/dw , i.e. of $\partial x/\partial\phi + i\partial y/\partial\phi$, we have

$$\frac{1}{q^2} = \left(\frac{\partial x}{\partial\phi}\right)^2 + \left(\frac{\partial y}{\partial\phi}\right)^2, \quad \dots \dots \dots (3)$$

which may, by (1), be put into the equivalent forms

$$\frac{1}{q^2} = \left(\frac{\partial x}{\partial\phi}\right)^2 + \left(\frac{\partial x}{\partial\psi}\right)^2 = \left(\frac{\partial y}{\partial\psi}\right)^2 + \left(\frac{\partial y}{\partial\phi}\right)^2 = \left(\frac{\partial y}{\partial\psi}\right)^2 + \left(\frac{\partial x}{\partial\psi}\right)^2 = \frac{\partial x}{\partial\phi} \frac{\partial y}{\partial\psi} - \frac{\partial x}{\partial\psi} \frac{\partial y}{\partial\phi} \dots \dots (4)$$

The last formula, viz
$$\frac{1}{q^2} = \frac{\partial(x, y)}{\partial(\phi, \psi)}, \quad \dots \dots \dots (5)$$

expresses the fact that corresponding elementary areas in the planes of z and w are in the ratio of the square of the modulus of dz/dw to unity.

66 The following examples of this procedure are important

1° Assume
$$z = c \cosh w, \quad \dots \dots \dots (1)$$

or
$$\left. \begin{aligned} x &= c \cosh \phi \cos \psi, \\ y &= c \sinh \phi \sin \psi. \end{aligned} \right\} \quad \dots \dots \dots (2)$$

The curves $\phi = \text{const}$ are the ellipses

$$\frac{x^2}{c^2 \cosh^2 \phi} + \frac{y^2}{c^2 \sinh^2 \phi} = 1, \quad \dots \dots \dots (3)$$

and the curves $\psi = \text{const}$ are the hyperbolas


$$\frac{x^2}{c^2 \cos^2 \psi} - \frac{y^2}{c^2 \sin^2 \psi} = 1, \quad \dots \dots \dots (4)$$

these conics having the common foci $(\pm c, 0)$. The two systems of curves are shewn on the next page.

Since at the foci we have $\phi = 0$, $\psi = n\pi$, n being some integer, we see by (2) of the preceding Art that the velocity there is infinite. If the hyperbolas be taken as the stream-lines, the portions of the axis of x which lie outside the points $(\pm c, 0)$ may be taken as rigid boundaries. We obtain in this manner the case of a liquid flowing from one side to the other of a thin plane partition, through an aperture of breadth $2c$, the velocity at the edges is however infinite.

If the ellipses be taken as the stream-lines we get the case of a liquid circulating round an elliptic cylinder, or, as an extreme case, round a rigid lamina whose section is the line joining the foci $(\pm c, 0)$.

At an infinite distance from the origin ϕ is infinite, of the order $\log r$, where r is the radius vector, and the velocity is infinitely small of the order $1/r$



2° Let

$$z = w + e^w, \dots\dots\dots (5)$$

or

$$x = \phi + e^\phi \cos \psi, \quad y = \psi + e^\phi \sin \psi. \dots\dots (6)$$

The stream-line $\psi=0$ coincides with the axis of x . Again the portion of the line $y=\pi$ between $x=-\infty$ and $x=-1$, considered as a line bent back on itself, forms the stream-line $\psi=\pi$, viz as ϕ decreases from $+\infty$ through 0 to $-\infty$, x increases from $-\infty$ to -1 and then decreases to $-\infty$ again. Similarly for the stream-line $\psi=-\pi$


Since

$$\zeta = -dz/dw = -1 - e^\phi \cos \psi - ie^\phi \sin \psi,$$

it appears that for large negative values of ϕ the velocity is in the direction of x -negative, and equal to unity, whilst for large positive values it is zero

The above formulae therefore express the motion of a liquid flowing into a canal bounded by two thin parallel walls from an open space. At the ends of the walls we have $\phi=0$, $\psi=\pm\pi$, and therefore $\zeta=0$, i.e. the velocity is infinite. The direction of the flow will be reversed if we change the sign of w in (5). The forms of the stream-lines, drawn, as in all similar cases in this chapter, for equidistant values of ψ , are shewn on the opposite page*.

* This example was given by Helmholtz, *Berl Monatsber*, April 23, 1868 [*Phil Mag*, Nov 1868, *Ges. Abh*, t 1 p 154]



67. It is known that a function $f(z)$ which is finite, continuous, and single-valued, and has its first derivative finite, at all points of the space included between two concentric circles about the origin, can be expanded in the form

$$f(z) = A_0 + A_1 z + A_2 z^2 + \dots + B_1 z^{-1} + B_2 z^{-2} + \dots \quad (1)$$

If the above conditions be satisfied at all points within a circle having the origin as centre, we retain only the ascending series, if at all points without such a circle, the descending series, with the addition of the constant A_0 , is sufficient. If the conditions be fulfilled for all points of the plane xy without exception, $f(z)$ can be no other than a constant A_0 .

Putting $f(z) = \phi + i\psi$, introducing polar co-ordinates, and writing the complex constants A_n, B_n , in the forms $P_n + iQ_n, R_n + iS_n$, respectively, we obtain

$$\begin{aligned} \phi &= P_0 + \sum_1^\infty r^n (P_n \cos n\theta - Q_n \sin n\theta) + \sum_1^\infty r^{-n} (R_n \cos n\theta + S_n \sin n\theta), \\ \psi &= Q_0 + \sum_1^\infty r^n (Q_n \cos n\theta + P_n \sin n\theta) + \sum_1^\infty r^{-n} (S_n \cos n\theta - R_n \sin n\theta) \end{aligned} \quad (2)$$

These formulae are convenient in treating problems where we have the value of ϕ , or of $\partial\phi/\partial n$, given over the circular boundaries. This value may be expanded for each boundary in a series of sines and cosines of multiples of θ , by Fourier's theorem. The series thus found must be equivalent to those obtained from (2), whence, equating separately coefficients of $\sin n\theta$ and $\cos n\theta$, we obtain equations to determine P_n, Q_n, R_n, S_n .

68 As a simple example let us take the case of an infinitely long circular cylinder of radius a moving with velocity U perpendicular to its length, in an infinite mass of liquid which is at rest at infinity.

Let the origin be taken in the axis of the cylinder, and the axes of x, y in a plane perpendicular to its length. Further let the axis of x be in the direction of the velocity U . The motion, having originated from rest, will necessarily be irrotational, and ϕ will be single-valued. Also, since $\int \partial\phi/\partial n \, ds$, taken round the section of the cylinder, is zero, ψ is also single-valued (Art 59), so that the formulae (2) apply. Moreover, since $\partial\phi/\partial n$ is given at every point of the internal boundary of the fluid, viz

$$-\frac{\partial\phi}{\partial r} = U \cos \theta, \text{ for } r = a, \quad \dots \dots \dots (3)$$

and since the fluid is at rest at infinity, the problem is determinate, by Art. 41. These conditions give $P_n = 0$, $Q_n = 0$, and

$$U \cos \theta = \sum_1^\infty n a^{-n-1} (R_n \cos n\theta + S_n \sin n\theta),$$

which only can be satisfied by making $R_1 = Ua^2$, and all the other coefficients zero. The complete solution is therefore

$$\phi = \frac{Ua^2}{r} \cos \theta, \quad \psi = -\frac{Ua^2}{r} \sin \theta. \quad \dots \dots \dots (4)$$

The stream-lines $\psi = \text{const}$ are circles, as shewn on the opposite page

The kinetic energy of the liquid is given by the formula (2) of Art 61, viz.

$$2T = \rho \int \phi d\psi = \rho U^2 a^2 \int_0^{2\pi} \cos^2 \theta \, d\theta = M' U^2, \quad \dots \dots (5)$$

if $M' = \pi a^2 \rho$, be the mass of fluid displaced by unit length of the cylinder. This result shews that the whole effect of the presence of the fluid may be represented by an addition M' to the inertia per unit length of the cylinder. Thus, in the case of rectilinear motion, if we have an extraneous force X per unit length acting on the cylinder, the equation of energy gives

$$\frac{d}{dt} \left(\frac{1}{2} M U^2 + \frac{1}{2} M' U^2 \right) = X U,$$

or

$$(M + M') \frac{dU}{dt} = X, \quad \dots \dots \dots (6)$$

where M represents the mass of the cylinder itself

Writing this in the form


$$M \frac{dU}{dt} = X - M' \frac{dU}{dt},$$

we learn that the pressure of the fluid is equivalent to a force $-M'dU/dt$ per unit length in the direction of motion. This vanishes when U is constant.

The above result must of course admit of verification by direct calculation. The pressure is given by the formula

$$\frac{p}{\rho} = \frac{\partial \phi}{\partial t} - \frac{1}{2} q^2 + F(t), \dots \dots \dots (7)$$

where we have omitted the term due to the extraneous forces (if any) acting on the fluid, the effect of which can be found by the rules of Hydrostatics. The term $\partial \phi / \partial t$ here expresses the rate at which ϕ is increasing at a fixed point of space, whereas the value of ϕ in (4) is referred to an origin which is in motion with the velocity U . In consequence



of this the value of r for any fixed point is increasing at the rate $-U \cos \theta$, and that of θ at the rate $U/r \sin \theta$. Hence we must put

$$\frac{\partial \phi}{\partial t} = \frac{dU}{dt} \frac{\alpha^2}{r} \cos \theta - U \cos \theta \frac{\partial \phi}{\partial r} + \frac{U \sin \theta}{r} \frac{\partial \phi}{\partial \theta} = \frac{dU}{dt} \frac{\alpha^2}{r} \cos \theta + \frac{U^2 \alpha^2}{r^2} \cos 2\theta$$

Since, also, $q^2 = U^2 \alpha^4 / r^4$, the pressure at any point of the cylindrical surface ($r = \alpha$) is

$$p = \rho \left(\alpha \frac{dU}{dt} \cos \theta + U^2 \cos 2\theta - \frac{1}{2} U^2 + F(t) \right). \dots \dots (8)$$


The resultant force on unit length of the cylinder is evidently parallel to the initial line $\theta = 0$; to find its amount we multiply by $-\alpha d\theta \cos \theta$ and integrate with respect to θ between the limits 0 and π . The result is $-M'dU/dt$, as before

If in the above example we impress on the fluid and the cylinder a velocity $-U$ we have the case of a current flowing with the general velocity

U past a fixed cylindrical obstacle Adding to ϕ and ψ the terms $Ur \cos \theta$ and $Ur \sin \theta$, respectively, we get

$$\phi = U \left(r + \frac{a^2}{r} \right) \cos \theta, \quad \psi = U \left(r - \frac{a^2}{r} \right) \sin \theta \quad \dots \dots (9)$$

If no extraneous forces act, and if U be constant, the resultant force on the cylinder is zero Cf Art 92



69 To render the formula (1) of Art. 67 capable of representing *any* case of continuous irrotational motion in the space between two concentric circles, we must add to the right-hand side the term

$$A \log z. \quad \dots \dots \dots (1)$$

If $A = P + iQ$, the corresponding terms in ϕ, ψ are


$$P \log r - Q\theta, \quad P\theta + Q \log r, \quad \dots \dots \dots (2)$$

respectively The meaning of these terms is evident, viz $2\pi P$, the cyclic constant of ψ , is the flux across the inner (or outer) circle, and $2\pi Q$, the cyclic constant of ϕ , is the circulation in any circuit embracing the origin

For example, returning to the problem of the last Art, let us suppose that in addition to the motion produced by the cylinder we have an independent circulation round it, the cyclic constant being κ . The boundary-condition is then satisfied by

$$\phi = U \frac{a^2}{r} \cos \theta - \frac{\kappa}{2\pi} \theta. \quad \dots \dots \dots (3)$$

The effect of the cyclic motion, superposed on that due to the cylinder, will be to augment the velocity on one side, and to diminish (and, it may be, to reverse) it on the other. Hence when the cylinder moves in a straight line with constant velocity, there will be a diminished pressure on one side, and an increased pressure on the other, so that a constraining force must be applied at right angles to the direction of motion.



The figure shews the lines of flow. At a distance from the origin they approximate to the form of concentric circles, the disturbance due to the cylinder becoming small in comparison with the cyclic motion. When, as in the case represented, $U > \kappa/2\pi a$, there is a point of zero velocity in the fluid. The stream-line system has the same configuration in all cases, the only effect of a change in the value of U being to alter the scale, relative to the diameter of the cylinder.

To calculate the effect of the fluid pressures on the cylinder when moving in any manner we write

$$\phi = \frac{Ua^2}{r} \cos(\theta - \chi) - \frac{\kappa}{2\pi} \theta, \quad . \quad . \quad . \quad (4)$$

where χ is the angle which the direction of motion makes with the axis of x . In the formula for the pressure [Art. 68 (7)] we must put, for $r = a$,

$$\begin{aligned} \frac{\partial \phi}{\partial t} &= a \frac{dU}{dt} \cos(\theta - \chi) + aU \frac{d\chi}{dt} \sin(\theta - \chi) - U \cos(\theta - \chi) \frac{\partial \phi}{\partial r} + \frac{U}{a} \sin(\theta - \chi) \frac{\partial \phi}{\partial \theta} \\ &= a \frac{dU}{dt} \cos(\theta - \chi) + aU \frac{d\chi}{dt} \sin(\theta - \chi) + U^2 \cos 2(\theta - \chi) - \frac{\kappa}{2\pi a} U \sin(\theta - \chi), \quad . \quad (5) \end{aligned}$$

and
$$\frac{1}{2} Q^2 = \frac{1}{2} U^2 + \frac{1}{8} \frac{\kappa^2}{\pi^2 a^3} + \frac{\kappa}{2\pi a} U \sin(\theta - \chi) \quad . \quad . \quad . \quad . \quad . \quad . \quad (6)$$

The resultant force on the cylinder is found to be made up of a component

$$-M' \frac{dU}{dt}, \dots \dots \dots (7)$$

in the direction of motion, and a component

$$\kappa \rho U - M' U \frac{d\chi}{dt}, \dots \dots \dots (8)$$

at right angles, where $M' = \pi \rho a^2$ as before. Hence if P , Q denote the components of the extraneous forces, if any, acting on the cylinder in the directions of the tangent and the normal to the path, respectively, the equations of motion of the cylinder are

$$\left. \begin{aligned} (M + M') \frac{dU}{dt} &= P, \\ (M + M') U \frac{d\chi}{dt} &= \kappa \rho U + Q \end{aligned} \right\} \dots \dots \dots (9)$$

If there be no extraneous forces, U is constant, and writing $d\chi/dt = U/R$, where R is the radius of curvature of the path, we find

$$R = (M + M') U / \kappa \rho \dots \dots \dots (10)$$

The path is therefore a circle, described in the direction of the cyclic motion*

If ξ , η be the rectangular co-ordinates of the axis of the cylinder, the equations (9) are equivalent to

$$\left. \begin{aligned} (M + M') \xi &= -\kappa \rho \eta + X, \\ (M + M') \eta &= \kappa \rho \xi + Y, \end{aligned} \right\} \dots \dots \dots (11)$$

where X , Y are the components of the extraneous forces. To find the effect of a constant force, we may put

$$X = (M + M') g', \quad Y = 0 \dots \dots \dots (12)$$

The solution then is

$$\left. \begin{aligned} \xi &= a + c \cos (nt + \epsilon), \\ \eta &= \beta + \frac{g'}{n} t + c \sin (nt + \epsilon), \end{aligned} \right\} \dots \dots \dots (13)$$

where a , β , c , ϵ are arbitrary constants, and

$$n = \kappa \rho / (M + M'). \dots \dots \dots (14)$$

This shews that the path is a trochoid, described with a mean velocity g'/n perpendicular to x †. It is remarkable that the cylinder has on the whole no progressive motion in the direction of the extraneous force. In the particular case $c = 0$ its path is a straight line perpendicular to the force. The problem is an illustration of the theory of 'gyrostatic systems,' to be referred to in Chap. VI.

70 The formula (1) of Art. 67, as amended by the addition of the term $A \log z$, may readily be generalized so as to apply to any case of irrotational motion in a region with circular boundaries, one of which encloses all the rest. In fact, for each internal boundary we have a series of the form

$$A \log (z - c) + \frac{A_1}{z - c} + \frac{A_2}{(z - c)^2} + \dots,$$

where $c = a + ib$ say, refers to the centre, and the coefficients A , A_1 , A_2 , ...

* Lord Rayleigh, "On the Irregular Flight of a Tennis Ball," *Mess. of Math.*, t. VII (1878) [*Sci. Papers*, t. I p. 344], Greenhill, *Mess. of Math.*, t. IX. p. 113 (1880).

† Greenhill, *l.c.*

are in general complex quantities. The difficulty however of determining these coefficients so as to satisfy given boundary conditions is now so great as to render this method of very limited application.

Indeed the determination of the irrotational motion of a liquid subject to given boundary conditions is a problem whose exact solution can be effected by direct processes in only a very few cases*. Most of the cases for which we know the solution have been obtained by an inverse process, viz instead of trying to find a value of ϕ or ψ which satisfies $\nabla^2\phi = 0$ or $\nabla^2\psi = 0$ and given boundary conditions, we take some known solution of the differential equations and enquire what boundary conditions it can be made to satisfy. Examples of this method have already been given in Arts 63, 64, and we may carry it further in the following two important cases of the general problem in two dimensions.

71 CASE I The boundary of the fluid consists of a rigid cylindrical surface which is in motion with velocity U in a direction perpendicular to its length.

Let us take as axis of x the direction of this velocity U , and let δs be an element of the section of the surface by the plane xy .

Then at all points of this section the velocity of the fluid in the direction of the normal, which is denoted by $\partial\psi/\partial s$, must be equal to the velocity of the boundary normal to itself, or $-U dy/ds$. Integrating along the section, we have

$$\psi = -Uy + \text{const} \quad \dots \dots \dots (1)$$

If we take any admissible form of ψ , this equation defines a system of curves each of which would by its motion parallel to x give rise to the stream-lines $\psi = \text{const}$ †. We give a few examples.

1° If we choose for ψ the form $-Uy$, (1) is satisfied identically for all forms of the boundary. Hence the fluid contained within a cylinder of any shape which has a motion of translation only may move as a solid body. If, further, the cylindrical space occupied by the fluid be simply-connected, this is the only kind of motion possible. This is otherwise evident from

* A very powerful method of transformation, applicable to cases where the boundaries of the fluid consist of fixed plane walls, has however been developed by Schwarz, "Ueber einige Abbildungsaufgaben," *Crelle*, t lxx [*Gesammelte Abhandlungen*, Berlin, 1890, t ii p 65], Christoffel, "Sul problema delle temperature stazionarie e la rappresentazione di una data superficie," *Annali di Matematica*, Serie II t i. p 89, and Kuchhoff, "Zur Theorie des Condensators," *Berl Monatsber.*, March 15, 1877 [*Ges Abh*, p 101]. Many of the solutions which can be thus obtained are of great interest in the mathematically cognate subjects of Electrostatics, Heat-Conduction, &c. See, for example, J J Thomson, *Recent Researches in Electricity and Magnetism*, Oxford, 1893, c iii.

† Cf Rankine, *l c ante*, p 61, where the method is applied to obtain curves resembling the lines of ships.

Art 40, for the motion of the fluid and the solid as one mass evidently satisfies all the conditions, and is therefore the only solution which the problem admits of.

2° Let $\psi = A/r \cdot \sin \theta$, then (1) becomes

$$\frac{A}{r} \sin \theta = -Ur \sin \theta + \text{const} \dots \dots \dots (2)$$

In this system of curves is included a circle of radius a , provided $A/a = -Ua$. Hence the motion produced in an infinite mass of liquid by a circular cylinder moving through it with velocity u perpendicular to its length, is given by

$$\psi = -\frac{Ua^2}{r} \sin \theta, \dots \dots \dots (3)$$

which agrees with Art 68

3° Let us introduce the elliptic co-ordinates ξ, η , connected with x, y by the relation

$$x + iy = c \cosh(\xi + i\eta), \dots \dots \dots (4)$$

or

$$\left. \begin{aligned} x &= c \cosh \xi \cos \eta, \\ y &= c \sinh \xi \sin \eta, \end{aligned} \right\} \dots \dots \dots (5)$$

(cf Art 66), where ξ may be supposed to range from 0 to ∞ , and η from 0 to 2π . If we now put

$$\phi + i\psi = Ce^{-(\xi + i\eta)}, \dots \dots \dots (6)$$

where C is some real constant, we have

$$\psi = -Ce^{-\xi} \sin \eta, \dots \dots \dots (7)$$

so that (1) becomes $Ce^{-\xi} \sin \eta = Uc \sinh \xi \sin \eta + \text{const}$

In this system of curves is included the ellipse whose parameter ξ_0 is determined by

$$Ce^{-\xi_0} = Uc \sinh \xi_0$$

If a, b be the semi-axes of this ellipse we have

$$a = c \cosh \xi_0, \quad b = c \sinh \xi_0,$$

so that

$$C = \frac{Ubc}{a-b} = Ub \left(\frac{a+b}{a-b} \right)^{\frac{1}{2}}$$

Hence the formula

$$\psi = -Ub \left(\frac{a+b}{a-b} \right)^{\frac{1}{2}} e^{-\xi} \sin \eta \dots \dots \dots (8)$$

gives the motion of an infinite mass of liquid produced by an elliptic cylinder of semi-axes a, b , moving parallel to the greater axis with velocity U .

That the above formulae make the velocity zero at infinity appears from the consideration that, when ξ is large, δx and δy are of the same order as $e^{\xi} \delta \xi$ or $e^{\xi} \delta \eta$, so that $\partial \psi / \partial x$, $\partial \psi / \partial y$ are of the order $e^{-2\xi}$ or $1/r^2$, ultimately, where r denotes the distance of any point from the axis of the cylinder.


If the motion of the cylinder were parallel to the minor axis the formula would be

$$\psi = Va \left(\frac{a+b}{a-b} \right)^{\frac{1}{2}} e^{-\xi} \cos \eta. \dots \dots \dots .(9)$$

The stream-lines are in each case the same for all confocal elliptic forms of the cylinder, so that the formulae hold even when the section reduces to the straight line joining the foci In this case (9) becomes

$$\psi = Vc e^{-\xi} \cos \eta, \dots\dots\dots .(10)$$

which would give the motion produced by an infinitely long lamina of breadth 2c moving ‘broadside on’ in an infinite mass of liquid Since



however this solution makes the velocity infinite at the edges, it is subject to the practical limitation already indicated in several instances*

* This investigation was given in the *Quant Journ of Math*, t xiv (1875) Results equivalent to (8), (9) had however been obtained, in a different manner, by Beltrami, “Su principu fondamentali dell’ idrodinamica razionale,” *Mem dell’ Accad delle Scienze di Bologna*, 1873, p. 394.

The kinetic energy of the fluid is given by

$$2T = \rho \int \phi d\psi = \rho C^2 e^{-2\xi_0} \int_0^{2\pi} \cos^2 \eta d\eta \\ = \pi \rho b^2 U^2, \quad \dots \dots \dots (11)$$

where b is the half-breadth of the cylinder perpendicular to the direction of motion

If the units of length and time be properly chosen we may write

$$x + iy = \cosh(\xi + i\eta), \quad \phi + i\psi = e^{-(\xi + i\eta)},$$

whence

$$x = \phi \left(1 + \frac{1}{\phi^2 + \psi^2} \right), \quad y = \psi \left(1 - \frac{1}{\phi^2 + \psi^2} \right)$$

These formulae are convenient for tracing the curves $\phi = \text{const}$, $\psi = \text{const}$, which are figured on the preceding page

By superposition of the results (8) and (9) we obtain, for the case of an elliptic cylinder having a velocity of translation whose components are U , V ,

$$\psi = - \left(\frac{a+b}{a-b} \right)^{\frac{1}{2}} e^{-\xi} (U b \sin \eta - V a \cos \eta). \quad (12)$$

To find the motion relative to the cylinder we must add to this the expression

$$Uy - Vx = c (U \sinh \xi \sin \eta - V \cosh \xi \cos \eta) \quad (13)$$


For example, the stream-function for a current impinging at an angle of 45° on a plane lamina whose edges are at $x = \pm c$ is

$$\psi = - \frac{1}{\sqrt{2}} q_0 c \sinh \xi (\cos \eta - \sin \eta), \quad \dots \dots \dots (14)$$

where q_0 is the velocity at infinity This immediately verifies, for it makes $\psi = 0$ for $\xi = 0$, and gives

$$\psi = - \frac{q_0}{\sqrt{2}} (x - y)$$

for $\xi = \infty$ The stream-lines for this case are shewn in the annexed figure (turned through



45° for convenience)* This will serve to illustrate some results to be obtained later in Chap VI

* Prof Hele Shaw has made a number of beautiful experimental delineations of the forms of the stream-lines in cases of steady irrotational motion in two dimensions, including those figured on pp 74, 80, see *Trans Inst. Nav. Arch*, t. xI (1898). The theory of his method will find a place in Chap XI

If we trace the course of the stream-line $\psi=0$ from $\phi=+\infty$ to $\phi=-\infty$, we find that it consists in the first place of the hyperbolic arc $\eta=\frac{1}{4}\pi$, meeting the lamina at right angles, it then divides into two portions, following the faces of the lamina, which finally re-unite and are continued as the hyperbolic arc $\eta=\frac{5}{4}\pi$. The points where the hyperbolic arcs abut on the lamina are points of zero velocity, and therefore of maximum pressure. It is plain that the fluid pressures on the lamina are equivalent to a couple tending to set it broadside on to the stream, and it is easily found that the moment of this couple, per unit length, is $\frac{1}{2}\pi\rho q_0^2c^2$. Compare Art 124

72 CASE II The boundary of the fluid consists of a rigid cylindrical surface rotating with angular velocity ω about an axis parallel to its length

Taking the origin in the axis of rotation, and the axes of x, y in a perpendicular plane, then, with the same notation as before, $\partial\psi/\partial s$ will be equal to the normal component of the velocity of the boundary, or

$$\frac{\partial\psi}{\partial s} = \omega r \frac{dr}{ds},$$

if r denote the radius vector from the origin. Integrating we have, at all points of the boundary,

$$\psi = \frac{1}{2}\omega r^2 + \text{const.} \dots\dots\dots (1)$$

If we assume any possible form of ψ , this will give us the equation of a series of curves, each of which would, by rotation round the origin, produce the system of stream-lines determined by ψ

As examples we may take the following

1° If we assume $\psi = Ar^2 \cos 2\theta = A(x^2 - y^2)$, (2)

the equation (1) becomes

$$(\tfrac{1}{2}\omega - A)x^2 + (\tfrac{1}{2}\omega + A)y^2 = C,$$

which, for any given value of A , represents a system of similar conics. That this system may include the ellipse

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1,$$

we must have

$$(\tfrac{1}{2}\omega - A)a^2 = (\tfrac{1}{2}\omega + A)b^2,$$

or

$$A = \tfrac{1}{2}\omega \frac{a^2 - b^2}{a^2 + b^2}$$

Hence

$$\psi = \tfrac{1}{2}\omega \frac{a^2 - b^2}{a^2 + b^2} (x^2 - y^2) \dots\dots\dots (3)$$

gives the motion of a liquid contained within a hollow cylinder whose section is an ellipse with semi-axes a, b , produced by the rotation of the cylinder about its longitudinal axis with angular velocity ω . The arrangement of the stream-lines $\psi = \text{const}$ is shewn in the figure on p. 84

The corresponding formula for ϕ is

$$\phi = -\omega \cdot \frac{a^2 - b^2}{a^2 + b^2} xy \quad \dots \quad (4)$$

The kinetic energy of the fluid, per unit length of the cylinder, is given by

$$2T = \rho \iint \left\{ \left(\frac{\partial \phi}{\partial x} \right)^2 + \left(\frac{\partial \phi}{\partial y} \right)^2 \right\} dx dy = \frac{1}{4} \frac{(a^2 - b^2)^2}{a^2 + b^2} \omega^2 \times \pi \rho ab. \quad \dots \quad (5)$$

This is less than if the fluid were to rotate with the boundary, as one rigid mass, in the ratio of

$$\left(\frac{a^2 - b^2}{a^2 + b^2} \right)^2$$

to unity. We have here an illustration of Lord Kelvin's minimum theorem, proved in Art 45.

2° Let us assume

$$\psi = Ar^3 \cos 3\theta = A(x^3 - 3xy^2)$$

The equation (1) of the boundary then becomes

$$A(x^3 - 3xy^2) - \frac{1}{2}\omega(x^2 + y^2) = C \quad \dots \quad (6)$$

We may choose the constants so that the straight line $x = a$ shall form part of the boundary. The conditions for this are

$$Aa^3 - \frac{1}{2}\omega a^2 = C, \quad 3Aa + \frac{1}{2}\omega = 0$$

Substituting the values of A , C hence derived in (6), we have

$$x^3 - a^3 - 3xy^2 + 3a(x^2 - a^2 + y^2) = 0$$

Dividing out by $x - a$, we get

$$x^2 + 4ax + 4a^2 = 3y^2,$$

or

$$x + 2a = \pm \sqrt{3} \cdot y.$$

The rest of the boundary consists therefore of two straight lines passing through the point $(-2a, 0)$, and inclined at angles of 30° to the axis of x .

We have thus obtained the formulae for the motion of the fluid contained within a vessel in the form of an equilateral prism, when the latter is rotating with angular velocity ω about an axis parallel to its length and passing through the centre of its section, viz we have

$$\psi = -\frac{1}{6} \frac{\omega}{a} r^3 \cos 3\theta, \quad \phi = \frac{1}{6} \frac{\omega}{a} r^3 \sin 3\theta, \quad \dots \dots \dots (7)$$

where $2\sqrt{3}a$ is the length of a side of the prism*.

* The problem of fluid motion in a rotating cylindrical case is to a certain extent mathematically identical with that of the torsion of a uniform rod or bar. The above examples are mere adaptations of two of de Saint-Venant's solutions of the latter problem. See Thomson and Tait, *Natural Philosophy*, Art 704, *et seq*

3°. In the case of a liquid contained in a rotating cylinder whose section is a circular sector of radius a and angle 2α , the axis of rotation passing through the centre, we may assume

$$\psi = \frac{1}{2}\omega r^2 \frac{\cos 2\theta}{\cos 2\alpha} + \sum A_{2n+1} \left(\frac{r}{a}\right)^{(2n+1)\pi/2\alpha} \cos(2n+1)\frac{\pi\theta}{2\alpha}, \quad \dots \dots (8)$$

the middle radius being taken as initial line. For this makes $\psi = \frac{1}{2}\omega r^2$ for $\theta = \pm \alpha$, and the constants A_{2n+1} can be determined by Fourier's method so as to make $\psi = \frac{1}{2}\omega a^2$ for $r = a$. We find

$$A_{2n+1} = (-)^{n+1} \omega a^2 \left\{ \frac{1}{(2n+1)\pi - 4\alpha} - \frac{2}{(2n+1)\pi} + \frac{1}{(2n+1)\pi + 4\alpha} \right\}. \quad (9)$$

The conjugate expression for ϕ is

$$\phi = -\frac{1}{2}\omega r^2 \frac{\sin 2\theta}{\cos 2\alpha} - \sum A_{2n+1} \left(\frac{r}{a}\right)^{(2n+1)\pi/2\alpha} \sin(2n+1)\frac{\pi\theta}{2\alpha} \quad \dots (10)$$

The kinetic energy is given by

$$2T = -\rho \int \phi \frac{\partial \phi}{\partial n} ds = -2\rho\omega \int_0^\alpha \phi_a r dr, \quad \dots \dots (11)$$

where ϕ_a denotes the value of ϕ for $\theta = \alpha$, the value of $\partial\phi/\partial n$ being zero over the circular part of the boundary*.

The case of the semicircle $\alpha = \frac{1}{2}\pi$ will be of use to us later. We then have

$$A_{2n+1} = (-)^{n+1} \frac{\omega a^2}{\pi} \left\{ \frac{1}{2n-1} - \frac{2}{2n+1} + \frac{1}{2n+3} \right\}, \quad \dots \dots (12)$$

and therefore

$$\int_0^a \phi_a r dr = \frac{\omega a^4}{\pi} \sum \frac{1}{2n+3} \left\{ \frac{1}{2n-1} - \frac{2}{2n+1} + \frac{1}{2n+3} \right\} = -\frac{\omega a^4}{\pi} \left(2 - \frac{\pi^2}{8} \right).$$

Hence†

$$2T = \frac{1}{2}\pi\rho\omega^2 a^4 \left(\frac{8}{\pi^2} - \frac{1}{2} \right) = 3106a^2 \times \frac{1}{2}\pi\rho\omega^2 a^2 \quad \dots \dots (13)$$

This is less than if the fluid were solidified, in the ratio of 6212 to 1. See Art 45

4°. With the same notation of elliptic coordinates as in Art. 71, 3°, let us assume

$$\phi + i\psi = C e^{-2(\xi + i\eta)} \quad \dots \dots (14)$$

Since

$$x^2 + y^2 = \frac{1}{2}c^2 (\cosh 2\xi + \cos 2\eta),$$

* This problem was first solved by Stokes, "On the Critical Values of the Sums of Periodic Series," *Camb Trans*, t viii (1847) [*Math and Phys Papers*, t i p 305]. See also Hicks, *Mess of Math*, t. viii p 42 (1878), Greenhill, *ibid* t viii p. 89, and t x. p 83

† Greenhill, l c.

the equation (1) becomes

$$Ce^{-2\xi} \cos 2\eta - \frac{1}{4}\omega c^2 (\cosh 2\xi + \cos 2\eta) = \text{const}$$

This system of curves includes the ellipse whose parameter is ξ_0 , provided

$$Ce^{-2\xi_0} - \frac{1}{4}\omega c^2 = 0,$$

or, using the values of a, b already given,


$$C = \frac{1}{4}\omega (a+b)^2,$$

so that

$$\left. \begin{aligned} \psi &= \frac{1}{4}\omega (a+b)^2 e^{-2\xi} \cos 2\eta, \\ \phi &= \frac{1}{4}\omega (a+b)^2 e^{-2\xi} \sin 2\eta \end{aligned} \right\} \quad \dots \dots (15)$$

At a great distance from the origin the velocity is of the order $1/r^3$

The above formulae therefore give the motion of an infinite mass of liquid, otherwise at rest, produced by the rotation of an elliptic cylinder about its axis with angular velocity ω^* . The diagram shews the stream-lines both inside and outside a rigid elliptical cylindrical case rotating about its axis



The kinetic energy of the external fluid is given by

$$2T = \frac{1}{8}\pi\rho c^4 \omega^2 \dots \dots \dots (16)$$

It is remarkable that this is the same for all confocal elliptic forms of the section of the cylinder

* *Quart Journ Math*, t. xiv (1875), see also Beltrami, *l c ante* p 79

Combining these results with those of Arts 66, 71 we find that if an elliptic cylinder be moving with velocities U , V parallel to the principal axes of its cross-section, and rotating with angular velocity ω , and if (further) the fluid be circulating irrotationally round it, the cyclic constant being κ , then the stream-function relative to the aforesaid axes is

$$\psi = - \sqrt{\left(\frac{a+b}{a-b}\right)} e^{-\xi} (Ub \sin \eta - Va \cos \eta) + \frac{1}{4} \omega (a+b)^2 e^{-2\xi} \cos 2\eta + \frac{\kappa}{2\pi} \xi$$

Steady Motions with a Free Surface.

73 The first solution of a problem of two-dimensional motion in which the fluid is bounded partly by fixed plane walls, and partly by surfaces of constant pressure, was given by von Helmholtz*. Kirchhoff† and others have since elaborated a general method of dealing with such questions. If the surfaces of constant pressure be regarded as free, we have a theory of jets, which furnishes some interesting results in illustration of Art 24. Again, since the space beyond these surfaces may be filled with liquid at rest, without altering the conditions of the problem, we obtain also a number of cases of 'discontinuous motion,' which are mathematically possible with perfect fluids, but whose practical significance is less easily estimated. We shall return to this point presently (Art 79), in the meantime we shall speak of the surfaces of constant pressure as 'free'. Extraneous forces, such as gravity, being neglected, the velocity must be constant along any such surface, by Art 21 (2).

The method in question is based on the properties of the function ζ introduced in Art 65. The moving fluid is supposed bounded by stream-lines $\psi = \text{const}$, which consist partly of straight walls, and partly of lines along which the resultant velocity (q) is constant. For convenience, we may in the first instance suppose the units of length and time to be so adjusted that this constant velocity is equal to unity. Then in the plane of the function ζ the lines for which $q = 1$ are represented by arcs of a circle of unit radius, having the origin as centre, and the straight walls (since the direction of the flow along each is constant) by radial lines drawn outwards from the circumference. The points where these lines meet the circle correspond to the points where the bounding stream-lines change their character.

Consider, next, the function $\log \zeta$. In the plane of this function the circular arcs for which $q = 1$ become transformed into portions of the imaginary

* *Loc cit ante* pp 20, 52

† "Zur Theorie freier Flüssigkeitsstrahlen," *Crelle*, t lxx (1869) [*Ges. Abh* p 416] See also his *Mechanik*, cc xxi, xxii

axis, and the radial lines into lines parallel to the real axis, since if $\zeta = q^{-1} e^{i\theta}$ we have

$$\log \zeta = \log \frac{1}{q} + i\theta \quad \dots \dots \dots (1)$$

It remains, then, to determine a relation of the form*

$$\log \zeta = f(w), \quad \dots \dots \dots (2)$$

where $w = \phi + i\psi$, as usual, such that the rectilinear boundaries in the plane of $\log \zeta$ shall correspond to straight lines $\psi = \text{const}$ in the plane of w . There are further conditions of correspondence between special points, one on the boundary, and one in the interior, of each region, which render the problem determinate

When the correspondence between the planes of ζ and w has been established, the connection between z and w is to be found, by integration, from the relation

$$\frac{dz}{dw} = -\zeta, \quad \dots \dots \dots (3)$$

The arbitrary constant which appears in the result is due to the arbitrary position of the origin in the plane of z

The problem is thus reduced to one of conformal representation between two areas bounded by straight lines†. This is resolved by the method of Schwarz and Christoffel, already referred to‡, in which each area is represented in turn on a half-plane. Let $Z (= X + iY)$ and t be two complex variables connected by the relation

$$\frac{dZ}{dt} = A (a-t)^{-\alpha/\pi} (b-t)^{-\beta/\pi} (c-t)^{-\gamma/\pi}, \quad \dots \dots \dots (4)$$

where a, b, c , are real quantities in ascending order of magnitude, whilst $\alpha, \beta, \gamma, \dots$ are angles (not necessarily all positive) such that

$$\alpha + \beta + \gamma + \dots = 2\pi, \quad \dots \dots \dots (5)$$

and consider the line made up of portions of the real axis of t with small semi-circular indentations (on the upper side) about the points a, b, c, \dots . If a point describe this line from $t = -\infty$ to $t = +\infty$, the modulus only of the expression in (4) will vary so long as a straight portion is being described, whilst the effect of the clock-wise description of the semi-circular portions is to introduce factors $e^{i\alpha}, e^{i\beta}, e^{i\gamma}, \dots$ in succession. Hence, regarding dZ/dt as an operator which converts δt into δZ , we see that the upper half of the plane of t is conformably represented on the area of a closed polygon whose *exterior* angles are $\alpha, \beta, \gamma, \dots$, by the formula

$$Z = A \int (a-t)^{-\alpha/\pi} (b-t)^{-\beta/\pi} (c-t)^{-\gamma/\pi} \dots dt + B, \quad \dots \dots (6)$$

* The use of $\log \zeta$, in place of ζ , is due to Planck, *Wied Ann*, t. xxi, 1884

† See Forsyth, *Theory of Functions*, c. xx

‡ See the first footnote on p. 77 *ante*

provided the path of integration in the t -plane lies wholly within the region above delimited. When $a, b, c, \dots, \alpha, \beta, \gamma, \dots$ are given, the polygon is completely determinate as to shape, the complex constants A, B only affect its scale and orientation, and its position, respectively

As already indicated, we are specially concerned with the conformal representation of *rectangular* areas. If $\alpha = \beta = \gamma = \delta = \frac{1}{2}\pi$, the formula (6) becomes

$$Z = A \int \frac{dt}{\sqrt{\{(a-t)(b-t)(c-t)(d-t)\}}} + B. \quad \dots \quad (7)$$

It is easily seen that the rectangle is finite in all its dimensions unless *two* at least of the points a, b, c, d are at infinity. The excepted case is the one specially important to us, the two finite points may then conveniently be taken to be $t = \pm 1$, so that

$$\begin{aligned} Z &= A \int \frac{dt}{\sqrt{(t^2 - 1)}} + B \\ &= A \cosh^{-1} t + B. \quad \dots \quad (8) \end{aligned}$$

In particular, the assumption

$$t = \cosh \frac{Z}{k}, \quad \dots \quad (9)$$

where k is real, transforms the space bounded by the positive halves of the lines $Y=0$, $Y=\pi k$, and the intervening portion of the axis of Y , into the upper half of the plane t . Cf Art 66, 1°

Again, if the two finite points coincide, say at the origin of t , we have

$$Z = A \int \frac{dt}{t} + B = A \log t + B. \quad \dots \quad (10)$$

This transforms the upper half of the t -plane into a strip bounded by two parallel straight lines. For example, if

$$t = e^{Z/k}, \quad \dots \quad (11)$$

where k is real, these may be the lines $Y=0$, $Y=\pi k$

74 As a first application of the method in question, we may take the case of a fluid escaping from a large vessel by a straight canal projecting inwards*. This is the two-dimensional form of Borda's mouthpiece, referred to in Art 24

The boundaries of corresponding areas in the planes of ζ , $\log \zeta$, and w , respectively, are easily traced, and are shewn in the figures†. It remains to


* This problem was first solved by Helmholtz, *l c ante* p 20

† The heavy lines represent rigid boundaries, and the fine continuous lines the free surfaces. Corresponding points in the various figures are indicated by the same letters

connect the areas in the planes of $\log \zeta$ and w each with the upper half-plane of an intermediate variable t . It appears from equations (8) and (10) of the preceding Art. that this is accomplished by the substitutions

$$\log \zeta = A \cosh^{-1} t + B, \quad w = C \log t + D \quad \dots \quad (1)$$

We have here made the corners A, A' in the plane of $\log \zeta$ correspond to $t = \pm 1$, and we have also assumed that $t = 0$ corresponds to $w = -\infty$, as is evident on inspection of the figures. To specify more precisely the values of the cyclic functions $\cosh^{-1} t$ and $\log t$ we will assume that they both vanish at $t = 1$, and that their values at other points in the positive half-plane are



determined by considerations of continuity. It follows that when $t = -1$ the value of each function will be $i\pi$. At the points A', A in the plane of $\log \zeta$, we have, on the simplest convention, $\log \zeta = 0$ and $2i\pi$, respectively, whence, towards determining the constants in (1) we have

$$0 = B, \quad 2i\pi = i\pi A + B,$$

so that

$$\log \zeta = 2 \cosh^{-1} t \quad \dots \quad (2)$$

Again, in the plane of w we take the line II' as the line $\psi = 0$, and if the final breadth of the issuing jet be $2b$, the bounding stream-lines will be $\psi = \pm b$. We may further suppose that $\phi = 0$ is the equipotential curve passing through A and A' . Hence, from (1)

$$ib = i\pi C + D, \quad -ib = D,$$

so that

$$w = \frac{2b}{\pi} \log t - ib \quad \dots \quad (3)$$

It is easy to eliminate t between (2) and (3), and thence to find the relation between z and w by integration, but the formulae are perhaps more convenient in their present shape

The course of either free stream-line, say $A'I$, from its origin at A' , is now easily traced. For points of this line t is real, and ranges from 1 to 0, we have, moreover, from (2), $i\theta = 2 \cosh^{-1} t$, or $t = \cos \frac{1}{2}\theta$. Hence, also, from (3),

$$\phi = \frac{2b}{\pi} \log \cos \frac{1}{2}\theta. \quad \dots\dots\dots (4)$$


Since, along this line, we have $d\phi/ds = -q = -1$, we may put $\phi = -s$, where the arc s is measured from A' . The intrinsic equation of the curve is therefore

$$s = \frac{2b}{\pi} \log \sec \frac{1}{2}\theta. \quad \dots\dots\dots (5)$$

From this we deduce in the ordinary way

$$x = \frac{2b}{\pi} (\sin^2 \frac{1}{2}\theta - \log \sec \frac{1}{2}\theta), \quad y = \frac{b}{\pi} (\theta - \sin \theta), \dots\dots\dots (6)$$

if the origin be at A' . By giving θ a series of values ranging from 0 to π , the curve is easily plotted



Since the asymptotic value of y is b , it appears that the distance between the fixed walls is $4b$. The coefficient of contraction is therefore $\frac{1}{2}$, in accordance with Borda's theory.


75 The solution for the case of fluid issuing from a large vessel by an aperture in a plane wall is analytically very similar. The chief difference is that the values of $\log \zeta$ at the points A, A' in the figures must now be taken to be 0 and $-i\pi$, respectively, whence, to determine the constants A, B in (1) we have

$$0 = i\pi A + B, \quad -i\pi = B, \\ \text{so that} \quad \log \zeta = \cosh^{-1} t - i\pi \quad \dots\dots\dots (7)$$

The relation between w and t is exactly as before, viz


$$w = \frac{2b}{\pi} \log t - ib, \quad \dots \dots \dots (8)$$

where $2b$ is the final breadth of the stream, between the free boundaries



For the stream-line AI , t is real, and ranges from -1 to 0 . Since, also, $i\theta = \cosh^{-1} t - i\pi$ we may put $t = \cos(\theta + \pi)$, where θ varies from 0 to $-\frac{1}{2}\pi$. Hence, from (8), with $\phi = -s$, we have, for the intrinsic equation of the stream-line,

$$s = \frac{2b}{\pi} \log(-\sec \theta). \quad \dots \dots \dots (9)$$



From this we find

$$x = \frac{4b}{\pi} \sin^2 \frac{1}{2} \theta, \quad y = \frac{2b}{\pi} \{ \log \tan (\frac{1}{4} \pi + \frac{1}{2} \theta) - \sin \theta \}, \quad \dots \quad (10)$$


if the point *A* in the first diagram be taken as origin*. The curve is shewn (in an altered position) at the foot of the opposite page

The asymptotic value of *x*, corresponding to $\theta = -\frac{1}{2}\pi$, is $2b/\pi$, the half width of the aperture is therefore $(\pi + 2) b/\pi$, and the coefficient of contraction is

$$\pi/(\pi + 2) = 611$$

76 In the next example a stream of infinite breadth is supposed to impinge directly on a fixed plane lamina, and thence to divide into two portions bounded internally by free surfaces

The middle stream-line, after meeting the lamina at right angles, branches off into two parts, which follow the lamina to the edges, and thence form the free boundaries. Let this be the line $\psi = 0$, and let us further suppose that at the point of divergence we have $\phi = 0$. The forms of the boundaries in the various planes are shewn in the figures. The region occupied by the



moving fluid now corresponds to the *whole* of the plane *w*, which must however be regarded as bounded internally by the two sides of the line $\psi = 0, \phi < 0$

With the same conventions as in the beginning of Art 75, we have

$$\log \zeta = \cosh^{-1} t - i\pi, \quad \dots \dots \dots (1)$$

or
$$t = -\cosh (\log \zeta) = -\frac{1}{2} \left(\zeta + \frac{1}{\zeta} \right). \quad \dots \dots \dots (2)$$

* This example was given by Kirchhoff (*l c*), and discussed more fully by Lord Rayleigh, "Notes on Hydrodynamics," *Phil Mag*, Dec 1876 [*Sc Papers*, t 1 p 297]

The correspondence between the planes of w and t is best established by considering first the boundary in the plane of w^{-1} . The method of Schwarz and Christoffel is then at once applicable. Putting $\alpha = -\pi$, $\beta = \gamma = \dots = 0$, in Art. 73 (4), we have

$$\frac{dw^{-1}}{dt} = At, \quad w^{-1} = \frac{1}{2} At^2 + B \quad \dots \dots \dots (3)$$

At I we have $t = 0$, $w^{-1} = 0$, so that $B = 0$, or (say)

$$w = -\frac{C}{t^2} \quad \dots \dots \dots (4)$$


To connect C (which is easily seen to be real) with the breadth (l) of the lamina, we notice that along CA we have $\zeta = q^{-1}$, and therefore, from (2)

$$t = -\frac{1}{2} \left(\frac{1}{q} + q \right), \quad q = -t - \sqrt{(t^2 - 1)}, \quad \dots \dots \dots (5)$$

the sign of the radical being determined so as to make $q = 0$ for $t = -\infty$. Also, $dx/d\phi = -1/q$. Hence, integrating along CA in the first figure we have

$$l = 2 \int_{-\infty}^{-1} \frac{dx}{d\phi} \frac{d\phi}{dt} dt = -4C \int_{-\infty}^{-1} \frac{dt}{qt^3} = -4C \int_{-\infty}^{-1} \{-t + \sqrt{(t^2 - 1)}\} \frac{dt}{t^3}, \quad \dots (6)$$

whence
$$C = \frac{l}{\pi + \frac{1}{2}} \quad \dots \dots \dots (7)$$



Along the free boundary AI , we have $\log \zeta = i\theta$, and therefore, from (2) and (4),

$$t = -\cos \theta, \quad \phi = -C \sec^2 \theta. \quad \dots \dots \dots (8)$$

The intrinsic equation of the curve is therefore

$$s = \frac{l}{\pi + 4} \sec^2 \theta, \quad \dots \dots \dots (9)$$

where θ ranges from 0 to $-\frac{1}{2}\pi$. This leads to

$$\left. \begin{aligned} x &= \frac{2l}{\pi + 4} (\sec \theta + \tfrac{1}{4}\pi), \\ y &= \frac{l}{\pi + 4} \{ \sec \theta \tan \theta - \log (\tfrac{1}{4}\pi + \tfrac{1}{2}\theta) \}, \end{aligned} \right\} \dots \dots \dots (10)$$

the origin being at the centre of the lamina. The curve is shewn on the opposite page.


The excess of pressure on the anterior face of the lamina is, by Art 23 (7), equal to $\frac{1}{2}\rho (1 - q^2)$. Hence the resultant force on the lamina is

$$\rho \int_{-\infty}^{-1} (1 - q^2) \frac{dx}{dt} dt = -2\rho C \int_{-\infty}^{-1} \left(\frac{1}{q} - q \right) \frac{dt}{t^3} = -4\rho C \int_{-\infty}^{-1} \sqrt{t^2 - 1} \frac{dt}{t^3} = \pi \rho C \quad (11)$$

It is evident from Art 23 (7), and from the obvious geometrical similarity of the motion in all cases, that the resultant pressure (P_0 , say) will vary as the square of the general velocity of the stream. We thus find, for an arbitrary velocity q_0^* ,

$$P_0 = \frac{\pi}{\pi + 4} \rho q_0^2 l = 440 \rho q_0^2 l \quad \dots \dots \dots (12)$$

77 If the stream be oblique to the lamina, making an angle α , say, with its plane, the problem is modified in the manner shewn in the figures



* Kirchhoff, *l. c ante* p 85, Lord Rayleigh, "On the Resistance of Fluids," *Phil. Mag*, Dec. 1876 [*Sc Papers*, t. 1 p 287]

The equations (1) and (2) of the preceding Art still apply, but at the point I we now have $\zeta = e^{-i(\pi - \alpha)}$, and therefore $t = \cos \alpha$. Hence, in place of (4)*,

$$w = -\frac{C}{(t - \cos \alpha)^2} \quad (13)$$

At points on the front face of the lamina, we have, since $q^{-1} = |\zeta|$,

$$\frac{1}{q} = \pm t + \sqrt{(t^2 - 1)}, \quad q = \pm t - \sqrt{(t^2 - 1)}, \quad (14)$$

where the upper or the lower signs are to be taken, according as $t \geq 0$, i.e. according as the point referred to lies to the left or right of C in the first figure. Hence

$$\frac{dx}{dt} = \pm \frac{1}{q} \frac{d\phi}{dt} = \frac{2C}{(t - \cos \alpha)^3} \{t \pm \sqrt{(t^2 - 1)}\} \quad (15)$$

Between A' and C , t varies from 1 to ∞ , whilst between A and C the range is from $-\infty$ to -1 . If we put

$$t = \frac{1 - \cos \alpha \cos \omega}{\cos \alpha - \cos \omega},$$

the corresponding ranges of ω will be from π to α , and from α to 0, respectively, and we find

$$\frac{dt}{(t - \cos \alpha)^3} = -\frac{\cos \alpha - \cos \omega}{\sin^4 \alpha} \sin \omega d\omega, \quad \pm \sqrt{(t^2 - 1)} = \frac{\sin \alpha \sin \omega}{\cos \alpha - \cos \omega}$$

Hence
$$\frac{dx}{d\omega} = -\frac{2C}{\sin^4 \alpha} (1 - \cos \alpha \cos \omega + \sin \alpha \sin \omega) \sin \omega, \quad (16)$$

and therefore

$$x = \frac{C}{\sin^4 \alpha} \{2 \cos \omega + \cos \alpha \sin^2 \omega + \sin \alpha \sin \omega \cos \omega + (\tfrac{1}{2}\pi - \omega) \sin \alpha\}, \quad (17)$$

where the origin has been adjusted so that x shall have equal and opposite values when $\omega = 0$ and $\omega = \pi$, respectively, i.e. it has been taken at the centre of the lamina. Hence, in terms of C , the whole breadth is

$$l = \frac{4 + \pi \sin \alpha}{\sin^4 \alpha} C \quad (18)$$

The distance, from the centre, of the point ($\omega = \alpha$) at which the stream divides is

$$x = \frac{2 \cos \alpha (1 + \sin^2 \alpha) + (\tfrac{1}{2}\pi - \alpha) \sin \alpha}{4 + \pi \cos \alpha} l \quad (19)$$

To find the total pressure on the front face, we have

$$\begin{aligned} \tfrac{1}{2} \rho (1 - q^2) dx &= \pm \tfrac{1}{2} \rho \left(\frac{1}{q} - q \right) \frac{d\phi}{dt} dt = \pm 2\rho C \sqrt{(t^2 - 1)} \frac{dt}{(t - \cos \alpha)^3} \\ &= -\frac{2\rho C}{\sin^3 \alpha} \sin^2 \omega d\omega \quad (20) \end{aligned}$$

Integrated between the limits π and 0, this gives $\pi \rho C / \sin^3 \alpha$. Hence, in terms of l , and of an arbitrary velocity q_0 of the stream, we find

$$P_0 = \frac{\pi \sin \alpha}{4 + \pi \sin \alpha} \rho q_0^2 l \quad (21)$$

* The solution up to this point was given by Kirchhoff (*Crelle*, l.c.), the subsequent discussion is taken, with merely analytical modifications, from the paper by Lord Rayleigh

To find the centre of pressure, we take moments about the centre of the lamina. Thus

$$\begin{aligned} \frac{1}{2}\rho \int (1-q^2) x dx &= -\frac{2\rho C}{\sin^3 \alpha} \cdot \int_{\pi}^0 x \sin^2 \omega d\omega \\ &= \frac{\pi\rho C}{\sin^3 \alpha} \times \frac{1}{4} \frac{C \cos \alpha}{\sin^4 \alpha}, \quad \dots \quad \dots \quad (22) \end{aligned}$$

on substituting the value of x from (17). The first factor represents the total pressure, the abscissa \bar{x} of the centre of pressure is therefore given by the second, or, in terms of the breadth

$$\bar{x} = \frac{1}{4} \frac{\cos \alpha}{4 + \pi \sin \alpha} \cdot l \quad \dots \quad \dots \quad (23)$$

In the following table, derived from Lord Rayleigh's paper, the column I gives the excess of pressure on the anterior face, in terms of its value when $\alpha=90^\circ$, whilst columns II and III give respectively the distances of the centre of pressure, and of the point where the stream divides, from the middle point of the lamina, expressed as fractions of the total breadth*

α	I	II	III
90°	1 000	000	000
70°	965	037	232
50°	854	075	402
30°	641	117	483
20°	481	139	496
10°	273	163	500

78 An interesting variation of the problem of Art 76 has been discussed by Bobyleff†. A stream is supposed to impinge symmetrically on a bent lamina whose section consists of two equal straight lines forming an angle

If 2α be the angle, measured on the down-stream side, the boundaries in the plane of ζ can be transformed, so as to have the same shape as in the Art cited, by the assumption

$$\zeta = A\zeta'^n,$$

provided A and n be determined so as to make $\zeta'=1$ when $\zeta=e^{-i(\frac{1}{2}\pi-\alpha)}$, and $\zeta'=e^{-i\pi}$ when $\zeta=e^{-i(\frac{1}{2}\pi+\alpha)}$. This gives

$$A=e^{-i(\frac{1}{2}\pi-\alpha)}, \quad n=2\alpha/\pi.$$

On the right-hand half of the lamina, t will be negative as before, and, since $q^{-1}=|\zeta|$,

$$\frac{1}{q} = \{-t + \sqrt{(t^2-1)}\}^n, \quad q = \{-t - \sqrt{(t^2-1)}\}^n \quad \dots \quad \dots \quad (24)$$

Hence

$$\begin{aligned} \int_{-\infty}^{-1} \frac{1}{q} \frac{d\phi}{dt} dt &= 2C \int_{-\infty}^{-1} \{-t + \sqrt{(t^2-1)}\}^n \frac{dt}{t^3} = -C - nC \int_{-\infty}^{-1} \{-t + \sqrt{(t^2-1)}\}^n \frac{dt}{t^2 \sqrt{(t^2-1)}}, \\ \int_{-\infty}^{-1} q \frac{d\phi}{dt} dt &= 2C \int_{-\infty}^{-1} \{-t - \sqrt{(t^2-1)}\}^n \frac{dt}{t^3} = -C + nC \int_{-\infty}^{-1} \{-t - \sqrt{(t^2-1)}\}^n \frac{dt}{t^2 \sqrt{(t^2-1)}} \end{aligned}$$

* For the comparison with experimental results see Rayleigh, *loc. cit.* and *Nature*, t. xlv (1891) [*Sci. Papers*, t. iii p. 491].

† *Journal of the Russian Physico-Chemical Society*, t. xiii (1881) [Wiedemann's *Beiblätter*, t. vi p. 163]. The problem appears, however, to have been previously discussed in a similar manner by M. Réthy, *Klausenburger Berichte*, 1879.

These can be reduced to known forms by the substitution

$$t = -\frac{1}{2} \left(\frac{1}{\sqrt{\omega}} + \sqrt{\omega} \right),$$

where ω ranges from 0 to 1. We thus find

$$\frac{1}{C} \int_{-\infty}^{-1} \frac{1}{q} \frac{d\phi}{dt} dt = -1 - 2n \int_0^1 \frac{\omega^{-\frac{1}{2}n}}{(1+\omega)^2} d\omega = -1 - n - n^2 \int_0^1 \frac{\omega^{-\frac{1}{2}n}}{1+\omega} d\omega, \quad (25)$$

$$\frac{1}{C} \int_{-\infty}^{-1} q \frac{d\phi}{dt} dt = -1 + 2n \int_0^1 \frac{\omega^{\frac{1}{2}n}}{(1+\omega)^2} d\omega = -1 - n + n^2 \int_0^1 \frac{\omega^{\frac{1}{2}n-1}}{1+\omega} d\omega \quad (26)$$

We have here used the formulae

$$\begin{aligned} \int_0^1 \frac{\omega^{-k}}{(1+\omega)^2} d\omega &= \frac{1}{2} + k \int_0^1 \frac{\omega^{-k}}{1+\omega} d\omega, \\ \int_0^1 \frac{\omega^k}{(1+\omega)^2} d\omega &= -\frac{1}{2} + k \int_0^1 \frac{\omega^{k-1}}{1+\omega} d\omega, \end{aligned}$$

where $1 > k > 0$

Since, along the stream-line, $ds/d\phi = -1/q$, we have from (25), if b denote the half-breadth of the lamina,

$$b = C \left\{ 1 + \frac{2a}{\pi} + \frac{4a^2}{\pi^2} \int_0^1 \frac{\omega^{-a/\pi}}{1+\omega} d\omega \right\} \quad \dots \quad (27)$$

The definite integral which occurs in this expression can be calculated from the formula

$$\int_0^1 \frac{\omega^{-k}}{1+\omega} d\omega = \frac{1}{(1-k)(2-k)} + \frac{1}{2} \Psi(1 - \frac{1}{2}k) - \frac{1}{2} \Psi(\frac{1}{2} - \frac{1}{2}k), \quad (28)$$

where $\Psi(m) = d/dm \log \Pi(m)$, is the function introduced and tabulated by Gauss*.

The normal pressure on either half is, by the method of Art 76,

$$= -\frac{1}{2} \rho \int_{-\infty}^{-1} \left(\frac{1}{q} - q \right) \frac{d\phi}{dt} dt = \frac{1}{2} n^2 C \rho \int_0^1 \frac{\omega^{-\frac{1}{2}n}}{1+\omega} d\omega = \frac{1}{2} n^2 C \rho \frac{\pi}{\sin \frac{1}{2} n \pi} = \rho C \frac{2a^2}{\pi \sin a}. \quad (29)$$

The resultant pressure in the direction of the stream is therefore

$$= \frac{4a^2}{\pi} \rho C \quad \dots \quad (30)$$

Hence, for any arbitrary velocity q_0 of the stream, the resultant pressure is

$$P = \frac{4a^2}{\pi L} \rho q_0^2 b, \quad \dots \quad (31)$$

where L stands for the numerical factor in (27)

For $a = \frac{1}{2}\pi$, we have $L = 2 + \frac{1}{2}\pi$, leading to the same result as in Art 76 (12).

In the following table, taken (with a slight modification) from Bobileff's paper, the second column gives the ratio P/P_0 of the resultant pressure to that experienced by a plane strip of the same area. This ratio is a maximum when $a = 100^\circ$, about, the lamina being then concave on the up-stream side. In the third column the ratio of P to the distance ($2b \sin a$) between the edges of the lamina is compared with $\frac{1}{2} \rho q_0^2$. For values of a nearly equal to 180° , this ratio tends to the value unity, as we should expect, since the fluid within the acute angle is then nearly at rest, and the pressure-excess therefore practically

* "Disquisitiones generales circa seriem infinitam," *Werke*, Gottingen, 1870, t. iii p. 161

equal to $\frac{1}{2}\rho q_0^2$. The last column gives the ratio of the resultant pressure to that experienced by a plane strip of breadth $2b \sin \alpha$, as calculated from (12)

α	P/P_0	$P/\rho q_0^2 b \sin \alpha$	$P/P_0 \sin \alpha$
10°	039	199	227
20°	140	359	409
30°	278	489	555
40°	433	593	674
45°	512	637	724
50°	589	677	769
60°	733	745	846
70°	854	800	909
80°	945	844	959
90°	1 000	879	1 000
100°	1 016	907	1 031
110°	995	931	1 059
120°	935	950	1 079
130°	840	964	1 096
135°	780	970	1 103
140°	713	975	1 109
150°	559	984	1 119
160°	385	990	1 126
170°	197	996	1 132

Discontinuous Motions.

79. It must suffice to have given a few of the more important examples of steady motion with a free surface, treated by what is perhaps the most systematic method. Considerable additions to the subject have been made by Michell*, Love†, and other writers‡. It remains to say something of the physical considerations which led in the first instance to the investigation of such problems

We have, in the preceding pages, had several instances of the flow of a liquid round a sharp projecting edge, and it appeared in each case that the velocity there was infinite. This is indeed a necessary consequence of the assumed irrotational character of the motion, whether the fluid be incompressible or not, as may be seen by considering the configuration of the equipotential surfaces (which meet the boundary at right angles) in the immediate neighbourhood

The occurrence of infinite values of the velocity may be avoided by supposing the edge to be slightly rounded, but even then the velocity near the edge will much exceed that which obtains at a distance great in comparison with the radius of curvature

* "On the Theory of Free Stream-lines," *Phil. Trans.*, A, t. clxxx. (1890)

† "On the Theory of Discontinuous Fluid Motions in Two Dimensions," *Proc Camb. Phil. Soc.*, t vii, 1891.


‡ For references see Love, *Encycl d math Wiss*, t iv (2), pp 97 . .

In order that the motion of a fluid may conform to such conditions, it is necessary that the pressure at a distance should greatly exceed that at the edge. This excess of pressure is demanded by the *inertia* of the fluid, which cannot be guided round a sharp curve, in opposition to centrifugal force, except by a distribution of pressure increasing with a very rapid gradient outwards.

Hence, unless the pressure at a distance be very great, the maintenance of the motion in question would require a negative pressure at the corner, such as fluids under ordinary conditions are unable to sustain.

To put the matter in as definite a form as possible, let us imagine the following case. Let us suppose that a straight tube, whose length is large compared with the diameter, is fixed in the middle of a large closed vessel filled with frictionless liquid, and that this tube contains, at a distance from the ends, a sliding plug, or piston, P , which can be moved in any required manner by extraneous forces applied to it. The thickness of the walls of the tube is supposed to be small in comparison with the diameter, and the edges, at the two ends, to be rounded off, so that there are no sharp angles. Let us further suppose that at some point of the walls of the vessel there is a lateral tube, with a piston Q , by means of which the pressure in the interior can be adjusted at will.

Everything being at rest to begin with, let a slowly increasing velocity be communicated to the plug P , so that (for simplicity) the motion at any



instant may be regarded as approximately steady. At first, provided a sufficient force be applied to Q , a continuous motion of the kind indicated in the diagram on p 71 will be produced in the fluid, there being in fact only one type of motion consistent with the conditions of the question. As the acceleration of the piston P proceeds, the pressure on Q may become

normous, even with very moderate velocities of P , and if Q be allowed to yield, an annular cavity will be formed at each end of the tube.

It is not easy to make out the further course of the motion in such a case from a theoretical stand-point, even in the case of a 'perfect' fluid. In actual liquids the problem is modified by viscosity, which prevents any slipping of the fluid immediately in contact with the tube, and must further exercise considerable influence on such rapid differential motions of the fluid as are here in question.

As a matter of observation, the motions of fluids are often found to differ widely, under the circumstances supposed in each case, from the types represented in such diagrams as those of pp. 70, 71, 79, 80. In such a case as we have just described, the fluid issuing from the mouth of the tube does not immediately spread out in all directions, but forms, at all events for some distance, a more or less compact stream, bounded on all sides by fluid nearly at rest. A familiar instance is the smoke-laden stream of gas issuing from a chimney. In all such cases, however, the motion in the immediate neighbourhood of the boundary of the stream is found to be wildly irregular*.

It was the endeavour to construct types of steady motion of a frictionless liquid, in two dimensions, which should resemble more closely what is observed in such cases as we have referred to, that led von Helmholtz† and Kirchhoff‡ to investigate the theory of free stream-lines. It is obvious that we may imagine the space beyond a free boundary to be occupied, if we choose, by liquid of the same density at rest, since the condition of constant pressure along the stream-line is not thereby affected. In this way the problems of Arts 76, 77, for example, give us a theory of the pressure exerted on a fixed lamina by a stream flowing past it, or (what comes to the same thing) the resistance experienced by a lamina when made to move with constant velocity through a liquid which would otherwise be at rest.

As to the practical value of this theory opinions have differed. One obvious criticism is that the unlimited mass of 'dead-water' following the disk implies an infinite kinetic energy, but this only means that the type of motion in question could not be completely established in a finite time from rest, although it might (conceivably) be approximated asymptotically. Another objection is that, as will appear in Chap. IX, surfaces of discontinuity between fluids of comparable density are as a rule highly unstable. It has been urged, however, by Lord Rayleigh that this instability may not seriously affect the character of the motion for some distance from the place of origin of the surfaces in question.

Lord Kelvin, on the other hand, maintains that the types of motion here contemplated, with surfaces of discontinuity, have no resemblance to anything which occurs in actual fluids, and that the only legitimate application of the methods of von Helmholtz and Kirchhoff is to the case of free surfaces, as of a jet‡.

* Recent experiments would indicate that jets may be formed *before* the limiting velocity of Helmholtz is reached, and that viscosity plays an essential part in the process. Smoluchowski, "Sur la formation des veines d'efflux dans les liquides," *Bull de l'Acad de Cracovie*, 1904

† *Uc ante* pp 20, 85

‡ *Nature*, t 1 pp 524, 549, 573, 597 (1894)

Flow in a Curved Stratum

80 The theory developed in Arts 59, 60, may be readily extended to the two-dimensional motion of a *curved* stratum of liquid, whose thickness is small compared with the radii of curvature. This question has been discussed, from the point of view of electric conduction, by Boltzmann*, Kuchhoff†, Topley‡, and others.

As in Art 59, we take a fixed point A , and a variable point P , on the surface defining the form of the stratum, and denote by ψ the flux across any curve AP drawn on this surface. Then ψ is a function of the position of P , and by displacing P in any direction through a small distance δs , we find that the flux across the element δs is given by $\partial\psi/\partial s \delta s$. The *velocity* perpendicular to this element will be $\delta\psi/h\delta s$, where h is the thickness of the stratum, not assumed as yet to be uniform.

If, further, the motion be irrotational, we shall have in addition a velocity-potential ϕ , and the equipotential curves $\phi = \text{const}$ will cut the stream-lines $\psi = \text{const}$ at right angles.

In the case of *uniform* thickness, to which we now proceed, it is convenient to write ψ for ψ/h , so that the velocity perpendicular to an element δs is now given indifferently by $\partial\psi/\partial s$ and $\partial\phi/\partial n$, δn being an element drawn at right angles to δs in the proper direction. The further relations are then exactly as in the plane problem, in particular the curves $\phi = \text{const}$, $\psi = \text{const}$, drawn for a series of values in arithmetic progression, the common difference being infinitely small and the same in each case, will divide the surface into elementary squares. For, by the orthogonal property, the elementary spaces in question are rectangles, and if δs_1 , δs_2 be elements of a stream-line and an equipotential line, respectively, forming the sides of one of these rectangles, we have $\partial\psi/\partial s_2 = \partial\phi/\partial s_1$, whence $\delta s_1 = \delta s_2$, since by construction $\delta\psi = \delta\phi$.

Any problem of irrotational motion in a curved stratum (of uniform thickness) is therefore reduced by orthomorphic projection to the corresponding problem *in plano*. Thus for a spherical surface we may use, among an infinity of other methods, that of stereographic projection. As a simple example of this, we may take the case of a stratum of uniform depth covering the surface of a sphere with the exception of two circular islands (which may be of any size and in any relative position). It is evident that the only (two-dimensional) irrotational motion which can take place in the doubly-connected space occupied by the fluid is one in which the fluid circulates in opposite

* *Wiener Sitzungsberichte*, t. lxx. p. 214 (1865)

† *Berl Monatsber.*, July 19, 1875 [*Ges Abh* p. 56]

‡ *Pogg Ann.*, t. clx. p. 375 (1877).

directions round the two islands, the cyclic constant being the same in each case. Since circles project into circles, the plane problem is that solved in Art. 64, 2°, viz. the stream-lines are a system of coaxial circles with real 'limiting points' (A, B , say), and the equipotential lines are the orthogonal system passing through A, B . Returning to the sphere, it follows from well-known theorems of stereographic projection that the stream-lines (including the contours of the two islands) are the circles in which the surface is cut by a system of planes passing through a fixed line, viz. the intersection of the tangent planes at the points corresponding to A and B , whilst the equipotential lines are the circles in which the sphere is cut by planes passing through these points*.

In any case of transformation by orthomorphic projection, whether the motion be irrotational or not, the velocity ($\partial\psi/\partial n$) is transformed in the inverse ratio of a linear element, and therefore the kinetic energies of the portions of the fluid occupying corresponding areas are equal (provided, of course, the density and the thickness be the same). In the same way the circulation ($\int \partial\psi/\partial n \cdot ds$) in any circuit is unaltered by projection.

* This example is given by Kirchhoff, in the electrical interpretation, the problem considered being the distribution of current in a uniform spherical conducting sheet, the electrodes being situate at any two points A, B of the surface.

CHAPTER V.

IRROTATIONAL MOTION OF A LIQUID PROBLEMS IN THREE DIMENSIONS

81 Of the methods available for obtaining solutions of the equation

$$\nabla^2 \phi = 0 \quad \dots \dots \dots (1)$$

in three dimensions, the most important is that of Spherical Harmonics. This is especially suitable when the boundary conditions have relation to spherical or nearly spherical surfaces.

For a full account of this method we must refer to the special treatises*, but as the subject is very extensive, and has been treated from different points of view, it may be worth while to give a slight sketch, without formal proofs, or with mere indications of proofs, of such parts of it as are most important for our present purpose.

It is easily seen that since the operator ∇^2 is homogeneous with respect to x, y, z , the part of ϕ which is of any specified algebraic degree must satisfy (1) separately. Any such homogeneous solution of (1) is called a 'spherical solid harmonic' of the algebraic degree in question. If ϕ_n be a spherical solid harmonic of degree n , then if we write

$$\phi_n = r^n S_n, \quad \dots \dots \dots (2)$$

S_n will be a function of the direction (only) in which the point (x, y, z) lies with respect to the origin, in other words, a function of the position of the point in which the radius vector meets a unit sphere described with the origin as centre. It is therefore called a 'spherical surface harmonic' of order n †.

* Todhunter, *Functions of Laplace, Lamé, and Bessel*, Cambridge, 1875. Ferrers, *Spherical Harmonics*, Cambridge, 1877. Heine, *Handbuch der Kugelfunctionen*, 2nd ed., Berlin, 1878. Thomson and Tait, *Natural Philosophy*, 2nd ed., Cambridge, 1879, t. i pp 171—218. Byerly, *Fourier's Series and Spherical, Cylindrical, and Ellipsoidal Harmonics*, Boston, U.S.A., 1893. Whittaker, *Modern Analysis*, Cambridge, 1902.

For the history of the subject see Todhunter, *History of the Theories of Attraction, &c.*, Cambridge, 1873, t. ii. Also Wangerin, "Theorie d. Kugelfunktionen, u. s. w.," *Encycl. d. math. Wiss.*, t. ii (1) (1904).

† The symmetrical treatment of spherical solid harmonics in terms of Cartesian co-ordinates was introduced by Clebsch, in a much neglected paper, *Crelle*, t. lxi p 195 (1863). It was adopted independently by Thomson and Tait as the basis of their exposition.

To any solid harmonic ϕ_n of degree n corresponds another of degree $-n-1$, obtained by division by r^{2n+1} , i.e. $\phi = r^{-2n-1}\phi_n$ is also a solution of (1). Thus, corresponding to any spherical surface harmonic S_n , we have the two spherical solid harmonics $r^n S_n$ and $r^{-n-1} S_n$.

82. The most important case is when n is integral, and when the surface-harmonic S_n is further restricted to be finite over the unit sphere. In the form in which the theory (for this case) is presented by Thomson and Tait, and by Maxwell*, the primary solution of (1) is

$$\phi_{-1} = A/r \qquad \dots \qquad \dots \qquad \dots \qquad (3)$$

This represents as we have seen (Art. 56) the velocity-potential due to a point-source at the origin. Since (1) is still satisfied when ϕ is differentiated with respect to x , y , or z , we derive a solution

$$\phi_{-2} = A \left(l \frac{\partial}{\partial x} + m \frac{\partial}{\partial y} + n \frac{\partial}{\partial z} \right) \frac{1}{r}. \qquad \dots \qquad (4)$$

This is the velocity-potential of a double-source at the origin, having its axis in the direction (l, m, n) , see Art. 56 (3). The process can be continued, and the general type of spherical solid harmonic obtainable in this way is

$$\phi_{-n-1} = A \frac{\partial^n}{\partial h_1 \partial h_2 \dots \partial h_n} \frac{1}{r^n}, \qquad \dots \dots \dots (5)$$

where

$$\frac{\partial}{\partial h_s} = l_s \frac{\partial}{\partial x} + m_s \frac{\partial}{\partial y} + n_s \frac{\partial}{\partial z},$$

l_s, m_s, n_s being arbitrary direction-cosines.

This may be regarded as the velocity-potential of a certain configuration of simple sources about the origin, the dimensions of this system being small compared with r . To construct this system we premise that from any given system of sources we may derive a system of higher order by first displacing it through a space $\frac{1}{2}h_s$ in the direction (l_s, m_s, n_s) , and then superposing the reversed system, supposed displaced from its original position through a space $\frac{1}{2}h_s$ in the opposite direction. Thus, beginning with the case of a simple source O at the origin, a first application of the above process gives us two sources O_+, O_- equidistant from the origin, in opposite directions. The same process applied to the system O_+, O_- gives us four sources $O_{++}, O_{+-}, O_{-+}, O_{--}$ at the corners of a parallelogram. The next step gives us eight sources at the corners of a parallelepiped, and so on. The velocity-potential, at a distance, due to an arrangement of 2^n sources obtained in this way, will be given by (5), if $4\pi A = m' l_1 h_2 \dots h_n$, m' being the strength of the original source at O . The formula becomes exact, for all distances r ; when h_1, h_2, \dots, h_n are diminished, and m' increased, indefinitely, but so that A is finite.

* *Electricity and Magnetism*, c. ix.

The surface-harmonic corresponding to (5) is given by

$$S_n = A r^{n+1} \frac{\partial^n}{\partial h_1 \partial h_2 \dots \partial h_n} \frac{1}{r}, \quad \dots \quad (6)$$

and the complementary solid harmonic by

$$\phi_n = r^n S_n = r^{2n+1} \phi_{-n-1} \quad \dots \quad (7)$$

By the method of 'inversion*', applied to the above configuration of sources, it may be shewn that the solid harmonic (7) of positive degree n may be regarded as the velocity-potential due to a certain arrangement of 2^n simple sources at infinity

The lines drawn from the origin in the various directions (l_s, m_s, n_s) are called the 'axes' of the solid harmonic (5) or (7), and the points in which these lines meet the unit sphere are called the 'poles' of the surface harmonic S_n . The formula (5) involves $2n + 1$ arbitrary constants, viz the angular co-ordinates (two for each) of the n poles, and the factor A . It can be shewn that this expression is equivalent to the most general form of spherical surface harmonic which is of integral order n and finite over the unit sphere†.

83 In the original investigation of Laplace‡, the equation $\nabla^2 \phi = 0$ is first expressed in terms of spherical polar co-ordinates r, θ, ω , where

$$x = r \cos \theta, \quad y = r \sin \theta \cos \omega, \quad z = r \sin \theta \sin \omega$$

The simplest way of effecting the transformation is to apply the theorem of Art 36 (2) to the surface of a volume-element $r \delta \theta \cdot r \sin \theta \delta \omega \cdot \delta r$. Thus the difference of flux across the two faces perpendicular to r is

$$\frac{\partial}{\partial r} \left(\frac{\partial \phi}{\partial r} \cdot r \delta \theta \cdot r \sin \theta \delta \omega \right) \delta r.$$

Similarly for the two faces perpendicular to the meridian ($\omega = \text{const}$) we find

$$\frac{\partial}{\partial \theta} \left(\frac{\partial \phi}{\partial \theta} \cdot r \sin \theta \delta \omega \cdot \delta r \right) \delta \theta,$$

and for the two faces perpendicular to a parallel of latitude ($\theta = \text{const}$)

$$\frac{\partial}{\partial \omega} \left(\frac{\partial \phi}{\partial \omega} \cdot r \sin \theta \delta \theta \cdot \delta r \right) \delta \omega$$

Hence, by addition,

$$\sin \theta \frac{\partial}{\partial r} \left(r^2 \frac{\partial \phi}{\partial r} \right) + \frac{\partial}{\partial \theta} \left(\sin \theta \frac{\partial \phi}{\partial \theta} \right) + \frac{1}{\sin \theta} \frac{\partial^2 \phi}{\partial \omega^2} = 0 \quad \dots \quad (1)$$

This might of course have been derived from Art 81 (1) by the usual method of change of independent variables.

* Explained by Thomson and Tait, *Natural Philosophy*, Art 515.

† Sylvester, *Phil Mag*, Oct 1876

‡ "Théorie de l'attraction des sphéroïdes et de la figure des planètes," *Mém de l'Acad roy des Sciences*, 1782 [*Oeuvres Complètes*, Paris, 1878, t. x. p. 341], *Mécanique Céleste*, Livre 2^{me}, c. 11

If we now assume that ϕ is homogeneous, of degree n , and put

$$\phi = r^n S_n,$$

we obtain
$$\frac{1}{\sin \theta} \frac{\partial}{\partial \theta} \left(\sin \theta \frac{\partial S_n}{\partial \theta} \right) + \frac{1}{\sin^2 \theta} \frac{\partial^2 S_n}{\partial \omega^2} + n(n+1) S_n = 0, \dots \dots (2)$$

which is the general differential equation of spherical surface harmonics. Since the product $n(n+1)$ is unchanged in value when we write $-n-1$ for n , it appears that

$$\phi = r^{-n-1} S_n$$

will also be a solution of (1), as already stated.

84 In the case of symmetry about the axis of x , the term $\partial^2 S_n / \partial \omega^2$ disappears, and putting $\cos \theta = \mu$ we get

$$\frac{d}{d\mu} \left\{ (1 - \mu^2) \frac{dS_n}{d\mu} \right\} + n(n+1) S_n = 0, \dots \dots (1)$$

the differential equation of spherical 'zonal' harmonics*. This equation, containing only terms of two different dimensions in μ , is adapted for integration by series. We thus obtain

$$S_n = A \left\{ 1 - \frac{n(n+1)}{1 \cdot 2} \mu^2 + \frac{(n-2)n(n+1)(n+3)}{1 \cdot 2 \cdot 3 \cdot 4} \mu^4 - \dots \right\} \\ + B \left\{ \mu - \frac{(n-1)(n+2)}{1 \cdot 2 \cdot 3} \mu^3 + \frac{(n-3)(n-1)(n+2)(n+4)}{1 \cdot 2 \cdot 3 \cdot 4 \cdot 5} \mu^5 - \dots \right\}. \quad (2)$$

The series which here present themselves are of the kind called 'hypergeometric', viz if we write, after Gauss†,

$$F(\alpha, \beta, \gamma, x) = 1 + \frac{\alpha}{1} \frac{\beta}{\gamma} x + \frac{\alpha}{1} \frac{\alpha+1}{2} \frac{\beta}{\gamma} \frac{\beta+1}{\gamma+1} x^2 \\ + \frac{\alpha}{1} \frac{\alpha+1}{2} \frac{\alpha+2}{3} \frac{\beta}{\gamma} \frac{\beta+1}{\gamma+1} \frac{\beta+2}{\gamma+2} x^3 + \dots \dots (3)$$

we have

$$S_n = A F\left(-\frac{1}{2}n, \frac{1}{2} + \frac{1}{2}n, \frac{1}{2}, \mu^2\right) + B \mu F\left(\frac{1}{2} - \frac{1}{2}n, 1 + \frac{1}{2}n, \frac{3}{2}, \mu^2\right). \dots (4)$$

The series (3) is of course essentially convergent when x lies between 0 and 1, but when $x=1$ it is convergent if, and only if

$$\gamma - \alpha - \beta > 0$$

In this case we have

$$F(\alpha, \beta, \gamma, 1) = \frac{\Pi(\gamma-1) \cdot \Pi(\gamma-\alpha-\beta-1)}{\Pi(\gamma-\alpha-1) \Pi(\gamma-\beta-1)}, \dots \dots (5)$$

where $\Pi(m)$ is in Gauss's notation the equivalent of Euler's $\Gamma(m+1)$

* So called by Thomson and Tait, because the nodal lines ($S_n=0$) divide the unit sphere into parallel belts

† *l. c. ante* p 96

The degree of divergence of the series (3) when

$$\gamma - \alpha - \beta < 0,$$

as x approaches the value 1, is given by the theorem*

$$F(\alpha, \beta, \gamma, x) = (1-x)^{\gamma-\alpha-\beta} F(\gamma-\alpha, \gamma-\beta, \gamma, x) \quad (6)$$

Since the latter series will now be convergent when $x=1$, we see that $F(\alpha, \beta, \gamma, x)$ becomes divergent as $(1-x)^{\gamma-\alpha-\beta}$, more precisely, for values of x infinitely nearly equal to unity, we have

$$F(\alpha, \beta, \gamma, x) = \frac{\Pi(\gamma-1)}{\Pi(\alpha-1)} \frac{\Pi(\alpha+\beta-\gamma-1)}{\Pi(\beta-1)} (1-x)^{\gamma-\alpha-\beta}, \quad (7)$$

ultimately

For the critical case where $\gamma - \alpha - \beta = 0$,
we may have recourse to the formula

$$\frac{d}{dx} F(\alpha, \beta, \gamma, x) = \frac{\alpha\beta}{\gamma} F(\alpha+1, \beta+1, \gamma+1, x), \quad (8)$$

which, with (6), gives in the case supposed

$$\begin{aligned} \frac{d}{dx} F(\alpha, \beta, \gamma, x) &= \frac{\alpha\beta}{\gamma} (1-x)^{-1} F(\gamma-\alpha, \gamma-\beta, \gamma+1, x) \\ &= \frac{\alpha\beta}{\gamma} (1-x)^{-1} F(\alpha, \beta, \alpha+\beta+1, x) \quad (9) \end{aligned}$$

The last factor is now convergent when $x=1$, so that $F(\alpha, \beta, \gamma, x)$ is ultimately divergent as $\log(1-x)$. More precisely we have, for values of x near this limit,

$$F(\alpha, \beta, \alpha+\beta, x) = \frac{\Pi(\alpha+\beta-1)}{\Pi(\alpha-1)} \frac{1}{\Pi(\beta-1)} \log \frac{1}{1-x} \quad (10)$$

85 Of the two series which occur in the general expression Art 84 (2) of a zonal harmonic, the former terminates when n is an even, and the latter when n is an odd integer. For other values of n both series are essentially convergent for values of μ between ± 1 , but since in each case we have $\gamma - \alpha - \beta = 0$, they diverge at the limits $\mu = \pm 1$, becoming infinite as $\log(1-\mu^2)$.

It follows that the terminating series corresponding to integral values of n are the only zonal surface harmonics which are finite over the unit sphere. If we reverse the series we find that both these cases (n even, and n odd) are included in the formula†

$$\begin{aligned} P_n(\mu) = & \frac{1}{1} \frac{3}{2} \frac{5}{3} \dots \frac{(2n-1)}{n} \left\{ \mu^n - \frac{n(n-1)}{2(2n-1)} \mu^{n-2} \right. \\ & \left. + \frac{n(n-1)(n-2)(n-3)}{2 \cdot 4 (2n-1)(2n-3)} \mu^{n-4} - \dots \right\}, \quad \dots\dots\dots(1) \end{aligned}$$

* Forsyth, *Differential Equations*, 3rd ed, London, 1903, c vi.

† For n even this corresponds to $A = (-)^{\frac{1}{2}n} \frac{1}{2} \frac{3}{4} \frac{5}{n} \frac{(n-1)}{n}$, $B=0$, whilst for n odd we have $A=0$, $B = (-)^{\frac{1}{2}(n-1)} \frac{3}{2} \frac{5}{4} \frac{n}{(n-1)}$. See Heine, t i pp 12, 147

where the constant factor has been adjusted so as to make $P_n(\mu) = 1$ for $\mu = 1$ * The formula may also be written

$$P_n(\mu) = \frac{1}{2^n n!} \frac{d^n}{d\mu^n} (\mu^2 - 1)^n. \quad \dots \quad (2)$$

The series (1) may otherwise be obtained by development of Art 82 (6), which in the case of the zonal harmonic assumes the form

$$S_n = A r^{n+1} \frac{\partial^n}{\partial x^n} \frac{1}{r} \quad \dots \quad (3)$$

As particular cases of (2) we have

$$P_0(\mu) = 1, \quad P_1(\mu) = \mu, \quad P_2(\mu) = \frac{1}{2}(3\mu^2 - 1), \quad P_3(\mu) = \frac{1}{2}(5\mu^3 - 3\mu)$$

Expansions of P_n in terms of other functions of θ as independent variables, in place of μ , have been obtained by various writers For example, we have

$$P_n(\cos \theta) = 1 - \frac{n(n+1)}{1^2} \sin^2 \frac{1}{2}\theta + \frac{(n-1)n(n+1)(n+2)}{1^2 \cdot 2^2} \sin^4 \frac{1}{2}\theta - \dots \quad (4)$$

This may be deduced from (2)†, or it may be obtained independently by putting $\mu = 1 - 2z$ in Art 84 (1), and integrating by a series

The function $P_n(\mu)$ was first introduced into analysis by Legendre‡ as the coefficient of h^n in the expansion of

$$(1 - 2\mu h + h^2)^{-\frac{1}{2}}$$

The connection of this with our present point of view is that if ϕ be the velocity-potential of a unit source on the axis of r at a distance c from the origin, we have, on Legendre's definition, for values of r less than c ,

$$\begin{aligned} 4\pi\phi &= (c^2 - 2\mu cr + r^2)^{-\frac{1}{2}} \\ &= \frac{1}{c} + P_1 \frac{r}{c^2} + P_2 \frac{r^2}{c^3} + \dots \end{aligned} \quad (5)$$

Each term in this expansion must separately satisfy $\nabla^2\phi = 0$, and therefore the coefficient P_n must be a solution of Art 84 (1) Since P_n , as thus defined, is obviously finite for all values of μ , and becomes equal to unity for $\mu = 1$, it must be identical with (1)

* The functions P_1, P_2, \dots, P_7 were tabulated by Glaisher, for values of μ at intervals of .01, *Brit Ass Report*, 1879 A table of the same functions for every degree of the quadrant, calculated under the direction of Prof Perry, was published in the *Phil Mag* for Dec 1891 Both tables are reproduced by Byerly, who also gives graphs of the functions The values of the first 20 zonal harmonics, at intervals of 5° , have recently been published by Prof A Lodge, *Phil Trans*, A, t cccii (1904).

† Murphy, *Elementary Principles of the Theories of Electricity, &c*, Cambridge, 1883, p 7 [Thomson and Tait, Art 782]

‡ "Sur l'attraction des sphéroïdes homogènes," *Mém des Savans Étrangers*, t x, 1785

For values of r greater than c , the corresponding expansion is

$$4\pi\phi = \frac{1}{r} + P_1 \frac{c}{r^2} + P_2 \frac{c^2}{r^3} + \dots \quad (6)$$

We can hence deduce expressions, which will be useful to us later, Art. 98, for the velocity-potential due to a *double-source* of unit strength, situate on the axis of x at a distance c from the origin, and having its axis pointing *from* the origin. This is evidently equal to $\partial\phi/\partial c$, where ϕ has either of the above forms, so that the required potential is, for $r < c$,

$$-\frac{1}{4\pi} \left(\frac{1}{c^2} + 2P_1 \frac{r}{c^3} + 3P_2 \frac{r^2}{c^4} + \dots \right), \quad (7)$$

and for $r > c$,

$$\frac{1}{4\pi} \left(P_1 \frac{1}{r^2} + 2P_2 \frac{c}{r^3} + \dots \right) \quad (8)$$

The remaining solution of Art. 84 (1), in the case of n integral, can be put into the more compact form*

$$Q_n(\mu) = \frac{1}{2} P_n(\mu) \log \frac{1+\mu}{1-\mu} - Z_n, \quad \dots \dots \dots (9)$$

where

$$Z_n = \frac{2n-1}{1-n} P_{n-1} + \frac{2n-5}{3(n-1)} P_{n-3} + \dots \dots \dots (10)$$

This function $Q_n(\mu)$ is sometimes called the zonal harmonic 'of the second kind'

Thus

$$\begin{aligned} Q_0(\mu) &= \frac{1}{2} \log \frac{1+\mu}{1-\mu}, & Q_2(\mu) &= \frac{1}{4} (3\mu^2 - 1) \log \frac{1+\mu}{1-\mu} - \frac{3}{2}\mu, \\ Q_1(\mu) &= \frac{1}{2}\mu \log \frac{1+\mu}{1-\mu} - 1, & Q_3(\mu) &= \frac{1}{4} (5\mu^2 - 3\mu) \log \frac{1+\mu}{1-\mu} - \frac{5}{2}\mu^2 + \frac{3}{2}. \end{aligned}$$

86 When we abandon the restriction as to symmetry about the axis of x , we may suppose S_n a finite and single-valued function of ω , to be expanded in a series of terms varying as $\cos s\omega$ and $\sin s\omega$ respectively. If this expansion is to apply to the whole sphere (i.e. from $\omega = 0$ to $\omega = 2\pi$), we may further (by Fourier's theorem) suppose the values of s to be integral. The differential equation satisfied by any such term is

$$\frac{d}{d\mu} \left\{ (1-\mu^2) \frac{dS_n}{d\mu} \right\} + \left\{ n(n+1) - \frac{s^2}{1-\mu^2} \right\} S_n = 0 \quad \dots \dots (1)$$

* This is equivalent to Art. 84 (4) with, for n even, $A=0$, $B=(-)^{\frac{1}{2}n} \frac{2 \cdot 4 \cdot n}{1 \cdot 3 \cdot (n-1)}$; whilst for n odd we have $A=(-)^{\frac{1}{2}(n+1)} \frac{2 \cdot 4 \cdot (n-1)}{3 \cdot 5 \cdot n}$, $B=0$. See Heine, t. 1 pp. 141, 147.

If we put
this takes the form

$$(1 - \mu^2) \frac{d^2 v}{d\mu^2} - 2(s+1)\mu \frac{dv}{d\mu} + (n-s)(n+s+1)v = 0,$$

which is suitable for integration by series. We thus obtain

$$\begin{aligned} S_n = A (1 - \mu^2)^{\frac{1}{2}s} \left\{ 1 - \frac{(n-s)(n+s+1)}{1 \cdot 2} \mu^2 \right. \\ \left. + \frac{(n-s-2)(n-s)(n+s+1)(n+s+3)}{1 \cdot 2 \cdot 3 \cdot 4} \mu^4 - \dots \right\} \\ + B (1 - \mu^2)^{\frac{1}{2}s} \left\{ \mu - \frac{(n-s-1)(n+s+2)}{1 \cdot 2 \cdot 3} \mu^3 \right. \\ \left. + \frac{(n-s-3)(n-s-1)(n+s+2)(n+s+4)}{1 \cdot 2 \cdot 3 \cdot 4 \cdot 5} \mu^5 - \dots \right\}, \quad (2) \end{aligned}$$

the factor $\cos s\omega$ or $\sin s\omega$ being for the moment omitted. In the hypergeometric notation this may be written

$$S_n = (1 - \mu^2)^{\frac{1}{2}s} \{ A F(\tfrac{1}{2}s - \tfrac{1}{2}n, \tfrac{1}{2} + \tfrac{1}{2}s + \tfrac{1}{2}n, \tfrac{1}{2}, \mu^2) + B \mu F(\tfrac{1}{2} + \tfrac{1}{2}s - \tfrac{1}{2}n, 1 + \tfrac{1}{2}s + \tfrac{1}{2}n, \tfrac{3}{2}, \mu^2) \}. \quad (3)$$

These expressions converge when $\mu^2 < 1$, but since in each case we have

$$\gamma - \alpha - \beta = -s,$$

the series become infinite as $(1 - \mu^2)^{-s}$ at the limits $\mu = \pm 1$, unless they terminate*. The former series terminates when $n-s$ is an even, and the latter when it is an odd integer. By reversing the series we can express both these finite solutions by the single formula†

$$\begin{aligned} P_n^s(\mu) = \frac{(2n)!}{2^n (n-s)! n!} (1 - \mu^2)^{\frac{1}{2}s} \left\{ \mu^{n-s} - \frac{(n-s)(n-s-1)}{2 \cdot (2n-1)} \mu^{n-s-2} \right. \\ \left. + \frac{(n-s)(n-s-1)(n-s-2)(n-s-3)}{2 \cdot 4 \cdot (2n-1)(2n-3)} \mu^{n-s-4} - \dots \right\} \quad (4) \end{aligned}$$

On comparison with Art. 85 (1) we find that

$$P_n^s(\mu) = (1 - \mu^2)^{\frac{1}{2}s} \frac{d^s P_n(\mu)}{d\mu^s} \quad \dots \quad (5)$$

That this is a solution of (1) may of course be verified independently,

In terms of $\sin \frac{1}{2}\theta$, we have

$$\begin{aligned} P_n^s(\cos \theta) = \frac{(n+s)!}{2^s (n-s)! s!} \sin^s \theta \left\{ 1 - \frac{(n-s)(n+s+1)}{1 \cdot (s+1)} \sin^2 \tfrac{1}{2}\theta \right. \\ \left. + \frac{(n-s-1)(n-s)(n+s+1)(n+s+2)}{1 \cdot 2 \cdot (s+1)(s+2)} \sin^4 \tfrac{1}{2}\theta - \dots \right\} \quad (6) \end{aligned}$$

This corresponds to Art. 85 (4), from which it can easily be derived

* Lord Rayleigh, *Theory of Sound*, London, 1877, Art. 338

† There are great varieties of notation in connection with these 'associated functions,' as they have been called. That chosen in the text was proposed by F. Neumann, and is adopted by Whittaker, p. 231

Collecting our results we learn that a surface harmonic which is finite over the unit sphere is necessarily of integral order, and is further expressible, if n denote the order, in the form

$$S_n = A_0 P_n(\mu) + \sum_{s=1}^{s=n} (A_s \cos s\omega + B_s \sin s\omega) P_n^s(\mu), \quad \dots (7)$$

containing $2n+1$ arbitrary constants. The terms of this involving ω are called 'tesseral' harmonics, with the exception of the last two, which are given by the formula

$$(1 - \mu^2)^{\frac{1}{2}n} (A_n \cos n\omega + B_n \sin n\omega),$$

and are called 'sectorial' harmonics*, the names being suggested by the forms of the compartments into which the unit sphere is divided by the nodal lines $S_n = 0$.

The formula for the tesseral harmonic of rank s may be obtained otherwise from the general expression (6) of Art. 82 by making $n-s$ out of the n poles of the harmonic coincide at the point $\theta=0$ of the sphere, and distributing the remaining s poles evenly round the equatorial circle $\theta=\frac{1}{2}\pi$.

The remaining solution of (1), in the case of n integral, may be put in the form

$$S_n = (A_s \cos s\omega + B_s \sin s\omega) Q_n^s(\mu), \quad \dots (8)$$

where†
$$Q_n^s(\mu) = (1 - \mu^2)^{\frac{1}{2}s} \frac{d^s Q_n(\mu)}{d\mu^s} \quad \dots (9)$$

This is sometimes called a tesseral harmonic 'of the second kind'

87 Two surface harmonics S, S' are said to be 'conjugate' when

$$\iint SS' d\omega = 0, \quad \dots (1)$$

where $d\omega$ is an element of surface of the unit sphere, and the integration extends over this sphere.

It may be shewn that any two surface harmonics, of different orders, which are finite over the unit sphere, are conjugate, and also that the $2n+1$ harmonics of any given order n , of the zonal, tesseral, and sectorial types specified in Arts 85, 86 are all mutually conjugate. It will appear, later, that the conjugate property is of great importance in the physical applications of the subject.

Since $\delta\omega = \sin\theta\delta\theta\delta\omega = -\delta\mu\delta\omega$, we have, as particular cases of this theorem,

$$\int_{-1}^1 P_m(\mu) d\mu = 0, \quad \dots (2)$$

* The prefix 'spherical' is implied, it is often omitted for brevity.

† A table of the functions $Q_n(\mu)$, $Q_n^s(\mu)$, for various values of n and s , is given by Bryan, *Proc Camb Phil Soc*, t vi p 297.

For example, we may put

$$\alpha, \beta, \gamma = 1, \quad i \cos \vartheta, \quad i \sin \vartheta, \quad \dots \dots \dots (3)$$

or, again,

$$\alpha, \beta, \gamma = 1, \quad i \cosh u, \quad \sinh u \quad \dots \dots \dots (4)$$

It may be shewn* that the most general solution possible can be obtained by superposition of solutions of the type (1)

Using (3), and introducing the cylindrical co-ordinates x, ϖ, ω , where

$$y = \varpi \cos \omega, \quad z = \varpi \sin \omega \dots \dots \dots (5)$$

we build up a solution symmetrical about the axis of x if we take

$$\phi = \frac{1}{2\pi} \int_0^{2\pi} f\{x + i\varpi \cos(\vartheta - \omega)\} d\vartheta.$$

For, since the integration extends over a whole circumference, it is immaterial where the origin of ϑ is placed, and the formula may therefore be written†

$$\phi = \frac{1}{2\pi} \int_0^{2\pi} f(x + i\varpi \cos \vartheta) d\vartheta = \frac{1}{\pi} \int_0^\pi f(x + i\varpi \cos \vartheta) d\vartheta. \quad (6)$$

This is remarkable as giving a value of ϕ , symmetrical about the axis of x , in terms of its values $f(x)$ at points of this axis‡. It may be shewn, by means of the theorem of Art. 38, that the form of ϕ is in such a case completely determined by the values over any finite length of the axis§

As particular cases of (6) we have the functions

$$\frac{1}{\pi} \int_0^\pi (x + i\varpi \cos \vartheta)^n d\vartheta, \quad \frac{1}{\pi} \int_0^\pi (x + i\varpi \cos \vartheta)^{-n-1} d\vartheta,$$

where n will be supposed to be integral. Since these are solid harmonics finite over the unit sphere, and since, for $\varpi = 0$, they reduce to r^n and r^{-n-1} , they must be equivalent to $P_n(\mu)r^n$, and $P_n(\mu)r^{-n-1}$, respectively. We thus obtain the forms

$$P_n(\mu) = \frac{1}{\pi} \int_0^\pi \{\mu + i\sqrt{1-\mu^2} \cos \vartheta\}^n d\vartheta, \quad \dots \dots \dots (7)$$

$$P_n(\mu) = \frac{1}{\pi} \int_0^\pi \frac{d\vartheta}{\{\mu + i\sqrt{1-\mu^2} \cos \vartheta\}^{n+1}}, \quad \dots \dots \dots (8)$$

due originally to Laplace|| and Jacobi¶, respectively

* Whittaker, *Month. Not. R. Ast. Soc.*, t. LXII. (1902)

† Whittaker, *Modern Analysis*, c. XIII

‡ Whittaker, p. 321

§ Thomson and Tait, Art. 498

|| *Méc. Céleste*, Livre II^{me}, c. II

¶ *Crelle*, t. XXVI (1843) [*Gesammelte Werke*, Berlin, 1881, t. VI. p. 148]

90 As a first application of the foregoing theory let us suppose that an arbitrary distribution of impulsive pressure is applied to the surface of a spherical mass of fluid initially at rest. This is equivalent to prescribing an arbitrary value of ϕ over the surface, the value of ϕ in the interior is thence determinate, by Art 40. To find it, we may suppose the given surface value to be expanded, in accordance with the theorem quoted in Art 88, in a series of surface-harmonics of integral order, thus

$$\phi = S_0 + S_1 + S_2 + \dots + S_n + \dots \dots \dots (1)$$

The required value is then

$$\phi = S_0 + \frac{r}{a} S_1 + \frac{r^2}{a^2} S_2 + \dots + \frac{r^n}{a^n} S_n + \dots, \dots \dots (2)$$

for this satisfies $\nabla^2 \phi = 0$, and assumes the prescribed form (1) when $r = a$, the radius of the sphere.

The corresponding solution for the case of a prescribed value of ϕ over the surface of a spherical cavity in an infinite mass of liquid initially at rest is evidently

$$\phi = \frac{a}{r} S_0 + \frac{a^2}{r^2} S_1 + \frac{a^3}{r^3} S_2 + \dots + \frac{a^{n+1}}{r^{n+1}} S_n + \dots \dots \dots (3)$$

Combining these two results we get the case of an infinite mass of fluid whose continuity is interrupted by an infinitely thin vacuous stratum, of spherical form, within which an arbitrary impulsive pressure is applied. The values (2) and (3) of ϕ are of course continuous at the stratum, but the values of the normal velocity are discontinuous, viz. we have, for the internal fluid,

$$\frac{\partial \phi}{\partial r} = \Sigma n \frac{S_n}{a},$$

and for the external fluid

$$\frac{\partial \phi}{\partial r} = - \Sigma (n+1) \frac{S_n}{a}.$$

The motion, whether internal or external, is therefore that due to a distribution of simple sources with surface-density

$$\Sigma (2n+1) \frac{S_n}{a} \dots \dots \dots (4)$$

over the sphere, see Art. 58.

91. Let us next suppose that, instead of the impulsive pressure, it is the normal velocity which is prescribed over the spherical surface, thus

$$\frac{\partial \phi}{\partial r} = S_1 + S_2 + \dots + S_n + \dots \dots \dots (1)$$

the term of zero order being necessarily absent, since we must have

$$\iint \frac{\partial \phi}{\partial r} d\varpi = 0, \quad \dots \quad (2)$$

on account of the constancy of volume of the included mass

The value of ϕ for the internal space is of the form

$$\phi = A_1 r S_1 + A_2 r^2 S_2 + \dots + A_n r^n S_n + \dots, \quad (3)$$

for this is finite and continuous, and satisfies $\nabla^2 \phi = 0$, and the constants can be determined so as to make $\partial \phi / \partial r$ assume the given surface-value (1), viz we have $n A_n a^{n-1} = 1$. The required solution is therefore

$$\phi = a \sum \frac{1}{n} \frac{r^n}{a^n} S_n \quad (4)$$

The corresponding solution for the external space is found in like manner to be

$$\phi = -a \sum \frac{1}{n+1} \frac{a^{n+1}}{r^{n+1}} S_n \quad \dots \quad (5)$$

The two solutions, taken together, give the motion produced in an infinite mass of liquid which is divided into two portions by a thin spherical membrane, when a prescribed normal velocity is given to every point of the membrane, subject to the condition (2)

The value of ϕ changes from $a \sum S_n / n$ to $-a \sum S_n / (n+1)$, as we cross the membrane, so that the *tangential* velocity is now discontinuous. The motion, whether inside or outside, is that due to a *double-sheet* of density

$$-a \sum \frac{2n+1}{n(n+1)} S_n, \quad (6)$$

see Art. 58

The kinetic energy of the internal fluid is given by the formula (4) of Art 44, viz

$$2T = \rho \iint \phi \frac{\partial \phi}{\partial r} dS = \rho a^3 \sum \frac{1}{n} \iint S_n^2 d\varpi, \quad \dots \quad (7)$$

the parts of the integral which involve products of surface-harmonics of different orders disappearing in virtue of the conjugate property of Art. 87

For the external fluid we have

$$2T = -\rho \iint \phi \frac{\partial \phi}{\partial r} dS = \rho a^3 \sum \frac{1}{n+1} \iint S_n^2 d\varpi \quad \dots \quad (8)$$

92 A particular, but very important, case of the problem of the preceding Article is that of the motion of a solid sphere in an infinite mass of liquid which is at rest at infinity. If we take the origin at the centre of the sphere, and the axis of x in the direction of motion, the

normal velocity at the surface is Ux/r , $= U \cos \theta$, where U is the velocity of the centre. Hence the conditions to determine ϕ are (1°) that we must have $\nabla^2 \phi = 0$ everywhere, (2°) that the space-derivatives of ϕ must vanish at infinity, and (3°) that at the surface of the sphere ($r = a$), we must have

$$-\frac{\partial \phi}{\partial r} = U \cos \theta. \quad \dots \dots \dots (1)$$

The form of this suggests at once the zonal harmonic of the first order, we therefore assume

$$\phi = A \frac{\partial}{\partial x} \frac{1}{r} = -A \frac{\cos \theta}{r^2}$$

The condition (1) gives $-2A/a^3 = U$, so that the required solution is*

$$\phi = \frac{1}{2} U \frac{a^3}{r^2} \cos \theta \quad \dots \dots \dots (2)$$

It appears on comparison with Art. 56 (4) that the motion of the fluid is the same as would be produced by a *double-source* of strength $2\pi Ua^3$, situate at the centre of the sphere. For the forms of the stream-lines see p. 121

To find the energy of the fluid motion we have

$$\begin{aligned} 2T &= -\rho \iint \phi \frac{\partial \phi}{\partial r} dS = \frac{1}{2} \rho a U^2 \int_0^\pi \cos^2 \theta \cdot 2\pi a \sin \theta \cdot a d\theta \\ &= \frac{2}{3} \pi \rho a^3 U^2 = M' U^2, \quad \dots \dots \dots (3) \end{aligned}$$

if $M' = \frac{2}{3} \pi \rho a^3$. It appears, exactly as in Art. 68, that the effect of the fluid pressure is equivalent simply to an addition to the *inertia* of the solid, the increment being now *half* the mass of the fluid displaced†

Thus in the case of rectilinear motion of the sphere, if no external forces act on the fluid, the resultant pressure is equivalent to a force

$$-M' \frac{dU}{dt}, \quad \dots \dots \dots (4)$$

in the direction of motion, vanishing when U is constant. Hence if the sphere be set in motion and left to itself, it will continue to move in a straight line with constant velocity.

The behaviour of a solid projected in an actual fluid is of course quite different, a continual application of force is necessary to maintain the motion, and if this be not supplied the solid is gradually brought to rest

* Stokes, "On some cases of Fluid Motion," *Camb. Trans.*, t. viii. (1843) [*Math. and Phys. Papers*, t. i. p. 17]

Dirichlet, "Ueber die Bewegung eines festen Körpers in einem incompressibeln flüssigen Medium," *Berl. Monatsber.*, 1852 [*Werke*, Berlin, 1889-97, t. ii. p. 115]

† Stokes, *l. c.* The result had been obtained otherwise, on the hypothesis of infinitely small motion, by Green, "On the Vibration of Pendulums in Fluid Media," *Edin. Trans.*, 1833 [*Math. Papers*, p. 315]

It must be remembered however, in making this comparison, that in a 'perfect' fluid there is no dissipation of energy, and that if, further, the fluid be incompressible, the solid cannot lose its kinetic energy by transfer to the fluid, since, as we have seen in Chapter III, the motion of the fluid is entirely determined by that of the solid, and therefore ceases with it

If we wish to verify the preceding results by direct calculation from the formula

$$\frac{p}{\rho} = \frac{\partial \phi}{\partial t} - \frac{1}{2} q^2 + F(t), \quad (5)$$

we must remember, as in Art 68, that the origin is in motion, and that the values of r and θ for a fixed point of space are therefore increasing at the rates $-U \cos \theta$, and $(U \sin \theta)/r$, respectively. We thus find, for $r=a$,

$$\frac{p}{\rho} = \frac{1}{2} a \frac{dU}{dt} \cos \theta + \frac{9}{16} U^2 \cos 2\theta - \frac{1}{16} U^2 + F(t) \quad (6)$$

The last three terms are the same for surface-elements in the positions θ and $\pi - \theta$, so that, when U is constant, the pressures on the various elements of the anterior half of the sphere are balanced by equal pressures on the corresponding elements of the posterior half. But when the motion of the sphere is being accelerated there is an excess of pressure on the anterior, and a defect on the posterior half. The reverse holds when the motion is being retarded. The resultant effect in the direction of motion is

$$-\int_0^\pi 2\pi a \sin \theta \, a d\theta \, p \cos \theta = -\frac{3}{2} \pi \rho a^3 \frac{dU}{dt},$$

as before

93. The same method can be applied to find the motion produced in a liquid contained between a solid sphere and a fixed concentric spherical boundary, when the sphere is moving with given velocity U .

The centre of the sphere being taken as origin, it is evident, since the space occupied by the fluid is limited both externally and internally, that solid harmonics of both positive and negative degrees are admissible, they are in fact required, in order to satisfy the boundary conditions, which are

$$-\partial \phi / \partial r = U \cos \theta,$$

for $r=a$, the radius of the sphere, and

$$\partial \phi / \partial r = 0,$$

for $r=b$, the radius of the external boundary, the axis of x being as before in the direction of motion.

$$\text{We therefore assume} \quad \phi = \left(Ar + \frac{B}{r^2} \right) \cos \theta, \quad \dots (1)$$

and the conditions in question give

$$A - \frac{2B}{a^3} = -U, \quad A - \frac{2B}{b^3} = 0,$$

$$\text{whence} \quad A = \frac{a^3}{b^3 - a^3} U, \quad B = \frac{1}{2} \frac{a^3 b^3}{b^3 - a^3} U \quad \dots (2)$$

The kinetic energy of the fluid motion is given by

$$2T = - \rho \iint \phi \frac{\partial \phi}{\partial r} dS,$$

the integration extending over the inner spherical surface, since at the outer we have $\partial \phi / \partial r = 0$. We thus find

$$2T = \frac{2}{3} \pi \frac{b^3 + 2a^3}{b^3 - a^3} \rho a^3 U^2 \quad \dots \dots \dots (3)$$

It appears that the effective addition to the inertia of the sphere is now*

$$\frac{2}{3} \pi \frac{b^3 + 2a^3}{b^3 - a^3} \rho a^3 \quad \dots \dots \dots (4)$$

As b diminishes from ∞ to a , this increases continually from $\frac{2}{3} \pi \rho a^3$ to ∞ , in accordance with Lord Kelvin's minimum theorem (Art 45). In other words, the introduction of a rigid spherical partition in the problem of Art 92 acts as a constraint increasing the kinetic energy for any given velocity of the sphere, and so virtually increasing the inertia of the system

94. In all cases where the motion of a liquid takes place in a series of planes passing through a common line, and is the same in each such plane, there exists a stream-function analogous in some of its properties to the two-dimensional stream-function of the last Chapter. If in any plane through the axis of symmetry we take two points A and P , of which A is arbitrary, but fixed, while P is variable, then considering the annular surface generated by any line AP , it is plain that the flux across this surface is a function of the position of P . Denoting this function by $2\pi\psi$, and taking the axis of x to coincide with that of symmetry, we may say that ψ is a function of x and ϖ , where x is the abscissa of P , and $\varpi = (y^2 + z^2)^{\frac{1}{2}}$, is its distance from the axis. The curves $\psi = \text{const}$ are evidently stream-lines

If P' be a point infinitely near to P in a meridian plane, it follows from the above definition that the velocity normal to PP' is equal to

$$\frac{2\pi \delta \psi}{2\pi \varpi \cdot PP'},$$

whence, taking PP' parallel first to ϖ and then to x ,

$$u = - \frac{1}{\varpi} \frac{\partial \psi}{\partial \varpi}, \quad v = \frac{1}{\varpi} \frac{\partial \psi}{\partial x}, \quad \dots \dots \dots (1)$$

where u and v are the components of fluid velocity in the directions of x and ϖ respectively, the convention as to sign being similar to that of Art 59

These kinematical relations may also be inferred from the form which the equation of continuity takes under the present circumstances. If we express

* Stokes, *l c ante* p. 115

that the total flux into the annular space generated by the revolution of an elementary rectangle $\delta x \delta \varpi$ is zero, we find

$$\frac{\partial}{\partial x} (u - 2\pi\varpi\delta\varpi) \delta x + \frac{\partial}{\partial \varpi} (v - 2\pi\varpi\delta x) \delta \varpi = 0,$$

or
$$\frac{\partial}{\partial x} (\varpi u) + \frac{\partial}{\partial \varpi} (\varpi v) = 0, \quad (2)$$

which shews that $\varpi v \, dx - \varpi u \, d\varpi$

is an exact differential Denoting this by $d\psi$ we obtain the relations (1)*

So far the motion has not been assumed to be irrotational, the condition that it should be so is

$$\frac{\partial v}{\partial x} - \frac{\partial u}{\partial \varpi} = 0,$$

which leads to
$$\frac{\partial^2 \psi}{\partial x^2} + \frac{\partial^2 \psi}{\partial \varpi^2} - \frac{1}{\varpi} \frac{\partial \psi}{\partial \varpi} = 0 \quad (3)$$

The differential equation of ϕ is obtained by writing

$$u = -\frac{\partial \phi}{\partial x}, \quad v = -\frac{\partial \phi}{\partial \varpi}$$

in (2), viz it is
$$\frac{\partial^2 \phi}{\partial x^2} + \frac{\partial^2 \phi}{\partial \varpi^2} + \frac{1}{\varpi} \frac{\partial \phi}{\partial \varpi} = 0 \quad (4)$$

It appears that the functions ϕ and ψ are not now (as they were in Art. 62) interchangeable They are, indeed, of different dimensions

The kinetic energy of the liquid contained in any region bounded by surfaces of revolution about the axis is given by

$$\begin{aligned} 2T &= -\rho \iint \phi \frac{\partial \phi}{\partial n} dS \\ &= \rho \int \phi \frac{\partial \psi}{\varpi \partial s} 2\pi\varpi ds \\ &= 2\pi\rho \int \phi d\psi, \quad \dots \dots \dots (5) \end{aligned}$$

δs denoting an element of the meridian section of the bounding surfaces, and the integration extending round the various parts of this section, in the proper directions. Compare Art. 61 (2).

* The stream-function for the case of symmetry about an axis was introduced in this manner by Stokes, "On the Steady Motion of Incompressible Fluids," *Camb Trans*, t vii (1842) [*Math and Phys Papers*, t i p 1] Its analytical theory has been treated very fully by Sampson, "On Stokes' Current-Function," *Phil Trans A* t clxxxii (1891)

95 The velocity-potential due to a point-source at the origin is of the form

$$\phi = \frac{1}{r}. \quad \dots \quad (1)$$

The flux through any closed curve is in this case numerically equal to the solid angle which the curve subtends at the origin. Hence for a circle with Oa as axis, whose radius subtends an angle θ at O , we have, attending to the sign,

$$2\pi\psi = -2\pi(1 - \cos\theta)$$

Omitting the constant term we have

$$\psi = \frac{r'}{r} = \frac{\partial r'}{\partial x}. \quad \dots \quad (2)$$

The solutions corresponding to any number of simple sources situate at various points of the axis of x may evidently be superposed, thus for the double-source

$$\phi = -\frac{\partial}{\partial x} \frac{1}{r} = \frac{\cos\theta}{r^2}, \quad \dots \quad (3)$$

we have

$$\psi = -\frac{\partial^2 r}{\partial x^2} = -\frac{\cos^2\theta}{r^3} = -\frac{\sin^2\theta}{r}. \quad \dots \quad (4)$$

And, generally, to the zonal solid harmonic of degree $-n-1$, viz to

$$\phi = A \frac{\partial^n 1}{\partial x^n r}, \quad \dots \quad (5)$$

corresponds*

$$\psi = A \frac{\partial^{n+1} r}{\partial x^{n+1}} \quad \dots \quad (6)$$

A more general formula, applicable to harmonics of any degree, fractional or not, may be obtained as follows. Using spherical polar co-ordinates r, θ , the component velocities along r , and perpendicular to r in the plane of the meridian, are found by making the linear element PP' of Art. 94 coincide successively with $r\delta\theta$ and δr , respectively, viz they are

$$-\frac{1}{r \sin\theta} \frac{\partial\psi}{\partial\theta}, \quad \frac{1}{r \sin\theta} \frac{\partial\psi}{\partial r} \quad \dots \quad (7)$$

Hence in the case of irrotational motion we have

$$\frac{\partial\psi}{\sin\theta \partial\theta} = r^2 \frac{\partial\phi}{\partial r}, \quad \frac{\partial\psi}{\partial r} = -\sin\theta \frac{\partial\phi}{\partial\theta}. \quad \dots \quad (8)$$

Thus if

$$\phi = r^n S_n, \quad \dots \quad (9)$$

where S_n is a zonal harmonic of order n , we have, putting $\mu = \cos\theta$,

$$\frac{\partial\psi}{\partial\mu} = -n^{n+1} S_n, \quad \frac{\partial\psi}{\partial r} = r^n (1 - \mu^2) \frac{dS_n}{d\mu}.$$

* Stefan, "Ueber die Kraftlinien eines um eine Axe symmetrischen Feldes," *Wied Ann*, t LVII (1882)

The latter equation gives

$$\psi = \frac{1}{n+1} r^{n+1} (1 - \mu^2) \frac{dS_n}{d\mu}, \quad \dots \dots (10)$$

which must necessarily also satisfy the former, this is readily verified by means of Art. 84 (1)

Thus in the case of the zonal harmonic P_n , we have as corresponding values

$$\phi = r^n P_n(\mu), \quad \psi = \frac{1}{n+1} r^{n+1} (1 - \mu^2) \frac{dP_n}{d\mu}, \quad \dots \dots (11)$$

and
$$\phi = r^{-n-1} P_n(\mu), \quad \psi = -\frac{1}{n} r^{-n} (1 - \mu^2) \frac{dP_n}{d\mu}, \quad \dots \dots (12)$$

of which the latter must be equivalent to (5) and (6). The same relations hold of course with regard to the zonal harmonic of the second kind, Q_n

96. We saw in Art 92 that the motion produced by a solid sphere in an infinite mass of liquid may be regarded as due to a double-source at the centre. Comparing the formulae there given with Art 95 (4), it appears that the stream-function due to the sphere is

$$\psi = -\frac{1}{2} U \frac{a^3}{r} \sin^2 \theta \quad \dots \dots (1)$$

The forms of the stream-lines corresponding to a number of equidistant values of ψ are shewn on the opposite page. The stream-lines *relative to the sphere* are figured in a diagram near the end of Chapter VII

Again, the stream-function due to two double-sources having their axes oppositely directed along the axis of x , will be of the form

$$\psi = \frac{A \varpi^2}{r_1^3} - \frac{B \varpi^2}{r_2^3}, \quad \dots \dots (2)$$

where r_1, r_2 denote the distances of any point from the positions, P_1 and P_2 , say, of the two sources. At the stream-surface $\psi = 0$ we have


$$r_1/r_2 = (A/B)^{\frac{1}{3}},$$

so the surface is a sphere in relation to which P_1 and P_2 are inverse points. If O be the centre of this sphere, and a its radius, we find

$$A/B = OP_1^3/a^3 = a^3/OP_2^3. \quad \dots \dots (3)$$

This sphere may be taken as a fixed boundary to the fluid on either side, and we thus obtain the motion due to a double-source (or say to an infinitely small sphere moving along Ox) in presence of a fixed spherical boundary. The disturbance of the stream-lines by the fixed sphere is that due to a double-source of the opposite sign placed at the 'inverse' point, the ratio of

the strengths being given by (3)* This fictitious double-source may be called the 'image' of the original one



97 Rankine† employed a method similar to that of Art 71 to discover forms of solids of revolution which will by motion parallel to their axes generate in a surrounding liquid any given type of irrotational motion symmetrical about an axis.

The velocity of the solid being U , and δs denoting an element of the meridian, the normal velocity at any point of the surface is $U \partial \varpi / \partial s$, and that

* This result was given by Stokes, "On the Resistance of a Fluid to two Oscillating Spheres," *Brit. Ass. Report*, 1847 [*Math and Phys Papers*, t 1 p 230]

† "On the Mathematical Theory of Stream-Lines, especially those with Four Foci and upwards," *Phil Trans*, 1871, p 267

of the fluid in contact is given by $-\partial\psi/\partial s$. Equating these and integrating along the meridian, we have

$$\psi = -\frac{1}{2}U\varpi^2 + \text{const} \quad \dots \quad (1)$$

If in this we substitute any value of ψ satisfying Art 94 (3), we obtain the equation of the meridian curves of a series of solids, each of which would by its motion parallel to x give rise to the given system of stream-lines

In this way we may readily verify the solution already obtained for the sphere, thus, assuming

$$\psi = A\varpi^2/r^3, \quad \dots \quad (2)$$

we find that (1) is satisfied for $r=a$, provided

$$A = -\frac{1}{2}Ua^3, \quad \dots \quad (3)$$

which agrees with Art 96 (1)


98 The motion of a liquid bounded by *two* spherical surfaces can be found by successive approximations in certain cases. For two solid spheres moving in the line of centres the solution is greatly facilitated by the result given at the end of Art 96, as to the 'image' of a double-source in a fixed sphere

Let a, b be the radii, and c the distance between the centres A, B . Let U be the velocity of A towards B , U' that of B towards A . Also, P being any point, let $AP=r$, $BP=r'$, $PAB=\theta$, $PBA=\theta'$. The velocity-potential will be of the form

$$U\phi + U'\phi', \quad \dots \quad (1)$$

where the functions ϕ and ϕ' are to be determined by the conditions that

$$\nabla^2\phi=0, \quad \nabla^2\phi'=0, \quad \dots \quad (2)$$



throughout the fluid, that their space-derivatives vanish at infinity, and that

$$\frac{\partial\phi}{\partial r} = -\cos\theta, \quad \frac{\partial\phi'}{\partial r} = 0, \quad (3)$$

over the surface of A , whilst

$$\frac{\partial\phi}{\partial r'} = 0, \quad \frac{\partial\phi'}{\partial r'} = -\cos\theta', \quad (4)$$

over the surface of B . It is evident that ϕ is the value of the velocity-potential when A moves with unit velocity towards B , while B is at rest, and similarly for ϕ'

To find ϕ , we remark that if B were absent the motion of the fluid would be that due to a certain double-source at A having its axis in the direction AB . The theorem of Art 96 shews that we may satisfy the condition of zero normal velocity over the surface of B by introducing a double-source, viz the 'image' of that at A in the sphere B . This image is at H_1 , the inverse point of A with respect to the sphere B , its axis coincides with AB , and its strength is $-\mu_0 b^3/c^3$, where μ_0 is the strength of the original source at A , viz

$$\mu_0 = 2\pi\alpha^3$$

The resultant motion due to the two sources at A and H_1 will however violate the condition to be satisfied at the surface of the sphere A , and in order to neutralize the normal velocity at this surface, due to H_1 , we must superpose a double-source at H_2 , the image of H_1 in the sphere A . This will introduce a normal velocity at the surface of B , which may again be neutralized by adding the image of H_2 in B , and so on. If $\mu_1, \mu_2, \mu_3, \dots$ be the strengths of the successive images, and f_1, f_2, f_3, \dots their distances from A , we have

$$\left. \begin{aligned} f_1 &= c - \frac{b^2}{c}, & f_2 &= \frac{a^2}{f_1}, & \frac{\mu_1}{\mu_0} &= -\frac{b^3}{c^3}, & \frac{\mu_2}{\mu_1} &= -\frac{a^3}{f_1^3}, \\ f_3 &= c - \frac{b^2}{f_2}, & f_4 &= \frac{a^2}{f_3}, & \frac{\mu_3}{\mu_2} &= -\frac{b^3}{(c-f_2)^3}, & \frac{\mu_4}{\mu_3} &= -\frac{a^3}{f_3^3}, \\ f_5 &= c - \frac{b^2}{f_4}, & f_6 &= \frac{a^2}{f_5}, & \frac{\mu_5}{\mu_4} &= -\frac{b^3}{(c-f_4)^3}, & \frac{\mu_6}{\mu_5} &= -\frac{a^3}{f_5^3}, \end{aligned} \right\} \quad (5)$$

and so on, the laws of formation being obvious. The images continually diminish in intensity, and thus very rapidly if the radius of either sphere is small compared with the shortest distance between the two surfaces

The formula for the kinetic energy is

$$2T = -\rho \iint (U\phi + U'\phi') \left(U \frac{\partial \phi}{\partial n} + U' \frac{\partial \phi'}{\partial n} \right) dS = LU^2 + 2MUU' + N{U'}^2, \quad \dots \quad (6)$$

provided

$$L = -\rho \iint \phi \frac{\partial \phi}{\partial n} dS_n, \quad M = -\rho \iint \phi \frac{\partial \phi'}{\partial n} dS_n = -\rho \iint \phi' \frac{\partial \phi}{\partial n} dS_n, \quad N = -\rho \iint \phi' \frac{\partial \phi'}{\partial n} dS_n, \quad (7)$$

where the suffixes indicate over which sphere the integration is to be effected. The equality of the two forms of M follows from Green's Theorem (Art 44)

The value of ϕ near the surface of A can be written down at once from the results (7) and (8) of Art 85, viz we have

$$4\pi\phi = (\mu_0 + \mu_2 + \mu_4 + \dots) \frac{\cos \theta}{r^2} - 2 \left(\frac{\mu_1}{f_1} + \frac{\mu_3}{f_3} + \dots \right) r \cos \theta + \&c, \quad \dots \quad (8)$$

the remaining terms, involving zonal harmonics of higher orders, being omitted, as they will disappear in the subsequent surface-integration, in virtue of the conjugate property of Art 87. Hence, putting $\partial \phi / \partial n = -\cos \theta$, we find with the help of (5)

$$L = \frac{1}{2}\rho (\mu_0 + 3\mu_2 + 3\mu_4 + \dots) = \frac{2}{3}\pi\rho\alpha^3 \left(1 + 3 \frac{a^3 b^3}{c^3 f_1^3} + 3 \frac{a^6 b^6}{c^3 f_1^3 (c-f_2)^3 f_3^3} + \dots \right) \quad (9)$$

It appears that the inertia of the sphere A is in all cases increased by the presence of a fixed sphere B . Compare Art 93

The value of N may be written down from symmetry, viz it is

$$N = \frac{2}{3}\pi\rho b^3 \left(1 + 3 \frac{a^3 b^3}{c^3 f_1^3} + 3 \frac{a^6 b^6}{c^3 f_1^3 (c-f_2)^3 f_3^3} + \dots \right), \quad \dots \quad (10)$$

where

$$\left. \begin{aligned} f_1' &= c - \frac{a^2}{c}, & f_2' &= \frac{b^2}{f_1'}, \\ f_3' &= c - \frac{a^2}{f_2'}, & f_4' &= \frac{b^2}{f_3'}, \\ f_5' &= c - \frac{a^2}{f_4'}, & f_6' &= \frac{b^2}{f_5'}, \end{aligned} \right\} \quad . \quad (11)$$

and so on

To calculate M we require the value of ϕ' near the surface of the sphere A ; this is due to double-sources $\mu_0', \mu_1', \mu_2', \mu_3', \dots$ at distances $c, c-f_1', c-f_2', c-f_3', \dots$ from A , where $\mu_0' = -2\pi b^3$, and

$$\left. \begin{aligned} \frac{\mu_1'}{\mu_0'} &= -\frac{a^3}{c^3}, & \frac{\mu_2'}{\mu_1'} &= -\frac{b^3}{f_1'^3}, \\ \frac{\mu_3'}{\mu_2'} &= -\frac{a^3}{(c-f_2')^3}, & \frac{\mu_4'}{\mu_3'} &= -\frac{b^3}{f_3'^3}, \\ \frac{\mu_5'}{\mu_4'} &= -\frac{a^3}{(c-f_4')^3}, & \frac{\mu_6'}{\mu_5'} &= -\frac{b^3}{f_5'^3}, \end{aligned} \right\} \quad (12)$$

and so on. This gives, for points near the surface of A ,

$$4\pi\phi' = (\mu_1' + \mu_3' + \mu_5' + \dots) \frac{\cos\theta}{r^2} - 2 \left(\frac{\mu_0'}{c^3} + \frac{\mu_2'}{(c-f_2')^3} + \frac{\mu_4'}{(c-f_4')^3} + \dots \right) \cos\theta + \&c \quad (13)$$

Hence

$$\begin{aligned} M &= -\rho \iint \phi' \frac{\partial\phi}{\partial n} dS = \rho (\mu_1' + \mu_3' + \mu_5' + \dots) \\ &= 2\pi\rho \frac{a^3 b^3}{c^3} \left\{ 1 + \frac{a^3 b^3}{f_1'^3 (c-f_2')^3} + \frac{a^6 b^6}{f_1'^3 f_3'^3 (c-f_2')^3 (c-f_4')^3} + \dots \right\} \end{aligned} \quad (14)$$

When the ratios a/c and b/c are both small we have

$$L = \frac{2}{3}\pi\rho a^3 \left(1 + 3 \frac{a^3 b^3}{c^6} \right), \quad M = 2\pi\rho \frac{a^3 b^3}{c^3}, \quad N = \frac{2}{3}\pi\rho b^3 \left(1 + 3 \frac{a^3 b^3}{c^6} \right), \quad (15)$$

approximately*.

If in the preceding results we put $b=a$, $U'=U$, the plane bisecting AB at right angles will be a plane of symmetry, and may therefore be taken as a fixed boundary to the fluid on either side. Hence, putting $c=2h$, we find, for the kinetic energy of the liquid when a sphere is in motion perpendicular to a rigid plane boundary, at a distance h from it,

$$2T = \frac{2}{3}\pi\rho a^3 \left(1 + 3 \frac{a^3}{h^3} + \dots \right) U^2, \quad (16)$$

a result due to Stokes

99. When the spheres are moving at right angles to the line of centres the problem is more difficult, we shall therefore content ourselves with the first steps in the approximation, referring, for a more complete treatment, to the papers cited below

* To this degree of approximation the results may be more easily obtained without the use of 'images,' the procedure being similar to that of the next Art

Let the spheres be moving with velocities V, V' in parallel directions at right angles to A, B , and let r, θ, ω and r', θ', ω' be two systems of spherical polar co-ordinates having their origins at A and B respectively, and their polar axes in the directions of the velocities V, V' . The velocity-potential will be of the form

$$V\phi + V'\phi',$$

with the surface conditions

$$\frac{\partial\phi}{\partial r} = -\cos\theta, \quad \frac{\partial\phi'}{\partial r'} = 0, \quad \text{for } r=a, \quad \dots \dots \dots (1)$$

$$\text{and} \quad \frac{\partial\phi}{\partial r'} = 0, \quad \frac{\partial\phi'}{\partial r} = -\cos\theta', \quad \text{for } r'=b \quad \dots \dots \dots (2)$$

If the sphere B were absent the velocity-potential due to unit velocity of A would be

$$\frac{1}{2} \frac{a^3}{r^2} \cos\theta$$

Since $r \cos\theta = r' \cos\theta'$, the value of this in the neighbourhood of B will be

$$\frac{1}{2} \frac{a^3}{c^3} r' \cos\theta',$$

approximately. The normal velocity at the surface of B , due to this, will be cancelled by the addition of the term

$$\frac{1}{4} \frac{a^3 b^3}{c^3} \frac{\cos\theta'}{r'^2},$$

which, in the neighbourhood of A becomes equal to

$$\frac{1}{4} \frac{a^3 b^3}{c^6} r \cos\theta,$$

nearly. To rectify the normal velocity at the surface of A , we add the term

$$\frac{1}{8} \frac{a^6 b^3}{c^6} \frac{\cos\theta}{r^2}.$$

Stopping at this point, and collecting our results, we have, over the surface of A ,

$$\phi = \frac{1}{2} a \left(1 + \frac{1}{4} \frac{a^3 b^3}{c^6} \right) \cos\theta, \quad \dots \dots \dots (3)$$

$$\text{and at the surface of } B, \quad \phi = \frac{1}{2} b \frac{a^3}{c^3} \cos\theta', \quad \dots \dots \dots (4)$$

Hence if we denote by P, Q, R the coefficients in the expression for the kinetic energy, viz

$$2T = P V^2 + 2Q V V' + R V'^2, \quad \dots \dots \dots (5)$$

we have

$$\left. \begin{aligned} P &= -\rho \iint \phi \frac{\partial\phi}{\partial n} dS_A = \frac{2}{3} \pi \rho a^3 \left(1 + \frac{1}{4} \frac{a^3 b^3}{c^6} \right), \\ Q &= -\rho \iint \phi \frac{\partial\phi'}{\partial n} dS_B = \pi \rho \frac{a^3 b^3}{c^3}, \\ R &= -\rho \iint \phi' \frac{\partial\phi'}{\partial n} dS_B = \frac{2}{3} \pi \rho b^3 \left(1 + \frac{1}{4} \frac{a^3 b^3}{c^6} \right) \end{aligned} \right\} \quad \dots \dots \dots (6)$$

The case of a sphere moving parallel to a fixed plane boundary, at a distance h , is obtained by putting $b=a$, $V=V'$, $c=2h$, and halving the consequent value of T , thus

$$2T = \frac{2}{3} \pi \rho a^3 \left(1 + \frac{3}{16} \frac{a^3}{h^3} \right) V^2 \quad (7)$$

This result, which was also given by Stokes, may be compared with that of Art 98 (16)*

Cylindrical Harmonics.

100 In terms of the cylindrical co-ordinates x , ϖ , ω introduced in Art 89, the equation $\nabla^2 \phi = 0$ takes the form

$$\frac{\partial^2 \phi}{\partial x^2} + \frac{\partial^2 \phi}{\partial \varpi^2} + \frac{1}{\varpi} \frac{\partial \phi}{\partial \varpi} + \frac{1}{\varpi^2} \frac{\partial^2 \phi}{\partial \omega^2} = 0 \quad (1)$$

This may be obtained by direct transformation, or more simply by expressing that the total flux across the boundary of an element $\delta x \delta \varpi \varpi \delta \omega$ is zero, after the manner of Art 83

In the case of symmetry about the axis of x , the equation reduces to the form (4) of Art 94. A particular solution is then $\phi = e^{\pm kx} \chi(\varpi)$, provided

$$\chi''(\varpi) + \frac{1}{\varpi} \chi'(\varpi) + k^2 \chi(\varpi) = 0 \quad \dots \dots \dots (2)$$

This is the differential equation of 'Bessel's Functions' of zero order. Its complete primitive consists, of course, of the sum of two definite functions of ϖ , each multiplied by an arbitrary constant. That solution which is finite for $\varpi = 0$ is easily found in the form of an ascending series, it is usually denoted by $CJ_0(k\varpi)$, where

$$J_0(\xi) = 1 - \frac{\xi^2}{2^2} + \frac{\xi^4}{2^2 \cdot 4^2} - \dots \dots \dots (3)$$

We have thus obtained solutions of $\nabla^2 \phi = 0$ of the types†

$$\phi = e^{\pm kx} J_0(k\varpi). \quad \dots \dots \dots (4)$$

It is easily seen from Art 94 (1) that the corresponding value of the stream-function is

$$\psi = \mp \varpi e^{\pm kx} J_0'(k\varpi) \quad \dots \dots \dots (5)$$

The formula (4) may be recognized as a particular case of Art. 89 (6), viz it is equivalent to

$$\phi = \frac{1}{\pi} \int_0^\pi e^{\pm k(x + i\varpi \cos \vartheta)} d\vartheta, \quad \dots \dots (6)$$

* For a fuller analytical treatment of the problem of the motion of two spheres we refer to the following papers: W. M. Hicks, "On the Motion of two Spheres in a Fluid," *Phil. Trans.*, 1880, p. 455; R. A. Herman, "On the Motion of two Spheres in Fluid," *Quart. Journ. Math.*, t. xxii (1887); Basset, "On the Motion of Two Spheres in a Liquid, &c.," *Proc. Lond. Math. Soc.*, t. xviii p. 369 (1887). See also C. Neumann, *Hydrodynamische Untersuchungen*, Leipzig, 1883; Basset, *Hydrodynamics*, Cambridge, 1888, t. i.

† Except as to notation these solutions are to be found in Poisson, *l. c. ante* p. 16.

since
$$J_0(\zeta) = \frac{1}{\pi} \int_0^\pi \cos(\zeta \cos \vartheta) d\vartheta = \frac{1}{\pi} \int_0^\pi e^{i\zeta \cos \vartheta} d\vartheta, \quad \dots \quad (7)$$

as may be verified by developing the cosine, and integrating term by term

Again, (4) may also be identified as the limiting form assumed by a spherical solid zonal harmonic when the order (n) is made infinite, provided that at the same time the distance of the origin from the point considered be made infinitely great, the two infinities being subject to a certain relation*

Thus we may take

$$\phi = \frac{r^n}{a^n} P_n(\mu) = \left(1 + \frac{x}{a}\right)^n H_n(\varpi), \quad \dots \quad (8)$$

where we have temporarily changed the meanings of x and ϖ , viz

$$r = a + x, \quad \varpi = 2a \sin \frac{1}{2}\theta,$$

whilst
$$H_n(\varpi) = 1 - \frac{n(n+1)}{2^2} \frac{\varpi^2}{a^2} + \frac{(n-1)n(n+1)(n+2)}{2^2 \cdot 4^2} \frac{\varpi^4}{a^4} - \dots, \quad (9)$$

see Art 85 (4). If we now put $k=n/a$, and suppose a and n to become infinite, whilst k remains finite, the symbols x and ϖ will regain their former meanings, and we reproduce the formula (4) with the upper sign in the exponential. The lower sign is obtained if we start with

$$\phi = \frac{a^{n+1}}{r^{n+1}} P_n(\mu)$$

The same procedure leads to an expression of an arbitrary function of ϖ in terms of the Bessel's Function of zero order†. According to Art 88, an arbitrary function of latitude on the surface of a sphere can be expanded in spherical zonal harmonics, thus

$$F(\mu) = \sum (n + \frac{1}{2}) P_n(\mu) \int_{-1}^1 F(\mu') P_n(\mu') d\mu' \quad \dots \quad (10)$$

If we denote by ϖ the length of the chord drawn to the variable point from the pole ($\theta=0$) of the sphere, we have

$$\varpi = 2a \sin \frac{1}{2}\theta, \quad \varpi \delta \varpi = -a^2 \delta \mu,$$

where a is the radius, so that the formula may be written

$$f(\varpi) = \frac{1}{a^2} \sum (n + \frac{1}{2}) H_n(\varpi) \int_0^{2a} f(\varpi') H_n(\varpi') \varpi' d\varpi' \quad (11)$$

* This process was indicated, without the restriction to symmetry, by Thomson and Tait, Art 783 (1867)

† The procedure appears to be due substantially to C Neumann (1862), for the history of the theorem (12) see Heine, t 1 p 442, and Nielsen (*op cit.* p 128) p 360.

If we now put $k = \frac{n}{a}$, $\delta k = \frac{1}{a}$,

and finally make a infinite, we obtain the important theorem :

$$f(\varpi) = \int_0^\infty J_0(k\varpi) k dk \int_0^\infty f(\varpi') J_0(k\varpi') \varpi' d\varpi'. \quad \dots \quad (12)$$

101. If in (1) we suppose ϕ to be expanded in a series of terms varying as $\cos s\omega$ or $\sin s\omega$, each such term will be subject to an equation of the form

$$\frac{\partial^2 \phi}{\partial x^2} + \frac{\partial^2 \phi}{\partial \varpi^2} + \frac{1}{\varpi} \frac{\partial \phi}{\partial \varpi} - \frac{s^2}{\varpi^2} \phi = 0. \quad \dots \quad (13)$$

This will be satisfied by $\phi = e^{\pm kx} \chi(\varpi)$, provided

$$\chi''(\varpi) + \frac{1}{\varpi} \chi'(\varpi) + \left(k^2 - \frac{s^2}{\varpi^2}\right) \chi(\varpi) = 0, \quad \dots \quad (14)$$

which is the differential equation of Bessel's Functions of order s^* . The solution which is finite for $\varpi = 0$ may be written $\chi(\varpi) = CJ_s(k\varpi)$, where

$$J_s(\xi) = \frac{\xi^s}{2^s s!} \left\{ 1 - \frac{\xi^2}{2(2s+2)} + \frac{\xi^4}{2 \cdot 4(2s+2)(2s+4)} - \dots \right\} \quad \dots \quad (15)$$

The complete solution of (14) involves, in addition, a Bessel's Function 'of the second kind' with whose form we shall be concerned at a later period in our subject†

We have thus obtained solutions of the equation $\nabla^2 \phi = 0$, of the types

$$\phi = e^{\pm kx} J_s(k\varpi) \frac{\cos}{\sin} s\omega \quad \dots \quad (16)$$

These may also be obtained as limiting forms of the spherical solid harmonics

$$\frac{r^n}{a^n} P_n^s(\mu) \frac{\cos}{\sin} s\omega, \quad \frac{a^{n+1}}{r^{n+1}} P_n^s(\mu) \frac{\cos}{\sin} s\omega,$$

with the help of the expansion (6) of Art 86‡.

* Forsyth, Art. 100, Whittaker, c xi

† For the further theory of the Bessel's Functions of both kinds recourse may be had to Lommel, *Studien ueber die Bessel'schen Funktionen*, Leipzig, 1868; Gray and Mathews, *Treatise on Bessel Functions*, London, 1895, H. Weber, *Partielle Differentialgleichungen d math Physik*, Braunschweig, 1900—01, Nielsen, *Handbuch d Theorie d Cylanderfunktionen*, Leipzig, 1904, and to the treatises of Heine, Todhunter, Forsyth, Byerly, and Whittaker, already cited. An ample account of the subject, from the physical point of view, will be found in Lord Rayleigh's *Theory of Sound*, cc ix, xviii, with many important applications.

Numerical tables of the functions have been constructed by Bessel and Hansen, and more recently by Meissel (*Berl Abh* 1888). Hansen's tables are reproduced by Lommel, and (partially) by Lord Rayleigh and Byerly, whilst Meissel's tables have been reprinted by Gray and Mathews.

‡ The connection between spherical surface-harmonics and Bessel's Functions was noticed by Mehler, "Ueber die Vertheilung d statischen Elektrizitat in einem v zwei Kugelkalotten begrenzten

102. The formula (12) of Art 100 enables us to write down expressions, which are sometimes convenient, for the value of ϕ on one side of an infinite plane ($x = 0$) in terms of the values of ϕ or $\partial\phi/\partial n$ at points of this plane, in the case of symmetry about an axis (Ox) normal to the plane*. Thus if

$$\phi = F(\varpi), \text{ for } x = 0, \quad \dots \dots \dots (1)$$

we have, on the side $x > 0$

$$\phi = \int_0^\infty e^{-kx} J_0(k\varpi) k dk \int_0^\infty F(\varpi') J_0(k\varpi') \varpi' d\varpi'. \quad \dots (2)$$

Again, if
$$-\frac{\partial\phi}{\partial x} = f(\varpi), \text{ for } x = 0, \quad \dots \dots \dots (3)$$

we have
$$\phi = \int_0^\infty e^{-kx} J_0(k\varpi) dk \int_0^\infty f(\varpi') J_0(k\varpi') \varpi' d\varpi'. \quad \dots (4)$$

The exponentials have been chosen so as to vanish for $x = \infty$.

Another solution of these problems has already been given in Art 58, from equations (12) and (11) of which we derive

$$\phi = \frac{1}{2\pi} \iint \phi \frac{\partial}{\partial x} \left(\frac{1}{r} \right) dS, \quad \dots \dots (5)$$

and
$$\phi = -\frac{1}{2\pi} \iint \frac{\partial\phi}{\partial x} \frac{dS}{r}, \quad \dots \dots (6)$$

respectively, where r denotes distance from the element δS of the plane to the point at which the value of ϕ is required.

We proceed to a few applications of the general formulæ (2) and (4).

1° If, in (4), we assume $f(\varpi)$ to vanish for all but infinitesimal values of ϖ , and to become infinite for these in such a way that

$$\int_0^\infty f(\varpi) 2\pi\varpi d\varpi = \frac{1}{2},$$

we obtain

$$4\pi\phi = \int_0^\infty e^{-kx} J_0(k\varpi) dk, \quad \dots \dots (7)$$

Korper," *Crelle*, t lxxviii. (1868) It was investigated independently by Lord Rayleigh, "On the Relation between the Functions of Laplace and Bessel," *Proc Lond Math Soc*, t ix. p 61 (1878) [*Sc Papers*, t i. p 338], see also *Theory of Sound*, Arts 336, 338

There are also methods of deducing Bessel's Functions 'of the second kind' as limiting forms of the spherical harmonics $Q_n(\mu)$, $Q_n^*(\mu) \begin{Bmatrix} \cos \\ \sin \end{Bmatrix} s\omega$, for these see Heine, t. i pp. 184, 232

* The method may be extended so as to be free from this restriction

and therefore, since $J_0' = -J_1$,

$$4\pi\psi = -\varpi \int_0^\infty e^{-kx} J_1(k\varpi) dk, \quad \dots \dots \dots (8)$$

by Art 100 (5)

By comparison with the primitive expressions for a point-source at the origin (Art. 95), we infer that

$$\int_0^\infty e^{-kx} J_0(k\varpi) dk = \frac{1}{r}, \quad \int_0^\infty e^{-kx} J_1(k\varpi) dk = \frac{\varpi}{r(r+x)}, \quad \dots (9)$$

where $r = \sqrt{(x^2 + \varpi^2)}$, these are in fact known results*

2°. Let us next suppose that sources are distributed with uniform density over the plane area contained by the circle, $\varpi = a$, $x = 0$. Using the series for J_0 , J_1 , or otherwise, we find

$$\int_0^a J_0(k\varpi) \varpi d\varpi = \frac{a}{k} J_1(ka) \quad \dots \dots \dots (10)$$

Hence†

$$\phi = \frac{1}{\pi a} \int_0^\infty e^{-kx} J_0(k\varpi) J_1(ka) \frac{dk}{k}, \quad \psi = -\frac{\varpi}{\pi a} \int_0^\infty e^{-kx} J_1(k\varpi) J_1(ka) \frac{dk}{k}, \dots (11)$$

where the constant factor has been chosen so as to make the total flux through the circle equal to unity

3°. Again, if the density of the sources, within the same circle, vary as $1/\sqrt{(a^2 - \varpi^2)}$, we have to deal with the integral‡

$$\int_0^a J_0(k\varpi) \frac{\varpi d\varpi}{\sqrt{(a^2 - \varpi^2)}} = a \int_0^{\frac{1}{2}\pi} J_0(ka \sin \vartheta) \sin \vartheta d\vartheta = \frac{\sin ka}{k}, \quad (12)$$

where the evaluation is effected by substituting the series form of J_0 , and treating each term separately. Hence

$$\phi = \frac{1}{2\pi a} \int_0^\infty e^{-kx} J_0(k\varpi) \sin ka \frac{dk}{k}, \quad \psi = -\frac{\varpi}{2\pi a} \int_0^\infty e^{-kx} J_1(k\varpi) \sin ka \frac{dk}{k}, \dots (13)$$

if the constant factor be determined by the same condition as before §

It is a known theorem of Electrostatics that the assumed law of density makes ϕ constant over the circular area. It may be shewn independently

* The former is due to Lipschitz, *Crelle*, t lvi p 189 (1859), see Gray and Mathews, p 72. The latter follows by differentiation with respect to ϖ and integration with respect to x .

† Cf H Weber, *Crelle*, t lxxv p 88, Heine, t ii p 180.

‡ The formula (12) has been given by various writers, see Rayleigh, *Sc Papers*, t iii p 98, Hobson, *Proc Lond Math Soc*, t xxv p 71 (1893).

§ Cf H. Weber, *Crelle*, t lxxv (1873), Heine, t ii p 192.

that

$$\left. \begin{aligned} \int_0^\infty J_0(k\varpi) \sin ka \frac{dk}{k} &= \frac{1}{2}\pi, \text{ or } \sin^{-1} \frac{a}{\varpi}, \\ \int_0^\infty J_1(k\varpi) \sin ka \frac{dk}{k} &= \frac{a - \sqrt{(a^2 - \varpi^2)}}{\varpi}, \text{ or } \frac{a}{\varpi}, \end{aligned} \right\} \quad \dots \quad (14)$$

according as $\varpi \leq a^*$. The formulae (13) therefore express the flow of a liquid through a circular aperture in a thin plane rigid wall. Another solution will be obtained in Art 108. The corresponding problem in two dimensions was solved in Art 66, 1°

4° Let us next suppose that when $x=0$, we have $\phi = C \sqrt{(a^2 - \varpi^2)}$ for $\varpi < a$, and $\phi = 0$ for $\varpi > a$. We find

$$\int_0^a J_0(k\varpi) \sqrt{(a^2 - \varpi^2)} \varpi d\varpi = a^3 \int_0^{\frac{1}{2}\pi} J_0(ka \sin \vartheta) \sin \vartheta \cos^2 \vartheta d\vartheta = a^3 \psi_1(ka), \quad \dots \quad (15)$$

provided $\psi_1(\xi) = \frac{1}{3} \left(1 - \frac{\xi^2}{2 \cdot 5} + \frac{\xi^4}{2 \cdot 4 \cdot 5 \cdot 7} - \dots \right) = -\frac{d}{\xi d\xi} \frac{\sin \xi}{\xi} \quad \dots \quad (16)$

Hence, by (2), $\phi = -C \int_0^\infty e^{-kx} J_0(k\varpi) \frac{d}{dk} \left(\frac{\sin ka}{k} \right) dk \quad \dots \quad (17)$

This gives, for $x=0$,

$$-\left(\frac{\partial \phi}{\partial x}\right)_0 = C \int_0^\infty J_0(k\varpi) \sin ka \frac{dk}{k} + C\varpi \int_0^\infty J_0'(k\varpi) \sin ka dk, \quad (18)$$

after a partial integration. The value of the former integral is given in (14), and that of the latter can be deduced from it by differentiation with respect to ϖ . Hence

$$-\left(\frac{\partial \phi}{\partial x}\right)_0 = \frac{1}{2}\pi C, \text{ or } C \left(\sin^{-1} \frac{a}{\varpi} - \frac{a}{\sqrt{(a^2 - \varpi^2)}} \right), \quad \dots \quad (19)$$

according as $\varpi \leq a$. It follows that if $C = 2/\pi \cdot U$, the formula (17) will relate to the motion of a thin circular disk with velocity U normal to its plane, in an infinite mass of liquid. The expression for the kinetic energy is

$$2T = -\rho \iint \phi \frac{\partial \phi}{\partial n} dS = \pi \rho C^2 \int_0^a \sqrt{(a^2 - \varpi^2)} 2\pi \varpi d\varpi = \frac{2}{3} \pi^2 \rho a^3 C^2,$$

or $2T = \frac{8}{3} \rho a^3 U^2 \quad \dots \quad (20)$

The effective addition to the inertia of the disk is therefore $2/\pi (= \cdot 6366)$ times the mass of a spherical portion of the fluid, of the same radius. For another investigation of this question, see Art 108.

* H. Weber, *Crelle*, t. lxxv, Part D[iv]-GL., t. 1. p 189, Gray and Mathews, p 126. See also *Proc. Lond. Math. Soc.*, t xxxiv p. 282.

Ellipsoidal Harmonics

103 The method of Spherical Harmonics can also be adapted to the solution of the equation

$$\nabla^2 \phi = 0, \quad (1)$$

under boundary-conditions having relation to ellipsoids of revolution*.

Beginning with the case where the ellipsoids are *prolate*, we write

$$\begin{aligned} x &= k \cos \theta \cosh \eta = k \mu \zeta, & y &= \varpi \cos \omega, & z &= \varpi \sin \omega, \\ \text{where} \quad \varpi &= k \sin \theta \sinh \eta = k (1 - \mu^2)^{\frac{1}{2}} (\zeta^2 - 1)^{\frac{1}{2}} \end{aligned} \quad (2)$$

The surfaces $\zeta = \text{const.}$, $\mu = \text{const.}$, are confocal ellipsoids, and hyperboloids of two sheets, respectively, the common foci being the points $(\pm k, 0, 0)$. The value of ζ may range from 1 to ∞ , whilst μ lies between ± 1 . The coordinates μ, ζ, ω form an orthogonal system, and the values of the linear elements $\delta s_\mu, \delta s_\zeta, \delta s_\omega$ described by the point (x, y, z) when μ, ζ, ω separately vary, are

$$\delta s_\mu = k \left(\frac{\zeta^2 - \mu^2}{1 - \mu^2} \right)^{\frac{1}{2}} \delta \mu, \quad \delta s_\zeta = k \left(\frac{\zeta^2 - \mu^2}{\zeta^2 - 1} \right)^{\frac{1}{2}} \delta \zeta, \quad \delta s_\omega = k (1 - \mu^2)^{\frac{1}{2}} (\zeta^2 - 1)^{\frac{1}{2}} \delta \omega. \quad (3)$$

To express (1) in terms of our new variables we equate to zero the total flux across the walls of a volume element $\delta s_\mu \delta s_\zeta \delta s_\omega$, and obtain

$$\frac{\partial}{\partial \mu} \left(\frac{\partial \phi}{\partial s_\mu} \delta s_\zeta \delta s_\omega \right) \delta \mu + \frac{\partial}{\partial \zeta} \left(\frac{\partial \phi}{\partial s_\zeta} \delta s_\mu \delta s_\omega \right) \delta \zeta + \frac{\partial}{\partial \omega} \left(\frac{\partial \phi}{\partial s_\omega} \delta s_\mu \delta s_\zeta \right) \delta \omega = 0,$$

or, on substitution from (3),

$$\frac{\partial}{\partial \mu} \left\{ (1 - \mu^2) \frac{\partial \phi}{\partial \mu} \right\} + \frac{\partial}{\partial \zeta} \left\{ (\zeta^2 - 1) \frac{\partial \phi}{\partial \zeta} \right\} + \frac{\zeta^2 - \mu^2}{(1 - \mu^2)(\zeta^2 - 1)} \frac{\partial^2 \phi}{\partial \omega^2} = 0$$

This may also be written

$$\frac{\partial}{\partial \mu} \left\{ (1 - \mu^2) \frac{\partial \phi}{\partial \mu} \right\} + \frac{1}{1 - \mu^2} \frac{\partial^2 \phi}{\partial \omega^2} = \frac{\partial}{\partial \zeta} \left\{ (1 - \zeta^2) \frac{\partial \phi}{\partial \zeta} \right\} + \frac{1}{1 - \zeta^2} \frac{\partial^2 \phi}{\partial \omega^2} \quad (4)$$

104 If ϕ be a finite function of μ and ω , from $\mu = -1$ to $\mu = +1$ and from $\omega = 0$ to $\omega = 2\pi$, it may be expanded in a series of surface harmonics of integral orders, of the types given by Art. 86 (7), where the coefficients are functions of ζ ; and it appears on substitution in (4) that each term of the expansion must satisfy the equation separately. Taking first the case of the zonal harmonic, we write

$$\phi = P_n(\mu) Z, \quad \dots \dots \dots (5)$$

* Heine, "Ueber einige Aufgaben, welche auf partielle Differentialgleichungen fuhren," *Crelle*, t xxvi. p 185 (1843), and *Kugelfunktionen*, t ii. Art. 38 See also FERRERS, c vi

and on substitution we find, in virtue of Art. 84 (1),

$$\frac{d}{d\xi} \left\{ (1 - \xi^2) \frac{dZ}{d\xi} \right\} + n(n+1)Z = 0, \quad \dots \quad (6)$$

which is of the same form as the equation referred to. We thus obtain the solutions

$$\phi = P_n(\mu) P_n(\xi), \quad \dots \quad (7)$$

and

$$\phi = P_n(\mu) Q_n(\xi), \quad \dots \quad (8)$$

where $Q_n(\xi) = P_n(\xi) \int_{\xi}^{\infty} \frac{d\xi}{\{P_n(\xi)\}^2 (\xi^2 - 1)},$

$$\begin{aligned} &= \frac{1}{2} P_n(\xi) \log \frac{\xi+1}{\xi-1} - \frac{2n-1}{1 \cdot n} P_{n-1}(\xi) - \frac{2n-5}{3(n-1)} P_{n-3}(\xi) - \dots \\ &= \frac{1}{3} \dots \frac{n!}{(2n+1)} \left\{ \xi^{-n-1} + \frac{(n+1)(n+2)}{2(2n+3)} \xi^{-n-3} \right. \\ &\quad \left. + \frac{(n+1)(n+2)(n+3)(n+4)}{2 \cdot 4 (2n+3)(2n+5)} \xi^{-n-5} + \dots \right\}. \quad (9)^* \end{aligned}$$

The solution (7) is finite when $\xi = 1$, and is therefore adapted to the space *within* an ellipsoid of revolution, whilst (8) is infinite for $\xi = 1$, but vanishes for $\xi = \infty$, and is therefore appropriate to the external region. As particular cases of the formula (9) we note

$$\begin{aligned} Q_0(\xi) &= \frac{1}{2} \log \frac{\xi+1}{\xi-1}, & Q_1(\xi) &= \frac{1}{2} \xi \log \frac{\xi+1}{\xi-1} - 1, \\ Q_2(\xi) &= \frac{1}{4} (3\xi^2 - 1) \log \frac{\xi+1}{\xi-1} - \frac{3}{2} \xi \end{aligned}$$

The definite-integral form of Q_n shews that

$$P_n(\xi) \frac{dQ_n(\xi)}{d\xi} - \frac{dP_n(\xi)}{d\xi} Q_n(\xi) = -\frac{1}{\xi^2 - 1}. \quad \dots \quad (10)$$

The corresponding expressions for the stream-function are readily found, thus, from the definition of Art. 94,

$$\frac{\partial \phi}{\partial s_{\xi}} = -\frac{1}{\omega} \frac{\partial \psi}{\partial s_{\mu}}, \quad \frac{\partial \phi}{\partial s_{\mu}} = \frac{1}{\omega} \frac{\partial \psi}{\partial s_{\xi}}, \quad \dots \quad (11)$$

whence $\frac{\partial \psi}{\partial \mu} = -k(\xi^2 - 1) \frac{\partial \phi}{\partial \xi}, \quad \frac{\partial \psi}{\partial \xi} = k(1 - \mu^2) \frac{\partial \phi}{\partial \mu} \quad \dots \quad (12)$

Thus, in the case of (7), we have

$$\begin{aligned} \frac{\partial \psi}{\partial \mu} &= -k(\xi^2 - 1) \frac{dP_n(\xi)}{d\xi} \cdot P_n(\mu) \\ &= \frac{k}{n(n+1)} (\xi^2 - 1) \frac{dP_n(\xi)}{d\xi} \frac{d}{d\mu} \left\{ (1 - \mu^2) \frac{dP_n(\mu)}{d\mu} \right\}, \end{aligned}$$

* FEYERER, c. v ; TODDhunter, c. vi , FORSYTH, Arts. 96-99.

whence
$$\psi = \frac{k}{n(n+1)} (1 - \mu^2) \frac{dP_n(\mu)}{d\mu} (\zeta^2 - 1) \frac{dP_n(\zeta)}{d\zeta} \dots (13)$$

The same result will follow of course from the second of equations (12)

In the same way, the stream-function corresponding to (8) is

$$\psi = \frac{k}{n(n+1)} (1 - \mu^2) \frac{dP_n(\mu)}{d\mu} (\zeta^2 - 1) \frac{dQ_n(\zeta)}{d\zeta} \dots (14)$$

105 We can apply this to the case of an ovary ellipsoid moving parallel to its axis in an infinite mass of liquid. The elliptic co-ordinates must be chosen so that the ellipsoid in question is a member of the confocal family, say that for which $\zeta = \zeta_0$. Comparing with Art 103 (2) we see that if a, c be the polar and equatorial radii, and e the eccentricity of the meridian section, we must have

$$k = ae, \quad \zeta_0 = 1/e, \quad k(\zeta_0^2 - 1)^{\frac{1}{2}} = c$$

The surface condition is given by Art 97 (1), viz we must have

$$\psi = -\frac{1}{2} U k^2 (1 - \mu^2) (\zeta^2 - 1) + \text{const}, \dots (1)$$

for $\zeta = \zeta_0$. Hence putting $n = 1$ in Art 104 (14), and introducing an arbitrary multiplier A , we have

$$\psi = \frac{1}{2} A k (1 - \mu^2) (\zeta^2 - 1) \left\{ \frac{1}{2} \log \frac{\zeta + 1}{\zeta - 1} - \frac{\zeta}{\zeta^2 - 1} \right\}, \dots (2)$$

with the condition

$$A = U k - \left\{ \frac{\zeta_0}{\zeta_0^2 - 1} - \frac{1}{2} \log \frac{\zeta_0 + 1}{\zeta_0 - 1} \right\} = U a - \left\{ \frac{1}{1 - e^2} - \frac{1}{2e} \log \frac{1 + e}{1 - e} \right\} \dots (3)$$

The corresponding formula for the velocity-potential is

$$\phi = A \mu \left\{ \frac{1}{2} \zeta \log \frac{\zeta + 1}{\zeta - 1} - 1 \right\} \dots (4)$$

The kinetic energy, and thence the inertia-coefficient due to the fluid, may be readily calculated, if required, by the formula (5) of Art 94.

106 Leaving the case of symmetry, the solutions of $\nabla^2 \phi = 0$ when ϕ is a tesseral or sectorial harmonic in μ and ω are found by a similar method to be of the types

$$\phi = P_n^s(\mu) \cdot P_n^s(\zeta) \frac{\cos}{\sin} \left\{ s\omega, \dots \dots \dots (1) \right.$$

$$\phi = P_n^s(\mu) \cdot Q_n^s(\zeta) \frac{\cos}{\sin} \left\{ s\omega, \dots \dots \dots (2) \right.$$

where, as in Art 86, $P_n^s(\mu) = (1 - \mu^2)^{\frac{1}{2}s} \frac{d^s P_n(\mu)}{d\mu^s}, \dots \dots \dots (3)$

whilst (to avoid imaginaries) we write

$$P_n^s(\xi) = (\xi^2 - 1)^{\frac{1}{2}s} \frac{d^s P_n(\xi)}{d\xi^s}, \quad \dots \dots \dots (4)$$

and

$$Q_n^s(\xi) = (\xi^2 - 1)^{\frac{1}{2}s} \frac{d^s Q_n(\xi)}{d\xi^s} \dots \dots \dots (5)$$

It may be shewn that

$$Q_n^s(\xi) = (-)^s \frac{(n+s)!}{(n-s)!} P_n^s(\xi) \int_{\xi}^{\infty} \frac{d\xi}{\{P_n^s(\xi)\}^2 (\xi^2 - 1)}, \quad \dots \dots (6)$$

$$\text{whence } P_n^s(\xi) \frac{dQ_n^s(\xi)}{d\xi} - \frac{dP_n^s(\xi)}{d\xi} Q_n^s(\xi) = (-)^{s+1} \frac{(n+s)!}{(n-s)!} \frac{1}{\xi^2 - 1} \dots \dots (7)$$

As examples we may take the case of an ovary ellipsoid moving parallel to an *equatorial* axis, say that of y , or rotating about this axis

1°. In the former case, the surface-condition is

$$\frac{\partial \phi}{\partial \xi} = -V \frac{\partial y}{\partial \xi},$$

for $\xi = \xi_0$, where V is the velocity of translation, or

$$\frac{\partial \phi}{\partial \xi} = -V \frac{k\xi_0}{(\xi_0^2 - 1)^{\frac{1}{2}}} (1 - \mu^2)^{\frac{1}{2}} \cos \omega \dots \dots \dots (8)$$

This is satisfied by putting $n = 1$, $s = 1$, in (2), viz

$$\phi = A (1 - \mu^2)^{\frac{1}{2}} (\xi^2 - 1)^{\frac{1}{2}} \cdot \left\{ \frac{1}{2} \log \frac{\xi + 1}{\xi - 1} - \frac{\xi}{\xi^2 - 1} \right\} \cos \omega, \quad \dots \dots (9)$$

the constant A being given by

$$A \left\{ \frac{1}{2} \log \frac{\xi_0 + 1}{\xi_0 - 1} - \frac{\xi_0^2 - 2}{\xi_0(\xi_0^2 - 1)} \right\} = -kV \dots \dots \dots (10)$$

2°. In the case of rotation about Oy , if Ω_y be the angular velocity, we must have

$$\frac{\partial \phi}{\partial \xi} = -\Omega_y \left(z \frac{\partial x}{\partial \xi} - x \frac{\partial z}{\partial \xi} \right),$$

$$\text{for } \xi = \xi_0 \text{ or } \frac{\partial \phi}{\partial \xi} = k^2 \Omega_y \cdot \frac{1}{(\xi_0^2 - 1)^{\frac{1}{2}}} \mu (1 - \mu^2)^{\frac{1}{2}} \sin \omega \dots \dots \dots (11)$$

Putting $n = 2$, $s = 1$, in the formula (2) we find

$$\phi = A\mu (1 - \mu^2)^{\frac{1}{2}} (\xi^2 - 1)^{\frac{1}{2}} \left\{ \frac{3}{2} \xi \log \frac{\xi + 1}{\xi - 1} - 3 - \frac{1}{\xi^2 - 1} \right\} \sin \omega, \dots (12)$$

A being determined by comparison with (11).

107 When the ellipsoid is of the *oblate* or 'planetary' form, the appropriate co-ordinates are given by

$$\left. \begin{aligned} x &= k \cos \theta \sinh \eta = k \mu \zeta, & y &= \varpi \cos \omega, & z &= \varpi \sin \omega, \\ \text{where} & & \varpi &= k \sin \theta \cosh \eta = k (1 - \mu^2)^{\frac{1}{2}} (\zeta^2 + 1)^{\frac{1}{2}}. \end{aligned} \right\} \dots (1)$$

Here ζ may range from 0 to ∞ (or, in some applications from $-\infty$ through 0 to $+\infty$), whilst μ lies between ± 1 . The quadrics $\zeta = \text{const}$, $\mu = \text{const}$ are planetary ellipsoids, and hyperboloids of revolution of one sheet, all having the common focal circle $x = 0$, $\varpi = k$. As limiting forms we have the ellipsoid $\zeta = 0$, which coincides with the portion of the plane $x = 0$ for which $\varpi < k$, and the hyperboloid $\mu = 0$ coinciding with the remaining portion of this plane

With the same notation as before we find

$$\delta s_\mu = k \left(\frac{\zeta^2 + \mu^2}{1 - \mu^2} \right)^{\frac{1}{2}} \delta \mu, \quad \delta s_\zeta = k \left(\frac{\zeta^2 + \mu^2}{\zeta^2 + 1} \right)^{\frac{1}{2}} \delta \zeta, \quad \delta s_\omega = k (1 - \mu^2)^{\frac{1}{2}} (\zeta^2 + 1)^{\frac{1}{2}} \delta \omega; \dots (2)$$

and the equation of continuity becomes

$$\frac{\partial}{\partial \mu} \left\{ (1 - \mu^2) \frac{\partial \phi}{\partial \mu} \right\} + \frac{\partial}{\partial \zeta} \left\{ (\zeta^2 + 1) \frac{\partial \phi}{\partial \zeta} \right\} + \frac{\zeta^2 + \mu^2}{(1 - \mu^2)(\zeta^2 + 1)} \frac{\partial^2 \phi}{\partial \omega^2} = 0,$$

or

$$\frac{\partial}{\partial \mu} \left\{ (1 - \mu^2) \frac{\partial \phi}{\partial \mu} \right\} + \frac{1}{1 - \mu^2} \frac{\partial^2 \phi}{\partial \omega^2} = - \frac{\partial}{\partial \zeta} \left\{ (\zeta^2 + 1) \frac{\partial \phi}{\partial \zeta} \right\} + \frac{1}{\zeta^2 + 1} \frac{\partial^2 \phi}{\partial \omega^2} \dots (3)$$

This is of the same form as Art 103 (4), with $v\zeta$ in place of ζ , and the like correspondence will run through the subsequent formulae

In the case of symmetry about the axis we have the solutions

$$\phi = P_n(\mu) \cdot p_n(\zeta), \dots (4)$$

and

$$\phi = P_n(\mu) \cdot q_n(\zeta), \dots (5)$$

where

$$p_n(\zeta) = \frac{1 \cdot 3 \cdot 5 \dots (2n-1)}{n!} \left\{ \zeta^n + \frac{n(n-1)}{2(2n-1)} \zeta^{n-2} + \frac{n(n-1)(n-2)(n-3)}{2 \cdot 4(2n-1)(2n-3)} \zeta^{n-4} + \dots \right\}, \dots (6)$$

and

$$\begin{aligned} q_n(\zeta) &= p_n(\zeta) \int_{\zeta}^{\infty} \frac{d\zeta}{\{p_n(\zeta)\}^2 (\zeta^2 + 1)}, \\ &= (-)^n \left\{ p_n(\zeta) \cot^{-1} \zeta - \frac{2n-1}{1 \cdot n} p_{n-1}(\zeta) + \frac{2n-5}{3(n-1)} p_{n-3}(\zeta) - \dots \right\}, \\ &= \frac{n!}{1 \cdot 3 \cdot 5 \dots (2n+1)} \left\{ \zeta^{-n-1} - \frac{(n+1)(n+2)}{2(2n+3)} \zeta^{-n-3} \right. \\ &\quad \left. + \frac{(n+1)(n+2)(n+3)(n+4)}{2 \cdot 4(2n+3)(2n+5)} \zeta^{-n-5} - \dots \right\}, \dots (7) \end{aligned}$$

the latter expansion being however convergent only when $\zeta > 1^*$. As before, the solution (4) is appropriate to the region included within an ellipsoid of the family $\zeta = \text{const}$, and (5) to the external space.

We note that
$$p_n(\zeta) \frac{dq_n(\zeta)}{d\zeta} - \frac{dp_n(\zeta)}{d\zeta} q_n(\zeta) = -\frac{1}{\zeta^2 + 1} \quad \dots \quad (8)$$

As particular cases of the formula (7) we have

$$q_0(\zeta) = \cot^{-1} \zeta, \quad q_1(\zeta) = 1 - \zeta \cot^{-1} \zeta, \\ q_2(\zeta) = \frac{1}{2} (3\zeta^2 + 1) \cot^{-1} \zeta - \frac{3}{2} \zeta.$$

The formulae for the stream-function corresponding to (4) and (5) are

$$\psi = \frac{k}{n(n+1)} (1 - \mu^2) \frac{dP_n(\mu)}{d\mu} (\zeta^2 + 1) \frac{dp_n(\zeta)}{d\zeta}, \quad \dots \quad (9)$$

and
$$\psi = \frac{k}{n(n+1)} (1 - \mu^2) \frac{dP_n(\mu)}{d\mu} (\zeta^2 + 1) \frac{dq_n(\zeta)}{d\zeta} \quad \dots \quad (10)$$

108 1° The simplest case of Art 107 (5) is when $n = 0$, viz.

$$\phi = A \cot^{-1} \zeta, \quad \dots \quad (1)$$

where ζ is supposed to range from $-\infty$ to $+\infty$. The formula (10) of the last Art then assumes an indeterminate form, but we find by the method of Art 104,

$$\psi = Ak\mu \quad \dots \quad (2)$$

This solution represents the flow of a liquid through a circular aperture in an infinite plane wall, viz the aperture is the portion of the plane yz for which $\varpi < k$. The velocity at any point of the aperture ($\zeta = 0$) is

$$u = -\frac{1}{\varpi} \frac{\partial \psi}{\partial \varpi} = \frac{A}{(k^2 - \varpi^2)^{\frac{1}{2}}},$$

since, when $x = 0$, $k\mu = (k^2 - \varpi^2)^{\frac{1}{2}}$. The velocity is therefore infinite at the edge. Compare Art 102, 3°.

2° Again, the motion due to a planetary ellipsoid ($\zeta = \zeta_0$) moving with velocity U parallel to its axis in an infinite mass of liquid is given by

$$\phi = A\mu (1 - \zeta \cot^{-1} \zeta), \quad \psi = \frac{1}{2} Ak (1 - \mu^2) (\zeta^2 + 1) \left\{ \frac{\zeta}{\zeta_0^2 + 1} - \cot^{-1} \zeta \right\}, \dots (3)$$

where
$$A = -kU - \left\{ \frac{\zeta}{\zeta_0^2 + 1} - \cot^{-1} \zeta_0 \right\}.$$

Denoting the polar and equatorial radii by a and c , and the eccentricity of the meridian section by e , we have


$$a = k\zeta_0, \quad c = k(\zeta_0^2 + 1)^{\frac{1}{2}}, \quad e = (\zeta_0^2 + 1)^{-\frac{1}{2}}.$$

* The reader may easily adapt the demonstrations referred to in Art. 104 to the present case

In terms of these quantities

$$A = -Uc - \left\{ (1 - e^2)^{\frac{1}{2}} - \frac{1}{e} \sin^{-1} e \right\} \quad \dots \quad (4)$$

The forms of the lines of motion, for equidistant values of ψ , are shewn below Cf Art 71, 3°



The most interesting case is that of the circular disk, for which $e = 1$, and $A = 2Uc/\pi$. The value of ϕ given in (3) becomes equal to $\pm A\mu$, or $\pm A(1 - \varpi^2/c^2)^{\frac{1}{2}}$, for the two sides of the disk, and the normal velocity to $\pm U$. Hence the formula (4) of Art 44 gives

$$2T = \frac{2}{3}\rho c^3 U^2, \quad \dots \dots \dots (5)$$

as in Art. 102 (20).

109 The solutions of the equation Art. 107 (3) in tesseral harmonics are

$$\phi = P_n^s(\mu) p_n^s(\zeta) \frac{\cos}{\sin} \omega, \quad . \quad . \quad . \quad (1)$$

and
$$\phi = P_n^s(\mu) q_n^s(\zeta) \frac{\cos}{\sin} \omega, \quad . \quad . \quad . \quad . \quad (2)$$

where
$$p_n^s(\zeta) = (\zeta^2 + 1)^{\frac{1}{2}s} \frac{d^s p_n(\zeta)}{d\zeta^s}, \quad . \quad . \quad . \quad (3)$$

and
$$q_n^s(\zeta) = (\zeta^2 + 1)^{\frac{1}{2}s} \frac{d^s q_n(\zeta)}{d\zeta^s},$$

$$= (-)^s \frac{(n+s)!}{(n-s)!} p_n^s(\zeta) \int_{\zeta}^{\infty} \frac{d\zeta}{[p_n^s(\zeta)]^2 (\zeta^2 + 1)}. \quad . \quad . \quad . \quad (4)$$

These functions possess the property

$$p_n^s(\zeta) \frac{dq_n^s(\zeta)}{d\zeta} - \frac{dp_n^s(\zeta)}{d\zeta} q_n^s(\zeta) = (-)^{s+1} \frac{(n+s)!}{(n-s)!} \frac{1}{\zeta^2 + 1}. \quad (5)$$

We may apply these results as in Art 108

1° For the motion of a planetary ellipsoid ($\zeta = \zeta_0$) parallel to the axis of y we have $n=1$, $s=1$, and thence

$$\phi = A (1 - \mu^2)^{\frac{1}{2}} (\zeta^2 + 1)^{\frac{1}{2}} \left\{ \frac{\zeta}{\zeta^2 + 1} - \cot^{-1} \zeta \right\} \cos \omega, \quad (6)$$

with the condition
$$\frac{\partial \phi}{\partial \zeta} = -V \frac{\partial y}{\partial \zeta},$$

for $\zeta = \zeta_0$, V denoting the velocity of the solid. This gives

$$A \left\{ \frac{\zeta_0^2 + 2}{\zeta_0(\zeta_0^2 + 1)} - \cot^{-1} \zeta_0 \right\} = -kV. \quad . \quad . \quad . \quad (7)$$

In the case of the disk ($\zeta_0 = 0$), we have $A = 0$, as we should expect

2° Again, for a planetary ellipsoid rotating about the axis of y with angular velocity Ω_y , we have, putting $n=2$, $s=1$,

$$\phi = A\mu (1 - \mu^2)^{\frac{1}{2}} (\zeta^2 + 1)^{\frac{1}{2}} \left\{ 3\zeta \cot^{-1} \zeta - 3 + \frac{1}{\zeta^2 + 1} \right\} \sin \omega, \quad . \quad . \quad . \quad (8)$$

with the surface condition

$$\frac{\partial \phi}{\partial \zeta} = -\Omega_y \left(z \frac{\partial x}{\partial \zeta} - x \frac{\partial z}{\partial \zeta} \right)$$

$$= -\frac{k^2 \Omega_y}{(\zeta_0^2 + 1)^{\frac{1}{2}}} \mu (1 - \mu^2)^{\frac{1}{2}} \sin \omega \quad . \quad . \quad . \quad . \quad . \quad . \quad (9)$$

For the circular disk ($\zeta_0 = 0$) this gives

$$\frac{3}{2}\pi A = -k^2\Omega_y. \dots \dots \dots (10)$$

At the two surfaces of the disk we have

$$\phi = \mp 2A\mu(1 - \mu^2)^{\frac{1}{2}} \sin \omega, \quad \frac{\partial \phi}{\partial n} = \mp k\Omega_y(1 - \mu^2)^{\frac{1}{2}} \sin \omega,$$

and substituting in the formula

$$2T = -\rho \iint \phi \frac{\partial \phi}{\partial n} \varpi d\varpi d\omega,$$

we obtain

$$2T = \frac{1}{4} \rho c^5 \cdot \Omega_y^2 \dots \dots \dots (11)$$

110 In questions relating to ellipsoids with three unequal axes we may employ the more general type of Ellipsoidal Harmonics, usually known by the name of 'Lamé's Functions*'. Without attempting a formal account of these functions, we will investigate some solutions of the equation

$$\nabla^2 \phi = 0, \dots \dots \dots (1)$$

in ellipsoidal co-ordinates, which are analogous to spherical harmonics of the first and second orders, with a view to their hydrodynamical applications.

It is convenient to prefix an investigation of the motion of a liquid contained in an ellipsoidal envelope, which can be treated at once by Cartesian methods

Thus, when the envelope is in motion parallel to the axis of x with velocity U , the enclosed fluid moves as a solid, and the velocity-potential is simply $\phi = -Ux$

Next let us suppose that the envelope is rotating about a principal axis (say that of x) with angular velocity Ω_x . The equation of the surface being

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} + \frac{z^2}{c^2} = 1, \quad \dots \dots \dots (2)$$

the surface condition is

$$-\frac{x}{a^2} \frac{\partial \phi}{\partial x} - \frac{y}{b^2} \frac{\partial \phi}{\partial y} - \frac{z}{c^2} \frac{\partial \phi}{\partial z} = -\frac{y}{b^2} \Omega_x z + \frac{z}{c^2} \Omega_x y$$

We therefore assume $\phi = Ayz$, which is evidently a solution of (1), and obtain, on determining the constant by the condition just written,

$$\phi = -\frac{b^2 - c^2}{b^2 + c^2} \Omega_x \cdot yz.$$

Hence, if the centre be moving with a velocity whose components are

* See, for example, Ferrers, *Spherical Harmonics*, c vi, W D Niven, "On Ellipsoidal Harmonics," *Phil. Trans*, A. t cxxxii (1891); Poincaré, *Figures d'Équilibre d'une Masse Fluide*, Paris, 1902, c vi. An outline of the theory is given by Wangerin, *loc. ante*, p 102

U, V, W and if $\Omega_x, \Omega_y, \Omega_z$ be the angular velocities about the principal axes, we have by superposition *

$$\phi = -Ux - Vy - Wz - \frac{b^2 - c^2}{b^2 + c^2} \Omega_x yz - \frac{c^2 - a^2}{c^2 + a^2} \Omega_y zx - \frac{a^2 - b^2}{a^2 + b^2} \Omega_z xy. \quad (3)$$

We may also include the case where the envelope is changing its form as well as position, but so as to remain ellipsoidal. If the axes are changing at the rates a, b, c , respectively, the general boundary condition, Art 10 (3), becomes

$$\frac{x^2}{a^3} a + \frac{y^2}{b^3} b + \frac{z^2}{c^3} c + \frac{x}{a^2} \frac{\partial \phi}{\partial x} + \frac{y}{b^2} \frac{\partial \phi}{\partial y} + \frac{z}{c^2} \frac{\partial \phi}{\partial z} = 0, \quad \dots \quad (4)$$

which is satisfied † by
$$\phi = -\frac{1}{2} \left(\frac{a}{\alpha} x^2 + \frac{b}{\beta} y^2 + \frac{c}{\gamma} z^2 \right). \quad \dots \quad (5)$$

The equation (1) requires that

$$\frac{a}{\alpha} + \frac{b}{\beta} + \frac{c}{\gamma} = 0, \quad \dots \dots \dots (6)$$

which is in fact the condition which must be satisfied by the changing ellipsoidal surface in order that the enclosed volume ($\frac{4}{3}\pi abc$) may be constant.

111 The solutions of the corresponding problems for an infinite mass of fluid bounded *internally* by an ellipsoid involve the use of a special system of orthogonal curvilinear co-ordinates

If x, y, z be functions of three parameters λ, μ, ν , such that the surfaces

$$\lambda = \text{const}, \quad \mu = \text{const}, \quad \nu = \text{const}. \quad \dots \dots \dots (1)$$

are mutually orthogonal at their intersections, and if we write

$$\left. \begin{aligned} \frac{1}{h_1^2} &= \left(\frac{\partial x}{\partial \lambda} \right)^2 + \left(\frac{\partial y}{\partial \lambda} \right)^2 + \left(\frac{\partial z}{\partial \lambda} \right)^2, \\ \frac{1}{h_2^2} &= \left(\frac{\partial x}{\partial \mu} \right)^2 + \left(\frac{\partial y}{\partial \mu} \right)^2 + \left(\frac{\partial z}{\partial \mu} \right)^2, \\ \frac{1}{h_3^2} &= \left(\frac{\partial x}{\partial \nu} \right)^2 + \left(\frac{\partial y}{\partial \nu} \right)^2 + \left(\frac{\partial z}{\partial \nu} \right)^2, \end{aligned} \right\} \quad \dots \quad (2)$$

* This result appears to have been published independently by Beltrami, Bjerknes, and Maxwell, in 1873 See Hicks, "Report on Recent Progress in Hydrodynamics," *Brit Ass. Rep.*, 1882

† Bjerknes, "Verallgemeinerung des Problems von den Bewegungen, welche in einer ruhenden unelastischen Flüssigkeit die Bewegung eines Ellipsoids hervorbringt," *Göttinger Nachrichten*, 1873

the direction-cosines of the normals to the three surfaces which pass through (x, y, z) will be

$$\left(h_1 \frac{\partial x}{\partial \lambda}, h_1 \frac{\partial y}{\partial \lambda}, h_1 \frac{\partial z}{\partial \lambda}\right), \left(h_2 \frac{\partial x}{\partial \mu}, h_2 \frac{\partial y}{\partial \mu}, h_2 \frac{\partial z}{\partial \mu}\right), \left(h_3 \frac{\partial x}{\partial \nu}, h_3 \frac{\partial y}{\partial \nu}, h_3 \frac{\partial z}{\partial \nu}\right), \quad (3)$$

respectively. It follows that the lengths of linear elements drawn in the directions of these normals will be

$$\delta\lambda/h_1, \quad \delta\mu/h_2, \quad \delta\nu/h_3.$$

Hence if ϕ be the velocity-potential of any fluid motion, the total flux into the rectangular space included between the six surfaces $\lambda \pm \frac{1}{2}\delta\lambda$, $\mu \pm \frac{1}{2}\delta\mu$, $\nu \pm \frac{1}{2}\delta\nu$ will be

$$\frac{\partial}{\partial \lambda} \left(h_1 \frac{\partial \phi}{\partial \lambda} \cdot \frac{\delta\mu}{h_2} \frac{\delta\nu}{h_3} \right) \delta\lambda + \frac{\partial}{\partial \mu} \left(h_2 \frac{\partial \phi}{\partial \mu} \cdot \frac{\delta\nu}{h_3} \frac{\delta\lambda}{h_1} \right) \delta\mu + \frac{\partial}{\partial \nu} \left(h_3 \frac{\partial \phi}{\partial \nu} \cdot \frac{\delta\lambda}{h_1} \cdot \frac{\delta\mu}{h_2} \right) \delta\nu$$

It appears from Art 42 (3) that the same flux is expressed by $\nabla^2\phi$ multiplied by the volume of the space, *i.e.* by $\delta\lambda\delta\mu\delta\nu/h_1h_2h_3$. Hence*

$$\nabla^2\phi = h_1h_2h_3 \left\{ \frac{\partial}{\partial \lambda} \left(\frac{h_1}{h_2h_3} \frac{\partial \phi}{\partial \lambda} \right) + \frac{\partial}{\partial \mu} \left(\frac{h_2}{h_3h_1} \frac{\partial \phi}{\partial \mu} \right) + \frac{\partial}{\partial \nu} \left(\frac{h_3}{h_1h_2} \frac{\partial \phi}{\partial \nu} \right) \right\} \quad (4)$$

Equating this to zero, we obtain the general equation of continuity in orthogonal co-ordinates, of which particular cases have already been investigated in Arts 83, 103, 108

The theory of triple orthogonal systems of surfaces is very attractive mathematically, and abounds in interesting and elegant formulae. We may note that if λ, μ, ν be regarded as functions of x, y, z , the direction-cosines of the three line-elements above considered can also be expressed in the forms

$$\left(\frac{1}{h_1} \frac{\partial \lambda}{\partial x}, \frac{1}{h_1} \frac{\partial \lambda}{\partial y}, \frac{1}{h_1} \frac{\partial \lambda}{\partial z}\right), \left(\frac{1}{h_2} \frac{\partial \mu}{\partial x}, \frac{1}{h_2} \frac{\partial \mu}{\partial y}, \frac{1}{h_2} \frac{\partial \mu}{\partial z}\right), \left(\frac{1}{h_3} \frac{\partial \nu}{\partial x}, \frac{1}{h_3} \frac{\partial \nu}{\partial y}, \frac{1}{h_3} \frac{\partial \nu}{\partial z}\right), \quad (5)$$

from which, and from (3), various interesting relations can be inferred. The formulae already given are, however, sufficient for our present purpose.

112. In the applications to which we now proceed the triple orthogonal system consists of the confocal quadrics

$$\frac{x^2}{a^2 + \theta} + \frac{y^2}{b^2 + \theta} + \frac{z^2}{c^2 + \theta} - 1 = 0, \quad (1)$$

* The above method was given in a paper by W. Thomson, "On the Equations of Motion of Heat referred to Curvilinear Co-ordinates," *Camb. Math. Journ.*, t. iv (1843) [*Math. and Phys. Papers*, t. i p. 25]. Reference may also be made to Jacobi, "Ueber eine particuläre Lösung der partiellen Differentialgleichung," *Crelle*, t. xxxvi (1847) [*Weiske*, t. ii p. 198].

The transformation of $\nabla^2\phi$ to general orthogonal co-ordinates was first effected by Lamé, "Sur les lois de l'équilibre du fluide éthéré," *Journ. de l'École Polyt.*, t. xiv (1834). See also *Leçons sur les Coordonnées Curvilignes*, Paris, 1859, p. 22.

whose properties are explained in books on Solid Geometry. Through any given point (x, y, z) there pass three surfaces of the system, corresponding to the three roots of (1), considered as a cubic in θ . If (as we shall for the most part suppose) $a > b > c$, one of these roots (λ , say) will lie between ∞ and $-c^2$, another (μ) between $-c^2$ and $-b^2$, and the third (ν) between $-b^2$ and $-a^2$. The surfaces λ, μ, ν are therefore ellipsoids, hyperboloids of one sheet, and hyperboloids of two sheets, respectively

It follows immediately from this definition of λ, μ, ν , that

$$\frac{x^2}{a^2 + \theta} + \frac{y^2}{b^2 + \theta} + \frac{z^2}{c^2 + \theta} - 1 = \frac{(\lambda - \theta)(\mu - \theta)(\nu - \theta)}{(a^2 + \theta)(b^2 + \theta)(c^2 + \theta)}, \dots \quad (2)$$

identically, for all values of θ . Hence multiplying by $a^2 + \theta$, and afterwards putting $\theta = -a^2$, we obtain the first of the following equations.

$$\left. \begin{aligned} x^2 &= \frac{(a^2 + \lambda)(a^2 + \mu)(a^2 + \nu)}{(a^2 - b^2)(a^2 - c^2)}, \\ y^2 &= \frac{(b^2 + \lambda)(b^2 + \mu)(b^2 + \nu)}{(b^2 - c^2)(b^2 - a^2)}, \\ z^2 &= \frac{(c^2 + \lambda)(c^2 + \mu)(c^2 + \nu)}{(c^2 - a^2)(c^2 - b^2)}. \end{aligned} \right\} \dots \quad (3)$$

These give
$$\frac{\partial x}{\partial \lambda} = \frac{1}{2} \frac{x}{a^2 + \lambda}, \quad \frac{\partial y}{\partial \lambda} = \frac{1}{2} \frac{y}{b^2 + \lambda}, \quad \frac{\partial z}{\partial \lambda} = \frac{1}{2} \frac{z}{c^2 + \lambda}, \quad \dots \dots \dots (4)$$

and thence, in the notation of Art 111 (2),

$$\frac{1}{h_1^2} = \frac{1}{4} \left\{ \frac{x^2}{(a^2 + \lambda)^2} + \frac{y^2}{(b^2 + \lambda)^2} + \frac{z^2}{(c^2 + \lambda)^2} \right\} \dots \dots \dots (5)$$

If we differentiate (2) with respect to θ and afterwards put $\theta = \lambda$, we deduce the first of the following three relations

$$\left. \begin{aligned} h_1^2 &= 4 \frac{(a^2 + \lambda)(b^2 + \lambda)(c^2 + \lambda)}{(\lambda - \mu)(\lambda - \nu)}, \\ h_2^2 &= 4 \frac{(a^2 + \mu)(b^2 + \mu)(c^2 + \mu)}{(\mu - \nu)(\mu - \lambda)}, \\ h_3^2 &= 4 \frac{(a^2 + \nu)(b^2 + \nu)(c^2 + \nu)}{(\nu - \lambda)(\nu - \mu)} \end{aligned} \right\} \dots \dots \dots (6)$$

The remaining relations of the sets (3) and (6) have been written down from symmetry*

* It will be noticed that h_1, h_2, h_3 are double the perpendiculars from the origin on the tangent planes to the three quadrics λ, μ, ν .

Substituting in Art. 111 (4), we find*

$$\begin{aligned} \nabla^2 \phi = -\frac{4}{(\mu - \nu)(\nu - \lambda)(\lambda - \mu)} & \left[(\mu - \nu) \left\{ (a^2 + \lambda)^{\frac{1}{2}} (b^2 + \lambda)^{\frac{1}{2}} (c^2 + \lambda)^{\frac{1}{2}} \frac{\partial}{\partial \lambda} \right\}^2 \right. \\ & + (\nu - \lambda) \left\{ (a^2 + \mu)^{\frac{1}{2}} (b^2 + \mu)^{\frac{1}{2}} (c^2 + \mu)^{\frac{1}{2}} \frac{\partial}{\partial \mu} \right\}^2 \\ & \left. + (\lambda - \mu) \left\{ (a^2 + \nu)^{\frac{1}{2}} (b^2 + \nu)^{\frac{1}{2}} (c^2 + \nu)^{\frac{1}{2}} \frac{\partial}{\partial \nu} \right\}^2 \right] \phi \end{aligned} \quad (7)$$

113 The particular solutions of the transformed equation $\nabla^2 \phi = 0$ which first present themselves are those in which ϕ is a function of one (only) of the variables λ, μ, ν . Thus ϕ may be a function of λ alone, provided

$$(a^2 + \lambda)^{\frac{1}{2}} (b^2 + \lambda)^{\frac{1}{2}} (c^2 + \lambda)^{\frac{1}{2}} \frac{d\phi}{d\lambda} = \text{const.},$$

whence
$$\phi = C \int_{\lambda}^{\infty} \frac{d\lambda}{\Delta}, \quad \dots \quad (1)$$

if
$$\Delta = \{(a^2 + \lambda)(b^2 + \lambda)(c^2 + \lambda)\}^{\frac{1}{2}}, \quad \dots \quad (2)$$

the additive constant which attaches to ϕ being chosen so as to make ϕ vanish for $\lambda = \infty$

In this solution, which corresponds to $\phi = A/r$ in spherical harmonics, the equipotential surfaces are the confocal ellipsoids, and the motion in the space external to any one of these (say that for which $\lambda = 0$) is that due to a certain arrangement of simple sources over it. The velocity at any point is given by the formula

$$-h_1 \frac{d\phi}{d\lambda} = C \frac{h_1}{\Delta} \quad \dots \quad \dots \quad (3)$$

At a great distance from the origin the ellipsoids λ become spheres of radius $\lambda^{\frac{1}{2}}$, and the velocity is therefore ultimately equal to $2C/r^2$, where r denotes the distance from the origin. Over any particular equipotential surface λ , the velocity varies as the perpendicular from the centre on the tangent plane.

To find the distribution of sources over the surface $\lambda = 0$ which would produce the actual motion in the external space, we substitute for ϕ the value (1), in the formula (11) of Art. 58, and for ϕ' (which refers to the internal space) the constant value

$$\phi' = C \int_0^{\infty} \frac{d\lambda}{\Delta} \quad \dots \quad \dots \quad (4)$$

* Cf. Lamé, "Sur les surfaces isothermes dans les corps solides homogènes en équilibre de température," *Liouville*, t. II (1837).

The formula referred to then gives, for the surface-density of the required distribution,

$$\frac{C}{abc} \cdot h_1 \cdot \dots \dots \dots (5)$$

The solution (1) may also be interpreted as representing the motion due to a change in the dimensions of the ellipsoid, such that the surface remains similar to itself, and retains the directions of its principal axes unchanged. If we put

$$a/a = b/b = c/c = k, \text{ say,}$$

the surface-condition Art 110 (4) becomes

$$-\partial\phi/\partial n = \frac{1}{2}kh_1,$$

which is identical with (3), if we put $C = \frac{1}{2}kabc$

A particular case of (5) is where the sources are distributed over the *elliptic disk* for which $\lambda = -c^2$, and therefore $z^2 = 0$. This is important in Electrostatics, but a more interesting application from the present point of view is to the flow through an *elliptic aperture*, viz if the plane xy be occupied by a thin rigid partition with the exception of the part included by the ellipse

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1, \quad z = 0,$$

we have, putting $c = 0$ in the previous formulae,

$$\phi = \mp A \int_0^\lambda \frac{d\lambda}{(a^2 + \lambda)^{\frac{1}{2}} (b^2 + \lambda)^{\frac{1}{2}} \lambda^{\frac{1}{2}}}, \quad \dots \dots (6)$$

where the upper limit is the positive root of

$$\frac{x^2}{a^2 + \lambda} + \frac{y^2}{b^2 + \lambda} + \frac{z^2}{\lambda} = 1, \dots \dots \dots (7)$$

and the negative or the positive sign is to be taken according as the point for which ϕ is required lies on the positive or the negative side of the plane xy . The two values of ϕ are continuous at the aperture, where $\lambda = 0$. As before, the velocity at a great distance is equal to $2A/r^2$, nearly. For points in the aperture the velocity may be found immediately from (6) and (7), thus we may put

$$\delta n = z = \lambda^{\frac{1}{2}} \left(1 - \frac{x^2}{a^2} - \frac{y^2}{b^2} \right)^{\frac{1}{2}}, \quad \delta\phi = -\frac{2A\lambda^{\frac{1}{2}}}{ab},$$

approximately, since λ is small, whence

$$-\frac{\partial\phi}{\partial n} = \frac{2A}{ab} \left(1 - \frac{x^2}{a^2} - \frac{y^2}{b^2} \right)^{-\frac{1}{2}} \dots \dots \dots (8)$$

This becomes infinite, as we should expect, at the edge. The particular case of a *circular* aperture has already been solved otherwise in Arts. 102, 108

114. We proceed to investigate the solution of $\nabla^2\phi=0$, finite at infinity, which corresponds, for the space external to the ellipsoid, to the solution $\phi=x$ for the internal space. Following the analogy of spherical harmonics we may assume for trial

$$\phi = x\chi, \quad \dots \dots \quad (1)$$

which gives
$$\nabla^2\chi + \frac{2}{x} \frac{\partial\chi}{\partial x} = 0, \quad \dots \dots \quad (2)$$

and inquire whether this can be satisfied by making χ equal to some function of λ only. On this supposition we shall have, by Art 111,

$$\frac{\partial\chi}{\partial x} = h_1 \frac{d\chi}{d\lambda} \cdot h_1 \frac{\partial x}{\partial \lambda},$$

and therefore, by Art 112 (4), (6),

$$\frac{2}{x} \frac{\partial\chi}{\partial x} = 4 \frac{(b^2 + \lambda)(c^2 + \lambda)}{(\lambda - \mu)(\lambda - \nu)} \frac{d\chi}{d\lambda}.$$

On substituting the value of $\nabla^2\chi$ in terms of λ , the equation (2) becomes

$$\left\{ (a^2 + \lambda)^{\frac{1}{2}} (b^2 + \lambda)^{\frac{1}{2}} (c^2 + \lambda)^{\frac{1}{2}} \frac{d}{d\lambda} \right\}^2 \chi = - (b^2 + \lambda)(c^2 + \lambda) \frac{d\chi}{d\lambda},$$

which may be written

$$\frac{d}{d\lambda} \log \left\{ (a^2 + \lambda)^{\frac{1}{2}} (b^2 + \lambda)^{\frac{1}{2}} (c^2 + \lambda)^{\frac{1}{2}} \frac{d\chi}{d\lambda} \right\} = - \frac{1}{a^2 + \lambda}.$$

Hence
$$\chi = C \int_{\lambda}^{\infty} \frac{d\lambda}{(\bar{a}^2 + \bar{\lambda})^{\frac{1}{2}} (\bar{b}^2 + \bar{\lambda})^{\frac{1}{2}} (\bar{c}^2 + \bar{\lambda})^{\frac{1}{2}}}, \quad \dots \dots \quad (3)$$

the arbitrary constant which presents itself in the second integration being chosen as before so as to make χ vanish at infinity.

The solution contained in (1) and (3) enables us to find the motion of a liquid, at rest at infinity, produced by the translation of a solid ellipsoid through it, parallel to a principal axis. The notation being as before, and the ellipsoid

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} + \frac{z^2}{c^2} = 1, \quad \dots \dots \dots (4)$$

being supposed in motion parallel to x with velocity U , the surface-condition is

$$\frac{\partial\phi}{\partial\lambda} = -U \frac{\partial x}{\partial\lambda}, \quad \text{for } \lambda = 0 \quad \dots \dots \quad (5)$$

Let us write, for shortness,

$$\alpha_0 = abc \int_0^{\infty} \frac{d\lambda}{(\bar{a}^2 + \bar{\lambda}) \Delta}, \quad \beta_0 = abc \int_0^{\infty} \frac{d\lambda}{(\bar{b}^2 + \bar{\lambda}) \Delta}, \quad \gamma_0 = abc \int_0^{\infty} \frac{d\lambda}{(\bar{c}^2 + \bar{\lambda}) \Delta}, \quad \dots \dots \quad (6)$$

where

$$\Delta = \{(a^2 + \lambda)(b^2 + \lambda)(c^2 + \lambda)\}^{\frac{1}{2}}, \quad \dots \dots \dots (7)$$

it will be noticed that these quantities $\alpha_0, \beta_0, \gamma_0$ are purely numerical. The conditions of our problem are satisfied by

$$\phi = Cx \int_{\lambda}^{\infty} \frac{d\lambda}{(a^2 + \lambda)\Delta}, \quad \dots \dots \dots (8)$$

provided

$$C = \frac{abc}{2 - \alpha_0} U. \quad \dots \dots \dots (9)$$

The corresponding solution when the ellipsoid moves parallel to y or z can be written down from symmetry, and by superposition we derive the case where the ellipsoid has any motion of translation whatever*.

At a great distance from the origin, the formula (8) becomes equivalent to

$$\phi = \frac{2}{3} C \frac{x}{r}, \quad \dots \dots \dots (10)$$

which is the velocity-potential of a double source at the origin, of strength $\frac{8}{3}\pi C$, or

$$\frac{8}{3} \frac{\pi}{2 - \alpha_0} abc U,$$

compare Art 92

The kinetic energy of the fluid is given by

$$2T = -\rho \iint \phi \frac{\partial \phi}{\partial n} dS = \frac{\alpha_0}{2 - \alpha_0} \rho U^2 \cdot \iint x l dS,$$

where l is the cosine of the angle which the normal to the surface makes with the axis of x . Since the latter integral is equal to the volume of the ellipsoid, we have

$$2T = \frac{\alpha_0}{2 - \alpha_0} \frac{4}{3} \pi abc \rho U^2. \quad \dots \dots \dots (11)$$

The inertia-coefficient is therefore equal to the fraction $\alpha_0/(2 - \alpha_0)$ of the mass displaced by the solid. For the case of the sphere ($a = b = c$) we find $\alpha_0 = \frac{2}{3}$, this makes the fraction equal to $\frac{1}{2}$, in agreement with Art. 92. If we put $b = c$, we get the case of an ellipsoid of revolution, including (for $a = 0$) that of a circular disk. The identification with the results obtained by the methods of Arts 105, 106, 108, 109 for these cases may be left to the reader.

* This problem was first solved by Green, "Researches on the Vibration of Pendulums in Fluid Media," *Trans R S Edin*, 1833 [*Math Papers*, p 315]. The investigation is much shortened if we assume at once from the Theory of Attractions that (8) is a solution of $\nabla^2 \phi = 0$, being in fact (except for a constant factor) the x -component of the attraction of a homogeneous ellipsoid at an external point.

115 We next inquire whether the equation $\nabla^2\phi=0$ can be satisfied by

$$\phi = yz\chi, \quad \dots \dots \dots (1)$$

where χ is a function of λ only. This requires

$$\nabla^2\chi + \frac{2}{y}\frac{\partial\chi}{\partial y} + \frac{2}{z}\frac{\partial\chi}{\partial z} = 0. \quad \dots \dots (2)$$

Now, from Art. 112 (4), (6),

$$\begin{aligned} \frac{2}{y}\frac{\partial\chi}{\partial y} + \frac{2}{z}\frac{\partial\chi}{\partial z} &= 2h_1^2 \left(\frac{1}{y}\frac{\partial y}{\partial\lambda} + \frac{1}{z}\frac{\partial z}{\partial\lambda} \right) \frac{d\chi}{d\lambda} \\ &= 4 \frac{(a^2 + \lambda)(b^2 + \lambda)(c^2 + \lambda)}{(\lambda - \mu)(\lambda - \nu)} \left(\frac{1}{b^2 + \lambda} + \frac{1}{c^2 + \lambda} \right) \frac{d\chi}{d\lambda} \end{aligned}$$

On substitution in (2) we find, by Art. 112 (7),

$$\frac{d}{d\lambda} \log \left\{ (a^2 + \lambda)^{\frac{1}{2}} (b^2 + \lambda)^{\frac{1}{2}} (c^2 + \lambda)^{\frac{1}{2}} \frac{d\chi}{d\lambda} \right\} = -\frac{1}{b^2 + \lambda} - \frac{1}{c^2 + \lambda},$$

whence
$$\chi = C \int_{\lambda}^{\infty} \frac{d\lambda}{(b^2 + \lambda)(c^2 + \lambda)\Delta}, \quad \dots \dots (3)$$

the second constant of integration being chosen as before

For a rigid ellipsoid rotating about the axis of x with angular velocity Ω_x , the surface-condition is

$$\frac{\partial\phi}{\partial\lambda} = \Omega_x \left(z \frac{\partial y}{\partial\lambda} - y \frac{\partial z}{\partial\lambda} \right), \quad \dots \dots (4)$$

for $\lambda=0$ Assuming*

$$\phi = C yz \int_{\lambda}^{\infty} \frac{d\lambda}{(b^2 + \lambda)(c^2 + \lambda)\Delta}, \quad \dots \dots (5)$$

we find that the surface-condition (4) is satisfied, provided

$$-\frac{C}{ab^2c^2} + \frac{1}{2}C \left(\frac{1}{b^2} + \frac{1}{c^2} \right) \frac{\gamma_0 - \beta_0}{abc(b^2 - c^2)} = \frac{1}{2}\Omega_x \left(\frac{1}{b^2} - \frac{1}{c^2} \right),$$

or
$$C = \frac{(b^2 - c^2)^2}{2(b^2 - c^2) + (b^2 + c^2)(\beta_0 - \gamma_0)} abc \Omega_x. \quad \dots \dots (6)$$

The formulae for the cases of rotation about y or z can be written down from symmetry†

* The expression (5) differs only by a factor from

$$y \frac{\partial\Phi}{\partial z} - z \frac{\partial\Phi}{\partial y},$$

where Φ is the gravitation-potential of a uniform solid ellipsoid at an external point (x, y, z) . Since $\nabla^2\Phi=0$ it easily follows that the above is also a solution of the equation $\nabla^2\phi=0$

† The solution contained in (5) and (6) is due to Clebsch, "Ueber die Bewegung eines Ellipsoides in einer tropfbaren Flüssigkeit," *Crelle*, tt 111, 111 (1856—7)

The formula for the kinetic energy is

$$2T = -\rho \iiint \phi \frac{\partial \phi}{\partial n} dS \\ = \rho C \Omega_x^2 \int_0^\infty \frac{d\lambda}{(a^2 + \lambda)^{\frac{1}{2}} (b^2 + \lambda)^{\frac{1}{2}} (c^2 + \lambda)^{\frac{1}{2}}} \iint (ny - mz) yz dS,$$

if (l, m, n) denote the direction-cosines of the normal to the ellipsoid. The latter integral

$$= \iiint (y^2 - z^2) dx dy dz = \frac{1}{5} (b^2 - c^2) \frac{4}{3} \pi abc$$

Hence we find

$$2T = \frac{1}{5} \frac{(b^2 - c^2)^2 (\gamma_0 - \beta_0)}{2(b^2 - c^2) + (b^2 + c^2)(\beta_0 - \gamma_0)} \frac{4}{3} \pi abc \rho \cdot \Omega_x^2 \dots \dots (7)$$

The two remaining types of ellipsoidal harmonic of the second order, finite at the origin, are given by the expression

$$\frac{x^2}{a^2 + \theta} + \frac{y^2}{b^2 + \theta} + \frac{z^2}{c^2 + \theta} - 1, \quad \dots \dots (8)$$

where θ is either root of $\frac{1}{a^2 + \theta} + \frac{1}{b^2 + \theta} + \frac{1}{c^2 + \theta} = 0, \quad \dots \dots \dots (9)$

this being the condition that (8) should satisfy $\nabla^2 \phi = 0$

The method of obtaining the corresponding solutions for the external space is explained in the treatise of Ferrers. These solutions would enable us to express the motion produced in a surrounding liquid by variations in the lengths of the axes of an ellipsoid, subject to the condition of no variation of volume.

$$a/a + b/b + c/c = 0 \quad \dots \dots \dots (10)$$

We have already found, in Art. 113, the solution for the case where the ellipsoid expands (or contracts) remaining similar to itself, so that by superposition we could obtain the case of an internal boundary changing its position and dimensions in any manner whatever, subject only to the condition of remaining ellipsoidal. This extension of the results arrived at by Green and Clebsch was first treated, though in a different manner from that here indicated, by Bjerknes*.

116 The investigations of this chapter have related almost entirely to the case of spherical or ellipsoidal boundaries. It will be understood that solutions of the equation $\nabla^2 \phi = 0$ can be carried out, on lines more or less similar, which are appropriate to other forms of boundary. The surface which comes next in interest, from the point of view of the present subject, is that of the anchor-ring, or 'torus', this case has been very ably treated, by distinct methods, by Hicks, and Dyson†. We may also refer to the analytically remarkable problem of the spherical bowl, which has been investigated by Basset‡.

* *l. c. ante* p. 141

† Hicks, "On Toroidal Functions," *Phil. Trans.*, 1881, Dyson, "On the Potential of an Anchor-Ring," *Phil. Trans.*, 1893, see also C. Neumann, *l. c. ante* p. 126.

‡ "On the Potential of an Electrified Spherical Bowl, &c.," *Proc. Lond. Math. Soc.*, t. xvi (1885), *Hydrodynamics*, t. i p. 149.

CHAPTER VI.

ON THE MOTION OF SOLIDS THROUGH A LIQUID DYNAMICAL THEORY.

117 IN this Chapter it is proposed to study the very interesting dynamical problem furnished by the motion of one or more solids in a frictionless liquid. The development of this subject is due mainly to Thomson and Tait* and to Kirchhoff†. The cardinal feature of the methods followed by these writers consists in this, that the solids and the fluid are treated as forming one dynamical system, and thus the troublesome calculation of the effect of the fluid pressures on the surfaces of the solids is avoided.

To begin with the case of a single solid moving through an infinite mass of liquid, we will suppose in the first instance that the motion of the fluid is entirely due to that of the solid, and is therefore irrotational and acyclic. Some special cases of this problem have been treated incidentally in the foregoing pages, and it appeared that the whole effect of the fluid might be represented by an addition to the *inertia* of the solid. The same result will be found to hold in general, provided we use the term 'inertia' in a somewhat extended sense.

Under the circumstances supposed, the motion of the fluid is characterized by the existence of a single-valued velocity-potential ϕ which, besides satisfying the equation of continuity

$$\nabla^2 \phi = 0, \quad \dots \dots \dots (1)$$

fulfils the following conditions (1°) the value of $-\partial\phi/\partial n$, where δn denotes as usual an element of the normal at any point of the surface of the solid, drawn on the side of the fluid, must be equal to the velocity of the surface at that point normal to itself, and (2°) the differential coefficients $\partial\phi/\partial x$,

* *Natural Philosophy*, Art 320. Subsequent investigations by Lord Kelvin will be referred to later.

† "Ueber die Bewegung eines Rotationskörpers in einer Flüssigkeit," *Crelle*, t lxxi (1869) [*Ges. Abh.*, p 376], *Mechanik*, c xix.

$\partial\phi/\partial y$, $\partial\phi/\partial z$ must vanish at an infinite distance, in every direction, from the solid. The latter condition is rendered necessary by the consideration that a finite velocity at infinity would imply an infinite kinetic energy, which could not be generated by finite forces acting for a finite time on the solid. It is also the condition to which we are led by supposing the fluid to be enclosed within a fixed vessel infinitely large and infinitely distant, all round, from the moving body. For on this supposition the space occupied by the fluid may be conceived as made up of tubes of flow which begin and end on the surface of the solid, so that the total flux across any area, finite or infinite, drawn in the fluid must be finite, and therefore the velocity at infinity zero.

It has been shewn in Art. 41 that under the above conditions the motion of the fluid is determinate.

118 In the further study of the problem it is convenient to follow the method introduced by Euler in the dynamics of rigid bodies, and to adopt a system of rectangular axes Ox , Oy , Oz fixed in the body, and moving with it. If the motion of the body at any instant be defined by the angular velocities p , q , r about, and the translational velocities u , v , w of the origin parallel to, the instantaneous positions of these axes*, we may write, after Kirchhoff,

$$\phi = u\phi_1 + v\phi_2 + w\phi_3 + p\chi_1 + q\chi_2 + r\chi_3, \quad \dots \dots \dots (2)$$

where, as will appear immediately, ϕ_1 , ϕ_2 , ϕ_3 , χ_1 , χ_2 , χ_3 are certain functions of x , y , z determined solely by the configuration of the surface of the solid, relative to the co-ordinate axes. In fact, if l , m , n denote the direction-cosines of the normal, drawn towards the fluid, at any point of this surface, the kinematical surface-condition is

$$-\frac{\partial\phi}{\partial n} = l(u + qz - ry) + m(v + rx - pz) + n(w + py - qx),$$

whence, substituting the value (2) of ϕ , we find

$$\left. \begin{aligned} -\frac{\partial\phi_1}{\partial n} &= l, & -\frac{\partial\phi_2}{\partial n} &= m, & -\frac{\partial\phi_3}{\partial n} &= n, \\ -\frac{\partial\chi_1}{\partial n} &= ny - mz, & -\frac{\partial\chi_2}{\partial n} &= lz - nx, & -\frac{\partial\chi_3}{\partial n} &= mx - ly \end{aligned} \right\} \dots (3)$$

Since these functions must also satisfy (1), and have their derivatives zero at infinity, they are completely determinate, by Art. 41†.

* The symbols u , v , w , p , q , r are not at present required in their former meanings.

† For the particular case of an ellipsoidal surface, their values may be written down from the results of Arts. 114, 115.

119 Now whatever the motion of the solid and fluid at any instant, it might have been generated instantaneously from rest by a properly adjusted impulsive 'wrench' applied to the solid. This wrench is in fact that which would be required to counteract the impulsive pressures $\rho\phi$ on the surface, and, in addition, to generate the actual momentum of the solid. It is called by Lord Kelvin the 'impulse' of the system at the moment under consideration. It is to be noted that the impulse, as thus defined, cannot be asserted to be equivalent to the total momentum of the system, which is indeed in the present problem indeterminate*. We proceed to shew however that the impulse varies, in consequence of extraneous forces acting on the solid, in exactly the same way as the momentum of a finite dynamical system.

Let us in the first instance consider any actual motion of a solid, from time t_0 to time t_1 , under any given forces applied to it, in a *finite* mass of liquid enclosed by a fixed envelope of any form. Let us imagine the motion to have been generated from rest, previously to the time t_0 , by forces (whether continuous or impulsive) applied to the solid, and to be arrested, in like manner, by forces applied to the solid after the time t_1 . Since the momentum of the system is null both at the beginning and at the end of this process, the time-integrals of the forces applied to the solid, together with the time-integral of the pressures exerted on the fluid by the envelope, must form an equilibrating system. The effect of these latter pressures may be calculated, by Art. 22, from the formula

$$\frac{p}{\rho} = \frac{\partial\phi}{\partial t} - \frac{1}{2}q^2 + F(t) \quad \dots \dots \dots (1)$$

A pressure uniform over the envelope has no resultant effect, hence, since ϕ is constant at the beginning and end, the only effective part of the integral pressure $\int p dt$ is given by the term

$$-\frac{1}{2}\rho \int q^2 dt. \quad \dots \dots \dots (2)$$

Let us now revert to the original form of our problem, and suppose the containing envelope to be infinitely large, and infinitely distant in every direction from the moving solid. It is easily seen by considering the arrangement of the tubes of flow (Art 36) that the fluid velocity q at a great distance r from an origin in the neighbourhood of the solid will ultimately be, at most†, of the order $1/r^2$, and the integral pressure (2) therefore of the order $1/r^4$. Since the surface-elements of the envelope are of the order $r^2\delta\omega$, where $\delta\omega$ is an elementary solid angle, the force- and couple-resultants of the integral pressure (2) will now both be null. The same statement

* Viz, the attempt to calculate it leads to 'improper' or 'indeterminate' integrals

† It is really of the order $1/r^3$ when, as in the case considered, the total flux outwards is zero

therefore holds with regard to the time-integral of the forces applied to the solid

If we imagine the motion to have been started *instantaneously* at time t_0 , and to be arrested *instantaneously* at time t_1 , the result at which we have arrived may be stated as follows.

The 'impulse' of the motion (in Lord Kelvin's sense) at time t_1 differs from the 'impulse' at time t_0 by the time-integral of the extraneous forces acting on the solid during the interval $t_1 - t_0^*$.

It will be noticed that the above reasoning is substantially unaltered when the single solid is replaced by a group of solids, which may moreover be flexible instead of rigid, and even when these solids are replaced by masses of liquid which are moving rotationally

120 To express the above result analytically, let $\xi, \eta, \zeta, \lambda, \mu, \nu$ be the components of the force- and couple-constituents of the impulse, and let X, Y, Z, L, M, N designate in the same manner the system of extraneous forces. The whole variation of $\xi, \eta, \zeta, \lambda, \mu, \nu$, due partly to the motion of the axes to which these quantities are referred, and partly to the action of the extraneous forces, is then given by the formulae†

$$\left. \begin{aligned} \frac{d\xi}{dt} &= r\eta - q\zeta + X, & \frac{d\lambda}{dt} &= w\eta - v\zeta + r\mu - q\nu + L, \\ \frac{d\eta}{dt} &= p\zeta - r\xi + Y, & \frac{d\mu}{dt} &= u\zeta - w\xi + p\nu - r\lambda + M, \\ \frac{d\zeta}{dt} &= q\xi - p\eta + Z, & \frac{d\nu}{dt} &= v\xi - u\eta + q\lambda - p\mu + N. \end{aligned} \right\} \quad \dots(1)$$

For at time $t + \delta t$ the moving axes make with their positions at time t angles whose cosines are

$$(1, r\delta t, -q\delta t), \quad (-r\delta t, 1, p\delta t), \quad (q\delta t, -p\delta t, 1),$$

respectively. Hence, resolving parallel to the new position of the axis of x ,

$$\xi + \delta\xi = \xi + \eta \cdot r\delta t - \zeta \cdot q\delta t + X\delta t$$

Again, taking moments about the new position of Ox , and remembering that O has been displaced through spaces $u\delta t, v\delta t, w\delta t$ parallel to the axes, we find

$$\lambda + \delta\lambda = \lambda + \eta \cdot w\delta t - \zeta \cdot v\delta t + \mu \cdot r\delta t - \nu \cdot q\delta t + L\delta t$$

These, with the similar results which can be written down from symmetry, give the equations (1)

* Sir W Thomson, *l c ante* p 30. The form of the argument given above was kindly suggested to the author by Prof Larmor.

† Cf Hayward, "On a Direct Method of Estimating Velocities, Accelerations, and all similar Quantities, with respect to Axes moveable in any manner in space" *Camb Trans*, t x (1856)

When no extraneous forces act, we verify at once that these equations have the integrals

$$\xi^2 + \eta^2 + \zeta^2 = \text{const.}, \quad \lambda\xi + \mu\eta + \nu\zeta = \text{const.}, \quad \dots \dots (2)$$

which express that the magnitudes of the force- and couple-resultants of the impulse are constant

121 It remains to express $\xi, \eta, \zeta, \lambda, \mu, \nu$ in terms of u, v, w, p, q, r . In the first place let \mathbf{T} denote the kinetic energy of the *fluid*, so that

$$2\mathbf{T} = -\rho \iint \phi \frac{\partial \phi}{\partial n} dS, \quad \dots \dots \dots (1)$$

where the integration extends over the surface of the moving solid. Substituting the value of ϕ from Art. 118 (2), we get

$$\begin{aligned} 2\mathbf{T} = & \mathbf{A}u^2 + \mathbf{B}v^2 + \mathbf{C}w^2 + 2\mathbf{A}'vw + 2\mathbf{B}'wu + 2\mathbf{C}'uv \\ & + \mathbf{P}p^2 + \mathbf{Q}q^2 + \mathbf{R}r^2 + 2\mathbf{P}'qr + 2\mathbf{Q}'rp + 2\mathbf{R}'pq \\ & + 2p(\mathbf{F}u + \mathbf{G}v + \mathbf{H}w) + 2q(\mathbf{F}'u + \mathbf{G}'v + \mathbf{H}'w) + 2r(\mathbf{F}''u + \mathbf{G}''v + \mathbf{H}''w), \\ & \dots \dots \dots (2) \end{aligned}$$

where the 21 coefficients $\mathbf{A}, \mathbf{B}, \mathbf{C}$, &c. are certain constants determined by the form and position of the surface relative to the co-ordinate axes. Thus, for example,

$$\left. \begin{aligned} \mathbf{A} &= -\rho \iint \phi_1 \frac{\partial \phi_1}{\partial n} dS = \rho \iint \phi_1 l dS, \\ \mathbf{A}' &= -\frac{1}{2}\rho \iint \left(\phi_2 \frac{\partial \phi_3}{\partial n} + \phi_3 \frac{\partial \phi_2}{\partial n} \right) dS \\ &= -\rho \iint \phi_2 \frac{\partial \phi_3}{\partial n} dS = -\rho \iint \phi_3 \frac{\partial \phi_2}{\partial n} dS \\ &= \rho \iint \phi_2 n dS = \rho \iint \phi_3 m dS, \\ \mathbf{P} &= -\rho \iint \chi_1 \frac{\partial \chi_1}{\partial n} dS = \rho \iint \chi_1 (ny - mz) dS, \end{aligned} \right\} \dots \dots (3)$$

the transformations depending on Art 118 (3) and on a particular case of Green's Theorem (Art 44 (2)). These expressions for the coefficients were given by Kirchhoff.

The actual values of the coefficients in the expression for $2\mathbf{T}$ have been found in the preceding chapter for the case of the ellipsoid, viz we have from Arts 114, 115

$$\mathbf{A} = \frac{a_0}{2-a_0} \frac{4}{3}\pi pabc, \quad \mathbf{P} = \frac{1}{2} \frac{(b^2 - c^2)^2 (\gamma_0 - \beta_0)}{(b^2 - c^2) + (b^2 + c^2)(\beta_0 - \gamma_0)} \frac{4}{3}\pi pabc, \quad \dots (4)$$

with similar expressions for **B**, **C**, **Q**, **R**. The remaining coefficients, as will appear presently, in this case all vanish. We note that

$$\mathbf{A} - \mathbf{B} = \frac{2(\alpha_0 - \beta_0)}{(2 - \alpha_0)(2 - \beta_0)} \pi \rho a b c, \quad (5)$$

so that if $\alpha > b > c$, then $\mathbf{A} < \mathbf{B} < \mathbf{C}$, as might have been anticipated.

The formulae for an ellipsoid of revolution may be deduced by putting $b = c$, they may also be obtained independently by the method of Arts 104-109. Thus for a circular disk ($a = 0$, $b = c$) we have

$$\mathbf{A}, \mathbf{B}, \mathbf{C} = \frac{8}{3} \rho c^3, 0, 0, \quad \mathbf{P}, \mathbf{Q}, \mathbf{R} = 0, \frac{4}{3} \rho c^5, \frac{4}{3} \rho c^5 \quad (6)$$

The kinetic energy, \mathbf{T}_1 say, of the solid alone is given by an expression of the form

$$\begin{aligned} 2\mathbf{T}_1 = & \mathbf{m} (u^2 + v^2 + w^2) \\ & + \mathbf{P}_1 p^2 + \mathbf{Q}_1 q^2 + \mathbf{R}_1 r^2 + 2\mathbf{P}_1' q r + 2\mathbf{Q}_1' r p + 2\mathbf{R}_1' p q \\ & + 2\mathbf{m} \{ \alpha (v r - w q) + \beta (w p - u r) + \gamma (u q - v p) \} \quad \dots \dots \dots (7) \end{aligned}$$

Hence the total energy $\mathbf{T} + \mathbf{T}_1$, of the system, which we shall denote by T , is given by an expression of the same general form as (2), say

$$\begin{aligned} 2T = & A u^2 + B v^2 + C w^2 + 2A' v w + 2B' w u + 2C' u v \\ & + P p^2 + Q q^2 + R r^2 + 2P' q r + 2Q' r p + 2R' p q \\ & + 2p (F u + G v + H w) + 2q (F' u + G' v + H' w) + 2r (F'' u + G'' v + H'' w), \\ & \dots \dots \dots (8) \end{aligned}$$

where the coefficients are printed in uniform type, although six of them have of course the same values as in (2).

122 The values of the several components of the impulse in terms of the velocities u, v, w, p, q, r can now be found by a well-known dynamical method*. Let a system of indefinitely great forces (X, Y, Z, L, M, N) act for an indefinitely short time τ on the solid, so as to change the impulse from $(\xi, \eta, \zeta, \lambda, \mu, \nu)$ to $(\xi + \delta\xi, \eta + \delta\eta, \zeta + \delta\zeta, \lambda + \delta\lambda, \mu + \delta\mu, \nu + \delta\nu)$. The work done by the force X , viz

$$\int_0^\tau X u dt,$$

lies between

$$u_1 \int_0^\tau X dt \quad \text{and} \quad u_2 \int_0^\tau X dt,$$

where u_1 and u_2 are the greatest and least values of u during the time τ , i.e. it lies between $u_1 \delta\xi$ and $u_2 \delta\xi$. If we now introduce the supposition that $\delta\xi, \delta\eta, \delta\zeta, \delta\lambda, \delta\mu, \delta\nu$ are infinitely small, u_1 and u_2 are each equal to u , and the work done is $u \delta\xi$. In the same way we may calculate the work done by the remaining forces and couples. The total result must be equal to the

* See Thomson and Tait, *Natural Philosophy*, Art 313, or Maxwell, *Electricity and Magnetism*, Part IV, c v

increment of the kinetic energy, whence

$$u\delta\xi + v\delta\eta + w\delta\zeta + p\delta\lambda + q\delta\mu + r\delta\nu \\ = \delta T = \frac{\partial T}{\partial u} \delta u + \frac{\partial T}{\partial v} \delta v + \frac{\partial T}{\partial w} \delta w + \frac{\partial T}{\partial p} \delta p + \frac{\partial T}{\partial q} \delta q + \frac{\partial T}{\partial r} \delta r. \quad \dots (1)$$

Now if the velocities be all altered in any given ratio, the impulses will be altered in the same ratio. If then we take

$$\frac{\delta u}{u} = \frac{\delta v}{v} = \frac{\delta w}{w} = \frac{\delta p}{p} = \frac{\delta q}{q} = \frac{\delta r}{r} = k,$$

$$\text{it will follow that} \quad \frac{\delta\xi}{\xi} = \frac{\delta\eta}{\eta} = \frac{\delta\zeta}{\zeta} = \frac{\delta\lambda}{\lambda} = \frac{\delta\mu}{\mu} = \frac{\delta\nu}{\nu} = k$$

Substituting in (1), we find

$$u\xi + v\eta + w\zeta + p\lambda + q\mu + r\nu \\ = u \frac{\partial T}{\partial u} + v \frac{\partial T}{\partial v} + w \frac{\partial T}{\partial w} + p \frac{\partial T}{\partial p} + q \frac{\partial T}{\partial q} + r \frac{\partial T}{\partial r} = 2T, \quad \dots \dots (2)$$

since T is a homogeneous quadratic function. Now performing the arbitrary variation δ on the first and last members of (2), and omitting terms which cancel by (1), we find

$$\xi\delta u + \eta\delta v + \zeta\delta w + \lambda\delta p + \mu\delta q + \nu\delta r = \delta T$$

Since the variations $\delta u, \delta v, \delta w, \delta p, \delta q, \delta r$ are all independent, this gives the required formulae

$$\xi, \eta, \zeta = \frac{\partial T}{\partial u}, \frac{\partial T}{\partial v}, \frac{\partial T}{\partial w}, \quad \lambda, \mu, \nu = \frac{\partial T}{\partial p}, \frac{\partial T}{\partial q}, \frac{\partial T}{\partial r} \quad \dots (3)$$

It may be noted that since ξ, η, ζ, \dots are linear functions of u, v, w, \dots , the latter quantities may also be expressed as linear functions of the former, and thence T may be regarded as a homogeneous quadratic function of $\xi, \eta, \zeta, \lambda, \mu, \nu$. When expressed in this manner we may denote it by T' . The equation (1) then gives at once

$$u\delta\xi + v\delta\eta + w\delta\zeta + p\delta\lambda + q\delta\mu + r\delta\nu \\ = \frac{\partial T'}{\partial \xi} \delta\xi + \frac{\partial T'}{\partial \eta} \delta\eta + \frac{\partial T'}{\partial \zeta} \delta\zeta + \frac{\partial T'}{\partial \lambda} \delta\lambda + \frac{\partial T'}{\partial \mu} \delta\mu + \frac{\partial T'}{\partial \nu} \delta\nu,$$

$$\text{whence} \quad u, v, w = \frac{\partial T'}{\partial \xi}, \frac{\partial T'}{\partial \eta}, \frac{\partial T'}{\partial \zeta}, \quad p, q, r = \frac{\partial T'}{\partial \lambda}, \frac{\partial T'}{\partial \mu}, \frac{\partial T'}{\partial \nu} \quad \dots (4)$$

These formulae are in a sense reciprocal to (3).

We can utilize this last result to obtain, when no extraneous forces act, another integral of the equations of motion, in addition to those found in Art 120. Thus

$$\begin{aligned}\frac{dT}{dt} &= \frac{\partial T}{\partial \xi} \frac{d\xi}{dt} + \dots + \dots + \frac{\partial T}{\partial \lambda} \frac{d\lambda}{dt} + \dots + \dots \\ &= u \frac{d\xi}{dt} + \dots + \dots + p \frac{d\lambda}{dt} + \dots + \dots,\end{aligned}$$

which vanishes identically, by Art. 120 (1). Hence we have the equation of energy

$$T = \text{const} \quad \dots \dots \dots (5)$$

123 If in the formulae (3) we put, in the notation of Art. 121,

$$T = \mathbf{T} + \mathbf{T}_1,$$

it is known from the dynamics of rigid bodies that the terms in \mathbf{T}_1 represent the linear and angular momentum of the solid by itself. Hence the remaining terms, involving \mathbf{T} , must represent the system of impulsive pressures exerted by the surface of the solid on the fluid, in the supposed instantaneous generation of the motion from rest.

This is easily verified. For example, the x -component of the above system of impulsive pressures is

$$\begin{aligned}\iint \rho \phi l dS &= -\rho \iint \phi \frac{\partial \phi_1}{\partial n} dS \\ &= \mathbf{A}u + \mathbf{C}'v + \mathbf{B}'w + \mathbf{F}p + \mathbf{F}'q + \mathbf{F}''r = \frac{\partial \mathbf{T}}{\partial u}, \quad \dots \dots \dots (6)\end{aligned}$$

by the formulae of Arts. 118, 121. In the same way, the moment of the impulsive pressures about Ox is

$$\begin{aligned}\iint \rho \phi (ny - mz) dS &= -\rho \iint \phi \frac{\partial \chi_1}{\partial n} dS \\ &= \mathbf{F}u + \mathbf{G}v + \mathbf{H}w + \mathbf{P}p + \mathbf{R}'q + \mathbf{Q}'r = \frac{\partial \mathbf{T}}{\partial p} \quad \dots \quad (7)\end{aligned}$$

124 The equations of motion may now be written*

$$\left. \begin{aligned}\frac{d}{dt} \frac{\partial T}{\partial u} &= r \frac{\partial T}{\partial v} - q \frac{\partial T}{\partial w} + X, \\ \frac{d}{dt} \frac{\partial T}{\partial v} &= p \frac{\partial T}{\partial w} - r \frac{\partial T}{\partial u} + Y, \\ \frac{d}{dt} \frac{\partial T}{\partial w} &= q \frac{\partial T}{\partial u} - p \frac{\partial T}{\partial v} + Z, \\ \frac{d}{dt} \frac{\partial T}{\partial p} &= w \frac{\partial T}{\partial v} - v \frac{\partial T}{\partial w} + r \frac{\partial T}{\partial q} - q \frac{\partial T}{\partial r} + L, \\ \frac{d}{dt} \frac{\partial T}{\partial q} &= u \frac{\partial T}{\partial w} - w \frac{\partial T}{\partial u} + p \frac{\partial T}{\partial r} - r \frac{\partial T}{\partial p} + M, \\ \frac{d}{dt} \frac{\partial T}{\partial r} &= v \frac{\partial T}{\partial u} - u \frac{\partial T}{\partial v} + q \frac{\partial T}{\partial p} - p \frac{\partial T}{\partial q} + N.\end{aligned}\right\} \quad \dots \quad (1)$$

* See Kirchhoff, *loc. cit.* p. 150, also Sir W. Thomson, "Hydrokinetic Solutions and Observations," *Phil. Mag.*, Nov. 1871 [reprinted in *Baltimore Lectures*, Cambridge, 1904, p. 584].

If in these we write $T = \mathbf{T} + \mathbf{T}_1$, and isolate the terms due to \mathbf{T} , we obtain expressions for the forces exerted on the moving solid by the pressure of the surrounding fluid, thus the total component (\mathbf{X} , say) of the fluid pressure parallel to x is

$$\mathbf{X} = -\frac{d}{dt} \frac{\partial \mathbf{T}}{\partial u} + r \frac{\partial \mathbf{T}}{\partial v} - q \frac{\partial \mathbf{T}}{\partial w}, \quad \dots \quad (2)$$

and the moment (\mathbf{L}) of the same pressures about x is*

$$\mathbf{L} = -\frac{d}{dt} \frac{\partial \mathbf{T}}{\partial p} + w \frac{\partial \mathbf{T}}{\partial v} - v \frac{\partial \mathbf{T}}{\partial w} + r \frac{\partial \mathbf{T}}{\partial q} - q \frac{\partial \mathbf{T}}{\partial r} \quad \dots \quad (3)$$

For example, if the solid be constrained to move with a constant velocity (u, v, w), without rotation, we have

$$\left. \begin{aligned} \mathbf{X}, \mathbf{Y}, \mathbf{Z} &= 0, \\ \mathbf{L}, \mathbf{M}, \mathbf{N} &= w \frac{\partial \mathbf{T}}{\partial v} - v \frac{\partial \mathbf{T}}{\partial w}, \quad u \frac{\partial \mathbf{T}}{\partial w} - w \frac{\partial \mathbf{T}}{\partial u}, \quad v \frac{\partial \mathbf{T}}{\partial u} - u \frac{\partial \mathbf{T}}{\partial v}, \end{aligned} \right\} \quad (4)$$

where

$$2\mathbf{T} = \mathbf{A}u^2 + \mathbf{B}v^2 + \mathbf{C}w^2 + 2\mathbf{A}'vw + 2\mathbf{B}'wu + 2\mathbf{C}'uw$$

The fluid pressures thus reduce to a couple, which moreover vanishes if

$$\frac{\partial \mathbf{T}}{\partial u} \quad u = \frac{\partial \mathbf{T}}{\partial v} \quad v = \frac{\partial \mathbf{T}}{\partial w} \quad w,$$

i.e. provided the velocity (u, v, w) be in the direction of one of the principal axes of the ellipsoid

$$\mathbf{A}x^2 + \mathbf{B}y^2 + \mathbf{C}z^2 + 2\mathbf{A}'yz + 2\mathbf{B}'zx + 2\mathbf{C}'xy = \text{const} \quad \dots \quad (5)$$

Hence, as was first pointed out by Kirchhoff, there are, for any solid, three mutually perpendicular directions of permanent translation, that is to say, if the solid be set in motion parallel to one of these, without rotation, and left to itself, it will continue to move in this manner. It is evident that these directions are determined solely by the configuration of the surface of the body. It must be observed however that the impulse necessary to produce one of these permanent translations does not in general reduce to a single force, thus if the axes of co-ordinates be chosen, for simplicity, parallel to the three directions in question, so that $\mathbf{A}', \mathbf{B}', \mathbf{C}' = 0$, we have, corresponding to the motion u alone,

$$\xi, \eta, \zeta = \mathbf{A}u, \quad 0, \quad 0, \quad \lambda, \mu, \nu = F'u, \quad F''u, \quad F'''u,$$

so that the impulse consists of a wrench of pitch F/\mathbf{A}

With the same choice of axes, the components of the couple which is the

* The forms of these expressions being known, it is not difficult to verify them by direct calculation from the pressure-equation, Art 20 (4). See a paper "On the Forces experienced by a Solid moving through a Liquid," *Quart. Journ Math.*, t. xix (1883).

equivalent of the fluid pressures on the solid, in the case of any uniform translation (u, v, w) , are

$$\mathbf{L}, \mathbf{M}, \mathbf{N} = (\mathbf{B} - \mathbf{C})vw, (\mathbf{C} - \mathbf{A})wu, (\mathbf{A} - \mathbf{B})uv. \quad \dots(6)$$

Hence if in the ellipsoid

$$\mathbf{A}x^2 + \mathbf{B}y^2 + \mathbf{C}z^2 = \text{const}, \quad \dots \dots (7)$$

we draw a radius-vector r in the direction of the velocity (u, v, w) and erect the perpendicular h from the centre on the tangent plane at the extremity of r , the plane of the couple is that of h and r , its magnitude is proportional to $\sin(h, r)/h$, and its tendency is to turn the solid in the direction from h to r . Thus if the direction of (u, v, w) differs but slightly from that of the axis of x , the tendency of the couple is to diminish the deviation when \mathbf{A} is the greatest, and to increase it when \mathbf{A} is the least, of the three quantities $\mathbf{A}, \mathbf{B}, \mathbf{C}$, whilst if \mathbf{A} is intermediate to \mathbf{B} and \mathbf{C} the tendency depends on the position of r relative to the circular sections of the above ellipsoid. It appears then that of the three permanent translations one only is thoroughly stable, viz. that corresponding to the greatest of the three coefficients $\mathbf{A}, \mathbf{B}, \mathbf{C}$. For example, the only stable direction of translation of an ellipsoid is that of its *least* axis; see Art. 121*.

125. The above, although the simplest, are not the only steady motions of which the body is capable, under the action of no extraneous forces. The instantaneous motion of the body at any instant consists, by a well-known theorem of Kinematics, of a twist about a certain screw; and the condition that this motion should be permanent is that it should not affect the configuration of the impulse (which is fixed in space) relatively to the body. This requires that the axes of the screw and of the corresponding impulsive wrench should coincide. Since the general equations of a straight line involve four independent constants, this gives four linear relations to be satisfied by the five ratios $u : v : w : p : q : r$. There exists then for every body, under the circumstances here considered, a singly-infinite system of possible steady motions.

The steady motions next in importance to the three permanent translations are those in which the impulse reduces to a *couple*. The equations (1) of Art. 120 shew that we may have $\xi, \eta, \zeta = 0$, and λ, μ, ν constant, provided

$$\lambda/p = \mu/q = \nu/r, = k, \text{ say} \quad \dots \dots (1)$$

If the axes of co-ordinates have the special directions referred to in the preceding Art, the conditions $\xi, \eta, \zeta = 0$ give us at once u, v, w in terms of p, q, r , viz

$$u = -\frac{Fp + F'q + F''r}{A}, \quad v = -\frac{Gp + G'q + G''r}{B}, \quad w = -\frac{Hp + H'q + H''r}{C}. \quad \dots (2)$$

* The physical cause of this tendency of a flat shaped body to set itself broadside-on to the relative motion is clearly indicated in the diagram on p 80. A number of interesting practical illustrations are given by Thomson and Tait, Art 325.

Substituting these values in the expressions for λ , μ , ν obtained from Art. 122 (3), we find

$$\lambda, \mu, \nu = \frac{\partial \Theta}{\partial p}, \frac{\partial \Theta}{\partial q}, \frac{\partial \Theta}{\partial r}, \quad (3)$$

provided
$$2\Theta(p, q, r) = \mathfrak{P}p^2 + \mathfrak{Q}q^2 + \mathfrak{R}r^2 + 2\mathfrak{P}'qr + 2\mathfrak{Q}'rp + 2\mathfrak{R}'pq, \quad (4)$$

the coefficients in this expression being determined by formulae of the types

$$\mathfrak{P} = P - \frac{F^2}{A} - \frac{G^2}{B} - \frac{H^2}{C}, \quad \mathfrak{P}' = P' - \frac{F'F''}{A} - \frac{G'G''}{B} - \frac{H'H''}{C}. \quad (5)$$

These formulae hold for any case in which the force-constituent of the impulse is zero. Introducing the conditions (1) of steady motion, the ratios p, q, r are to be determined from the three equations

$$\left. \begin{aligned} \mathfrak{P}p + \mathfrak{R}'q + \mathfrak{Q}'r &= kp, \\ \mathfrak{R}'p + \mathfrak{Q}q + \mathfrak{P}'r &= kq, \\ \mathfrak{Q}p + \mathfrak{P}'q + \mathfrak{R}r &= kr \end{aligned} \right\} \quad \dots (6)$$

The form of these shews that the line whose direction-ratios are p, q, r must be parallel to one of the principal axes of the ellipsoid

$$\Theta(x, y, z) = \text{const} \quad (7)$$

There are therefore three permanent screw-motions such that the corresponding impulsive wrench in each case reduces to a couple only. The axes of these three screws are mutually at right angles, but do not in general intersect.

It may now be shewn that in all cases where the impulse reduces to a couple only, the motion can be completely determined. It is convenient, retaining the same directions of the axes, to change the origin. Now the origin may be transferred to any point (x, y, z) by writing

$$u + ry - qz, \quad v + pz - rx, \quad w + qx - py,$$

for u, v, w respectively. The coefficient of $2vr$ in the expression for the kinetic energy, Art. 121 (8), becomes $-Bx + G''$, that of $2wq$ becomes $Cx + H'$, and so on. Hence if we take

$$x = \frac{1}{2} \left(\frac{G''}{B} - \frac{H'}{C} \right), \quad y = \frac{1}{2} \left(\frac{H}{C} - \frac{F''}{A} \right), \quad z = \frac{1}{2} \left(\frac{F'}{A} - \frac{G}{B} \right), \quad (8)$$

the coefficients in the transformed expression for $2T$ will satisfy the relations

$$\frac{G''}{B} = \frac{H'}{C}, \quad \frac{H}{C} = \frac{F''}{A}, \quad \frac{F'}{A} = \frac{G}{B}. \quad (9)$$

If we denote the values of these pairs of equal quantities by α, β, γ respectively, the formulae (2) may be written

$$u = -\frac{\partial \Psi}{\partial p}, \quad v = -\frac{\partial \Psi}{\partial q}, \quad w = -\frac{\partial \Psi}{\partial r}, \quad (10)$$

where

$$2\Psi(p, q, r) = \frac{F}{A} p^2 + \frac{G'}{B} q^2 + \frac{H''}{C} r^2 + 2\alpha qr + 2\beta rp + 2\gamma pq. \quad (11)$$

The motion of the body at any instant may be conceived as made up of two parts; viz. a motion of translation equal to that of the origin, and one of rotation about an instantaneous axis passing through the origin. Since $\xi, \eta, \zeta = 0$ the latter part is to be determined by the equations

$$\frac{d\lambda}{dt} = r\mu - q\nu, \quad \frac{d\mu}{dt} = p\nu - r\lambda, \quad \frac{d\nu}{dt} = q\lambda - p\mu,$$

which express that the vector (λ, μ, ν) is constant in magnitude and has a fixed direction in space. Substituting from (3),

$$\left. \begin{aligned} \frac{d}{dt} \frac{\partial \Theta}{\partial p} &= r \frac{\partial \Theta}{\partial q} - q \frac{\partial \Theta}{\partial r}, \\ \frac{d}{dt} \frac{\partial \Theta}{\partial q} &= p \frac{\partial \Theta}{\partial r} - r \frac{\partial \Theta}{\partial p}, \\ \frac{d}{dt} \frac{\partial \Theta}{\partial r} &= q \frac{\partial \Theta}{\partial p} - p \frac{\partial \Theta}{\partial q} \end{aligned} \right\} \quad . \quad . \quad (12)$$

These are identical in form with the equations of motion of a rigid body about a fixed point, so that we may make use of Poincaré's well-known solution of the latter problem. The angular motion of the body is obtained by making the ellipsoid (7), which is fixed in the body, roll on a plane

$$\lambda x + \mu y + \nu z = \text{const},$$

which is fixed in space, with an angular velocity proportional to the length OI of the radius vector drawn from the origin to the point of contact I . The representation of the actual motion is then completed by impressing on the whole system of rolling ellipsoid and plane a velocity of translation whose components are given by (10). This velocity is in the direction of the normal OM to the tangent plane of the quadric

$$\Psi(x, y, z) = -\epsilon^2, \quad . \quad . \quad . \quad (13)$$

at the point P where OI meets it, and is equal to

$$\frac{\epsilon^3}{OP \cdot OM} \times \text{angular velocity of body} \quad . \quad . \quad . \quad (14)$$

When OI does not meet the quadric (13), but the conjugate quadric obtained by changing the sign of ϵ , the sense of the velocity (14) is reversed*.

126. The problem of the integration of the equations of motion of a solid in the general case has engaged the attention of several mathematicians, but, as might be anticipated from the complexity of the question, the physical meaning of the results is not easily grasped†.

In what follows we shall in the first place inquire what simplifications occur in the formula for the kinetic energy, for special classes of solids, and then proceed to investigate one or two particular problems of considerable interest which can be treated without difficult mathematics.

The general expression for the kinetic energy contains, as we have seen, twenty-one coefficients, but by the choice of special directions for the co-ordinate axes, and a special origin, these can be reduced to fifteen‡.

* The substance of this Art is taken from a paper, "On the Free Motion of a Solid through an Infinite Mass of Liquid," *Proc Lond Math Soc.*, t viii (1877). Similar results were obtained independently by Craig, "The Motion of a Solid in a Fluid," *Amer Journ of Math*, t xi (1879).

† For references see Wien, *Lehrbuch d Hydrodynamik*, Leipzig, 1900, p 164.

‡ Cf Clebsch, "Ueber die Bewegung eines Körpers in einer Flüssigkeit," *Math Ann*, t iii p 238 (1870). This paper deals with the 'reciprocal' form of the dynamical equations, obtained by substituting from Art 122 (4) in Art 120 (1).

The most symmetrical way of writing the general expression is

$$\begin{aligned}
 2T = & Au^2 + Bv^2 + Cw^2 + 2A'vw + 2B'wu + 2C'uv \\
 & + Pp^2 + Qq^2 + Rr^2 + 2P'qr + 2Q'rp + 2R'pq \\
 & + 2Lwp + 2Mvq + 2Nwr \\
 & + 2F(vr + wq) + 2G(wp + ur) + 2H(uq + vp) \\
 & + 2F'(vr - wq) + 2G'(wp - ur) + 2H'(uq - vp) \quad \dots \quad (1)
 \end{aligned}$$

It has been seen that we may choose the directions of the axes so that $A', B', C' = 0$, and it may easily be verified that by displacing the origin we can further make $F', G', H' = 0$. We shall henceforward suppose these simplifications to have been made

1° If the solid has a plane of symmetry, it is evident from the configuration of the relative stream-lines that a translation normal to this plane must be one of the permanent translations of Art 124. If we take this plane as that of xy , it is further evident that the energy of the motion must be unaltered if we reverse the signs of w, p, q . This requires that P', Q', L, M, N, H should vanish. The three screws of Art 125 are now pure rotations, but their axes do not in general intersect

2° If the body has a second plane of symmetry, at right angles to the former one, we may take this as the plane xz . We find that in this case R' and G must also vanish, so that

$$2T = Au^2 + Bv^2 + Cw^2 + Pp^2 + Qq^2 + Rr^2 + 2F(vr + wq) \quad \dots (2)$$

The axis of x is the axis of one of the permanent rotations, and those of the other two intersect it at right angles, though not necessarily in the same point

3° If the body has a third plane of symmetry, say that of yz , at right angles to the two former ones, we have

$$2T = Au^2 + Bv^2 + Cw^2 + Pp^2 + Qq^2 + Rr^2 \quad \dots \dots \dots (3)$$

4° Returning to (2°), we note that in the case of a solid of *revolution* about Ox , the expression for $2T$ must be unaltered when we write $v, q, -w, -r$ for w, r, v, q , respectively, since this is equivalent to rotating the axes of y, z through a right angle. Hence $B = C, Q = R, F = 0$, and therefore

$$2T = Au^2 + B(v^2 + w^2) + Pp^2 + Q(q^2 + r^2) \quad \dots \dots (4)$$

The same reduction obtains in some other cases, for example when the solid is a right prism whose section is any regular polygon*. This is seen at once from the consideration that, the axis of x coinciding with the axis of the prism, it is impossible to assign any uniquely symmetrical directions to the axes of y and z .

* See Larmor, "On Hydrokinetic Symmetry," *Quant Journ Math.*, t. xx (1885)

5° If, in the last case, the form of the solid be similarly related to each of the co-ordinate planes (for example a sphere, or a cube), the expression (3) takes the form

$$2T = A (u^2 + v^2 + w^2) + P (p^2 + q^2 + r^2) \quad . \quad . \quad (5)$$

This again may be extended, for a like reason, to other cases, for example any regular polyhedron. Such a body is practically for the present purpose 'isotropic,' and its motion will be exactly that of a sphere under similar conditions.

6° We may next consider another class of cases. Let us suppose that the body has a sort of skew symmetry about a certain axis (say that of x), viz that it is identical with itself turned through two right angles about this axis, but has not necessarily a plane of symmetry*. The expression for $2T$ must be unaltered when we change the signs of v , w , q , r , so that the coefficients Q' , R' , G , H must all vanish. We have then

$$2T = Au^2 + Bv^2 + Cw^2 + Pp^2 + Qq^2 + Rr^2 + 2P'qr \\ + 2Lup + 2Mvq + 2Nwr + 2F(vr + wq) \quad . \quad . \quad . \quad (6)$$

The axis of x is one of the directions of permanent translation; and is also the axis of one of the three screws of Art 125, the pitch being $-L/A$. The axes of the two remaining screws intersect it at right angles, but not in general in the same point.

7° If, further, the body be identical with itself turned through *one* right angle about the above axis, the expression (6) must be unaltered when v , q , $-w$, $-r$ are written for w , r , v , q , respectively. This requires that $B = C$, $Q = R$, $P' = 0$, $M = N$, $F = 0$. Hence†

$$2T = Au^2 + B(v^2 + w^2) + Pp^2 + Q(q^2 + r^2) + 2Lup + 2M(vq + wr). \quad . \quad . \quad (7)$$

The form of this expression is unaltered when the axes of y , z are turned in their own plane through any angle. The body is therefore said to possess helicoidal symmetry about the axis of x .

8°. If the body possess the same properties of skew symmetry about an axis intersecting the former one at right angles, we must evidently have

$$2T = A(u^2 + v^2 + w^2) + P(p^2 + q^2 + r^2) + 2L(pu + qv + rw) \quad . \quad . \quad (8)$$

Any direction is now one of permanent translation, and any line drawn through the origin is the axis of a screw of the kind considered in Art 125, of pitch $-L/A$. The form of (8) is unaltered by any change in the directions of the axes of co-ordinates. The solid is therefore in this case said to be 'helicoidally isotropic'.

* A two-bladed screw-propeller of a ship is an example of a body of this kind.

† This result admits of the same kind of generalization as (4), *e.g.* it applies to a body shaped like a screw-propeller with *three* symmetrically-disposed blades.

127 For the case of a solid of revolution, or of any other form to which the formula

$$2T = Aw^2 + B(v^2 + w^2) + Pp^2 + Q(q^2 + r^2) . \quad (1)$$

applies, the complete integration of the equations of motion was effected by Kirchhoff* in terms of elliptic functions

The particular case where the solid moves without rotation about its axis, and with this axis always in one plane, admits of very simple treatment†, and the results are very interesting

If the fixed plane in question be that of xy we have $p, q, w = 0$, so that the equations of motion, Art 124 (1), reduce to

$$\left. \begin{aligned} A \frac{du}{dt} &= rBv, & B \frac{dv}{dt} &= -rAu, \\ Q \frac{dr}{dt} &= (A - B)uv \end{aligned} \right\} \quad \dots (2)$$

Let \mathbf{x}, \mathbf{y} be the co-ordinates of the moving origin relative to fixed axes in the plane (xy) in which the axis of the solid moves, the axis of \mathbf{x} coinciding with the line of the resultant impulse (I , say) of the motion, and let θ be the angle which the line Ox (fixed in the solid) makes with \mathbf{x} . We have then

$$Au = I \cos \theta, \quad Bv = -I \sin \theta, \quad r = \theta$$

The first two of equations (2) merely express the fixity of the direction of the impulse in space, the third gives

$$Q\theta + \frac{A - B}{AB} I^2 \sin \theta \cos \theta = 0 \quad \dots (3)$$

We may suppose, without loss of generality, that $A > B$. If we write $2\theta = \mathfrak{S}$, (3) becomes

$$\mathfrak{S} + \frac{(A - B) I^2}{ABQ} \sin \mathfrak{S} = 0, \quad \dots (4)$$

which is the equation of motion of the common pendulum. Hence the angular motion of the body is that of a 'quadrantal pendulum,' i.e. a body whose motion follows the same law in regard to a quadrant as the ordinary pendulum does in regard to a half-circumference. When θ has been determined from (3) and the initial conditions, \mathbf{x}, \mathbf{y} are to be found from the equations

$$\left. \begin{aligned} \mathbf{x} &= u \cos \theta - v \sin \theta = \frac{I}{A} \cos^2 \theta + \frac{I}{B} \sin^2 \theta, \\ \mathbf{y} &= u \sin \theta + v \cos \theta = \left(\frac{I}{A} - \frac{I}{B} \right) \sin \theta \cos \theta = \frac{Q}{I} \theta, \end{aligned} \right\} \quad \dots (5)$$

* *loc. ante* p 150

† See Thomson and Tait, *Natural Philosophy*, Art 322; Greenhill, "On the Motion of a Cylinder through a Frictionless Liquid under no Forces," *Mess. of Math.*, t ix (1880)

the latter of which gives

$$y = \frac{Q}{I} \dot{\theta}, \quad \dots \dots \dots (6)$$

as is otherwise obvious, the additive constant being zero since the axis of \mathbf{x} is taken to be coincident with, and not merely parallel to, the line of the impulse I

Let us first suppose that the body makes complete revolutions, in which case the first integral of (3) is of the form

$$\dot{\theta}^2 = \omega^2 (1 - k^2 \sin^2 \theta), \quad \dots \dots \dots (7)$$

where

$$k^2 = \frac{A - B}{ABQ} \frac{I^2}{\omega^2} \quad \dots \dots \dots (8)$$

Hence, reckoning t from the position $\theta = 0$, we have

$$\omega t = \int_0^\theta \frac{d\theta}{(1 - k^2 \sin^2 \theta)^{\frac{1}{2}}} = F(k, \theta), \quad \dots \dots \dots (9)$$

in the usual notation of elliptic integrals. If we eliminate t between (5) and (7), and then integrate with respect to θ , we find

$$\left. \begin{aligned} \mathbf{x} &= \left(\frac{I}{AB\omega} + \frac{Q\omega}{I} \right) F(k, \theta) - \frac{Q\omega}{I} E(k, \theta), \\ y &= \frac{Q}{I} \dot{\theta} = \frac{Q\omega}{I} (1 - k^2 \sin^2 \theta)^{\frac{1}{2}}, \end{aligned} \right\} \quad \dots \dots \dots (10)$$

the origin of \mathbf{x} being taken to correspond to the position $\theta = 0$. The path can then be traced, in any particular case, by means of Legendre's Tables. See the curve marked I on the next page

If, on the other hand, the solid does not make a complete revolution, but oscillates through an angle α on each side of the position $\theta = 0$, the proper form of the first integral of (3) is

$$\dot{\theta}^2 = \omega^2 \left(1 - \frac{\sin^2 \theta}{\sin^2 \alpha} \right), \quad \dots \dots \dots (11)$$

where

$$\sin^2 \alpha = \frac{ABQ}{A - B} \frac{\omega^2}{I^2} \quad \dots \dots \dots (12)$$

If we put

$$\sin \theta = \sin \alpha \sin \psi,$$

this gives

$$\dot{\psi}^2 = \frac{\omega^2}{\sin^2 \alpha} (1 - \sin^2 \alpha \sin^2 \psi),$$


whence

$$\frac{\omega t}{\sin \alpha} = F(\sin \alpha, \psi) \quad \dots \dots \dots (13)$$

Transforming to ψ as independent variable, in (5), and integrating, we find

$$\left. \begin{aligned} \mathbf{x} &= \frac{I}{B\omega} \sin \alpha \cdot F(\sin \alpha, \psi) - \frac{Q\omega}{I} \operatorname{cosec} \alpha \cdot E(\sin \alpha, \psi), \\ y &= \frac{Q\omega}{I} \cos \psi. \end{aligned} \right\} \quad \dots \dots \dots (14)$$

The path of the point O is now a sinuous curve crossing the line of the impulse at intervals of time equal to a half-period of the angular motion. This is illustrated by the curves III and IV of the figure



There remains a critical case between the two preceding, where the solid just makes a half-revolution, θ having as asymptotic limits the two values

$\pm \frac{1}{2}\pi$. This case may be obtained by putting $k=1$ in (7), or $\alpha = \frac{1}{2}\pi$ in (11), and we find

$$\dot{\theta} = \omega \cos \theta, \quad \dots \dots \dots (15)$$

$$\omega t = \log \tan (\tfrac{1}{4}\pi + \tfrac{1}{2}\theta), \quad \dots \dots \dots (16)$$

$$\left. \begin{aligned} x &= \frac{I}{B\omega} \log \tan (\tfrac{1}{4}\pi + \tfrac{1}{2}\theta) - \frac{Q\omega}{I} \sin \theta, \\ y &= \frac{Q\omega}{I} \cos \theta \end{aligned} \right\} \dots \dots (17)$$

See the curve II of the figure*

It is to be observed that the above investigation is not restricted to the case of a solid of revolution, it applies equally well to a body with two perpendicular planes of symmetry, moving parallel to one of these planes, provided the origin be properly chosen. If the plane in question be that of xy , then on transferring the origin to the point $(F/B, 0, 0)$ the last term in the formula (2) of Art. 126 disappears, and the equations of motion take the form (2) above. On the other hand, if the motion be parallel to zx we must transfer the origin to the point $(-F/C, 0, 0)$.

The results of this Article, with the accompanying diagrams, serve to exemplify the statements made near the end of Art. 124. Thus the curve IV illustrates, with exaggerated amplitude, the case of a slightly disturbed *stable* steady motion parallel to an axis of permanent translation. The case of a slightly disturbed *unstable* steady motion would be represented by a curve contiguous to II, on one side or the other, according to the nature of the disturbance.

128. The mere question of the stability of the motion of a body parallel to an axis of symmetry may of course be more simply treated by approximate methods. Thus, in the case of a body with three planes of symmetry, as in Art. 126, 3°, slightly disturbed from a state of steady motion parallel to x , we find, writing $u = u_0 + u'$, and assuming u', v, w, p, q, r to be all small,

$$\left. \begin{aligned} A \frac{du'}{dt} &= 0, & B \frac{dv}{dt} &= -A u_0 r, & C \frac{dw}{dt} &= A u_0 q, \\ I \frac{dp}{dt} &= 0, & Q \frac{dq}{dt} &= (C - A) u_0 v, & R \frac{dr}{dt} &= (A - B) u_0 v \end{aligned} \right\} \dots \dots (1)$$

* In order to bring out the peculiar features of the motion, the curves have been drawn for the somewhat extreme case of $A=5B$. In the case of an infinitely thin disk, without inertia of its own, we should have $A/B=\infty$, the curves would then have *cusps* where they meet the axis of y . It appears from (5) that x has always the same sign, so that *loops* cannot occur in any case.

In the various cases figured the body is projected always with the same impulse, but with different degrees of rotation. In the curve I, the maximum angular velocity is $\sqrt{2}$ times what it is in the critical case II, whilst the curves III and IV represent oscillations of amplitude 45° and 18° respectively.

The conditions to be satisfied in this case are most easily obtained from the equations of motion of Art 124, which become, on substitution from Art 126 (4),

$$\left. \begin{aligned} A \frac{du}{dt} &= B(rv - qw), & P \frac{dp}{dt} &= 0, \\ B \frac{dv}{dt} &= Bpw - Aru, & Q \frac{dq}{dt} &= -(A-B)uv - (P-Q)pr, \\ B \frac{dw}{dt} &= AQu - Bpv, & Q \frac{dr}{dt} &= (A-B)uv + (P-Q)pq \end{aligned} \right\} \quad (1)$$

It appears that p is in any case constant, and that $q^2 + r^2$ will also be constant provided

$$v/q = w/r, \quad = k, \text{ say} \quad (2)$$

This makes $du/dt = 0$, and $v^2 + w^2 = \text{const}$. It follows that k will also be constant; and it only remains to satisfy the equations

$$kB \frac{dq}{dt} = (kBp - Au), \quad Q \frac{dr}{dt} = \{(A-B)ku + (P-Q)p\}r$$

These will be consistent provided

$$kB \{(A-B)ku + (P-Q)p\} + Q(kBp - Au) = 0,$$

whence

$$\frac{u}{p} = \frac{kBP}{AQ - k^2B(A-B)}. \quad (3)$$

Hence by variation of k we obtain an infinite number of possible modes of steady motion, of the kind above defined. In each of these the instantaneous axis of rotation and the direction of translation of the origin are in one plane with the axis of the solid. It is easily seen that the origin describes a helix about the line of the impulse.

These results are due to Kirchhoff.

130 The only case of a body possessing *helical* property, where simple results can be obtained, is that of the 'isotropic helicoid' defined by Art 126 (8). Let O be the centre of the body, and let us take as axes of co-ordinates at any instant a line Ox parallel to the axis of the impulse, a line Oy drawn outwards from this axis, and a line Oz perpendicular to the plane of the two former. If I and K denote the force- and couple-constituents of the impulse, we have

$$\left. \begin{aligned} Au + Lp &= \xi = I, & Av + Lq &= \eta = 0, & Aw + Lr &= \zeta = 0, \\ Pp + Lu &= \lambda = K, & Pq + Lv &= \mu = 0, & Pr + Lw &= \nu = I\varpi, \end{aligned} \right\} \quad \dots (1)$$

where ϖ denotes the distance of O from the axis of the impulse.

Since $AP - L^2 \neq 0$, the second and fifth of these equations shew that $v = 0$, $q = 0$. Hence ϖ is constant throughout the motion, and the remaining quantities are also constant; in particular

$$u = \frac{PI - LK}{AP - L^2}, \quad w = -\frac{LI\varpi}{AP - L^2}. \quad \dots (2)$$

The origin O therefore describes a helix about the axis of the impulse, of pitch

$$\frac{K}{I} - \frac{P}{L}.$$

This example is due to Lord Kelvin*.

131 Before leaving this part of the subject we remark that the preceding theory applies, with obvious modifications, to the acyclic motion of a liquid occupying a cavity in a moving solid. If the origin be taken at the centre of inertia of the liquid, the formula for the kinetic energy of the fluid motion is of the type

$$2\mathbf{T} = \mathbf{m}(u^2 + v^2 + w^2) + \mathbf{P}p^2 + \mathbf{Q}q^2 + \mathbf{R}r^2 + 2\mathbf{P}'qp + 2\mathbf{Q}'rp + 2\mathbf{R}'pq \quad (1)$$

For the kinetic energy is equal to that of the whole fluid mass (\mathbf{m}), supposed concentrated at its centre of inertia and moving with this point, together with the kinetic energy of the motion relative to the centre of inertia. The latter part of the energy is easily proved by the method of Arts. 118, 121 to be a homogeneous quadratic function of p, q, r .

Hence the fluid may be replaced by a solid of the same mass, having the same centre of inertia, provided the principal axes and moments of inertia be properly assigned.

The values of the coefficients in (1), for the case of an ellipsoidal cavity, may be calculated from Art. 110. Thus, if the axes of x, y, z coincide with the principal axes of the ellipsoid, we find

$$\mathbf{P}, \mathbf{Q}, \mathbf{R} = \frac{1}{2}\mathbf{m} \frac{(b^2 - c^2)^2}{b^2 + c^2}, \quad \frac{1}{2}\mathbf{m} \frac{(c^2 - a^2)^2}{c^2 + a^2}, \quad \frac{1}{2}\mathbf{m} \frac{(a^2 - b^2)^2}{a^2 + b^2}, \quad \mathbf{P}', \mathbf{Q}', \mathbf{R}' = 0$$

Case of a Perforated Solid

132 If the moving solid have one or more apertures or perforations, so that the space external to it is multiply-connected, the fluid may have a motion independent of that of the solid, viz a cyclic motion in which the circulations in the several irreducible circuits which can be drawn through the apertures may have any given constant values. We will briefly indicate how the foregoing methods may be adapted to this case.

* *l.c. ante* p. 157. It is there pointed out that a solid of the kind here in question may be constructed by attaching vanes to a sphere, at the middle points of twelve quadrantal arcs drawn so as to divide the surface into octants. The vanes are to be perpendicular to the surface, and are to be inclined at angles of 45° to the respective arcs. Prof. Larmor (*l.c. ante* p. 162) gives another example. "If we take a regular tetrahedron (or other regular solid), and replace the edges by skew bevel faces placed in such wise that when looked at from any corner they all slope the same way, we have an example of an isotropic helicoid."

For some further investigations in the present connection see a paper by Miss Fawcett, "On the Motion of Solids in a Liquid," *Quart. Journ. Math.*, t. xxvi (1893).

Let $\kappa, \kappa', \kappa'', \dots$ be the circulations in the various circuits, and let $\delta\sigma, \delta\sigma', \delta\sigma'', \dots$ be elements of the corresponding barriers, drawn as in Art 48. Further, let l, m, n denote the direction-cosines of the normal, drawn towards the fluid at any point of the surface of the solid, or drawn on the positive side at any point of a barrier. The velocity-potential is then of the form

$$\phi + \phi_0,$$

$$\left. \begin{aligned} \phi &= u\phi_1 + v\phi_2 + w\phi_3 + p\chi_1 + q\chi_2 + r\chi_3, \\ \phi_0 &= \kappa\omega + \kappa'\omega' + \kappa''\omega'' + \dots \end{aligned} \right\} \dots \quad (1)$$

The functions $\phi_1, \phi_2, \phi_3, \chi_1, \chi_2, \chi_3$ are determined by the same conditions as in Art 118. To determine ω , we have the conditions (1°) that it must satisfy $\nabla^2\omega = 0$ at all points of the fluid, (2°) that its derivatives must vanish at infinity, (3°) that $\partial\omega/\partial n$ must = 0 at the surface of the solid, and (4°) that ω must be a cyclic function, diminishing by unity whenever the point to which it refers completes a circuit cutting the first barrier once (only) in the positive direction, and recovering its original value whenever the point completes a circuit not cutting this barrier. It appears from Art 52 that these conditions determine ω save as to an additive constant. In like manner the remaining functions ω', ω'', \dots are determined.

By the formula (5) of Art 55, twice the kinetic energy of the fluid is equal to

$$\begin{aligned} & -\rho \iint (\phi + \phi_0) \frac{\partial}{\partial n} (\phi + \phi_0) dS \\ & - \rho \kappa \iint \frac{\partial}{\partial n} (\phi + \phi_0) d\sigma - \rho \kappa' \iint \frac{\partial}{\partial n} (\phi + \phi_0) d\sigma' - \dots \quad \dots \quad (2) \end{aligned}$$

Since the cyclic constants of ϕ are zero, and since $\partial\phi_0/\partial n$ vanishes at the surface of the solid, we have, by Art 54 (4),

$$\iint \phi_0 \frac{\partial \phi}{\partial n} dS + \kappa \iint \frac{\partial \phi}{\partial n} d\sigma + \kappa' \iint \frac{\partial \phi}{\partial n} d\sigma' + \dots = \iint \phi \frac{\partial \phi_0}{\partial n} dS = 0$$

Hence (2) reduces to

$$-\rho \iint \phi \frac{\partial \phi}{\partial n} dS - \rho \kappa \iint \frac{\partial \phi_0}{\partial n} d\sigma - \rho \kappa' \iint \frac{\partial \phi_0}{\partial n} d\sigma' - \dots \quad \dots \quad (3)$$

Substituting the values of ϕ, ϕ_0 from (1) we find that the kinetic energy of the fluid is equal to

$$\mathbf{T} + K, \quad \dots \dots \dots \quad (4)$$

where \mathbf{T} is a homogeneous quadratic function of u, v, w, p, q, r , of the form defined by Art 121 (2) (3), and

$$2K = (\kappa, \kappa) \kappa^2 + (\kappa', \kappa') \kappa'^2 + \dots + 2(\kappa, \kappa') \kappa \kappa' + \dots \quad (5)$$

where, for example,

$$\left. \begin{aligned} (\kappa, \kappa) &= -\rho \iint \frac{\partial \omega}{\partial n} d\sigma, \\ (\kappa, \kappa') &= -\frac{1}{2}\rho \iint \frac{\partial \omega'}{\partial n} d\sigma - \frac{1}{2}\rho \iint \frac{\partial \omega}{\partial n} d\sigma' \\ &= -\rho \iint \frac{\partial \omega'}{\partial n} d\sigma = -\rho \iint \frac{\partial \omega}{\partial n} d\sigma' \end{aligned} \right\} \dots \dots (6)$$

The identity of the different forms of (κ, κ') follows from Art. 54 (4).

Hence the total energy of fluid and solid is given by

$$T = \mathfrak{T} + K, \dots \dots (7)$$

where \mathfrak{T} is a homogeneous quadratic function of u, v, w, p, q, r of the same form as Art 121 (8), and K is defined by (5) and (6) above.

133 The 'impulse' of the motion now consists partly of impulsive forces applied to the solid, and partly of impulsive pressures $\rho\kappa, \rho\kappa', \rho\kappa'', \dots$ applied uniformly (as explained in Art. 54) over the several membranes which are supposed for a moment to occupy the positions of the barriers. Let us denote by $\xi_1, \eta_1, \zeta_1, \lambda_1, \mu_1, \nu_1$ the components of the extraneous impulse applied to the solid. Expressing that the x -component of the momentum of the solid is equal to the similar component of the total impulse acting on it, we have

$$\begin{aligned} \frac{\partial \mathbf{T}_1}{\partial u} &= \xi_1 - \rho \iint (\phi + \phi_0) l dS \\ &= \xi_1 + \rho \iint (u\phi_1 + \dots + p\chi_1 + \dots + \kappa\omega + \dots) \frac{\partial \phi_1}{\partial n} dS \\ &= \xi_1 - \frac{\partial \mathbf{T}}{\partial u} + \rho\kappa \iint \omega \frac{\partial \phi_1}{\partial n} dS + \rho\kappa' \iint \omega' \frac{\partial \phi_1}{\partial n} dS + \dots, \dots (1) \end{aligned}$$

where, as before, \mathbf{T}_1 denotes the kinetic energy of the solid, and \mathbf{T} that part of the energy of the fluid which is independent of the cyclic motion. Again, considering the angular momentum of the solid about the axis of x ,

$$\begin{aligned} \frac{\partial \mathbf{T}_1}{\partial p} &= \lambda_1 - \rho \iint (\phi + \phi_0) (ny - mz) dS \\ &= \lambda_1 + \rho \iint (u\phi_1 + \dots + p\chi_1 + \dots + \kappa\omega + \dots) \frac{\partial \chi_1}{\partial n} dS \\ &= \lambda_1 - \frac{\partial \mathbf{T}}{\partial p} + \rho\kappa \iint \omega \frac{\partial \chi_1}{\partial n} dS + \rho\kappa' \iint \omega' \frac{\partial \chi_1}{\partial n} dS + \dots (2) \end{aligned}$$

Hence, since $\mathcal{T} = \mathbf{T} + \mathbf{T}_1$, we have

$$\left. \begin{aligned} \xi_1 &= \frac{\partial \mathcal{T}}{\partial u} - \rho\kappa \iint \omega \frac{\partial \phi_1}{\partial n} dS - \rho\kappa' \iint \omega' \frac{\partial \phi_1}{\partial n} dS - \dots, \\ \lambda_1 &= \frac{\partial \mathcal{T}}{\partial p} - \rho\kappa \iint \omega \frac{\partial \chi_1}{\partial n} dS - \rho\kappa' \iint \omega' \frac{\partial \chi_1}{\partial n} dS - \dots \end{aligned} \right\} \quad (3)$$

By virtue of Lord Kelvin's extension of Green's theorem, already referred to, these may be written in the alternative forms

$$\left. \begin{aligned} \xi_1 &= \frac{\partial \mathcal{T}}{\partial u} + \rho\kappa \iint \frac{\partial \phi_1}{\partial n} d\sigma + \rho\kappa' \iint \frac{\partial \phi_1}{\partial n} d\sigma' + \dots, \\ \lambda_1 &= \frac{\partial \mathcal{T}}{\partial p} + \rho\kappa \iint \frac{\partial \chi_1}{\partial n} d\sigma + \rho\kappa' \iint \frac{\partial \chi_1}{\partial n} d\sigma' + \dots \end{aligned} \right\} \quad \dots (4)$$

Adding to these the terms due to the impulsive pressures applied to the barriers, we have, finally, for the components of the total impulse of the motion*,

$$\left. \begin{aligned} \xi, \eta, \zeta &= \frac{\partial \mathcal{T}}{\partial u} + \xi_0, \quad \frac{\partial \mathcal{T}}{\partial v} + \eta_0, \quad \frac{\partial \mathcal{T}}{\partial w} + \zeta_0, \\ \lambda, \mu, \nu &= \frac{\partial \mathcal{T}}{\partial p} + \lambda_0, \quad \frac{\partial \mathcal{T}}{\partial q} + \mu_0, \quad \frac{\partial \mathcal{T}}{\partial r} + \nu_0, \end{aligned} \right\} \quad \dots \dots \dots (5)$$

where, for example,

$$\left. \begin{aligned} \xi_0 &= \rho\kappa \iint \left(l + \frac{\partial \phi_1}{\partial n} \right) d\sigma + \rho\kappa' \iint \left(l + \frac{\partial \phi_1}{\partial n} \right) d\sigma' + \dots, \\ \lambda_0 &= \rho\kappa \iint \left(ny - mz + \frac{\partial \chi_1}{\partial n} \right) d\sigma + \rho\kappa' \iint \left(ny - mz + \frac{\partial \chi_1}{\partial n} \right) d\sigma' + \dots \end{aligned} \right\} \dots (6)$$

It is evident that the constants $\xi_0, \eta_0, \zeta_0, \lambda_0, \mu_0, \nu_0$ are the components of the impulse of the cyclic fluid motion which would remain if the solid were, by forces applied to it alone, brought to rest

By the argument of Art 119, the total impulse is subject to the same laws as the momentum of a finite dynamical system. Hence the equations of motion of the solid are obtained by substituting from (5) in the equations (1) of Art 120†

134 As a simple example we may take the case of an annular solid of revolution. If the axis of x coincide with that of the ring, we see by reasoning of the same kind as in Art. 126, 4° that if the situation of the origin on this axis be properly chosen we may write

$$2T = Au^2 + B(v^2 + w^2) + Pp^2 + Q(q^2 + r^2) + (\kappa, \kappa) \kappa^2. \quad \dots (1)$$

$$\text{Hence} \quad \xi, \eta, \zeta = Au + \xi_0, \quad Bv, \quad Bw, \quad \lambda, \mu, \nu = Pp, \quad Qq, \quad Qr \quad \dots (2)$$

* Cf Sir W Thomson, *loc. ante* p 157

† This conclusion may be verified by direct calculation from the pressure-formula of Art 20, see Bryan, "Hydrodynamical Proof of the Equations of Motion of a Perforated Solid," *Phil Mag*, May, 1893

Substituting in the equations of Art 120, we find $dp/dt=0$, or $p=\text{const}$, as is otherwise obvious. Let us suppose that the ring is slightly disturbed from a state of motion in which v, w, p, q, r , are zero, *i.e.* a steady motion parallel to the axis. In the beginning of the disturbed motion v, w, p, q, r will be small quantities whose products we may neglect. The first of the equations referred to then gives $du/dt=0$, or $u=\text{const}$, and the remaining equations become

$$\left. \begin{aligned} B \frac{dv}{dt} &= -(Au + \xi_0) r, & Q \frac{dq}{dt} &= -\{(A-B)u + \xi_0\} w, \\ B \frac{dw}{dt} &= (Au + \xi_0) q, & Q \frac{dr}{dt} &= \{(A-B)u + \xi_0\} v \end{aligned} \right\} \quad (3)$$

Eliminating r , we find

$$BQ \frac{d^2v}{dt^2} = -(Au + \xi_0) \{(A-B)u + \xi_0\} v \quad \dots \dots \dots (4)$$

Exactly the same equation is satisfied by w . It is therefore necessary and sufficient for stability that the coefficient of v on the right-hand side of (4) should be negative, and the time of a small oscillation, when this condition is satisfied, is*

$$2\pi \left[\frac{BQ}{(Au + \xi_0) \{(A-B)u + \xi_0\}} \right]^{\frac{1}{2}} \quad \dots \dots (5)$$

We may also notice another case of steady motion of the ring, *viz.* where the impulse reduces to a couple about a diameter. It is easily seen that the equations of motion are satisfied by $\xi, \eta, \zeta, \lambda, \mu=0$, and ν constant, in which case

$$u = -\xi_0/A, \quad r = \text{const}$$

The ring then rotates about an axis in the plane yz parallel to that of z , at a distance u/r from it†

Equation of Motion in Generalized Co-ordinates

135 When we have more than one moving solid, or when the fluid is bounded, wholly or in part, by fixed walls, we may have recourse to Lagrange's method of 'generalized co-ordinates'. This was first applied to hydrodynamical problems by Thomson and Tait‡

In any dynamical system whatever, if ξ, η, ζ are the Cartesian co-ordinates at time t of any particle m , and X, Y, Z the components of the total force acting on it, we have of course

$$m\ddot{\xi} = X, \quad m\ddot{\eta} = Y, \quad m\ddot{\zeta} = Z \quad \dots \dots \dots (1)$$

* Sir W. Thomson, *l.c. ante* p. 157.

† For further investigations on this subject we refer to papers by Basset, "On the Motion of a Ring in an Infinite Liquid," *Proc. Camb. Phil. Soc.*, t. vi (1887), and Miss Fawcett, *l.c. ante* p. 170.

‡ *Natural Philosophy* (1st ed.), Oxford, 1867, Art. 331.

Now let $\xi + \Delta\xi$, $\eta + \Delta\eta$, $\zeta + \Delta\zeta$ be the co-ordinates of the same particle, at time t , in any arbitrary motion of the system differing infinitely little from the actual motion, and let us form the equation

$$\Sigma m (\xi \Delta\xi + \eta \Delta\eta + \zeta \Delta\zeta) = \Sigma (X \Delta\xi + Y \Delta\eta + Z \Delta\zeta), \quad (2)$$

where the summation Σ embraces all the particles of the system. This follows at once from the equations (1), and includes these, on account of the arbitrary character of the variations $\Delta\xi$, $\Delta\eta$, $\Delta\zeta$. Its chief advantages, however, consist in the extensive elimination of internal forces which, by imposing suitable restrictions on the values of $\Delta\xi$, $\Delta\eta$, $\Delta\zeta$ we are able to effect, and in the facilities which it affords for transformation of co-ordinates. It is to be noticed that

$$\frac{d}{dt} \Delta\xi = \frac{d}{dt} (\xi + \Delta\xi) - \frac{d\xi}{dt} = \Delta\dot{\xi}, \text{ \&c, \&c,}$$

so that the symbols d and Δ are commutative

The systems ordinarily contemplated in Analytical Dynamics are of finite freedom, *i.e.* the position of every particle is completely determined when we know the values of a finite number of independent variables or 'generalized co-ordinates' q_1, q_2, \dots, q_n , so that, for example,

$$\left. \begin{aligned} \dot{\xi} &= \frac{\partial \xi}{\partial q_1} q_1 + \frac{\partial \xi}{\partial q_2} q_2 + \dots + \frac{\partial \xi}{\partial q_n} q_n, \\ \Delta\xi &= \frac{\partial \xi}{\partial q_1} \Delta q_1 + \frac{\partial \xi}{\partial q_2} \Delta q_2 + \dots + \frac{\partial \xi}{\partial q_n} \Delta q_n. \end{aligned} \right\} \dots \dots (3)$$

The kinetic energy can then be expressed as a homogeneous quadratic function of the 'generalized velocity-components' q_1, q_2, \dots, q_n , thus

$$2T = A_{11}q_1^2 + A_{22}q_2^2 + \dots + 2A_{12}q_1q_2 + \dots \dots (4)$$

where

$$A_{rs} = \Sigma m \left\{ \left(\frac{\partial \xi}{\partial q_r} \right)^2 + \left(\frac{\partial \eta}{\partial q_r} \right)^2 + \left(\frac{\partial \zeta}{\partial q_r} \right)^2 \right\}, \quad A_{rs} = \Sigma m \left\{ \frac{\partial \xi}{\partial q_r} \frac{\partial \xi}{\partial q_s} + \frac{\partial \eta}{\partial q_r} \frac{\partial \eta}{\partial q_s} + \frac{\partial \zeta}{\partial q_r} \frac{\partial \zeta}{\partial q_s} \right\} \dots \dots (5)$$

The quantities A_{11}, A_{22}, \dots are called the 'inertia-coefficients' of the system, they are in general functions of the co-ordinates q_1, q_2, \dots, q_n

Again, we have

$$\Sigma (X \Delta\xi + Y \Delta\eta + Z \Delta\zeta) = Q_1 \Delta q_1 + Q_2 \Delta q_2 + \dots + Q_n \Delta q_n, \quad (6)$$

where

$$Q_r = \Sigma \left(X \frac{\partial \xi}{\partial q_r} + Y \frac{\partial \eta}{\partial q_r} + Z \frac{\partial \zeta}{\partial q_r} \right). \quad (7)$$

The quantities Q_r are called the 'generalized components of force'. In the case of a conservative system we have

$$Q_r = - \frac{\partial V}{\partial q_r} \quad \dots \dots \dots (8)$$

Also, from (3) and (5),

$$\begin{aligned}\Sigma m (\dot{\xi}\Delta\xi + \eta\Delta\eta + \dot{\zeta}\Delta\zeta) &= (A_{11}q_1 + A_{12}q_2 + \dots + A_{1n}q_n) \Delta q_1 \\ &\quad + (A_{21}q_1 + A_{22}q_2 + \dots + A_{2n}q_n) \Delta q_2 \\ &\quad + \dots \\ &\quad + (A_{n1}q_1 + A_{n2}q_2 + \dots + A_{nn}q_n) \Delta q_n \\ &= \frac{\partial T}{\partial q_1} \Delta q_1 + \frac{\partial T}{\partial q_2} \Delta q_2 + \dots + \frac{\partial T}{\partial q_n} \Delta q_n, \quad (9)\end{aligned}$$

$$\text{or} \quad \Sigma m (\dot{\xi}\Delta\xi + \eta\Delta\eta + \dot{\zeta}\Delta\zeta) = p_1\Delta q_1 + p_2\Delta q_2 + \dots + p_n\Delta q_n, \quad (10)$$

$$\text{where} \quad p_r = \frac{\partial T}{\partial q_r} \quad \dots \quad \dots \quad (11)$$

The quantities p_r are called the 'generalized components of momentum' of the system. When T is expressed as in (4) as a homogeneous quadratic function of q_1, q_2, \dots, q_n , we have

$$2T = p_1q_1 + p_2q_2 + \dots + p_nq_n \quad (12)$$

$$\text{Since} \quad \Sigma m (\dot{\xi}\Delta\xi + \eta\Delta\eta + \dot{\zeta}\Delta\zeta) = \frac{d}{dt} \Sigma m (\xi\Delta\xi + \eta\Delta\eta + \zeta\Delta\zeta) - \Delta T, \quad (13)$$

the transformation of (2) to generalized co-ordinates is easily completed by substitution from (9) and (6). The variations Δq_r of the *velocities* cancel, and, equating coefficients of the independent variations Δq_r of the co-ordinates, we obtain n equations of the type*

$$\frac{d}{dt} \frac{\partial T}{\partial q_r} - \frac{\partial T}{\partial q_r} = Q_r, \quad \dots \quad \dots \quad (14)$$

From (12) and (14) we derive

$$\begin{aligned}2 \frac{dT}{dt} &= p_1\dot{q}_1 + p_1\dot{q}_1 + p_2\dot{q}_2 + p_2\dot{q}_2 + \dots + p_n\dot{q}_n + p_n\dot{q}_n \\ &= \left(\frac{\partial T}{\partial q_1} + Q_1 \right) q_1 + \left(\frac{\partial T}{\partial q_2} + Q_2 \right) q_2 + \dots + \left(\frac{\partial T}{\partial q_n} + Q_n \right) q_n \\ &\quad + \frac{\partial T}{\partial q_1} q_1 + \frac{\partial T}{\partial q_2} q_2 + \dots + \frac{\partial T}{\partial q_n} q_n \\ &= \frac{dT}{dt} + Q_1q_1 + Q_2q_2 + \dots + Q_nq_n,\end{aligned}$$

$$\text{whence} \quad \frac{dT}{dt} = Q_1q_1 + Q_2q_2 + \dots + Q_nq_n \quad (15)$$

or, in the case of a conservative system

$$\frac{d}{dt} (T + V) = 0, \quad (16)$$

which is the equation of energy

* This summary of Lagrange's proof is introduced merely to facilitate reference to the various steps, in the hydrodynamical investigation of the next Art. A proof by direct transformation of co-ordinates, not involving the method of 'variations,' has been given by Hamilton (*Phil Trans*, 1835, p. 96), Jacobi, Bertrand, and Thomson and Tait, see also Whittaker, *Analytical Dynamics*, Cambridge, 1904, p. 33.

If we multiply (2) by δt , and integrate between the limits t_0 and t_1 , we find, having regard to (13),

$$\int_{t_0}^{t_1} \{\Delta T + \Sigma (X\Delta\xi + Y\Delta\eta + Z\Delta\zeta)\} dt = \left[\Sigma m (\dot{\xi}\Delta\xi + \dot{\eta}\Delta\eta + \dot{\zeta}\Delta\zeta) \right]_{t_0}^{t_1}. \quad (17)$$

If we now introduce the additional condition that in the varied motion the initial and final positions shall be respectively the same for each particle as in the actual motion, the quantities $\Delta\xi$, $\Delta\eta$, $\Delta\zeta$ will vanish at both limits, and the equation reduces to

$$\int_{t_0}^{t_1} \{\Delta T + \Sigma (X\Delta\xi + Y\Delta\eta + Z\Delta\zeta)\} dt = 0, \quad \dots \quad (18)$$

or, for a conservative system*,

$$\Delta \int_{t_0}^{t_1} (T - V) dt = 0. \quad \dots \quad (19)$$

In words, if the actual motion of the system between any two configurations through which it passes be compared with *any* slightly varied motion, between the same configurations, which the system is (by the application of suitable forces) made to execute *in the same time*, the time-integral of the 'kinetic potential'† $V - T$ is stationary

In terms of generalized co-ordinates, the equation (18) takes the form

$$\int_{t_0}^{t_1} (\Delta T + Q_1\Delta q_1 + Q_2\Delta q_2 + \dots + Q_n\Delta q_n) dt = 0 \quad \dots \quad (20)$$

This embraces the whole dynamics of the system in a mathematically compact form. From it Lagrange's equations can immediately be deduced; cf. Art 139.

136 Proceeding now to the hydrodynamical problem, let q_1, q_2, \dots, q_n be a system of generalized co-ordinates which serve to specify the configuration of the solids. We will suppose, for the present, that the motion of the fluid is entirely due to that of the solids, and is therefore irrotational and acyclic.

In this case the velocity-potential at any instant will be of the form

$$\phi = q_1\phi_1 + q_2\phi_2 + \dots + q_n\phi_n, \quad \dots \quad (1)$$

where ϕ_1, ϕ_2, \dots are determined in a manner analogous to that of Art 118. The formula for the kinetic energy of the fluid is then

$$2\mathbf{T} = -\rho \iint \phi \frac{\partial \phi}{\partial n} dS = \mathbf{A}_{11}q_1^2 + \mathbf{A}_{22}q_2^2 + \dots + 2\mathbf{A}_{12}q_1q_2 + \dots \quad (2)$$

* See W. R. Hamilton, "On a General Method in Dynamics," *Phil. Trans.*, 1834, 1835.

† The name was introduced by v. Helmholtz, "Die physikalische Bedeutung des Principes der kleinsten Wirkung," *Crelle*, t. c. p. 137 (1886) [*Ges. Abh.* t. iii. p. 203]. Whittaker, *Analytical Dynamics*, p. 38, reverses the sign.

where

$$\mathbf{A}_{rr} = -\rho \iint \phi_r \frac{\partial \phi_r}{\partial n} dS, \quad \mathbf{A}_{rs} = -\rho \iint \phi_r \frac{\partial \phi_s}{\partial n} dS = -\rho \iint \phi_s \frac{\partial \phi_r}{\partial n} dS, \quad (3)$$

the integrations extending over the instantaneous positions of the bounding surfaces of the fluid. The identity of the two forms of \mathbf{A}_{rs} follows from Green's Theorem. The coefficients \mathbf{A}_{rr} , \mathbf{A}_{rs} will in general be functions of the co-ordinates q_1, q_2, \dots, q_n .

If we add to (2) twice the kinetic energy, \mathbf{T}_1 , of the solids themselves, we get an expression of the same form, with altered coefficients, say

$$2T = A_{11}q_1^2 + A_{22}q_2^2 + \dots + 2A_{12}q_1q_2 + \dots \dots \dots (4)$$

It remains to shew that, although our system is one of infinite freedom, the equations of motion of the solids can, under the circumstances presupposed, be obtained by substituting this value of T in the Lagrangian equations, Art 135 (14). We are not at liberty to assume this without further examination, for the positions of the various particles of the fluid are *not* determined by the instantaneous values q_1, q_2, \dots, q_n of the co-ordinates of the solids. For instance, if the solids, after performing various evolutions, return each to its original position, the individual particles of the fluid will in general be found to be finitely displaced*.

Going back to the general formula (2) of Art 135, let us suppose that in the varied motion, to which the symbol Δ refers, the solids undergo no change of size or shape, and that the fluid remains incompressible, and has, at the boundaries, the same displacement in the direction of the normal as the solids with which it is in contact. It is known that under these conditions the terms due to the internal reactions of the solids will disappear from the sum

$$\Sigma (X\Delta\xi + Y\Delta\eta + Z\Delta\zeta)$$

The terms due to the mutual pressures of the fluid elements are equivalent to

$$- \iiint \left(\frac{\partial p}{\partial x} \Delta\xi + \frac{\partial p}{\partial y} \Delta\eta + \frac{\partial p}{\partial z} \Delta\zeta \right) dx dy dz,$$

or
$$\iint p (l\Delta\xi + m\Delta\eta + n\Delta\zeta) dS + \iiint p \left(\frac{\partial \Delta\xi}{\partial x} + \frac{\partial \Delta\eta}{\partial y} + \frac{\partial \Delta\zeta}{\partial z} \right) dx dy dz,$$

where the former integral extends over the bounding surfaces, and l, m, n denote the direction-cosines of the normal, drawn towards the fluid. The volume-integral vanishes by the condition of incompressibility

$$\frac{\partial \Delta\xi}{\partial x} + \frac{\partial \Delta\eta}{\partial y} + \frac{\partial \Delta\zeta}{\partial z} = 0. \quad \dots \dots \dots (5)$$

* As a simple example, take the case of a circular disk which is made to move, without rotation, so that its centre describes a rectangle two of whose sides are normal to its plane, and examine the displacements of a particle initially in contact with the disk at its centre.

The surface-integral vanishes at a fixed boundary, where

$$l\Delta\xi + m\Delta\eta + n\Delta\zeta = 0,$$

and in the case of a moving solid it is cancelled by the terms due to the pressure exerted by the fluid on the solid. Hence the symbols X, Y, Z may be taken to refer only to the *extraneous* forces acting on the system, and we may write

$$\Sigma(X\Delta\xi + Y\Delta\eta + Z\Delta\zeta) = Q_1\Delta q_1 + Q_2\Delta q_2 + \dots + Q_n\Delta q_n, \quad \dots (6)$$

where Q_1, Q_2, \dots, Q_n denote the generalized components of extraneous force

The varied motion of the fluid has still a high degree of generality. We will now further limit it by supposing that while the solids are, by suitable forces applied to them, made to execute an arbitrary motion, the fluid is left to take its own course in consequence of this. The varied motion of the fluid may accordingly be taken to be irrotational, in which case the varied kinetic energy $T + \Delta T$ of the system will be the same function of the varied co-ordinates $q_r + \Delta q_r$, and the varied velocities $\dot{q}_r + \Delta \dot{q}_r$, that the actual energy T is of q_r and \dot{q}_r .

Again, considering the particles of the fluid alone, we shall have, on the same supposition,

$$\begin{aligned} \Sigma m(\xi\Delta\xi + \eta\Delta\eta + \zeta\Delta\zeta) &= -\rho \iiint \left(\frac{\partial\phi}{\partial x} \Delta x + \frac{\partial\phi}{\partial y} \Delta y + \frac{\partial\phi}{\partial z} \Delta z \right) dx dy dz \\ &= \rho \iint \phi (l\Delta\xi + m\Delta\eta + n\Delta\zeta) dS, \end{aligned}$$

where use has again been made of the condition (5) of incompressibility. By the kinematical condition to be satisfied at the boundaries, we have

$$l\Delta\xi + m\Delta\eta + n\Delta\zeta = -\frac{\partial\phi_1}{\partial n} \Delta q_1 - \frac{\partial\phi_2}{\partial n} \Delta q_2 - \dots - \frac{\partial\phi_n}{\partial n} \Delta q_n,$$

and therefore

$$\begin{aligned} \Sigma m(\xi\Delta\xi + \eta\Delta\eta + \zeta\Delta\zeta) &= -\rho \iint \phi \left(\frac{\partial\phi_1}{\partial n} \Delta q_1 + \frac{\partial\phi_2}{\partial n} \Delta q_2 + \dots + \frac{\partial\phi_n}{\partial n} \Delta q_n \right) dS \\ &= (\mathbf{A}_{11}q_1 + \mathbf{A}_{12}q_2 + \dots + \mathbf{A}_{1n}q_n) \Delta q_1 + (\mathbf{A}_{21}q_1 + \mathbf{A}_{22}q_2 + \dots + \mathbf{A}_{2n}q_n) \Delta q_2 + \dots \\ &\quad + (\mathbf{A}_{n1}q_1 + \mathbf{A}_{n2}q_2 + \dots + \mathbf{A}_{nn}q_n) \Delta q_n \\ &= \frac{\partial \mathbf{T}}{\partial q_1} \Delta q_1 + \frac{\partial \mathbf{T}}{\partial q_2} \Delta q_2 + \dots + \frac{\partial \mathbf{T}}{\partial q_n} \Delta q_n, \quad \dots \dots \dots (7) \end{aligned}$$

by (1), (2), (3) above. If we add the terms due to the solids, we find that the relation (9) of Art 135 still holds, and the deduction of Lagrange's equations

$$\frac{d}{dt} \frac{\partial T}{\partial \dot{q}_r} - \frac{\partial T}{\partial q_r} = Q_r \quad \dots \dots \dots (8)$$

then proceeds exactly as before*

* This investigation was briefly indicated in the last edition

As in Art 135, these equations lead to

$$\frac{dT}{dt} = Q_1 q_1 + Q_2 q_2 + \dots + Q_n q_n,$$

or, in the case of a conservative system,

$$T + V = \text{const} \quad \dots (9)$$

137 As a first application of the foregoing theory we may take an example given by Thomson and Tait*, where a sphere is supposed to move in a liquid which is limited only by an infinite plane wall

Taking, for simplicity, the case where the centre moves in a plane perpendicular to that of the wall, let us specify its position at time t by rectangular co-ordinates x, y in this plane, of which y denotes distance from the wall. We have

$$2T = A\dot{x}^2 + B\dot{y}^2, \quad \dots (1)$$

where A and B are functions of y only, it being plain that the term $x\dot{y}$ cannot occur, since the energy must remain unaltered when the sign of x is reversed. The values of A, B can be written down from the results of Arts 98, 99, viz if m denote the mass of the sphere, and a its radius, we have

$$A = m + \frac{2}{3}\pi\rho a^3 \left(1 + \frac{3}{16}\frac{a^3}{y^3}\right), \quad B = m + \frac{2}{3}\pi\rho a^3 \left(1 + \frac{3}{8}\frac{a^3}{y^3}\right), \quad \dots (2)$$

approximately, if y be great in comparison with a .

The equations of motion give

$$\frac{d}{dt}(A\dot{x}) = X, \quad \frac{d}{dt}(B\dot{y}) - \frac{1}{2} \left(\frac{dA}{dy} \dot{x}^2 + \frac{dB}{dy} \dot{y}^2 \right) = Y, \quad \dots (3)$$

where X, Y are the components of extraneous force, supposed to act on the sphere in a line through the centre

If there be no extraneous force, and if the sphere be projected in a direction normal to the wall, we have $\dot{x} = 0$, and

$$B\dot{y}^2 = \text{const} \quad \dots (4)$$

Since B diminishes as y increases, the sphere experiences an acceleration from the wall.

Again, if the sphere be constrained to move in a line parallel to the wall, we have $\dot{y} = 0$, and the necessary constraining force is

$$Y = -\frac{1}{2} \frac{dA}{dy} \dot{x}^2 \quad \dots (5)$$

* *l. c. ante* p. 174

Since dA/dy is negative, the sphere appears to be *attracted* by the wall. The reason of this is easily seen by reducing the problem to one of steady motion. The fluid velocity will evidently be greater, and the pressure therefore less, on the side of the sphere next the wall than on the further side, see Art 23

The above investigation will also apply to the case of two spheres projected in an unlimited mass of fluid, in such a way that the plane $y = 0$ is a plane of symmetry in all respects

138. Let us next take the case of two spheres moving in the line of centres

The kinematical part of this problem has been treated in Art 98. If we now denote by x, y the distances of the centres of the spheres A, B from some fixed origin O in the line joining them, we have

$$2T = Lx^2 - 2Mxy + Ny^2, \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

where the coefficients L, M, N are functions of $y - x$, or c , the distance between the centres. Hence the equations of motion are

$$\left. \begin{aligned} \frac{d}{dt}(Lv - My) + \frac{1}{2} \left(\frac{dL}{dc} x^2 - 2 \frac{dM}{dc} xy + \frac{dN}{dc} y^2 \right) &= X, \\ \frac{d}{dt}(-Mx + Ny) - \frac{1}{2} \left(\frac{dL}{dc} x^2 - 2 \frac{dM}{dc} xy + \frac{dN}{dc} y^2 \right) &= Y, \end{aligned} \right\} \quad (2)$$

where X, Y are the forces acting on the spheres along the line of centres. If the radii a, b are both small compared with c , we have, by Art 98 (15), keeping only the most important terms,

$$L = m + \frac{3}{2} \pi \rho a^3, \quad M = 2\pi \rho \frac{a^3 b^3}{c^3}, \quad N = m' + \frac{3}{2} \pi \rho b^3, \quad (3)$$

approximately, where m, m' are the masses of the two spheres. Hence to this order of approximation

$$\frac{dL}{dc} = 0, \quad \frac{dM}{dc} = -6\pi \rho \frac{a^3 b^3}{c^4}, \quad \frac{dN}{dc} = 0$$

If each sphere be constrained to move with constant velocity, the force which must be applied to A to maintain its motion is

$$X = - \frac{dM}{dc} y (y - x) - \frac{dM}{dc} xy = 6\pi \rho \frac{a^3 b^3}{c^4} y^2. \quad . \quad . \quad . \quad (4)$$

This tends towards B , and depends only on the velocity of B . The spheres therefore appear to repel one another, and it is to be noticed that the apparent forces are not equal and opposite unless $x = \pm y$.

Again, if each sphere make small periodic oscillations about a mean position, the period being the same for each, the mean values of the first terms in (2) will be zero, and the spheres therefore will appear to act on one another with forces equal to

$$6\pi \rho \frac{a^3 b^3}{c^4} [\overline{xy}], \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

where $[\overline{xy}]$ denotes the mean value of xy . If x, y differ in phase by less than a quarter-period, this force is one of repulsion, if by more than a quarter-period it is one of attraction

Next, let B perform small periodic oscillations, while A is held at rest. The mean force which must be applied to A to prevent it from moving is

$$X = \frac{1}{2} \frac{dN}{dc} [y^2], \quad (6)$$

where $[y^2]$ denotes the mean square of the velocity of B . To the above order of approximation dN/dc is zero, on reference to Art. 98 we find that the most important term in it is $-12\pi\rho a^3 b^6/c^7$, so that the force exerted on A is attractive, and equal to

$$6\pi\rho \frac{a^3 b^6}{c^7} [y^2] \quad (7)$$

This result comes under a general principle enunciated by Lord Kelvin. If we have two bodies immersed in a fluid, one of which (A) performs small vibrations while the other (B) is held at rest, the fluid velocity at the surface of B will on the whole be greater on the side nearer A than on that which is more remote. Hence the average pressure on the former side will be less than that on the latter, so that B will experience on the whole an attraction towards A . As practical illustrations of this principle we may cite the apparent attraction of a delicately-suspended card by a vibrating tuning-fork, and other similar phenomena studied experimentally by Guthrie* and explained in the above manner by Lord Kelvin†

Modification of Lagrange's Equations in the case of Cyclic Motion

139 We return to the investigations of Art 135, with the view of adapting them to the case where the fluid has cyclic irrotational motion through channels in the moving solids, or (it may be) in an enclosing vessel, independently of the motion due to the solids themselves.

Let us imagine barrier-surfaces to be drawn across the several apertures in the case of channels in a containing vessel we shall suppose these ideal surfaces to be fixed in space, and in the case of channels in a moving solid we shall suppose them to be fixed relatively to the solid. Let χ, χ', χ'' , be the fluxes at time t across, and *relative to*, the several barriers, and let $\chi, \chi', \chi'', \dots$ be the time-integrals of these fluxes, reckoned from some arbitrary epoch, these quantities determining (therefore) the volumes of fluid which have up to the time t crossed the respective barriers. It will appear that the analogy with a dynamical system of finite freedom is still preserved, provided the quantities $\chi, \chi', \chi'', \dots$ be reckoned as generalized co-ordinates of the system, in addition to those (q_1, q_2, \dots, q_n) which specify the positions of the moving solids. It is obvious already that the absolute values of $\chi, \chi', \chi'', \dots$ will not enter into the expression for the kinetic energy, but only their rates of variation.

* "On Approach caused by Vibration," *Proc Roy Soc*, t. xix (1869) [*Phil Mag*, Nov 1870]

† *Reprint of Papers on Electrostatics, &c*, Art 741. For references to further investigations, both experimental and theoretical, by Bjerknes and others, on the mutual influence of oscillating spheres in a fluid, see Hicks, "Report on Recent Researches in Hydrodynamics," *Brit. Ass Rep*, 1902, pp 52, Love, *Encycl. d. math. Wiss*, t. iv. (2) pp 111, 112

In the first place, we may shew that the motion of the fluid, in any given configuration of the solids, is completely determined by the instantaneous values of $q_1, q_2, \dots q_n, \dot{\chi}, \dot{\chi}', \dot{\chi}'', \dots$. For if there were two modes of irrotational motion consistent with these values, then, in the motion which is the *difference* of these, the boundaries of the fluid would be at rest, and the flux across each barrier would be zero. The formula (5) of Art 55 shews that under these conditions the kinetic energy must vanish.

It follows that the velocity-potential can be expressed in the form

$$\phi = q_1\phi_1 + q_2\phi_2 + \dots + q_n\phi_n + \dot{\chi}\Omega + \dot{\chi}'\Omega' + \dots \quad (1)$$

Here ϕ_r is the velocity-potential of a motion in which q_r alone varies and the flux across each barrier is accordingly zero. Again Ω is the velocity-potential of a motion in which the solids are all at rest, whilst the flux through the first aperture is unity, and that through every other aperture is zero. It is to be observed that $\phi_1, \phi_2, \dots \phi_n, \Omega, \Omega', \dots$ are in general all of them cyclic functions, which may however be treated as single-valued, on the conventions of Art 50.

The kinetic energy of the fluid is given by the expression

$$2\mathbf{T} = \rho \iiint \left\{ \left(\frac{\partial \phi}{\partial x} \right)^2 + \left(\frac{\partial \phi}{\partial y} \right)^2 + \left(\frac{\partial \phi}{\partial z} \right)^2 \right\} dx dy dz, \dots \quad (2)$$

where the integral is taken over the region occupied by the fluid at the instant under consideration. If we substitute from (1) we obtain \mathbf{T} as a homogeneous quadratic function of $q_1, q_2, \dots q_n, \dot{\chi}, \dot{\chi}', \dot{\chi}'', \dots$ with coefficients which depend on the instantaneous configuration of the solids, and are therefore functions of $q_1, q_2, \dots q_n$ only. Moreover, we find, by Art 53 (1),

$$\begin{aligned} \frac{\partial \mathbf{T}}{\partial \dot{\chi}} &= \rho \iiint \left\{ \frac{\partial \phi}{\partial x} \frac{\partial \Omega}{\partial x} + \frac{\partial \phi}{\partial y} \frac{\partial \Omega}{\partial y} + \frac{\partial \phi}{\partial z} \frac{\partial \Omega}{\partial z} \right\} dx dy dz \\ &= -\rho \iint \phi \frac{\partial \Omega}{\partial n} dS - \rho \kappa \iint \frac{\partial \Omega}{\partial n} d\sigma - \rho \kappa' \iint \frac{\partial \Omega}{\partial n} d\sigma' - \dots, \end{aligned}$$

where κ, κ', \dots are the cyclic constants of ϕ , and the first surface-integral is to be taken over the surfaces of the solids, and the remaining ones over the several barriers. By the conditions which determine Ω , this gives the first equation of the system

$$\frac{\partial \mathbf{T}}{\partial \dot{\chi}} = \rho \kappa, \quad \frac{\partial \mathbf{T}}{\partial \dot{\chi}'} = \rho \kappa', \quad \dots \quad (3)$$

These shew that $\rho \kappa, \rho \kappa', \dots$ are to be regarded as the generalized components of momentum corresponding to the velocity-components $\dot{\chi}, \dot{\chi}', \dots$, respectively.

We have recourse to the general Hamiltonian formula* (17) of Art 135.

* It is possible to arrange an investigation on the Lagrangian plan, parallel to that of Art 136, but the proof of the formulae corresponding to (5) below involves some rather delicate considerations.

We will suppose that the varied motion of the solids is subject only to the condition that the initial and final configurations are to be the same as in the actual motion, also that the *initial* position of each particle of the fluid is the same in the two motions. The expression

$$\Sigma m (\xi \Delta \xi + \eta \Delta \eta + \zeta \Delta \zeta)$$

will accordingly vanish at time t_0 , but not in general at time t_1 , in the absence of further restrictions

We will now suppose that the varied motion of the fluid is irrotational, and accordingly determined by the instantaneous values of the varied generalized co-ordinates and velocities. Considering the particles of the fluid alone, we have


$$\begin{aligned} \Sigma m (\xi \Delta \xi + \eta \Delta \eta + \zeta \Delta \zeta) &= -\rho \iiint \left(\frac{\partial \phi}{\partial x} \Delta \xi + \frac{\partial \phi}{\partial y} \Delta \eta + \frac{\partial \phi}{\partial z} \Delta \zeta \right) dx dy dz \\ &= \rho \iint \phi (l \Delta \xi + m \Delta \eta + n \Delta \zeta) dS + \rho \kappa \iint (l \Delta \xi + m \Delta \eta + n \Delta \zeta) d\sigma \\ &\quad + \rho \kappa' \iint (l \Delta \xi + m \Delta \eta + n \Delta \zeta) d\sigma' + \dots \dots (4) \end{aligned}$$

where l, m, n are the direction-cosines of the normal to an element of the bounding surface, drawn towards the fluid, or (as the case may be) of the normal to an element of a barrier, drawn in the direction in which the corresponding circulation is estimated

At time t_1 we shall have

$$l \Delta \xi + m \Delta \eta + n \Delta \zeta = 0,$$

at the surfaces of the solids, as well as at the fixed boundaries. Again, if AB represent one of the barriers in its position at time t_1 , and if $A'B'$ represent the locus at the same instant, in the varied motion, of those particles which in the actual motion occupy the position AB , the volume included between AB and $A'B'$ will be equal to the corresponding $\Delta \chi$, whence



$$\left. \begin{aligned} \iint (l \Delta \xi + m \Delta \eta + n \Delta \zeta) d\sigma &= \Delta \chi, \\ \iint (l \Delta \xi + m \Delta \eta + n \Delta \zeta) d\sigma' &= \Delta \chi', \end{aligned} \right\} \dots \dots (5)$$

The varied circulations are, from instant to instant, still at our disposal. We may suppose them to be so adjusted as to make $\Delta \chi, \Delta \chi', \dots$ vanish at time t_1 . The right-hand member of Art 135 (17) will accordingly vanish, and if we further suppose that the extraneous forces do on the whole no

work when the boundary of the fluid is at rest, whatever relative displacements be given to the parts of the fluid, the formula reduces to

$$\int_{t_0}^{t_1} \{\Delta T + Q_1 \Delta q_1 + Q_2 \Delta q_2 + \dots + Q_n \Delta q_n\} dt = 0 \quad \dots (6)$$

From this Lagrange's equations follow by a known process We have

$$\begin{aligned} \Delta T = & \frac{\partial T}{\partial q_1} \Delta q_1 + \frac{\partial T}{\partial q_2} \Delta q_2 + \dots + \frac{\partial T}{\partial q_n} \Delta q_n \\ & + \frac{\partial T}{\partial \chi} \Delta \chi + \frac{\partial T}{\partial \chi'} \Delta \chi' + \dots \\ & + \frac{\partial T}{\partial q_1} \Delta q_1 + \frac{\partial T}{\partial q_2} \Delta q_2 + \dots + \frac{\partial T}{\partial q_n} \Delta q_n \quad \dots \dots \dots (7) \end{aligned}$$

Hence, by a partial integration, and remembering that by hypothesis $\Delta q_1, \Delta q_2, \dots \Delta q_n, \Delta \chi, \Delta \chi', \dots$ vanish at the limits t_0, t_1 , we find

$$\begin{aligned} \int_{t_0}^{t_1} \left\{ \left(\frac{d}{dt} \frac{\partial T}{\partial q_1} - \frac{\partial T}{\partial q_1} - Q_1 \right) \Delta q_1 + \left(\frac{d}{dt} \frac{\partial T}{\partial q_2} - \frac{\partial T}{\partial q_2} - Q_2 \right) \Delta q_2 \right. \\ \left. + \dots + \left(\frac{d}{dt} \frac{\partial T}{\partial q_n} - \frac{\partial T}{\partial q_n} - Q_n \right) \Delta q_n + \frac{d}{dt} \frac{\partial T}{\partial \chi} \Delta \chi + \frac{d}{dt} \frac{\partial T}{\partial \chi'} \Delta \chi' + \dots \right\} dt = 0 \end{aligned}$$

... .. (8)

Since the values of $\Delta q_1, \Delta q_2, \dots \Delta q_n, \Delta \chi, \Delta \chi', \dots$ within the range of integration are still arbitrary, their coefficients must separately vanish. We thus obtain n equations of the type

$$\frac{d}{dt} \frac{\partial T}{\partial q_r} - \frac{\partial T}{\partial q_r} = Q_r, \quad \dots (9)$$

together with

$$\frac{d}{dt} \frac{\partial T}{\partial \chi} = 0, \quad \frac{d}{dt} \frac{\partial T}{\partial \chi'} = 0, \quad \dots \dots \dots (10)$$

140 Equations of the types (9) and (10) present themselves in various problems of ordinary Dynamics, *e g* in questions relating to gyrostats, where the co-ordinates χ, χ', \dots , whose absolute values do not affect the kinetic or the potential energy of the system, are the angular co-ordinates of the gyrostats relative to their frames. The general theory of such systems has been treated by Routh*, Thomson and Tait†, and other writers

* *On the Stability of a Given State of Motion* (Adams Prize Essay), London, 1877, *Advanced Rigid Dynamics*, 5th ed, London, 1892

† *Natural Philosophy*, 2nd ed, Art 319 (1879). See also von Helmholtz, "Prinzipien der Statik monocyclischer Systeme," *Crelle*, t xxvii (1884) [*Ges Abh*, t iii, p 179], Larmor, "On the Direct Application of the Principle of Least Action to the Dynamics of Solid and Fluid Systems," *Proc. Lond Math. Soc*, t xv (1884), Lamb, Art. "Dynamics, Analytical," *Encyc. Brit*, t xxvii p 566 (1902), Whittaker, *Analytical Dynamics*, c. iii

We have seen that $\frac{\partial T}{\partial \chi} = \rho\kappa$, $\frac{\partial T}{\partial \chi'} = \rho\kappa'$, .., (11)

and the integration of (10) shews that the quantities κ , κ' , . are constants with regard to the time, as is otherwise known (Art. 50). Let us write

$$R = T - \rho\kappa\chi - \rho\kappa'\chi' - \dots \quad (12)$$

The equations (11), when written in full, determine $\dot{\chi}$, $\dot{\chi}'$, ... as linear functions of κ , κ' , ... and q_1 , q_2 , ... q_n , and by substitution in (12) we can express R as a homogeneous quadratic function of the same quantities, with coefficients which of course in general involve the co-ordinates q_1 , q_2 , . . q_n . On this supposition we have, performing the arbitrary variation Δ on both sides of (12), and omitting terms which cancel by (11),

$$\begin{aligned} \frac{\partial R}{\partial q_1} \Delta q_1 + \dots + \frac{\partial R}{\partial q_1} \Delta q_1 + \dots + \frac{\partial R}{\partial \kappa} \Delta \kappa + \dots \\ = \frac{\partial T}{\partial q_1} \Delta q_1 + \dots + \frac{\partial T}{\partial q_1} \Delta q_1 + \dots - \rho \dot{\chi} \Delta \kappa - \dots \end{aligned} \quad (13)$$

where, for brevity, only one term of each kind is exhibited. Hence we obtain $2n$ equations of the types

$$\frac{\partial R}{\partial q_r} = \frac{\partial T}{\partial q_r}, \quad \frac{\partial R}{\partial q_r} = \frac{\partial T}{\partial q_r}, \quad \dots \quad (14)$$

together with $\frac{\partial R}{\partial \kappa} = -\rho\chi$, $\frac{\partial R}{\partial \kappa'} = -\rho\chi'$, (15)

Hence the equations (9) may be written

$$\frac{d}{dt} \frac{\partial R}{\partial q_r} - \frac{\partial R}{\partial q_r} = Q_r, \quad \dots \quad (16)$$

where the velocities $\dot{\chi}$, $\dot{\chi}'$, . corresponding to the 'ignored' co-ordinates χ , χ' , .. have now been eliminated*.

141. In order to shew more explicitly the nature of the modification introduced by the cyclic motions into the dynamical equations, we proceed as follows

If we substitute in (12) from (15), we obtain

$$T = R - \left(\kappa \frac{\partial R}{\partial \kappa} + \kappa' \frac{\partial R}{\partial \kappa'} + \dots \right) \quad (17)$$

Now, remembering the composition of R , we may write for a moment

$$R = R_{2,0} + R_{1,1} + R_{0,2}, \quad \dots \quad (18)$$

where $R_{2,0}$ is a homogeneous quadratic function of q_1 , q_2 , . . q_n , $R_{0,2}$ is a

* This investigation is due to Routh, *l.c.*, of Whittaker, *Analytical Dynamics*, Art 38

homogeneous quadratic function of κ , κ' , and $R_{1,1}$ is bilinear in these two sets of variables. Hence (17) takes the form

$$T = R_{2,0} - R_{0,2}, \quad \dots \quad (19)$$

or, as we shall henceforth write it,

$$T = \mathfrak{T} + K, \quad \dots \quad (20)$$

where \mathfrak{T} and K are homogeneous quadratic functions of q_1, q_2, \dots, q_n , and of κ, κ' , respectively. It follows also from (18) that

$$R = \mathfrak{T} - K - \beta_1 q_1 - \beta_2 q_2 - \dots - \beta_n \dot{q}_n, \quad \dots \quad (21)$$

where β_1, β_2, \dots are linear functions of κ, κ' , say

$$\left. \begin{aligned} \beta_1 &= \alpha_1 \kappa + \alpha'_1 \kappa' + \dots, \\ \beta_2 &= \alpha_2 \kappa + \alpha'_2 \kappa' + \dots, \\ &\dots \dots \dots \\ \beta_n &= \alpha_n \kappa + \alpha'_n \kappa' + \dots \end{aligned} \right\} \quad \dots \quad (22)$$

The meaning of the coefficients α (in the hydrodynamical problem) appears from (15) and (21). We find

$$\left. \begin{aligned} \rho \dot{\chi} &= \frac{\partial K}{\partial \kappa} + \alpha_1 q_1 + \alpha_2 q_2 + \dots + \alpha_n \dot{q}_n, \\ \rho \chi' &= \frac{\partial K}{\partial \kappa'} + \alpha'_1 q_1 + \alpha'_2 q_2 + \dots + \alpha'_n \dot{q}_n, \end{aligned} \right\} \quad \dots \quad (23)$$

which shew that α_r is the contribution to the flux of matter across the first barrier due to unit rate of variation of the co-ordinate q_r , and so on

If we now substitute from (21) in the equations (16) we obtain the general equations of motion of a 'gyrostatic system,' in the form*

$$\left. \begin{aligned} \frac{d}{dt} \frac{\partial \mathfrak{T}}{\partial \dot{q}_1} - \frac{\partial \mathfrak{T}}{\partial q_1} &+ (1, 2) q_2 + (1, 3) q_3 + \dots + (1, n) q_n + \frac{\partial K}{\partial \dot{q}_1} = Q_1, \\ \frac{d}{dt} \frac{\partial \mathfrak{T}}{\partial \dot{q}_2} - \frac{\partial \mathfrak{T}}{\partial q_2} &+ (2, 1) q_1 + (2, 3) q_3 + \dots + (2, n) q_n + \frac{\partial K}{\partial \dot{q}_2} = Q_2, \\ &\dots \dots \dots \\ \frac{d}{dt} \frac{\partial \mathfrak{T}}{\partial \dot{q}_n} - \frac{\partial \mathfrak{T}}{\partial q_n} &+ (n, 1) q_1 + (n, 2) \dot{q}_2 + (n, 3) q_3 + \dots + \frac{\partial K}{\partial \dot{q}_n} = Q_n, \end{aligned} \right\} \quad \dots \quad (24)$$

where $(r, s) = \frac{\partial \beta_s}{\partial q_r} - \frac{\partial \beta_r}{\partial q_s} \quad \dots \quad (25)$

It is important to notice that $(r, s) = -(s, r)$, and $(r, r) = 0$.

* These equations were first given in a paper by Sir W. Thomson, "On the Motion of Rigid Solids in a Liquid circulating irrotationally through perforations in them or in a Fixed Solid," *Phil. Mag.*, May 1873. See also C. Neumann, *Hydrodynamische Untersuchungen* (1883).

If in the equations of motion of a fully-specified system of finite freedom (Art 135 (14)) we reverse the sign of the time-element δt , the equations are unaltered. The motion is therefore reversible, that is to say, if as the system is passing through any assigned configuration the velocities $q_1, q_2, \dots q_n$ be all reversed, it will (if the forces be always the same in the same configuration) retrace its former path. It is important to observe that this statement does not in general hold of a gyrostatic system, thus, the terms in (24) which are linear in $q_1, \dot{q}_2, \dots q_n$ change sign with δt , whilst the others do not. Hence, in the present application, the motion of the solids is not reversible, unless indeed we imagine the circulations κ, κ', \dots to be reversed simultaneously with the velocities $q_1, q_2, \dots q_n^*$.

If we multiply the equations (24) by q_1, q_2, \dots, q_n in order, and add, we find, by an obvious adaptation of the method of Art 135,

$$\frac{d}{dt}(\mathcal{T} + K) = Q_1 q_1 + Q_2 q_2 + \dots + Q_n \dot{q}_n, \quad (26)$$

or, if the system be conservative,

$$\mathcal{T} + K + V = \text{const} \quad . \quad (27)$$

142 The results of Art 141 may be applied to find the conditions of equilibrium of a system of solids surrounded by a liquid in cyclic motion. This problem of 'Kineto-Statics,' as it may be termed, is however more naturally treated by a simpler process.

The value of ϕ under the present circumstances can be expressed in the alternative forms

$$\phi = \chi \Omega + \chi' \Omega' + \dots, \quad \dots \quad (1)$$

$$\phi = \kappa \omega + \kappa' \omega' + \dots, \quad \dots \quad (2)$$

and the kinetic energy can accordingly be obtained as a homogeneous quadratic function either of χ, χ', \dots , or of κ, κ', \dots , with coefficients which are in each case functions of the co-ordinates $q_1, q_2, \dots q_n$ which specify the configuration of the solids. These two expressions for the energy may be distinguished by the symbols T_0 and K , respectively. Again, by Art 55 (5) we have a third formula

$$2T = \rho \kappa \chi + \rho \kappa' \chi' + \dots \quad (3)$$

The investigation at the beginning of Art 139, shortened by the omission of the terms involving $q_1, q_2, \dots q_n$, shews that

$$\rho \kappa = \frac{\partial T_0}{\partial \chi}, \quad \rho \kappa' = \frac{\partial T_0}{\partial \chi'}, \quad \dots \quad (4)$$

* Just as the motion of the axis of a top cannot be reversed unless we reverse the spin

Again, the explicit formula for K is

$$2K = -\rho\kappa \iint \frac{\partial\phi}{\partial n} d\sigma - \rho\kappa' \iint \frac{\partial\phi}{\partial n} d\sigma' - \dots \\ = (\kappa, \kappa) \kappa^2 + (\kappa', \kappa') \kappa'^2 + \dots + 2(\kappa, \kappa') \kappa\kappa' + \dots \quad (5)$$

where

$$(\kappa, \kappa) = -\rho \iint \frac{\partial\omega}{\partial n} d\sigma, \quad (\kappa, \kappa') = -\rho \iint \frac{\partial\omega'}{\partial n} d\sigma = -\rho \iint \frac{\partial\omega}{\partial n} d\sigma', \quad \dots \quad (6)$$

and so on. Hence

$$\frac{\partial K}{\partial \kappa} = (\kappa, \kappa) \kappa + (\kappa, \kappa') \kappa' + \dots = -\rho \iint \frac{\partial\phi}{\partial n} d\sigma.$$

We thus obtain
$$\rho\chi = \frac{\partial K}{\partial \kappa}, \quad \rho\chi' = \frac{\partial K}{\partial \kappa'}, \quad \dots \quad \dots \quad \dots \quad (7)$$

Again, writing $T_0 + K$ for $2T$ in (3), and performing a variation Δ on both sides of the resulting identity, we find, on omitting terms which cancel in virtue of (4) and (7)*,

$$\frac{\partial T_0}{\partial q_i} + \frac{\partial K}{\partial q_i} = 0 \quad \dots \quad \dots \quad (8)$$

This completes the requisite analytical formulae†.

If we now imagine the solids to be guided from rest in the configuration (q_1, q_2, \dots, q_n) to rest in an adjacent configuration

$$(q_1 + \Delta q_1, q_2 + \Delta q_2, \dots, q_n + \Delta q_n),$$

the work required is $Q_1\Delta q_1 + Q_2\Delta q_2 + \dots + Q_n\Delta q_n$,

where Q_1, Q_2, \dots, Q_n are the components of extraneous force which have to be applied to neutralize the pressures of the fluid on the solids. This must be equal to the increment ΔK of the kinetic energy, calculated on the supposition that the circulations κ, κ', \dots are constant. Hence

$$Q_r = \frac{\partial K}{\partial q_r}. \quad \dots \quad \dots \quad (9)$$

The forces representing the pressures of the fluid on the solids (when these are held at rest) are obtained by reversing the signs, viz. they are given by

$$Q_r' = -\frac{\partial K}{\partial q_r}, \quad \dots \quad \dots \quad (10)$$

the solids therefore tend to move so that the kinetic energy of the cyclic motion diminishes.

* It would be sufficient to assume either (4) or (7), the process then leads to an independent proof of the other set of formulae.

† It may be noted that the function R of Art. 140 now reduces to $-K$.

In virtue of (8) we have, also,

$$Q_i' = \frac{\partial T_0}{\partial q_i} \quad \dots \quad \dots \quad (11)$$

143 A simple application of the equations (24) of Art 141 is to the case of a sphere moving in a liquid which circulates irrotationally in a cyclic space with fixed boundaries

If the radius a , say, of the sphere be small compared with its least distance from the fixed boundary, the formula (20) of Art 141 becomes

$$2T = \mathbf{m} (x^2 + y^2 + z^2) + K, \quad (1)$$

where x, y, z are the co-ordinates of the centre, and \mathbf{m} denotes the mass of the sphere together with half that of the fluid displaced by it, see Art 92. To find K , the energy of the cyclic motion when the sphere is held at rest in its actual position, we note that if we equate x, y, z to the components u, v, w , respectively, of the fluid velocity which would obtain at the point (x, y, z) if the sphere were absent, and at the same time put $\mathbf{m} = 2\pi\rho a^3$, the resulting energy will be practically the same as that of the fluid when filling the region, whence

$$2\pi\rho a^3 (u^2 + v^2 + w^2) + K = \text{const},$$

$$\text{or} \quad K = \text{const} - W, \quad (2)$$

$$\text{where} \quad W = 2\pi\rho a^3 (u^2 + v^2 + w^2) \quad (3)$$

Again the coefficients a_1, a_2, a_3 of Art 141 (22) denote the fluxes across the first barrier, when the sphere moves with unit velocity parallel to x, y, z , respectively. If we denote by Ω the flux across this barrier due to a unit simple-source at (x, y, z) , then remembering the equivalence of a moving sphere to a double-source (Art 92), we have

$$a_1, a_2, a_3 = \frac{1}{2}a^3 \frac{\partial \Omega}{\partial x}, \quad \frac{1}{2}a^3 \frac{\partial \Omega}{\partial y}, \quad \frac{1}{2}a^3 \frac{\partial \Omega}{\partial z}, \quad \dots \quad (4)$$

so that the quantities denoted by (2, 3), (3, 1), (1, 2) in Art 141 (24) vanish identically. The equations therefore reduce in the present case to

$$\mathbf{m}x = X + \frac{\partial W}{\partial x}, \quad \mathbf{m}y = Y + \frac{\partial W}{\partial y}, \quad \mathbf{m}z = Z + \frac{\partial W}{\partial z}, \quad \dots \quad (5)$$

where X, Y, Z are the components of extraneous force applied to the sphere

When $X, Y, Z = 0$, the sphere tends to move towards places where the undisturbed velocity of the fluid is greatest

For example, in the case of cyclic motion round a fixed circular cylinder (Arts 27, 64), the fluid velocity varies inversely as the distance from the axis. The sphere will therefore move as if under the action of a force towards this axis varying inversely as the cube of the distance. The projection of its path on a plane perpendicular to the axis will therefore be a Cotes' spiral*

144. We may also notice one or two problems of Kineto-Statics, in illustration of the theory of Art 142.

* Cf Sir W. Thomson, *l c ante* p 187

It will be shewn in Art 153 that the energy K of the cyclic fluid motion is proportional to the energy of a system of electric current-sheets coincident with the fixed boundaries, the current-lines being orthogonal to the stream-lines of the fluid.

The electromagnetic forces between conductors carrying these currents are proportional* to the expressions on the right-hand of Art 142 (10) with the signs reversed. Hence in the hydrodynamical problem the forces on the solids are opposite to those which obtain in the electrical analogue. In the particular case where the fixed solids reduce to infinitely thin cores, round which the fluid circulates, the current-sheets in question are practically equivalent to a system of electric currents flowing in the cores, regarded as wires, with strengths κ, κ' , respectively. For example, two thin circular rings, having a common axis, will repel or attract one another according as the fluid circulates in the same or in opposite directions through them†. This might have been foreseen of course from the principle of Art 23.

Another interesting case is that of a number of open tubes, so narrow as not sensibly to impede the motion of the fluid outside them. If streams be established through the tubes, then as regards the external space the extremities will act as sources and sinks. The energy due to any distribution of positive or negative sources m_1, m_2, \dots is given, so far as it depends on the relative configuration of these, by the integral

$$-\frac{1}{2}\rho \iint \phi \frac{\partial \phi}{\partial n} dS, \quad \dots \quad (6)$$

taken over a system of small closed surfaces surrounding m_1, m_2, \dots respectively. If ϕ_1, ϕ_2, \dots be the velocity-potentials due to the several sources, the part of this expression which is due to the simultaneous presence of m_1, m_2 is

$$-\frac{1}{2}\rho \iint \left(\phi_1 \frac{\partial \phi_2}{\partial n} + \phi_2 \frac{\partial \phi_1}{\partial n} \right) dS, \quad \dots \quad (7)$$

which is by Green's Theorem equal to

$$-\rho \iint \phi_1 \frac{\partial \phi_2}{\partial n} dS \quad \dots \quad (8)$$

Since the surface-integral of $\partial \phi_2 / \partial n$ is zero over each of the closed surfaces except the one surrounding m_2 , we may ultimately confine the integration to this, and so obtain

$$-\rho \phi_1 \iint \frac{\partial \phi_2}{\partial n} dS_2 = \rho m_2 \phi_1 \quad \dots \quad (9)$$

Since the value of ϕ_1 at m_2 is $m_1/4\pi r_{12}$, where r_{12} denotes the distance between m_1 and m_2 , we obtain, for the part of the kinetic energy which varies with the relative positions of the sources, the expression

$$\frac{\rho}{4\pi} \sum \frac{m_i m_j}{r_{ij}} \quad \dots \quad (10)$$

The quantities m_1, m_2, \dots are in the present problem equal to the fluxes $\dot{\chi}_0, \dot{\chi}_0', \dots$ across the sections of the respective tubes, so that (10) corresponds to the form T_0 of the kinetic

* Maxwell, *Electricity and Magnetism*, Art 573

† The theorem of this paragraph was given by Kirchhoff, *loc. ante* p 52. See also Sir W. Thomson, "On the Forces experienced by Solids immersed in a Moving Liquid," *Proc. R. S. Edin.*, 1870 [*Reprint*, Art xli], Boltzmann, "Ueber die Druckkräfte welche auf Ringe wirksam sind die in bewegte Flüssigkeit tauchen," *Crelle*, t. lxxiii (1871)

energy The force apparently exerted by m_1 on m_2 , tending to increase r_{12} , is therefore, by Art 142 (11),

$$\frac{\rho}{4\pi} \frac{d}{dt} \cdot \frac{m_1 m_2}{r_{12}} = - \frac{\rho}{4\pi} \cdot \frac{m_1 m_2}{r_{12}^2}$$

Hence two sources of like sign attract, and two of unlike sign repel, with forces varying inversely as the square of the distance* This result, again, is easily seen to be in accordance with general principles It also follows independently from the electric analogy, the tubes corresponding to Ampère's 'solenoids'

We here take leave of this branch of our subject To avoid, as far as may be, the suspicion of vagueness which sometimes attaches to the use of 'generalized co-ordinates,' an attempt has been made in this Chapter to put the question on as definite a basis as possible, even at the expense of some degree of prolixity in the methods.

To some writers† the matter has presented itself as a much simpler one The problems are brought at one stroke under the sway of the ordinary formulae of Dynamics by the imagined introduction of an infinite number of 'ignored co-ordinates,' which would specify the configuration of the various particles of the fluid The corresponding components of momentum are assumed all to vanish, with the exception (in the case of a cyclic region) of those which are represented by the circulations through the several apertures

From a physical point of view it is difficult to refuse assent to such a generalization, especially when it has formed the starting-point of all the development of this part of the subject; but it is at least legitimate, and from the hydrodynamical standpoint even desirable, that it should be verified *à posteriori* by independent, if more pedestrian, methods

Whichever procedure be accepted, the result is that the systems contemplated in this Chapter are found to comport themselves (so far as the 'palpable' co-ordinates $q_1, q_2, \dots q_n$ are concerned) exactly like ordinary systems of finite freedom The further development of the general theory belongs to Analytical Dynamics, and must accordingly be sought for in books and memoirs devoted to that subject It may be worth while, however, to remark that the hydrodynamical systems afford extremely interesting and beautiful illustrations of the Principle of Least Action, the Reciprocal Theorems of von Helmholtz, and other general dynamical theories

* Sir W Thomson, *l.c.*

† See Thomson and Tait, and Larmor, *ll cit. ante* p 185.

CHAPTER VII.

VORTEX MOTION.

145 OUR investigations have thus far been confined for the most part to the case of irrotational motion. We now proceed to the study of rotational or 'vortex' motion. This subject was first investigated by von Helmholtz*, other and simpler proofs of some of his theorems were afterwards given by Lord Kelvin in the paper on vortex motion already cited in Chapter III.

We shall, throughout this Chapter, use the symbols ξ , η , ζ to denote, as in Chap. III, the components of the instantaneous angular velocity of a fluid element, viz

$$\xi = \frac{1}{2} \left(\frac{\partial w}{\partial y} - \frac{\partial v}{\partial z} \right), \quad \eta = \frac{1}{2} \left(\frac{\partial u}{\partial z} - \frac{\partial w}{\partial x} \right), \quad \zeta = \frac{1}{2} \left(\frac{\partial v}{\partial x} - \frac{\partial u}{\partial y} \right). \quad (1)$$

A line drawn from point to point so that its direction is everywhere that of the instantaneous axis of rotation of the fluid is called a 'vortex-line.' The differential equations of the system of vortex-lines are

$$\frac{dx}{\xi} = \frac{dy}{\eta} = \frac{dz}{\zeta}. \quad \dots \dots \dots (2)$$


If through every point of a small closed curve we draw the corresponding vortex-line, we mark out a tube, which we call a 'vortex-tube.' The fluid contained within such a tube constitutes what is called a 'vortex-filament,' or simply a 'vortex.'

Let ABC , $A'B'C'$ be any two circuits drawn on the surface of a vortex-tube and embracing it, and let AA' be a connecting line also drawn on the surface. Let us apply the theorem of Art. 32 to the circuit $ABCA'A'C'B'A'A$ and the part of the surface of the tube bounded by it. Since

$$l\xi + m\eta + n\zeta = 0$$

at every point of this surface, the line-integral

$$\int (u\delta x + v\delta y + w\delta z),$$



* "Ueber Integrale der hydrodynamischen Gleichungen welche den Wirbelbewegungen entsprechen," *Crelle*, t. 1v (1858) [*Ges. Abh.*, t. 1 p. 101]

taken round the circuit, must vanish, *ve* in the notation of Art. 31

$$I(ABCA) + I(AA') + I(A'C'B'A') + I(A'A) = 0,$$

which reduces to

$$I(ABCA) = I(A'B'C'A')$$

Hence the circulation is the same in all circuits embracing the same vortex-tube

Again, it appears from Art 31 that the circulation round the boundary of any cross-section of the tube, made normal to its length, is $2\omega\sigma$, where $\omega = (\xi^2 + \eta^2 + \zeta^2)^{\frac{1}{2}}$, is the angular velocity of the fluid, and σ the infinitely small area of the section

Combining these results we see that the product of the angular velocity into the cross-section is the same at all points of a vortex. The doubled product is conveniently taken as a measure of the 'strength' of the vortex*

The foregoing proof is due to Lord Kelvin; the theorem itself was first given by von Helmholtz, as a deduction from the relation

$$\frac{\partial \xi}{\partial x} + \frac{\partial \eta}{\partial y} + \frac{\partial \zeta}{\partial z} = 0, \quad \dots \dots (3)$$

which follows at once from the values of ξ, η, ζ given by (1). In fact writing, in Art 42 (1), ξ, η, ζ for U, V, W , respectively, we find

$$\iint (l\xi + m\eta + n\zeta) dS = 0, \quad \dots \dots (4)$$

where the integration extends over any closed surface lying wholly in the fluid. Applying this to the closed surface formed by two cross-sections of a vortex-tube and the part of the walls intercepted between them, we find $\omega_1\sigma_1 = \omega_2\sigma_2$, where ω_1, ω_2 denote the angular velocities at the sections σ_1, σ_2 , respectively

Lord Kelvin's proof shews that the theorem is true even when ξ, η, ζ are discontinuous (in which case there may be an abrupt bend at some point of a vortex), provided only that u, v, w are continuous

An important consequence of the above theorem is that a vortex-line cannot begin or end at any point in the interior of the fluid. Any vortex-lines which exist must either form closed curves, or else traverse the fluid, beginning and ending on its boundaries. Compare Art 36

The theorem of Art 32 (5) may now be enunciated as follows. The circulation in any circuit is equal to the sum of the strengths of all the vortices which it embraces

146 It was proved in Art 33 that in a perfect fluid whose density is either uniform or a function of the pressure only, and which is subject

* There is here a divergence from prevalent usage, but the *circulation* round a vortex would seem to be the most natural measure of its intensity.

to forces having a single-valued potential, the circulation in any circuit moving with the fluid is constant

Applying this theorem to a circuit embracing a vortex-tube we find that the strength of any vortex is constant

If we take at any instant a surface composed wholly of vortex-lines, the circulation in any circuit drawn on it is zero, by Art 32, for we have $l\xi + m\eta + n\zeta = 0$ at every point of the surface. The preceding Art shews that if the surface be now supposed to move with the fluid, the circulation will always be zero in any circuit drawn on it, and therefore the surface will always consist of vortex-lines. Again, considering two such surfaces, it is plain that their intersection must always be a vortex-line, whence we derive the theorem that the vortex-lines move with the fluid.

This remarkable theorem was first given by von Helmholtz for the case of incompressibility, the preceding proof, by Lord Kelvin, shews that it holds for all fluids subject to the conditions above stated.

The theorem that the circulation in any circuit moving with the fluid is invariable constitutes the sole and sufficient appeal to Dynamics which it is necessary to make in the investigations of this Chapter. It is based on the hypothesis of a continuous distribution of pressure, and (conversely) implies this. For if in any problem we have discovered functions u, v, w of x, y, z, t , which satisfy the kinematical conditions, then, if this solution is to be also *dynamically* possible, the relation of the pressures about two moving particles A, B must be given by the formula (2) of Art 33, viz.

$$\left[\int_A^B \frac{dp}{\rho} + \Omega - \frac{1}{2}U^2 \right]_A^B = - \frac{D}{Dt} \int_A^B (u dx + v dy + w dz) \quad \dots \quad (1)$$

It is therefore necessary and sufficient that the expression on the right hand should be the same for all paths of integration (moving with the fluid) which can be drawn from A to B . This is secured if, and only if, the assumed values of u, v, w make the vortex-lines move with the fluid, and also make the strength of every vortex constant with respect to the time.

It is easily seen that the argument is in no way impaired if the assumed values of u, v, w make ξ, η, ζ discontinuous at certain surfaces, provided only that u, v, w are themselves everywhere continuous.

On account of their historical interest, one or two independent proofs of the preceding theorems may be briefly indicated, and their mutual relations pointed out.

Of these perhaps the most conclusive is based upon a slight generalization of some equations given originally by Cauchy in the introduction to his great memoir on Waves*, and employed by him to demonstrate Lagrange's velocity-potential theorem.

* *l c ante* p 15

equations (2) of Art 15, yield, on elimination of the function χ by cross-differentia-

$$\frac{\partial u}{\partial b} \frac{\partial x}{\partial c} - \frac{\partial u}{\partial c} \frac{\partial x}{\partial b} + \frac{\partial v}{\partial b} \frac{\partial y}{\partial c} - \frac{\partial v}{\partial c} \frac{\partial y}{\partial b} + \frac{\partial w}{\partial b} \frac{\partial z}{\partial c} - \frac{\partial w}{\partial c} \frac{\partial z}{\partial b} = \frac{\partial w_0}{\partial b} - \frac{\partial v_0}{\partial c},$$

u, v, w have been written in place of $\partial x/\partial t, \partial y/\partial t, \partial z/\partial t$, respectively), with two symmetrical equations. If in these equations we replace the differential coefficients of with respect to a, b, c , by their values in terms of differential coefficients of the quantities with respect to x, y, z , we obtain

$$\left. \begin{aligned} \xi \frac{\partial(y, z)}{\partial(b, c)} + \eta \frac{\partial(z, x)}{\partial(b, c)} + \zeta \frac{\partial(x, y)}{\partial(b, c)} &= \xi_0, \\ \xi \frac{\partial(y, z)}{\partial(c, a)} + \eta \frac{\partial(z, x)}{\partial(c, a)} + \zeta \frac{\partial(x, y)}{\partial(c, a)} &= \eta_0, \\ \xi \frac{\partial(y, z)}{\partial(a, b)} + \eta \frac{\partial(z, x)}{\partial(a, b)} + \zeta \frac{\partial(x, y)}{\partial(a, b)} &= \zeta_0 \end{aligned} \right\} \quad (2)$$

multiply these by $\partial x/\partial a, \partial x/\partial b, \partial x/\partial c$, in order, and add, then, taking account of the Lagrangian equation of continuity (Art 14 (1)) we deduce the first of the following symmetrical equations

$$\left. \begin{aligned} \frac{\xi}{\rho} &= \frac{\xi_0}{\rho_0} \frac{\partial x}{\partial a} + \frac{\eta_0}{\rho_0} \frac{\partial x}{\partial b} + \frac{\zeta_0}{\rho_0} \frac{\partial x}{\partial c}, \\ \frac{\eta}{\rho} &= \frac{\xi_0}{\rho_0} \frac{\partial y}{\partial a} + \frac{\eta_0}{\rho_0} \frac{\partial y}{\partial b} + \frac{\zeta_0}{\rho_0} \frac{\partial y}{\partial c}, \\ \frac{\zeta}{\rho} &= \frac{\xi_0}{\rho_0} \frac{\partial z}{\partial a} + \frac{\eta_0}{\rho_0} \frac{\partial z}{\partial b} + \frac{\zeta_0}{\rho_0} \frac{\partial z}{\partial c} \end{aligned} \right\} \quad (3)$$

In the particular case of an incompressible fluid ($\rho = \rho_0$) these differ only in the use of notation ξ, η, ζ from the equations given by Cauchy. They shew at once that if the values ξ_0, η_0, ζ_0 of the component rotations vanish for any particle of the fluid, then they are always zero for that particle. This constitutes in fact Cauchy's proof of Lagrange's theorem.

Interpret (3) in the general case, let us take at time $t=0$ a linear element coincident with a vortex-line, say

$$\delta a, \delta b, \delta c = \epsilon \frac{\xi_0}{\rho_0}, \epsilon \frac{\eta_0}{\rho_0}, \epsilon \frac{\zeta_0}{\rho_0},$$

ϵ is infinitesimal. If we suppose this element to move with the fluid, the equations shew that its projections on the co-ordinate axes at any other time will be given by

$$\delta x, \delta y, \delta z = \epsilon \frac{\xi}{\rho}, \epsilon \frac{\eta}{\rho}, \epsilon \frac{\zeta}{\rho},$$

the element will still form part of a vortex-line, and its length (δs , say) will vary as $1/\rho$. Here ω is the resultant angular velocity. But if σ be the cross-section of a vortex-line having δs as axis, the product $\rho \sigma \delta s$ is constant with regard to the time. Hence the length $2\omega\sigma$ of the vortex is constant*.

The proof given originally by von Helmholtz depends on a system of three equations

see Nanson, *Mess of Math*, t iii p 120 (1874), Kirchhoff, *Mechanik*, c xv (1876), *Math and Phys. Papers*, t ii p 47 (1883)

which, when generalized so as to apply to any fluid in which ρ is a function of p only, become*

$$\left. \begin{aligned} \frac{D}{Dt} \left(\frac{\xi}{\rho} \right) &= \frac{\xi}{\rho} \frac{\partial u}{\partial x} + \frac{\eta}{\rho} \frac{\partial u}{\partial y} + \frac{\zeta}{\rho} \frac{\partial u}{\partial z}, \\ \frac{D}{Dt} \left(\frac{\eta}{\rho} \right) &= \frac{\xi}{\rho} \frac{\partial v}{\partial x} + \frac{\eta}{\rho} \frac{\partial v}{\partial y} + \frac{\zeta}{\rho} \frac{\partial v}{\partial z}, \\ \frac{D}{Dt} \left(\frac{\zeta}{\rho} \right) &= \frac{\xi}{\rho} \frac{\partial w}{\partial x} + \frac{\eta}{\rho} \frac{\partial w}{\partial y} + \frac{\zeta}{\rho} \frac{\partial w}{\partial z} \end{aligned} \right\} \quad (4)$$

These may be obtained as follows The dynamical equations of Art 6 may be written, when a force-potential Ω exists, in the forms

$$\left. \begin{aligned} \frac{\partial u}{\partial t} - 2v\zeta + 2w\eta &= -\frac{\partial \chi'}{\partial x}, \\ \frac{\partial v}{\partial t} - 2w\xi + 2u\zeta &= -\frac{\partial \chi'}{\partial y}, \\ \frac{\partial w}{\partial t} - 2u\eta + 2v\xi &= -\frac{\partial \chi'}{\partial z}, \end{aligned} \right\} \quad (5)$$

provided

$$\chi' = \int \frac{d\rho}{\rho} + \frac{1}{2} Q^2 + \Omega, \quad \dots \quad (6)$$

and $Q^2 = u^2 + v^2 + w^2$. From the second and third of these we obtain, eliminating χ' by cross-differentiation,

$$\frac{\partial \xi}{\partial t} + v \frac{\partial \xi}{\partial y} + w \frac{\partial \xi}{\partial z} - u \left(\frac{\partial \eta}{\partial y} + \frac{\partial \zeta}{\partial z} \right) = \eta \frac{\partial u}{\partial y} + \zeta \frac{\partial u}{\partial z} - \xi \left(\frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} \right).$$

$$\text{Remembering the relation} \quad \frac{\partial \xi}{\partial v} + \frac{\partial \eta}{\partial y} + \frac{\partial \zeta}{\partial z} = 0, \quad \dots \quad (7)$$

and the equation of continuity

$$\frac{D\rho}{Dt} + \rho \left(\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} \right) = 0, \quad \dots \quad (8)$$

we easily deduce the first of equations (4)

To interpret these equations we take, at time t , a linear element whose projections on the co-ordinate axes are

$$\delta x, \delta y, \delta z = \epsilon \frac{\xi}{\rho}, \epsilon \frac{\eta}{\rho}, \epsilon \frac{\zeta}{\rho}, \quad \dots \quad (9)$$

where ϵ is infinitesimal. If this element be supposed to move with the fluid, the rate at which δx is increasing is equal to the difference of the values of u at the two ends, whence

$$\frac{D\delta x}{Dt} = \epsilon \frac{\xi}{\rho} \frac{\partial u}{\partial x} + \epsilon \frac{\eta}{\rho} \frac{\partial u}{\partial y} + \epsilon \frac{\zeta}{\rho} \frac{\partial u}{\partial z}.$$

It follows, by (4), that

$$\frac{D}{Dt} \left(\delta x - \epsilon \frac{\xi}{\rho} \right) = 0, \quad \frac{D}{Dt} \left(\delta y - \epsilon \frac{\eta}{\rho} \right) = 0, \quad \frac{D}{Dt} \left(\delta z - \epsilon \frac{\zeta}{\rho} \right) = 0 \quad \dots \quad (10)$$

Von Helmholtz concludes that if the relations (9) hold at time t , they will hold at time $t + \delta t$, and so on, continually. The inference is, however, not quite rigorous, it is in fact

* Nanson, *l c.*

open to the criticisms which Stokes* directed against various defective proofs of Lagrange's velocity-potential theorem†.

By way of establishing a connection with Lord Kelvin's investigation we may notice that the equations (2) express that the circulation is constant in each of three infinitely small circuits initially perpendicular, respectively, to the three co-ordinate axes. Taking, for example, the circuit which initially bounded the rectangle $\delta b \delta c$, and denoting by A, B, C the areas of its projections at time t on the co-ordinate planes, we have

$$A = \frac{\partial(y, z)}{\partial(b, c)} \delta b \delta c, \quad B = \frac{\partial(z, x)}{\partial(b, c)} \delta b \delta c, \quad C = \frac{\partial(x, y)}{\partial(b, c)} \delta b \delta c,$$

so that the first of the equations referred to is equivalent‡ to

$$\xi A + \eta B + \zeta C = \xi_0 \delta b \delta c. \quad (11)$$

147. It is easily seen by the same kind of argument as in Art 41 that no continuous irrotational motion is possible in an incompressible fluid filling infinite space, and subject to the condition that the velocity vanishes at infinity. This leads at once to the following theorem.

The motion of a fluid which fills infinite space, and is at rest at infinity, is determinate when we know the values of the expansion (θ , say) and of the component angular velocities ξ, η, ζ , at all points of the region.

For, if possible, let there be two sets of values, u_1, v_1, w_1 , and u_2, v_2, w_2 , of the component velocities, each satisfying the equations

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = \theta, \quad . \quad . \quad (1)$$

$$\frac{\partial w}{\partial y} - \frac{\partial v}{\partial z} = 2\xi, \quad \frac{\partial u}{\partial z} - \frac{\partial w}{\partial x} = 2\eta, \quad \frac{\partial v}{\partial x} - \frac{\partial u}{\partial y} = 2\zeta, \quad . \quad . \quad (2)$$

throughout infinite space, and vanishing at infinity. The quantities

$$u' = u_1 - u_2, \quad v' = v_1 - v_2, \quad w' = w_1 - w_2,$$

will satisfy (1) and (2) with $\theta, \xi, \eta, \zeta = 0$, and will vanish at infinity. Hence, in virtue of the result above stated, they will everywhere vanish, and there is only one possible motion satisfying the given conditions.

* *l.c. ante* p 15

† It may be mentioned that, in the case of an incompressible fluid, equations somewhat similar to (4) had been established by Lagrange, *Miscell. Taur.*, t. II (1760) [*Oeuvres*, t. I p 442]. The author is indebted for this reference, and for the above remark on von Helmholtz' investigation, to Prof. Larmor. Equations equivalent to those given by Lagrange were obtained independently by Stokes, *l.c.*, and made the basis of a rigorous proof of the velocity-potential theorem.

‡ Nanson, *Mess. of Math.*, t. VII p 182 (1878). A similar interpretation of von Helmholtz' equations was given by the author of this work in the *Mess. of Math.*, t. VII p 41 (1877).

Finally it may be noted that another proof of Lagrange's theorem, based on elementary dynamical principles, without special reference to the hydrokinetic equations, was indicated by Stokes, *Camb. Trans.*, t. VIII [*Math. and Phys. Papers*, t. I p 113], and carried out by Lord Kelvin in his paper on Vortex Motion.

In the same way we can shew that the motion of a fluid occupying any *limited* simply-connected region is determinate when we know the values of the expansion, and of the component rotations, at every point of the region, and the value of the normal velocity at every point of the boundary. In the case of a multiply-connected region we must add to the above data the values of the circulations in the several independent circuits of the region.

148 If, in the case of infinite space, the quantities θ , ξ , η , ζ all vanish beyond some finite distance of the origin, the complete determination of u , v , w in terms of them can be effected as follows*.

The component velocities due to the *expansion* can be written down at once from Art. 56 (1), it being evident that the expansion θ' in an element $\delta x' \delta y' \delta z'$ is equivalent to a simple source of strength $\theta' \delta x' \delta y' \delta z'$. We thus obtain

$$u = -\frac{\partial \Phi}{\partial x}, \quad v = -\frac{\partial \Phi}{\partial y}, \quad w = -\frac{\partial \Phi}{\partial z}, \quad \dots \quad (1)$$

where
$$\Phi = \frac{1}{4\pi} \iiint \frac{\theta'}{r} dx' dy' dz', \quad \dots \dots \dots (2)$$

r denoting the distance between the point (x', y', z') at which the volume-element of the integral is situate and the point (x, y, z) at which the values of u , v , w are required, viz.

$$r = \{(x - x')^2 + (y - y')^2 + (z - z')^2\}^{\frac{1}{2}},$$

and the integration including all parts of space at which θ' differs from zero.

To find the velocities due to the *vortices*, we note that when there is no expansion, the flux across any two open surfaces bounded by the same curve as edge will be the same, and will therefore be determined solely by the configuration of the edge. This suggests that the flux through any closed curve may be expressed as a line-integral taken round the curve, say

$$\int (Fdx + Gdy + Hdz). \quad \dots \dots (3)$$

On this hypothesis we shall have, by the method of Art. 31,

$$u = \frac{\partial H}{\partial y} - \frac{\partial G}{\partial z}, \quad v = \frac{\partial F}{\partial z} - \frac{\partial H}{\partial x}, \quad w = \frac{\partial G}{\partial x} - \frac{\partial F}{\partial y}. \quad (4)$$

To test the assumption, we must have

$$2\xi = \frac{\partial w}{\partial y} - \frac{\partial u}{\partial z} = \frac{\partial}{\partial x} \left(\frac{\partial F}{\partial x} + \frac{\partial G}{\partial y} + \frac{\partial H}{\partial z} \right) - \nabla^2 F,$$

* The investigation which follows is substantially that given by Helmholtz. The kinematical problem in question was first solved, in a slightly different manner, by Stokes, "On the Dynamical Theory of Diffraction," *Camb. Trans.*, t. ix. (1849) [*Math. and Phys. Papers*, t. ii pp. 254]

with two similar equations. The quantities F , G , H will in any case be indeterminate to the extent of three additive functions of the forms $\partial\chi/\partial x$, $\partial\chi/\partial y$, $\partial\chi/\partial z$, respectively, and we may, if we please, suppose χ to be chosen so that

$$\frac{\partial F}{\partial x} + \frac{\partial G}{\partial y} + \frac{\partial H}{\partial z} = 0, \quad \dots \dots \dots (5)$$

in which case $\nabla^2 F = -2\xi$, $\nabla^2 G = -2\eta$, $\nabla^2 H = -2\zeta$ (6)

Particular solutions of these equations are obtained by equating F , G , H to the potentials of distributions of matter whose volume-densities are $\xi/2\pi$, $\eta/2\pi$, $\zeta/2\pi$, respectively, thus

$$F = \frac{1}{2\pi} \iiint \frac{\xi'}{r} dx' dy' dz', \quad G = \frac{1}{2\pi} \iiint \frac{\eta'}{r} dx' dy' dz', \quad H = \frac{1}{2\pi} \iiint \frac{\zeta'}{r} dx' dy' dz',$$

. (7)

where the accents attached to ξ , η , ζ are used to distinguish the values of these quantities at the point (x', y', z') . The integrations are to include, of course, all places where ξ , η , ζ differ from zero.

Moreover, since $\partial/\partial x \ r^{-1} = -\partial/\partial x' \ r^{-1}$, the formulae (7) make

$$\frac{\partial F}{\partial x} + \frac{\partial G}{\partial y} + \frac{\partial H}{\partial z} = -\frac{1}{2\pi} \iiint \left(\xi' \frac{\partial}{\partial x'} \frac{1}{r} + \eta' \frac{\partial}{\partial y'} \frac{1}{r} + \zeta' \frac{\partial}{\partial z'} \frac{1}{r} \right) dx' dy' dz'$$

The right-hand member vanishes, by the theorem of Art 42 (4), since

$$\frac{\partial \xi}{\partial x} + \frac{\partial \eta}{\partial y} + \frac{\partial \zeta}{\partial z} = 0$$

everywhere, whilst

$$l\xi + m\eta + n\zeta = 0$$

at the surfaces of the vortices (where ξ , η , ζ may be discontinuous), and ξ , η , ζ vanish at infinity. Hence no additions to the values (7) of F , G , H are necessary in order that (5) may be satisfied.

The complete solution of our problem is obtained by superposition of the results contained in (1) and (4), viz.

$$\left. \begin{aligned} u &= -\frac{\partial \Phi}{\partial x} + \frac{\partial H}{\partial y} - \frac{\partial G}{\partial z}, \\ v &= -\frac{\partial \Phi}{\partial y} + \frac{\partial F}{\partial z} - \frac{\partial H}{\partial x}, \\ w &= -\frac{\partial \Phi}{\partial z} + \frac{\partial G}{\partial x} - \frac{\partial F}{\partial y}, \end{aligned} \right\} \dots \dots \dots (8)$$

where Φ , F , G , H have the values given in (2) and (7).

When the region occupied by the fluid is not unlimited, but is bounded (in whole or in part) by surfaces at which the normal velocity is given, and

when further (in the case of a cyclic region) the value of the circulation in each of the independent circuits is prescribed, the problem may by a similar analysis be reduced to one of irrotational motion, of the kind considered in Chap III, and there proved to be determinate. This may be left to the reader, with the remark that if the vortices traverse the region, beginning and ending on the boundary, it is convenient to imagine them continued beyond it, or along the boundary, in such a manner that they form re-entrant filaments, and to make the integrals (7) refer to the complete system of vortices thus obtained. On this understanding the condition (5) will still be satisfied

There is an exact correspondence between the analytical relations above developed and those which obtain in the theory of Electro-magnetism. If, in the equations (1) and (2) of Art 147, we write

$$\alpha, \beta, \gamma, \rho, \quad p, \quad q, \quad r$$

for

$$u, v, w, \theta, \quad 2\xi, \quad 2\eta, \quad 2\zeta,$$

respectively, we obtain

$$\left. \begin{aligned} \frac{\partial \alpha}{\partial x} + \frac{\partial \beta}{\partial y} + \frac{\partial \gamma}{\partial z} &= \rho, \\ \frac{\partial \gamma}{\partial y} - \frac{\partial \beta}{\partial z} &= p, \quad \frac{\partial \alpha}{\partial z} - \frac{\partial \gamma}{\partial x} = q, \quad \frac{\partial \beta}{\partial x} - \frac{\partial \alpha}{\partial y} = r, \end{aligned} \right\} \dots \dots (9)$$

which are the fundamental relations of the theory referred to, viz. α, β, γ are the components of magnetic force, p, q, r those of electric current, and ρ is the volume-density of the imaginary magnetic matter by which any magnetization present in the field may be represented*. Hence, the vortex-filaments correspond to electric circuits, the strengths of the vortices to the strengths of the currents in these circuits, sources and sinks to positive and negative magnetic poles, and, finally, fluid velocity to magnetic force†

The analogy will of course extend to all results deduced from the fundamental relations, thus, in equations (8) Φ corresponds to the magnetic potential and F, G, H to the components of 'electro-magnetic momentum.'

149 To interpret the result contained in Art. 148 (8), we may calculate the values of u, v, w due to an isolated re-entrant vortex-filament situate in an infinite mass of incompressible fluid which is at rest at infinity

Since $\theta = 0$, we shall have $\Phi = 0$. Again, to calculate the values of F, G, H , we may replace the volume-element $\delta x' \delta y' \delta z'$ by $\sigma' \delta s'$, where $\delta s'$ is an element of the length of the filament, and σ' its cross-section. Also

$$\xi' = \omega' \frac{dx'}{ds'}, \quad \eta' = \omega' \frac{dy'}{ds'}, \quad \zeta' = \omega' \frac{dz'}{ds'},$$

* Cf Maxwell, *Electricity and Magnetism*, Art 607. The comparison has been simplified by the adoption of the 'rational' system of electrical units advocated by Heaviside, *Electrical Papers*, London, 1892, t 1 p 199

† This analogy was first pointed out by Helmholtz, it has been extensively utilized by Lord Kelvin in his papers on *Electrostatics and Magnetism* (cited *ante* p 36).

where ω' is the angular velocity of the fluid. Hence the formulae (7) of Art 148 become

$$F = \frac{\kappa}{4\pi} \int \frac{dx'}{r}, \quad G = \frac{\kappa}{4\pi} \int \frac{dy'}{r}, \quad H = \frac{\kappa}{4\pi} \int \frac{dz'}{r}, \quad \dots \quad (1)$$

where $\kappa = 2\omega'\sigma'$, measures the strength of the vortex, and the integrals are to be taken along the whole length of the filament.

Hence, by Art 148 (4), we have

$$u = \frac{\kappa}{4\pi} \int \left(\frac{\partial}{\partial y} \frac{1}{r} \cdot dz' - \frac{\partial}{\partial z} \frac{1}{r} dy' \right),$$

with similar results for v, w We thus find*

$$\left. \begin{aligned} u &= \frac{\kappa}{4\pi} \int \left(\frac{dy'}{ds'} \frac{z-z'}{r} - \frac{dz'}{ds'} \frac{y-y'}{r} \right) \frac{ds'}{r^2}, \\ v &= \frac{\kappa}{4\pi} \int \left(\frac{dz'}{ds'} \frac{x-x'}{r} - \frac{dx'}{ds'} \frac{z-z'}{r} \right) \frac{ds'}{r^2}, \\ w &= \frac{\kappa}{4\pi} \int \left(\frac{dx'}{ds'} \frac{y-y'}{r} - \frac{dy'}{ds'} \frac{x-x'}{r} \right) \frac{ds'}{r^2}. \end{aligned} \right\} \quad \dots \quad (2)$$

If $\Delta u, \Delta v, \Delta w$ denote the parts of these expressions which involve the element $\delta s'$ of the filament, it appears that the resultant of $\Delta u, \Delta v, \Delta w$ is perpendicular to the plane containing the direction of the vortex-line at (x', y', z') and the line r , and that its sense is that in which the point (x, y, z) would be carried if it were attached to a rigid body rotating with the fluid element at (x', y', z') For the magnitude of the resultant we have

$$\{(\Delta u)^2 + (\Delta v)^2 + (\Delta w)^2\}^{\frac{1}{2}} = \frac{\kappa}{4\pi} \frac{\sin \chi \delta s'}{r^2}, \quad \dots \quad (3)$$

where χ is the angle which r makes with the vortex-line at (x', y', z')

With the change of symbols indicated in the preceding Art this result becomes identical with the law of action of an electric current on a magnetic pole†.

Velocity-Potential due to a Vortex

150 At points external to the vortices there exists a velocity-potential, whose value may be obtained as follows Taking for shortness the case of a single re-entrant vortex, we have from the preceding Art., in the case of an incompressible fluid,

$$u = \frac{\kappa}{4\pi} \int \left(\frac{\partial}{\partial z'} \frac{1}{r} dy' - \frac{\partial}{\partial y'} \frac{1}{r} dz' \right) \dots \dots \dots (1)$$

* These are equivalent to the forms obtained by Stokes, *l.c. ante* p 199

† Ampère, *Théorie mathématique des phénomènes électro-dynamiques*, Paris, 1826

By Stokes' Theorem (Art 32 (6)) we can replace a line-integral extending round a closed curve by a surface-integral taken over any surface bounded by that curve; viz. we have, with a slight change of notation,

$$\int (Pdx' + Qdy' + Rdz') = \iint \left\{ l \left(\frac{\partial R}{\partial y'} - \frac{\partial Q}{\partial z'} \right) + m \left(\frac{\partial P}{\partial z'} - \frac{\partial R}{\partial x'} \right) + n \left(\frac{\partial Q}{\partial x'} - \frac{\partial P}{\partial y'} \right) \right\} dS'.$$

If we put $P = 0$, $Q = \frac{\partial}{\partial z'} \frac{1}{r}$, $R = -\frac{\partial}{\partial y'} \frac{1}{r}$,

we find

$$\frac{\partial R}{\partial y'} - \frac{\partial Q}{\partial z'} = \frac{\partial^2}{\partial x'^2} \frac{1}{r'}, \quad \frac{\partial P}{\partial z'} - \frac{\partial R}{\partial x'} = \frac{\partial^2}{\partial x' \partial y'} \frac{1}{r'}, \quad \frac{\partial Q}{\partial x'} - \frac{\partial P}{\partial y'} = \frac{\partial^2}{\partial x' \partial z'} \frac{1}{r'},$$

so that (1) may be written

$$u = \frac{\kappa}{4\pi} \iint \left(l \frac{\partial}{\partial x'} + m \frac{\partial}{\partial y'} + n \frac{\partial}{\partial z'} \right) \frac{d}{dx'} \frac{1}{r} dS'$$

Hence, and by similar reasoning, we have, since $\partial/\partial x' \ r^{-1} = -\partial/\partial x \ r^{-1}$,

$$u = -\frac{\partial \phi}{\partial x}, \quad v = -\frac{\partial \phi}{\partial y}, \quad w = -\frac{\partial \phi}{\partial z}, \quad \dots (2)$$

where $\phi = \frac{\kappa}{4\pi} \iint \left(l \frac{\partial}{\partial x'} + m \frac{\partial}{\partial y'} + n \frac{\partial}{\partial z'} \right) \frac{1}{r} dS'. \dots (3)$

Here l, m, n denote the direction-cosines of the normal to the element $\delta S'$ of a surface bounded by the vortex-filament.

The formula (3) may be otherwise written

$$\phi = \frac{\kappa}{4\pi} \iint \frac{\cos \mathfrak{S}}{r^2} dS', \quad \dots (4)$$

where \mathfrak{S} denotes the angle between r and the normal (l, m, n). Since $\cos \theta \delta S'/r^2$ measures the elementary solid angle subtended by $\delta S'$ at (x, y, z) , we see that the velocity-potential at any point, due to a single re-entrant vortex, is equal to the product of $\kappa/4\pi$ into the solid angle which a surface bounded by the vortex subtends at that point

Since this solid angle changes by 4π when the point in question describes a circuit embracing the vortex, we verify that the value of ϕ given by (4) is cyclic, the cyclic constant being κ Cf. Art 145

It may be noticed that the expression in (4) is equal to the flux (in the negative direction) through the aperture of the vortex, due to a point-source of strength κ at the point (x, y, z) .

Comparing (4) with Art 56 (4) we see that a vortex is, in a sense, equivalent to a uniform distribution of double sources over any surface bounded by it. The axes of the double sources must be supposed to be everywhere normal to the surface, and the density of the distribution to be

equal to the strength of the vortex. It is here assumed that the relation between the positive direction of the normal and the positive direction of the axis of the vortex-filament is of the 'right-handed' type. See Art 31

Conversely, it may be shewn that any distribution of double sources over a *closed* surface, the axes being directed along the normals, may be replaced by a system of closed vortex-filaments lying in the surface*. The same thing will appear independently from the investigation of the next Art

Vortex-Sheets

151 We have so far assumed u, v, w to be continuous. We may now shew how cases where surfaces of discontinuity present themselves may be brought within the scope of our theorems

The case of a discontinuity in the *normal* velocity alone has already been treated in Art 58. If u, v, w denote the component velocities on one side, and u', v', w' those on the other, it was found that the circumstances could be represented by imagining a distribution of simple sources, with surface-density

$$l(u' - u) + m(v' - v) + n(w' - w),$$

where l, m, n denote the direction-cosines of the normal drawn towards the side to which the accents refer

Let us next consider the case where the *tangential* velocity (only) is discontinuous, so that

$$l(u' - u) + m(v' - v) + n(w' - w) = 0 \quad . \quad . \quad (1)$$

We will suppose that the lines of *relative* motion, which are defined by the differential equations

$$\frac{dx}{u' - u} = \frac{dy}{v' - v} = \frac{dz}{w' - w}, \quad . \quad . \quad . \quad . \quad . \quad (2)$$

are traced on the surface, and that the system of orthogonal trajectories to these lines is also drawn. Let $PQ, P'Q'$ be linear elements drawn close to the surface, on the two sides, parallel to a line of the system (2), and let PP' and QQ' be normal to the surface and infinitely small in comparison with PQ or $P'Q'$. The circulation in the circuit $P'Q'QP$ will then be equal to $(q' - q)PQ$, where q, q' denote the absolute velocities on the two sides. This is the same as if the position of the surface were occupied by an infinitely thin stratum of vortices, the orthogonal trajectories above-mentioned being the vortex-lines, and the angular velocity ω and the (variable) thickness δn of the stratum being connected by the relation

$$2\omega\delta n = q' - q. \quad . \quad . \quad . \quad . \quad . \quad (3)$$

* Cf Maxwell, *Electricity and Magnetism*, Arts. 485, 652

The same result follows from a consideration of the discontinuities which occur in the values of u, v, w as determined by the formulae (4) and (7) of Art 148, when we apply these to the case of a stratum of thickness δn within which ξ, η, ζ are infinite, but so that $\xi\delta n, \eta\delta n, \zeta\delta n$ are finite*

It was shewn in Arts 147, 148 that any continuous motion of a fluid filling infinite space, and at rest at infinity, may be regarded as due to a suitable arrangement of sources and vortices distributed with finite density. We have now seen how by considerations of continuity we can pass to the case where the sources and vortices are distributed with infinite volume-density, but finite surface-density, over surfaces. In particular, we may take the case where the infinite fluid in question is incompressible, and is divided into two portions by a closed surface over which the normal velocity is continuous, but the tangential velocity discontinuous, as in Art. 58 (12). This is equivalent to a vortex-sheet, and we infer that every continuous irrotational motion, whether cyclic or not, of an incompressible substance occupying any region whatever, may be regarded as due to a certain distribution of vortices over the boundaries which separate it from the rest of infinite space. In the case of a region extending to infinity, the distribution is confined to the *finite* portion of the boundary, provided the fluid be at rest at infinity.

This theorem is complementary to the results obtained in Art. 58.

The foregoing conclusions may be illustrated by means of the results of Art 91. Thus when a normal velocity S_n was prescribed over the sphere $r=a$, the values of the velocity-potential for the internal and external space were found to be

$$\phi = \frac{a}{n} \left(\frac{r}{a}\right)^n S_n, \quad \text{and} \quad \phi = -\frac{a}{n+1} \left(\frac{a}{r}\right)^{n+1} S_n,$$

respectively. Hence if $\delta\epsilon$ be the angle which a linear element drawn on the surface subtends at the centre, the relative velocity estimated in the direction of this element will be

$$\frac{2n+1}{n(n+1)} \frac{\partial S_n}{\partial \epsilon}.$$

The resultant relative velocity is therefore tangential to the surface, and perpendicular to the contour lines ($S_n = \text{const}$) of the surface-harmonic S_n , which are therefore the vortex-lines.

For example, if we have a thin spherical shell filled with and surrounded by liquid, moving as in Art 92 parallel to the axis of x , the motion of the fluid, whether internal or external, will be that due to a system of vortices arranged in parallel circles on the sphere, the strength of an elementary vortex being proportional to the projection, on the axis of x , of the breadth of the corresponding zone of the surface†

* Helmholtz, *l.c.* ante p 193

† The same statements hold also for an ellipsoidal shell moving parallel to one of its principal axes. See Art 114.

Impulse and Energy of a Vortex-System

152. The following investigations relate to the case of a vortex-system of finite dimensions in an incompressible fluid which fills infinite space and is at rest at infinity.

If X' , Y' , Z' be components of a distribution of impulsive force (in general cyclic) which would generate the actual motion (u , v , w) instantaneously from rest, we have by Art 12 (1)

$$X' - \frac{1}{\rho} \frac{\partial \varpi}{\partial x} = u, \quad Y' - \frac{1}{\rho} \frac{\partial \varpi}{\partial y} = v, \quad Z' - \frac{1}{\rho} \frac{\partial \varpi}{\partial z} = w, \quad \dots \quad (1)$$

where ϖ is the impulsive pressure. The problem of finding X' , Y' , Z' , and ϖ , in terms of u , v , w , so as to satisfy these three equations, is to a certain extent indeterminate, but a sufficient solution for our purpose may be obtained as follows.

Let us imagine a simply-connected surface S to be drawn enclosing all the vortices. Over this surface, and through the external space, let us put

$$\varpi = \rho \phi, \quad \dots \quad (2)$$

where ϕ is the velocity-potential of the vortex-system, determined as in Art 150. Inside S let us take as the value of ϖ any single-valued function which is finite and continuous, coincides with (2) at S , and also satisfies the equation

$$\frac{\partial \varpi}{\partial n} = \rho \frac{\partial \phi}{\partial n}, \quad \dots \quad \dots \quad (3)$$

at S , where δn denotes as usual an element of the normal. It follows from these conditions, which can evidently be satisfied in an infinite number of ways, that the space-derivatives $\partial \varpi / \partial x$, $\partial \varpi / \partial y$, $\partial \varpi / \partial z$ will be continuous at the surface S . The values of X' , Y' , Z' are now given by the formulae (1); they vanish at the surface S , and at all external points.

The force- and couple-equivalents of the distribution (X' , Y' , Z') constitute the 'impulse' of the vortex-system. We are at present concerned only with the instantaneous state of the system, but it may be recalled that, when no extraneous forces act, this impulse is, by the argument of Art 119, constant in every respect.

Now, considering the matter inclosed within the surface S , we find, resolving parallel to x ,

$$\iiint \rho X' dx dy dz = \rho \iiint u dx dy dz - \rho \iint l \phi dS, \quad \dots \quad (4)$$

if l , m , n be the direction-cosines of the inwardly-directed normal to an element δS of the surface. Let us first take the case of a single vortex-filament of infinitely small section. The fluid velocity being everywhere

finite and continuous, the parts of the volume-integral on the right-hand side of (4) which are due to the substance of the vortex itself may be neglected in comparison with those due to the remainder of the space included within S . Hence we may write

$$\iiint u \, dx \, dy \, dz = - \iiint \frac{\partial \phi}{\partial x} \, dx \, dy \, dz = \iint l \phi \, dS + \kappa \iint l \, dS', \quad (5)$$

where ϕ has the value given by Art 150 (4), κ denoting the cyclic constant of ϕ , and $\delta S'$ an element of any surface bounded by the vortex. Substituting in (4), we infer that the components of the impulse parallel to the co-ordinate axes are

$$\kappa \rho \iint l \, dS', \quad \kappa \rho \iint m \, dS', \quad \kappa \rho \iint n \, dS' \quad \dots \quad (6)$$

Again, taking moments about Ox ,

$$\iiint \rho (yZ' - zY') \, dx \, dy \, dz = \rho \iiint (yw - zv) \, dx \, dy \, dz - \rho \iint (ny - mz) \phi \, dS \quad (7)$$

For the same reason as before, we may substitute, for the volume-integral on the right-hand side,

$$- \iint \left(y \frac{\partial \phi}{\partial z} - z \frac{\partial \phi}{\partial y} \right) \, dx \, dy \, dz = \iint (ny - mz) \phi \, dS + \kappa \iint (ny - mz) \, dS' \quad \dots (8)$$

Hence, and by symmetry, we find, for the moments of the impulse about the co-ordinate axes,

$$\kappa \rho \iint (ny - mz) \, dS', \quad \kappa \rho \iint (lz - nx) \, dS', \quad \kappa \rho \iint (mx - ly) \, dS' \quad \dots (9)$$

The surface-integrals contained in (6) and (9) may be replaced by line-integrals taken along the vortex. In the case of (6) it is obvious that the coefficients of $\kappa \rho$ are the projections on the co-ordinate axes of any area bounded by the vortex, so that the components in question take the forms

$$\frac{1}{2} \kappa \int \left(y' \frac{dz'}{ds'} - z' \frac{dy'}{ds'} \right) ds', \quad \frac{1}{2} \kappa \int \left(z' \frac{dx'}{ds'} - x' \frac{dz'}{ds'} \right) ds', \quad \frac{1}{2} \kappa \int \left(x' \frac{dy'}{ds'} - y' \frac{dx'}{ds'} \right) ds'. \quad \dots (10)$$

For the similar transformation of (9) we must have recourse to Stokes' Theorem, we obtain without difficulty the forms

$$\frac{1}{2} \kappa \rho \int (y'^2 + z'^2) \frac{dx'}{ds'} ds', \quad \frac{1}{2} \kappa \rho \int (z'^2 + x'^2) \frac{dy'}{ds'} ds', \quad \frac{1}{2} \kappa \rho \int (x'^2 + y'^2) \frac{dz'}{ds'} ds' \quad \dots (11)$$

From (10) and (11) we can derive by superposition the components of the force- and couple-resultants of any finite system of vortices. Denoting these by P , Q , R , and L , M , N , respectively, we find, putting

$$\begin{aligned} \kappa &= 2\omega' \sigma', \\ \omega' \frac{dx'}{ds'} &= \xi', & \omega' \frac{dy'}{ds'} &= \eta', & \omega' \frac{dz'}{ds'} &= \zeta', \end{aligned}$$

and replacing the volume-element $\sigma' \delta s'$ by $\delta x' \delta y' \delta z'$,

$$\left. \begin{aligned} P &= \rho \iiint (y\xi - z\eta) \, dx \, dy \, dz, & L &= \rho \iiint (y^2 + z^2) \xi \, dx \, dy \, dz, \\ Q &= \rho \iiint (z\xi - x\zeta) \, dx \, dy \, dz, & M &= \rho \iiint (z^2 + x^2) \eta \, dx \, dy \, dz, \\ R &= \rho \iiint (x\eta - y\xi) \, dx \, dy \, dz, & N &= \rho \iiint (x^2 + y^2) \zeta \, dx \, dy \, dz, \end{aligned} \right\} \dots (12)$$

where the accents have been dropped as no longer necessary*

153 Let us next consider the *energy* of the vortex-system. It is easily proved that under the circumstances presupposed, and in the absence of extraneous forces, this energy will be constant. For if T be the energy of the fluid bounded by any closed surface S , we have, putting $V=0$ in Art. 11 (5),

$$\frac{DT}{Dt} = \iint (lu + mv + nw) p \, dS \quad \dots \quad (1)$$

If the surface S enclose all the vortices, we may put

$$\frac{p}{\rho} = \frac{\partial \phi}{\partial t} - \frac{1}{2} q^2 + F(t), \quad \dots \quad (2)$$

and it easily follows from Art 150 (4) that at a great distance R from the vortices p will be finite, and $lu + mv + nw$ of the order R^{-3} , whilst when the surface S is taken wholly at infinity, the elements δS vary as R^2 . Hence, ultimately, the right-hand side of (1) vanishes, and we have

$$T = \text{const.} \quad \dots \quad (3)$$

We proceed to investigate one or two important kinematical expressions for T , still confining ourselves, for simplicity, to the case where the fluid (supposed incompressible) extends to infinity, and is at rest there, all the vortices being within a finite distance of the origin.

The first of these expressions is indicated by the electro-magnetic analogy pointed out in Art 148. Since $\theta=0$, and therefore $\Phi=0$, we have

$$\begin{aligned} 2T &= \rho \iiint (u^2 + v^2 + w^2) \, dx \, dy \, dz \\ &= \rho \iiint \left\{ u \left(\frac{\partial H}{\partial y} - \frac{\partial G}{\partial z} \right) + v \left(\frac{\partial F}{\partial z} - \frac{\partial H}{\partial x} \right) + w \left(\frac{\partial G}{\partial x} - \frac{\partial F}{\partial y} \right) \right\} \, dx \, dy \, dz, \end{aligned}$$

by Art 148 (4) The last member may be replaced by the sum of a surface-integral

$$\rho \iint \{ F(mw - nv) + G(nu - lw) + H(lv - mu) \} \, dS,$$

and a volume-integral

$$\rho \iiint \left\{ F \left(\frac{\partial w}{\partial y} - \frac{\partial v}{\partial z} \right) + G \left(\frac{\partial u}{\partial z} - \frac{\partial w}{\partial x} \right) + H \left(\frac{\partial v}{\partial x} - \frac{\partial u}{\partial y} \right) \right\} \, dx \, dy \, dz$$

* These expressions were given by J J Thomson, *On the Motion of Vortex Rings* (Adams Prize Essay), London, 1883, pp 5, 6

At points of the infinitely distant boundary, F , G , H are ultimately of the order R^{-2} , and u , v , w of the order R^{-3} , so that the surface-integral vanishes, and we have

$$T = \rho \iiint (F\xi + G\eta + H\zeta) dx dy dz, \quad \dots \dots \dots (4)$$

or, substituting the values of F , G , H from Art 148 (7),

$$T = \frac{\rho}{2\pi} \iiint \iiint \frac{\xi\xi' + \eta\eta' + \zeta\zeta'}{r} dx dy dz dx' dy' dz', \quad \dots \dots (5)$$

where each volume-integration extends over the whole space occupied by the vortices

A slightly different form may be given to this expression as follows. Regarding the vortex-system as made up of filaments, let δs , $\delta s'$ be elements of length of any two filaments, σ , σ' the corresponding cross-sections, and ω , ω' the corresponding angular velocities. The elements of volume may be taken to be $\sigma\delta s$ and $\sigma'\delta s'$, respectively, so that the expression following the integral signs in (5) is equivalent to

$$\frac{\cos \epsilon}{r} \omega \sigma \delta s \omega' \sigma' \delta s',$$

where ϵ is the angle between δs and $\delta s'$. If we put $2\omega\sigma = \kappa$, $2\omega'\sigma' = \kappa'$, we have

$$T = \frac{\rho}{4\pi} \sum \kappa \kappa' \iint \frac{\cos \epsilon}{r} ds ds', \quad \dots \dots \dots (6)$$

where the double integral is to be taken along the axes of the filaments, and the summation Σ includes (once only) every pair of filaments which are present

The factor of ρ in (6) is identical with the expression for the energy of a system of electric currents flowing along conductors coincident in position with the vortex-filaments, with strengths κ , κ' , respectively*. The above investigation is in fact merely an inversion of the argument given in treatises on Electro-magnetism, whereby it is proved that

$$\frac{1}{4\pi} \sum i i' \iint \frac{\cos \epsilon}{r} ds ds' = \frac{1}{2} \iiint (a^2 + \beta^2 + \gamma^2) dx dy dz,$$

i , i' denoting the strengths of the currents in the linear conductors whose elements are denoted by ds , ds' , and α , β , γ the components of magnetic force at any point of the field

The theorem of this Art is purely kinematical, and rests solely on the assumption that the functions u , v , w satisfy the equation of continuity,

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 0,$$

throughout infinite space, and vanish at infinity. It can therefore by an easy generalization be extended to a case considered in Art 143, where a liquid is supposed to circulate

* The 'rational' system of electrical units being understood, see *ante*, p. 201.

irrotationally through apertures in fixed solids, the values of u , v , w being now taken to be zero at all points of space not occupied by the fluid. The investigation of Art 151 shews that the distribution of velocity thus obtained may be regarded as due to a system of vortex-sheets coincident with the bounding surfaces. The energy of this system will be given by an obvious adaptation of the formula (3) above, and will therefore be proportional to that of the corresponding system of electric current-sheets. This proves a statement made by anticipation in Art 144.

Under the circumstances stated at the beginning of Art 152, we have another useful expression for T , viz

$$T = 2\rho \iiint \{u(y\zeta - z\eta) + v(z\xi - x\zeta) + w(x\eta - y\xi)\} dx dy dz \quad \dots (7)$$

To verify this, we take the right-hand member, and transform it by the process already so often employed, omitting the surface-integrals for the same reason as in the preceding Art. The first of the three terms gives

$$\begin{aligned} & \rho \iiint u \left\{ y \left(\frac{\partial v}{\partial x} - \frac{\partial u}{\partial y} \right) - z \left(\frac{\partial u}{\partial z} - \frac{\partial w}{\partial x} \right) \right\} dx dy dz \\ &= -\rho \iiint \left\{ (vy + wz) \frac{\partial u}{\partial x} - u^2 \right\} dx dy dz \end{aligned}$$

Transforming the remaining terms in the same way, adding, and making use of the equation of continuity, we obtain

$$\rho \iiint \left(u^2 + v^2 + w^2 + xu \frac{\partial u}{\partial x} + yv \frac{\partial v}{\partial y} + zw \frac{\partial w}{\partial z} \right) dx dy dz,$$

or, finally, on again transforming the last three terms,

$$\frac{1}{2}\rho \iiint (u^2 + v^2 + w^2) dx dy dz.$$

In the case of a finite region the surface-integrals must be retained*. This involves the addition to the right-hand side of (7) of the term

$$\rho \iint \{ (lu + mv + nw)(xu + yv + zw) - \frac{1}{2}(lx + my + nz) q^2 \} dS, \dots (8)$$

where $q^2 = u^2 + v^2 + w^2$. This simplifies in the case of a *fixed* boundary,

The value of the expression (7) must be unaltered by any displacement of the origin of co-ordinates. Hence we must have

$$\begin{aligned} \iint (v\zeta - w\eta) dx dy dz = 0, \quad \iint (w\xi - u\zeta) dx dy dz = 0, \quad \iint (u\eta - v\xi) dx dy dz = 0 \\ \dots \dots (9) \end{aligned}$$

These equations, which may easily be verified by partial integration, follow also from the consideration that the components of the impulse parallel to the co-ordinate axes must be constant. Thus, taking first the case of a fluid enclosed in a fixed envelope of finite size, we have, in the notation of Art 152,

$$P = \rho \iiint u dx dy dz - \rho \iint l \phi dS, \quad \dots \dots (10)$$

* J. J. Thomson, *l c.*

whence
$$\frac{dP}{dt} = \rho \iiint \frac{\partial u}{\partial t} dx dy dz - \rho \iint l \frac{\partial \phi}{\partial t} dS$$

$$= -\rho \iiint \frac{\partial \chi'}{\partial x} dx dy dz + 2\rho \iiint (v\xi - w\eta) dx dy dz - \rho \iint l \frac{\partial \phi}{\partial t} dS, \quad (11)$$

by Art 146 (5) The first and third terms of this cancel, since at the envelope we have $\chi' = \partial \phi / \partial t$ Hence for any re-entrant system of vortices enclosed in a fixed vessel, we have

$$\frac{dP}{dt} = 2\rho \iiint (v\xi - w\eta) dx dy dz, \quad (12)$$

with two similar equations It has been proved in Art 119 that if the containing vessel be infinitely large, and infinitely distant from the vortices, P is constant This gives the first of equations (9)

Conversely from (9), established otherwise, we could infer the constancy of the components P, Q, R of the impulse*

Rectilinear Vortices.

154 When the motion is in two dimensions x, y we have $w = 0$, whilst u, v are functions of x, y , only Hence $\xi = 0, \eta = 0$, so that the vortex-lines are straight lines parallel to z The theory then takes a very simple form

The formulae (8) of Art 148 are now replaced by

$$u = -\frac{\partial \phi}{\partial x} - \frac{\partial \psi}{\partial y}, \quad v = -\frac{\partial \phi}{\partial y} + \frac{\partial \psi}{\partial x}, \quad \dots \dots \dots (1)$$

the functions ϕ, ψ being subject to the equations

$$\nabla_1^2 \phi = -\theta, \quad \nabla_1^2 \psi = 2\zeta, \quad \dots \dots \dots (2)$$

where

$$\nabla_1^2 = \frac{\partial^2}{\partial x^2} + \frac{\partial^2}{\partial y^2},$$

and to the proper boundary-conditions

In the case of an incompressible fluid, to which we will now confine ourselves, we have

$$u = -\frac{\partial \psi}{\partial y}, \quad v = \frac{\partial \psi}{\partial x}, \quad \dots \dots \dots (3)$$

where ψ is the stream-function of Art 59 It is known from the theory of Attractions that the solution of

$$\nabla_1^2 \psi = 2\zeta, \quad \dots \dots \dots (4)$$

ζ being a given function of x, y , is

$$\psi = \frac{1}{\pi} \iint \zeta' \log r dx' dy' + \psi_0, \quad \dots \dots \dots (5)$$

where ζ' denotes the value of ζ at the point (x', y') , and r stands for

$$\{(x - x')^2 + (y - y')^2\}^{\frac{1}{2}}.$$

* Cf J. J. Thomson, *Motion of Vortex Rings*, p 5.

The 'complementary function' ψ_0 may be any solution of

$$\nabla_1^2 \psi_0 = 0, \quad \dots \dots \dots (6)$$

it enables us to satisfy the boundary-conditions.

In the case of an unlimited mass of liquid, at rest at infinity, ψ_0 is constant. The formulae (3) and (5) then give

$$u = -\frac{1}{\pi} \iint \zeta' \frac{y-y'}{r^2} dx' dy', \quad v = \frac{1}{\pi} \iint \zeta' \frac{x-x'}{r^2} dx' dy' \quad \dots (7)$$

Hence a vortex-filament whose co-ordinates are x', y' and whose strength is κ contributes to the motion at (x, y) a velocity whose components are

$$-\frac{\kappa}{2\pi} \frac{y-y'}{r^2}, \quad \text{and} \quad \frac{\kappa}{2\pi} \frac{x-x'}{r^2}$$

This velocity is perpendicular to the line joining the points (x, y) , (x', y') , and its amount is $\kappa/2\pi r$

Let us calculate the integrals $\iint u \zeta dx dy$, and $\iint v \zeta dx dy$, where the integrations include all portions of the plane xy for which ζ does not vanish. We have

$$\iint u \zeta dx dy = -\frac{1}{\pi} \iiint \zeta \zeta' \frac{y-y'}{r^2} dx dy dx' dy',$$

where each double integration includes the sections of all the vortices. Now, corresponding to any term

$$\zeta \zeta' \frac{y-y'}{r^2} dx dy dx' dy'$$

of this result, we have another

$$\zeta \zeta' \frac{y'-y}{r^2} dx dy dx' dy',$$

and these two neutralize each other. Hence, and by similar reasoning,

$$\iint u \zeta dx dy = 0, \quad \iint v \zeta dx dy = 0 \quad \dots \dots (8)$$

If as before we denote the strength of a vortex by κ , these results may be written

$$\sum \kappa u = 0, \quad \sum \kappa v = 0 \quad \dots \dots (9)$$

Since the strength of each vortex is constant with regard to the time, the equations (9) express that the point whose co-ordinates are

$$\bar{x} = \frac{\sum \kappa x}{\sum \kappa}, \quad \bar{y} = \frac{\sum \kappa y}{\sum \kappa}, \quad \dots \dots (10)$$

is fixed throughout the motion

This point, which coincides with the centre of inertia of a film of matter distributed over the plane xy with the surface-density ζ , may be called the 'centre' of the system of vortices, and the straight line parallel to z of which it is the projection may be called the 'axis' of the system. If $\Sigma\kappa=0$, the centre is at infinity, or else indeterminate.

155 Some interesting examples are furnished by the case of one or more isolated vortices of infinitely small section. Thus

1°. Let us suppose that we have only one vortex-filament present, and that the rotation ζ has the same sign throughout its infinitely small section. Its centre, as just defined, will lie either within the substance of the filament, or infinitely close to it. Since this centre remains at rest, the filament as a whole will be stationary, though its parts may experience relative motions, and its centre will not necessarily lie always in the same element of fluid. Any particle at a finite distance r from the centre of the filament will describe a circle about the latter as axis, with constant velocity $\kappa/2\pi r$. The region external to the vortex is doubly-connected, and the circulation in any (simple) circuit embracing it is of course κ . The irrotational motion of the surrounding fluid is the same as in Art 27 (2).

2°. Next suppose that we have two vortices, of strengths κ_1, κ_2 , respectively. Let A, B be their centres, O the centre of the system. The motion of each filament as a whole is entirely due to the other, and is therefore always perpendicular to AB . Hence the two filaments remain always at the same distance from one another, and rotate with constant angular velocity about O , which is fixed. This angular velocity is easily found, we have only to divide the velocity of A (say), viz $\kappa_2/(2\pi \cdot AB)$, by the distance AO , where

$$AO = \frac{\kappa_2}{\kappa_1 + \kappa_2} AB,$$

and so obtain

$$\frac{\kappa_1 + \kappa_2}{2\pi \cdot AB^2}$$

If κ_1, κ_2 be of the same sign, *i.e.* if the directions of rotation in the two vortices be the same, O lies between A and B , but if the rotations be of opposite signs, O lies in AB , or BA , produced.

If $\kappa_1 = -\kappa_2$, O is at infinity, but it is easily seen that A, B move with equal velocities $\kappa_1/(2\pi \cdot AB)$ at right angles to AB , which remains fixed in direction. Such a combination of two equal and opposite vortices may be called a 'vortex-pair'. It is the two-dimensional analogue of a circular vortex-ring (Art 160), and exhibits many of the properties of the latter.

The stream-lines of a vortex-pair form a system of coaxial circles, as shewn on p 68, the vortices being at the limiting points $(\pm a, 0)$. To find the

where κ is the circulation Hence

$$V=\frac{\kappa}{4\pi a},$$

which is exactly the velocity of translation of the vortex-pair, in the original form of the problem*

Since the velocity of the fluid at all points of the plane of symmetry is wholly tangential, we may suppose this plane to form a rigid boundary of the fluid on either side of it, and so obtain the case of a single rectilinear vortex in the neighbourhood of a fixed plane wall to which it is parallel. The filament moves parallel to the plane with the velocity $\kappa/4\pi h$, where h is the distance from the wall.


Again, since the stream-lines are circles, we can also derive the solution of the case where we have a single vortex-filament in a space bounded, either internally or externally, by a fixed circular cylinder

Thus, in the figure, let EPD be the section of the cylinder, A the position of the vortex (supposed in this case external), and let B be the ‘image’ of A with respect to the circle EPD , viz C being the centre, let

$$CB \cdot CA = c^2,$$

where c is the radius of the circle. If P be any point on the circle, we have

$$\frac{AP}{BP} = \frac{AE}{BE} = \frac{AD}{BD} = \text{const.},$$



so that the circle occupies the position of a stream-line due to a vortex-pair at A, B . Since the motion of the vortex A would be perpendicular to AB , it is plain that all the conditions of the problem will be satisfied if we suppose A to describe a circle about the axis of the cylinder with the constant velocity

$$- \frac{\kappa}{2\pi} \frac{CA}{AB} = - \frac{\kappa}{2\pi} \frac{CA}{(CA^2 - c^2)},$$

where κ denotes the strength of A

In the same way a single vortex of strength κ , situated inside a fixed circular cylinder, say at B , would describe a circle with constant velocity

$$\frac{\kappa}{2\pi} \frac{CB}{(c^2 - CB^2)}.$$

It is to be noticed, however†, that in the case of the external vortex the motion is not completely determinate unless, in addition to the strength κ , the value of the circulation in a circuit embracing the cylinder (but not the vortex) is prescribed. In the above solution, this circulation is that due to the vortex-image at B and is $-\kappa$. This may be annulled by the superposition of an additional vortex $+\kappa$ at C , in which case we have, for the velocity of A ,


$$- \frac{\kappa}{2\pi} \frac{CA}{(CA^2 - c^2)} + \frac{\kappa}{2\pi} \frac{CA}{CA} = - \frac{\kappa c^2}{2\pi \cdot CA (CA^2 - c^2)}$$

For a prescribed circulation κ' we must add to this the term $\kappa'/2\pi \cdot CA$

* A more exact investigation is given by Hicks, “On the Condition of Steady Motion of Two Cylinders in a Fluid,” *Quart Journ Math*, t. xvii p 194 (1881)

† F. A. Tarleton, “On a Problem in Vortex Motion,” *Proc. R. I. A.*, December 12, 1892

3° If we have four parallel rectilinear vortices whose centres form a rectangle $ABB'A'$, the strengths being κ for the vortices A', B , and $-\kappa$ for the vortices A, B' , it is evident that the centres will always form a rectangle. Further, the various rotations having the directions indicated in the figure,



we see that the effect of the presence of the pair A, A' on B, B' is to separate them, and at the same time to diminish their velocity perpendicular to the line joining them. The planes which bisect AB, AA' at right angles may (either or both) be taken as fixed rigid boundaries. We thus get the case where a pair of vortices, of equal and opposite strengths, move towards (or from) a plane wall, or where a single vortex moves in the angle between two perpendicular walls.

If x, y be the co-ordinates of the vortex A relative to the planes of symmetry, we readily find

$$x = -\frac{\kappa}{4\pi} \frac{x^2}{y^2}, \quad y = \frac{\kappa}{4\pi} \frac{y^2}{xy^2}, \quad (2)$$

where $r^2 = x^2 + y^2$. By division we obtain the differential equation of the path, viz

$$\frac{dx}{x^3} + \frac{dy}{y^3} = 0,$$

whence

$$a^2(x^2 + y^2) = 4x^2y^2,$$

a being an arbitrary constant, or, transforming to polar co-ordinates,

$$r = \frac{a}{\sin 2\theta}. \quad (3)$$

Also since

$$xy - ya = \frac{\kappa}{4\pi},$$

the vortex moves as if under a centre of force at the origin. This force is repulsive, and its law is that of the inverse cube*.

* Greenhill, "On Plane Vortex-Motion," *Quart Journ Math*, t. xv (1887), Grobli, "Die Bewegung paralleler geradliniger Wirbelfäden," Zurich, 1877. These papers contain other interesting examples of rectilinear vortex-systems. For further references as to special problems see Hicks, *Brit Ass. Rep* 1882, pp. 41, Love, *loc ante* p. 182.

An ingenious method of transforming plane problems in vortex-motion was given by Routh, "Some Applications of Conjugate Functions," *Proc Lond Math. Soc*, t. xii. p. 73 (1881).

156 When, as in the case of a vortex-pair, or a system of vortex-pairs, the algebraic sum of the strengths of all the vortices is zero, we may work out a theory of the 'impulse,' in two dimensions, analogous to that given in Arts 119, 152 for the case of a finite vortex-system. The detailed examination of this must be left to the reader. If P, Q denote the components of the impulse parallel to x and y , and N its moment about Oz , all reckoned per unit depth of the fluid parallel to z , it will be found that

$$\left. \begin{aligned} P &= \rho \iint y \zeta dx dy, & Q &= -\rho \iint x \zeta dx dy, \\ N &= \rho \iint (x^2 + y^2) \zeta dx dy \end{aligned} \right\} \quad \dots \quad (1)$$

For instance, in the case of a single vortex-pair, the strengths of the two vortices being $\pm \kappa$, and their distance apart c , the impulse is κc , in a line bisecting c at right angles

The constancy of the impulse gives

$$\left. \begin{aligned} \Sigma \kappa x &= \text{const}, & \Sigma \kappa y &= \text{const}, \\ \Sigma \kappa (x^2 + y^2) &= \text{const} \end{aligned} \right\} \quad \dots \quad (2)$$

It may also be shewn that the energy of the motion in the present case is given by

$$T = -\rho \iint \psi \zeta dx dy = -\frac{1}{2} \rho \Sigma \kappa \psi \quad \dots \quad (3)$$

When $\Sigma \kappa$ is not zero, the energy and the moment of the impulse are both infinite, as may be easily verified in the case of a single rectilinear vortex.

The theory of a system of isolated rectilinear vortices has been put in a very elegant form by Kirchhoff*

Denoting the positions of the centres of the respective vortices by $(x_1, y_1), (x_2, y_2), \dots$ and their strengths by $\kappa_1, \kappa_2, \dots$, it is evident from Art 154 that we may write

$$\left. \begin{aligned} \kappa_1 \frac{dx_1}{dt} &= -\frac{\partial W}{\partial y_1}, & \kappa_1 \frac{dy_1}{dt} &= \frac{\partial W}{\partial x_1}, \\ \kappa_2 \frac{dx_2}{dt} &= -\frac{\partial W}{\partial y_2}, & \kappa_2 \frac{dy_2}{dt} &= \frac{\partial W}{\partial x_2}, \end{aligned} \right\} \quad \dots \quad (4)$$

$$\text{where} \quad W = \frac{1}{2\pi} \Sigma \kappa_1 \kappa_2 \log r_{12}, \quad \dots \quad (5)$$

if r_{12} denote the distance between the vortices κ_1, κ_2

Since W depends only on the *relative* configuration of the vortices, its value is unaltered when x_1, x_2, \dots are increased by the same amount, whence $\Sigma \partial W / \partial x_1 = 0$, and, in the same way, $\Sigma \partial W / \partial y_1 = 0$. This gives the first two of equations (2), but the proof is not now limited to the case of $\Sigma \kappa = 0$. The argument is in fact substantially the same as in Art 154

* *Mechanik*, c. xx

Again, we obtain from (4)

$$\Sigma \kappa \left(x \frac{dx}{dt} + y \frac{dy}{dt} \right) = - \Sigma \left(x \frac{\partial W}{\partial y} - y \frac{\partial W}{\partial x} \right),$$

or if we introduce polar co-ordinates $(r_1, \theta_1), (r_2, \theta_2), \dots$ for the several vortices,

$$\Sigma \kappa r \frac{dr}{dt} = - \Sigma \frac{\partial W}{\partial \theta} \quad . \quad (6)$$

Since W is unaltered by a rotation of the axes of co-ordinates in their own plane about the origin, we have $\Sigma \partial W / \partial \theta = 0$, whence

$$\Sigma \kappa r^2 = \text{const}, \quad (7)$$

which agrees with the third of equations (2), but is free from the restriction there implied

An additional integral of (4) is obtained as follows We have

$$\Sigma \kappa \left(x \frac{dy}{dt} - y \frac{dx}{dt} \right) = \Sigma \left(x \frac{\partial W}{\partial x} + y \frac{\partial W}{\partial y} \right),$$

or

$$\Sigma \kappa_1^2 \frac{d\theta}{dt} = \Sigma_1 \frac{\partial W}{\partial r} \quad . \quad . \quad . \quad (8)$$

If every r be increased in the ratio $1 + \epsilon$, where ϵ is infinitesimal, the increment of W is equal to $\Sigma \epsilon r \partial W / \partial r$. But since the new configuration of the vortex-system is geometrically similar to the former one, the mutual distances r_{12} are altered in the same ratio $1 + \epsilon$, and therefore, from (5), the increment of W is $\epsilon / 2\pi \Sigma \kappa_1 \kappa_2$. Hence (8) may be written in the form

$$\Sigma \kappa_1^2 \frac{d\theta}{dt} = \frac{1}{2\pi} \Sigma \kappa_1 \kappa_2 \quad . \quad . \quad . \quad (9)$$

157. The results of Art 155 are independent of the form of the sections of the vortices, so long as the dimensions of these sections are small compared with the mutual distances of the vortices themselves. The simplest case is of course when the sections are circular, and it is of interest to inquire whether this form is stable. This question has been examined by Lord Kelvin*

When the disturbance is in two dimensions only, the calculations are very simple. Let us suppose, as in Art 27, that the space within a circle $r = a$, having the centre as origin, is occupied by fluid having a uniform rotation ζ , and that this is surrounded by fluid moving irrotationally. If the motion be continuous at this circle we have, for $r < a$,

$$\psi = -\frac{1}{2} \zeta (a^2 - r^2), \quad (1)$$

while for $r > a$,

$$\psi = -\zeta a^2 \log a/r \quad . \quad . \quad . \quad (2)$$

To examine the effect of a slight irrotational disturbance, we assume, for $r < a$,

$$\psi = -\frac{1}{2} \zeta (a^2 - r^2) + A \frac{r^s}{a^s} \cos(s\theta - \sigma t), \quad \left\{ \right.$$

and, for $r > a$,

$$\psi = -\zeta a^2 \log \frac{a}{r} + A \frac{a^s}{r^s} \cos(s\theta - \sigma t), \quad \left. \right\} \quad (3)$$

where s is integral, and σ is to be determined. The constant A must have the same value in these two expressions, since the radial component of the velocity, $-\partial \psi / r \partial \theta$, must

* Sir W. Thomson, "On the Vibrations of a Columnar Vortex," *Phil Mag* (5), t x p 155 (1880)

be continuous at the boundary of the vortex, for which $r=a$, approximately. Assuming for the equation to this boundary

$$r=a+a \cos (s\theta-\sigma t), \quad (4)$$

we have still to express that the tangential component $(\partial\psi/\partial r)$ of the velocity is continuous. This gives

$$\zeta + s \frac{A}{a} \cos (s\theta - \sigma t) = \zeta \frac{a^2}{r} - s \frac{A}{a} \cos (s\theta - \sigma t)$$

Substituting from (4), and neglecting the square of a , we find

$$\zeta a = -s \frac{A}{a} \quad (5)$$

So far the work is purely kinematical, the dynamical theorem that the vortex-lines move with the fluid shews that the normal velocity of a particle on the boundary must be equal to that of the boundary itself. This condition gives

$$\frac{\partial r}{\partial t} = -\frac{\partial \psi}{r \partial \theta} - \frac{\partial \psi}{\partial r} \frac{\partial r}{r \partial \theta},$$

where r has the value (4), or

$$\sigma a = s \frac{A}{a} + \zeta a \frac{sa}{a} \quad (6)$$

Eliminating the ratio A/a between (5) and (6) we find

$$\sigma = (s-1) \zeta \quad (7)$$

Hence the disturbance represented by the plane harmonics in (3) consists of a system of corrugations travelling round the circumference of the vortex with an angular velocity

$$\frac{\sigma}{s} = \frac{s-1}{s} \zeta \quad (8)$$

This is the angular velocity in space; relative to the rotating fluid the angular velocity is

$$\frac{\sigma}{s} - \zeta = -\frac{\zeta}{s}, \quad (9)$$

the direction being opposite to that of the rotation

When $s=2$, the disturbed section is an ellipse which rotates about its centre with angular velocity $\frac{1}{2}\zeta$

The transverse and longitudinal oscillations of an isolated rectilinear vortex-filament have also been discussed by Lord Kelvin in the paper cited.

158 The particular case of an elliptic disturbance can be solved without approximation as follows*

Let us suppose that the space within the ellipse

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1 \quad (1)$$

is occupied by liquid having a uniform rotation ζ , whilst the surrounding fluid is moving

* Kirchhoff, *Mechanik*, c. xx p 261, Basset, *Hydrodynamics*, t. II. p. 41.

irrotationally. It will appear that the conditions of the problem can all be satisfied if we imagine the elliptic boundary to rotate, without change of shape, with a constant angular velocity (n , say), to be determined.

The formula for the external space can be at once written down from Art 72, 4°, viz. we have

$$\psi = \frac{1}{4}n(a+b)^2 e^{-2\xi} \cos 2\eta + \xi ab\xi, \quad (2)$$

where ξ, η now denote the elliptic co-ordinates of Art 71, 3°, and the cyclic constant κ has been put $= 2\pi ab\xi$.

The value of ψ for the internal space has to satisfy

$$\frac{\partial^2 \psi}{\partial x^2} + \frac{\partial^2 \psi}{\partial y^2} = 2\xi, \quad (3)$$

$$\text{with the boundary-condition} \quad \frac{ux}{a^2} + \frac{vy}{b^2} = -ny \cdot \frac{x}{a^2} + nx \cdot \frac{y}{b^2} \quad (4)$$

These conditions are both fulfilled by

$$\psi = \xi(Ax^2 + By^2), \quad (5)$$

$$\text{provided} \quad A + B = 1, \quad Aa^2 - Bb^2 = \frac{n}{2\xi}(a^2 - b^2) \quad (6)$$

It remains to express that there is no tangential slipping at the boundary of the vortex, i.e. that the values of $\partial\psi/\partial\xi$ obtained from (2) and (5) there coincide. Putting $x = c \cosh \xi \cos \eta$, $y = c \sinh \xi \sin \eta$, where $c = (a^2 - b^2)^{\frac{1}{2}}$, differentiating, and equating coefficients of $\cos 2\eta$, we obtain the additional condition

$$-\frac{1}{2}n(a+b)^2 e^{-2\xi} = \xi c^2 (A - B) \cosh \xi \sinh \xi,$$

where ξ is the parameter of the ellipse (1). This is equivalent to

$$A - B = -\frac{n}{2\xi} \frac{a^2 - b^2}{ab}, \quad (7)$$

since, at points of the ellipse, $\cosh \xi = a/c$, $\sinh \xi = b/c$

$$\text{Combined with (6) this gives} \quad Aa = Bb = \frac{ab}{a+b}, \quad (8)$$

$$\text{and} \quad n = \frac{2ab}{(a+b)^2} \xi \quad (9)$$

When $a=b$, this agrees with our former approximate result

The component velocities x, y of a particle of the vortex relative to the principal axes of the ellipse are given by

$$x = -\frac{\partial\psi}{\partial y} + ny, \quad y = \frac{\partial\psi}{\partial x} - nx,$$

$$\text{whence we find} \quad \frac{x}{a} = -n \frac{y}{b}, \quad \frac{y}{b} = n \frac{x}{a} \quad (10)$$

$$\text{Integrating, we find} \quad x = ka \cos(nt + \epsilon), \quad y = kb \sin(nt + \epsilon), \quad (11)$$

where k, ϵ are arbitrary constants, so that the *relative* paths of the particles are ellipses similar to the boundary of the vortex, described according to the harmonic law. If x', y' be the co-ordinates relative to axes fixed in space, we find

$$\left. \begin{aligned} x' &= x \cos nt - y \sin nt = \frac{1}{2}h(a+b) \cos(2nt+\epsilon) + \frac{1}{2}h(a-b) \cos \epsilon, \\ y' &= v \sin nt + y \cos nt = \frac{1}{2}h(a+b) \sin(2nt+\epsilon) - \frac{1}{2}h(a-b) \sin \epsilon \end{aligned} \right\} \quad (12)$$

The absolute paths are therefore circles described with angular velocity $2n$ *

159 It was pointed out in Art 80 that the motion of an incompressible fluid in a curved stratum of small but uniform thickness is completely defined by a stream-function ψ , so that any kinematical problem of this kind may be transformed by projection into one relating to a plane stratum. If, further, the projection be 'orthomorphic,' the kinetic energy of corresponding portions of liquid, and the circulations in corresponding circuits, are the same in the two motions. The latter statement shows that vortices transform into vortices of equal strengths. It follows at once from Art 145 that in the case of a *closed* simply-connected surface the algebraic sum of the strengths of all the vortices present is zero.

Let us apply this to motion in a spherical stratum. The simplest case is that of a pair of isolated vortices situate at antipodal points, the stream-lines are then parallel small circles, the velocity varying inversely as the radius of the circle. For a vortex-pair situate at *any* two points A, B , the stream-lines are coaxial circles as in Art 80. It is easily found by the method of stereographic projection that the velocity at any point P is the resultant of two velocities $\kappa/2\pi a \cdot \cot \frac{1}{2}\theta_1$ and $\kappa/2\pi a \cot \frac{1}{2}\theta_2$, perpendicular respectively to the great-circle arcs AP, BP , where θ_1, θ_2 denote the lengths of these arcs, a the radius of the sphere, and $\pm \kappa$ the strengths of the vortices. The centre† (see Art 154) of either vortex moves perpendicular to AB with a velocity $\kappa/2\pi a \cot \frac{1}{2}AB$. The two vortices therefore describe parallel and equal small circles, remaining at a constant distance from each other.

Circular Vortices

160. Let us next take the case where all the vortices present in the liquid (supposed unlimited as before) are circular, having the axis of x as a common axis. Let ϖ denote the distance of any point P from this axis, v the velocity in the direction of ϖ , and ω the angular velocity of the fluid at P . It is evident that u, v, ω are functions of x, ϖ only.

* For further researches in this connection see Hill, "On the Motion of Fluid part of which is moving rotationally and part irrotationally," *Phil Trans.*, 1884, Love, "On the Stability of certain Vortex Motions," *Proc Lond Math Soc*, t xxv. p 18 (1893).

† To prevent possible misconception it may be remarked that the centres of corresponding vortices are not necessarily corresponding points. The paths of these centres are therefore not in general projective.

Under these circumstances there exists a stream-function ψ , defined as in Art 94, viz we have

$$u = -\frac{1}{\varpi} \frac{\partial \psi}{\partial \varpi}, \quad v = \frac{1}{\varpi} \frac{\partial \psi}{\partial x}, \quad (1)$$

whence
$$2\omega = \frac{\partial v}{\partial x} - \frac{\partial u}{\partial \varpi} = \frac{1}{\varpi} \left(\frac{\partial^2 \psi}{\partial x^2} + \frac{\partial^2 \psi}{\partial \varpi^2} - \frac{1}{\varpi} \frac{\partial \psi}{\partial \varpi} \right) \quad (2)$$

It is easily seen from the expressions (7) of Art 148 that the vector (F, G, H) will under the present conditions be everywhere perpendicular to the axis of x and the radius ϖ . If we denote its magnitude by S , the flux through the circle (x, ϖ) will be $2\pi\varpi S$, whence

$$\psi = -\varpi S \quad (3)$$

To find the value of ψ at (x, ϖ) due to a single vortex-filament of circulation κ , whose co-ordinates are x', ϖ' , we note that that element which makes an angle θ with the direction of S may be denoted by $\varpi' \delta\theta$, and therefore by Art. 149 (1)

$$\psi = -\varpi S = -\frac{\kappa\varpi\varpi'}{4\pi} \int_0^{2\pi} \frac{\cos \theta}{r} d\theta, \quad (4)$$

where
$$r = \{(x-x')^2 + \varpi^2 + \varpi'^2 - 2\varpi\varpi' \cos \theta\}^{\frac{1}{2}} \quad (5)$$

If we denote by r_1, r_2 the least and greatest distances, respectively, of the point P from the vortex, viz

$$r_1^2 = (x-x')^2 + (\varpi - \varpi')^2, \quad r_2^2 = (x-x')^2 + (\varpi + \varpi')^2, \quad (6)$$

we have
$$r^2 = r_1^2 \cos^2 \frac{1}{2}\theta + r_2^2 \sin^2 \frac{1}{2}\theta, \quad 4\varpi\varpi' \cos \theta = r_1^2 + r_2^2 - 2r^2, \quad \dots (7)$$

and therefore

$$\psi = -\frac{\kappa}{8\pi} \left[(r_1^2 + r_2^2) \int_0^\pi \frac{d\theta}{\sqrt{(r_1^2 \cos^2 \frac{1}{2}\theta + r_2^2 \sin^2 \frac{1}{2}\theta)}} - 2 \int_0^\pi \sqrt{(r_1^2 \cos^2 \frac{1}{2}\theta + r_2^2 \sin^2 \frac{1}{2}\theta)} d\theta \right] \quad (8)$$

The integrals are of the types met with in the theory of the 'arithmetico-geometrical mean.'* In the ordinary, less symmetrical, notation of 'complete' elliptic integrals we have

$$\psi = -\frac{\kappa}{2\pi} (\varpi\varpi')^{\frac{1}{2}} \left\{ \left(\frac{2}{k} - k \right) F_1(k) - \frac{2}{k} E_1(k) \right\}, \quad \dots (9)$$

provided
$$k^2 = 1 - \frac{r_1^2}{r_2^2} = \frac{4\varpi\varpi'}{(x-x')^2 + (\varpi + \varpi')^2} \quad (10)$$

The value of ψ at any assigned point can therefore be computed with the help of Legendre's tables

* See Cayley, *Elliptic Functions*, Cambridge, 1876, c. xiii

A neater expression may be obtained by means of 'Landen's transformation',*, thus

$$\psi = -\frac{\kappa}{2\pi} (r_1 + r_2) \{F_1(\lambda) - E_1(\lambda)\}, \quad (11)$$

provided

$$\lambda = \frac{r_2 - r_1}{r_2 + r_1} \quad \dots \quad (12)$$

To verify this, let AB be a straight line divided at P into two segments PA , PB of lengths r_1 , r_2 , respectively, and describe the circle on AB as diameter C being the centre, and Q any point on the circumference, let the angles QCA , QPA be denoted by θ , ϑ , respectively, and draw CN perpendicular to QP . If $PQ = r$, we have

$$r^2 = r_1^2 \cos^2 \frac{1}{2} \theta + r_2^2 \sin^2 \frac{1}{2} \theta, \quad r \delta \vartheta = CQ \delta \theta \quad \cos CQN = QN \delta \theta \quad \dots \quad (13)$$

$$\text{Also} \quad CP \cdot \frac{\cos \theta}{r} = \frac{CQ}{r} - \cos CQN = \frac{CQ}{r} - \frac{QN}{CQ},$$

and therefore

$$CP \cdot \frac{\cos \theta \delta \theta}{r} = CQ \cdot \frac{\delta \vartheta}{QN} - \frac{PQ \delta \vartheta}{CQ} = CQ \cdot \frac{\delta \vartheta}{QN} - \frac{QN \delta \vartheta}{CQ} + \frac{PN \delta \vartheta}{CQ}$$

Hence

$$\frac{1}{2} (r_2 - r_1) \int_0^\pi \frac{\cos \theta \delta \theta}{r} = \frac{1}{2} (r_1 + r_2) \int_0^\pi \frac{\delta \vartheta}{QN} - \frac{2}{r_1 + r_2} \int_0^\pi QN \delta \vartheta, \quad (14)$$

$$\text{since} \quad \int_0^\pi PN \delta \vartheta = CP \int_0^\pi \cos \vartheta \delta \vartheta = 0$$

$$\text{Now} \quad QN = \sqrt{(CQ^2 - CP^2 \sin^2 \vartheta)} = \frac{1}{2} (r_1 + r_2) \sqrt{(1 - \lambda^2 \sin^2 \vartheta)}, \quad (15)$$

$$\text{if} \quad \lambda = \frac{CP}{CQ} = \frac{r_2 - r_1}{r_2 + r_1}. \quad (16)$$

The formula (14) may therefore be written

$$\frac{1}{2} (r_2 - r_1) \int_0^\pi \frac{\cos \theta}{r} d\theta = 2 \{F_1(\lambda) - E_1(\lambda)\}, \quad \dots \quad (17)$$

which brings (4) into the required form (11)


The forms of the stream-lines corresponding to equidistant values of ψ are shewn on the next page. They are traced by a method devised by Maxwell, to whom the formula (11) is also due†

Expressions for the velocity-potential and the stream-function can also be obtained in the form of definite integrals involving Bessel's Functions.

Thus, supposing the vortex to occupy the position of the circle $x = 0$, $y = a$, it is evident that the portions of the positive side of the plane $x = 0$ which lie within and without this circle constitute two distinct equipotential


* See Cayley, *l c*

† *Electricity and Magnetism*, Arts 704, 705. See also Minchin, *Phil Mag* (5), t. xxxv. (1893), Nagaoka, *Phil Mag* (6), t. vi. (1903)



surfaces. Hence, assuming that we have $\phi = \frac{1}{2}\kappa$ for $x = 0$, $\varpi < a$, and $\phi = 0$ for $x = 0$, $\varpi > a$, we obtain from Art 102 (2)

$$\phi = \frac{1}{2}\kappa a \int_0^\infty e^{-kx} J_0(k\varpi) J_1(ka) dk, \quad . \quad . \quad (18)$$



and therefore, in accordance with Art 100 (5),

$$\psi = -\frac{1}{2}\kappa a\omega \int_0^\infty e^{-kz} J_1(k\omega) J_1(ka) dk \quad (19)$$

These formulae relate of course to the region $x > 0^*$.

It was shewn in Art 150 that the value of ϕ is that due to a system of double-sources distributed with uniform density κ over the interior of the circle. The values of ϕ and ψ for a uniform distribution of *simple* sources over the same area have been given in Art 102 (11). The above formulae (18) and (19) can thence be derived by differentiating with respect to x , and adjusting the constant factor†.

161 The energy of any system of circular vortices having the axis of x as a common axis, is

$$\begin{aligned} T &= \pi\rho \iint (u^2 + v^2) \omega dx d\omega = \pi\rho \iint \left(v \frac{\partial \psi}{\partial x} - u \frac{\partial \psi}{\partial \omega} \right) dx d\omega \\ &= -2\pi\rho \iint \psi \omega dx d\omega = -\pi\rho \Sigma \kappa \psi, \quad . \quad . \quad . \end{aligned} \quad (1)$$

by a partial integration, the integrated terms vanishing at the limits. We have here used κ to denote the strength $2\omega \delta x \delta \omega$ of an elementary vortex-filament

Again the formula (7) of Art 153 becomes‡

$$T = 4\pi\rho \iint (\omega u - xv) \omega \omega dx dy = 2\pi\rho \Sigma \kappa \omega (\omega u - xv) \quad . \quad (2)$$

The impulse of the system obviously reduces to a force along Ox . By Art 152 (12),

$$P = \rho \iint (y\zeta - z\eta) dx dy dz = 2\pi\rho \iint \omega^2 \omega dx d\omega = \pi\rho \Sigma \kappa \omega^2 \quad (3)$$

If we introduce two symbols x_0 , ω_0 defined by the equations

$$x_0 = \frac{\Sigma \kappa \omega^2 x}{\Sigma \kappa \omega^2}, \quad \omega_0 = \frac{\Sigma \kappa \omega^2}{\Sigma \kappa}, \quad . \quad (4)$$

these determine a circle whose position evidently depends on the strengths and the configuration of the vortices, and not on the position of the origin on the axis of symmetry. It may be called the 'circular axis' of the whole system of vortex-rings

* The formula for ψ occurs in Basset, *Hydrodynamics*, t. ii p. 93. See also Nagaoka, *loc.*

† Other expressions for ϕ and ψ can be obtained in terms of zonal spherical harmonics. Thus the value of ϕ is given in Thomson and Tait, Art 546, and that of ψ can be deduced by the formulae (11), (12) of Art 95 *ante*. The elliptic-integral forms are however the most useful for purposes of interpretation.

‡ At any point in the plane $z=0$ we have $y=\omega$, $\xi=0$, $\eta=0$, $\zeta=\omega$, $v=v$, the rest follows by symmetry.

Since κ is constant for each vortex, the constancy of the impulse shews, by (3) and (4), that the circular axis remains constant in radius. To find its motion parallel to x , we have, from (4),

$$\Sigma \kappa \cdot \varpi_0^2 \cdot \frac{dx_0}{dt} = \Sigma \kappa \varpi^2 \frac{dx}{dt} + 2 \Sigma \kappa \varpi x \frac{d\varpi}{dt} = \Sigma \kappa \varpi (\varpi u + 2xv). \quad (5)$$

With the help of (2) this can be put in the form

$$\Sigma \kappa \varpi_0^2 \frac{dx_0}{dt} = \frac{T}{2\pi\rho} + 3 \Sigma \kappa (x - x_0) \varpi v, \quad (6)$$

where the added term vanishes, since $\Sigma \kappa \varpi v = 0$ on account of the constancy of the mean radius (ϖ_0).

162 Let us now consider, in particular, the case of an isolated vortex-ring the dimensions of whose cross-section are small compared with the radius (ϖ_0). It has been shewn that

$$\psi = -\frac{1}{\pi} \iint \left\{ F_1 \left(\frac{r_2 - r_1}{r_2 + r_1} \right) - E_1 \left(\frac{r_2 - r_1}{r_2 + r_1} \right) \right\} (r_1 + r_2) \omega' dx' d\varpi', \quad (1)$$

where r_1, r_2 are defined by Art 160 (6). For points (x, ϖ) in or near the substance of the vortex, the ratio r_1/r_2 is small, and the modulus (λ) of the elliptic integrals is accordingly nearly equal to unity. We then have

$$F_1(\lambda) = \frac{1}{2} \log \frac{16}{\lambda'^2}, \quad E_1(\lambda) = 1, \quad \dots \quad (2)$$

approximately*, where λ' denotes the complementary modulus, viz

$$\lambda'^2 = 1 - \lambda^2 = \frac{4r_1 r_2}{(r_1 + r_2)^2}, \quad \dots \quad (3)$$

or $\lambda'^2 = 4r_1/r_2$, nearly

Hence at points within the substance of the vortex the value of ψ is of the order $\kappa \varpi_0 \log \varpi_0/\epsilon$, where ϵ is a small linear magnitude comparable with the dimensions of the section. The velocity at the same point, depending (Art 94) on the differential coefficients of ψ , will be of the order κ/ϵ .

We can now estimate the magnitude of the velocity dx_0/dt of translation of the vortex-ring. By Art. 161 (1), T is of the order $\rho \kappa^2 \varpi_0 \log \varpi_0/\epsilon$, and v is, as we have seen, of the order κ/ϵ , whilst $x - x_0$ is of course of the order ϵ . Hence the second term on the right-hand side of the formula (6) of the preceding Art is, in the present case, small compared with the first, and the velocity of translation of the ring is of the order $\kappa/\varpi_0 \log \varpi_0/\epsilon$, and approximately constant.

* See Cayley, *Elliptic Functions*, Arts 72, 77, and Maxwell (*l c*).

An isolated vortex-ring moves then, without sensible change of size, parallel to its rectilinear axis with nearly constant velocity. This velocity is small compared with that of the fluid in the immediate neighbourhood of the circular axis, but may be greater or less than $\frac{1}{2}\kappa/\omega_0$, the velocity of the fluid at the centre of the ring, with which it agrees in direction.

For the case of a *circular* section more definite results can be obtained as follows. If we neglect the variations of ϖ and ω over the section, the formulæ (1) and (2) give

$$\psi = -\frac{\omega}{\pi} \varpi_0 \iint \left(\log \frac{8\varpi_0}{r_1} - 2 \right) dx' d\varpi',$$

or, if we introduce polar co-ordinates (s, χ) in the plane of the section,

$$\psi = -\frac{\omega}{\pi} \varpi_0 \int_0^a \int_0^{2\pi} \left(\log \frac{8\varpi_0}{r_1} - 2 \right) s' ds' d\chi', \quad (4)$$

where a is the radius of the section. Now

$$\int_0^{2\pi} \log r_1 d\chi' = \int_0^{2\pi} \log \{s^2 + s'^2 - 2ss' \cos(\chi - \chi')\}^{\frac{1}{2}} d\chi',$$

and this definite integral is known to be equal to $2\pi \log s'$, or $2\pi \log s$, according as $s' \geq s$. Hence, for points within the section,

$$\begin{aligned} \psi &= -2\omega \varpi_0 \int_0^s \left(\log \frac{8\varpi_0}{s} - 2 \right) s' ds' - 2\omega \varpi_0 \int_s^a \left(\log \frac{8\varpi_0}{s'} - 2 \right) s' ds' \\ &= -\omega \varpi_0 a^2 \left\{ \log \frac{8\varpi_0}{a} - \frac{3}{2} - \frac{s^2}{a^2} \right\} \end{aligned} \quad (5)$$

The only variable part of this is the term $-\frac{1}{2}\omega \varpi_0 s^2$, this shews that to *our order of approximation* the stream-lines within the section are concentric circles, the velocity at a distance s from the centre being ωs . Substituting in Art. 161 (1) we find

$$\frac{T}{4\pi\rho} = -\frac{1}{2}\omega \int_0^a \int_0^{2\pi} \psi s ds d\chi = \frac{\kappa^2 \varpi_0}{8\pi} \left\{ \log \frac{8\varpi_0}{a} - \frac{7}{4} \right\}, \quad (6)$$

The last term in Art. 161 (6) is equivalent to

$$\frac{1}{2} \varpi_0 \omega \Sigma \kappa (x - v_0)^2,$$

in our present notation, κ denoting the strength of the whole vortex, this is equal to $\frac{1}{16} \kappa^2 \varpi_0 / \pi$. Hence the formula for the velocity of translation of the vortex becomes*

$$\frac{dx_0}{dt} = \frac{\kappa}{4\pi \varpi_0} \left\{ \log \frac{8\varpi_0}{a} - \frac{1}{4} \right\}. \quad (7)$$

The vortex-ring carries with it a certain body of irrotationally moving fluid in its career, cf. Art. 155, 2°. According to the formula (7) the velocity of translation of the vortex will be equal to the velocity of the fluid at its centre when $\varpi_0/a = 86$, about. The accompanying mass will be ring-shaped or not, according as ϖ_0/a exceeds or falls short of this critical value†.

The ratio of the fluid velocity at the periphery of the vortex to the velocity at the centre of the ring is $2\omega a \varpi_0 / \kappa$, or $\varpi_0 / \pi a$. For $a = \frac{1}{80} \varpi_0$, this is equal to 32, about.

* This result was given by Sir W. Thomson in an appendix to a translation of Helmholtz' paper, *Phil. Mag.* (4), t. xxxiii p. 511 (1867).

† Cf. Sir W. Thomson, *l.c. ante* p. 214.

163 If we have any number of circular vortex-rings, coaxial or not, the motion of any one of these may be conceived as made up of two parts, one due to the ring itself, the other due to the influence of the remaining rings. The preceding considerations shew that the second part is insignificant compared with the first, except when two or more rings approach within a very small distance of one another. Hence each ring will move, without sensible change of shape or size, with nearly uniform velocity in the direction of its rectilinear axis, until it passes within a short distance of a second ring.

A general notion of the result of the encounter of two rings may, in particular cases, be gathered from the result given in Art 149 (3). Thus, let us suppose that we have two circular vortices having the same rectilinear axis. If the sense of the rotation be the same for both, the two rings will advance, on the whole, in the same direction. One effect of their mutual influence will be to increase the radius of the one in front, and to contract the radius of the one in the rear. If the radius of the one in front become larger than that of the one in the rear, the motion of the former ring will be retarded, and that of the latter accelerated. Hence if the conditions as to relative size and strength of the two rings be favourable, it may happen that the second ring will overtake and pass through the first. The parts played by the two rings will then be reversed, the one which is now in the rear will in turn overtake and pass through the other, and so on, the rings alternately passing one through the other*.

If the rotations be opposite, and such that the rings approach one another, the mutual influence will be to enlarge the radius of each. If the two rings be moreover equal in size and strength, the velocity of approach will continually diminish. In this case the motion at all points of the plane which is parallel to the two rings, and half-way between them, is tangential to this plane. We may therefore, if we please, regard the plane as a fixed boundary to the fluid on either side, and so obtain the case of a single vortex-ring moving directly towards a fixed rigid wall.

The foregoing remarks are taken from von Helmholtz' paper. He adds, in conclusion, that the mutual influence of vortex-rings may easily be studied experimentally in the case of the (roughly) semicircular rings produced by drawing rapidly the point of a spoon for a short space through the surface of a liquid, the spots where the vortex-filaments meet the surface being marked by dimples. (Cf Art 27.) The method of experimental illustration by means of smoke-rings† is too well-known to need description here. A beautiful

* The corresponding case in two dimensions was worked out and illustrated graphically by Grob, *l.c. ante* p. 216, see also Love, "On the Motion of Paired Vortices with a Common Axis," *Proc. Lond. Math. Soc.*, t. xxv p. 185 (1894).

† Reusch, "Ueber Ringbildung der Flüssigkeiten," *Pogg. Ann.*, t. cx (1860), Tait, *Recent Advances in Physical Science*, London, 1876, c. xii.

variation of the experiment consists in forming the rings in water, the substance of the vortices being coloured*.

The motion of a vortex-ring in a fluid limited (whether internally or externally) by a fixed spherical surface, in the case where the rectilinear axis of the ring passes through the centre of the sphere, has been investigated by Lewis†, by the method of 'images'. The following simplified proof is due to Larmor‡. The vortex-ring is equivalent (Art 148) to a spherical sheet of double-sources of uniform density, concentric with the fixed sphere. The 'image' of this sheet will, by Art 96, be another uniform concentric double-sheet, which is, again, equivalent to a vortex-ring coaxial with the first. It easily follows from the Art last cited that the strengths (κ, κ') and the radii (ϖ, ϖ') of the vortex-ring and its image are connected by the relation

$$\kappa \varpi^{\frac{1}{2}} + \kappa' \varpi'^{\frac{1}{2}} = 0 \quad \dots \quad (1)$$

The argument obviously applies to the case of a re-entrant vortex of any form, provided it lie on a sphere concentric with the boundary

On the Conditions for Steady Motion

164 In steady motion, *i.e.* when

$$\frac{\partial u}{\partial t} = 0, \quad \frac{\partial v}{\partial t} = 0, \quad \frac{\partial w}{\partial t} = 0,$$

the equations (2) of Art 6 may be written

$$u \frac{\partial u}{\partial x} + v \frac{\partial v}{\partial x} + w \frac{\partial w}{\partial x} - 2(v\xi - w\eta) = -\frac{\partial \Omega}{\partial x} - \frac{1}{\rho} \frac{\partial p}{\partial x}, \quad \dots \quad (1)$$

Hence, if as in Art 146 we put

$$\chi' = \int \frac{dp}{\rho} + \frac{1}{2}Q^2 + \Omega, \quad \dots \quad (2)$$

$$\text{we have} \quad \frac{\partial \chi'}{\partial x} = 2(v\xi - w\eta), \quad \frac{\partial \chi'}{\partial y} = 2(w\xi - u\zeta), \quad \frac{\partial \chi'}{\partial z} = 2(u\eta - v\xi) \quad (3)$$

It follows that

$$u \frac{\partial \chi'}{\partial x} + v \frac{\partial \chi'}{\partial y} + w \frac{\partial \chi'}{\partial z} = 0,$$

$$\xi \frac{\partial \chi'}{\partial x} + \eta \frac{\partial \chi'}{\partial y} + \zeta \frac{\partial \chi'}{\partial z} = 0,$$

so that each of the surfaces $\chi' = \text{const}$ contains both stream-lines and

* Reynolds, "On the Resistance encountered by Vortex Rings &c.," *Brit Ass Rep*, 1876, *Nature*, t. xiv. p. 477

† "On the Images of Vortices in a Spherical Vessel," *Quart. Journ. Math.*, t. xvi. p. 338 (1879)

‡ "Electro-magnetic and other Images in Spheres and Planes," *Quart. Journ. Math.*, t. xxiii. p. 94 (1889)

vortex-lines If further δn denote an element of the normal at any point of such a surface, we have

$$\frac{\partial \chi'}{\partial n} = 2q\omega \sin \beta, \quad \dots \dots \dots (4)$$

where q is the current-velocity, ω the rotation, and β the angle between the stream-line and the vortex-line at that point.

Hence the conditions that a given state of motion of a fluid may be a possible state of steady motion are as follows It must be possible to draw in the fluid an infinite system of surfaces each of which is covered by a network of stream-lines and vortex-lines, and the product $q\omega \sin \beta \delta n$ must be constant over each such surface, δn denoting the length of the normal drawn to a consecutive surface of the system*

These conditions may also be deduced from the considerations that the stream-lines are, in steady motion, the actual paths of the particles, that the product of the angular velocity into the cross-section is the same at all points of a vortex, and that this product is, for the same vortex, constant with regard to the time.

The theorem that the function χ' , defined by (2), is constant over each surface of the above kind is an extension of that of Art 21, where it was shewn that χ' is constant along a stream-line

The above conditions are satisfied identically in all cases of irrotational motion, provided of course the boundary-conditions be such as are consistent with the steady motion

In the motion of a liquid in two dimensions (xy) the product $q\delta n$ is constant along a stream-line; the conditions in question then reduce to this, that the angular velocity ζ must be constant along each stream-line, or, by Art 59 (5),

$$\frac{\partial^2 \psi}{\partial x^2} + \frac{\partial^2 \psi}{\partial y^2} = f(\psi), \quad \dots \dots (5)$$

where $f(\psi)$ is an arbitrary function of ψ †.

This condition is satisfied in all cases of motion in concentric circles about the origin Another obvious solution of (5) is

$$\psi = \frac{1}{2}(Av^2 + 2Bxy + Cy^2), \quad (6)$$

in which case the stream-lines are similar and coaxial conics The angular velocity at any point is $\frac{1}{2}(A + C)$, and is therefore uniform

* See a paper "On the Conditions for Steady Motion of a Fluid," *Proc Lond Math Soc*, t ix p 91 (1878)

† Cf Lagrange, *Nouv Mém de l'Acad de Berlin*, 1781 [*Oeuvres*, t iv p 720], and Stokes, "On the Steady Motion of Incompressible Fluids," *Camb Trans*, t vii (1842) [*Math and Phys Papers*, t i p 15]

Again, if we put $f(\psi) = -k^2\psi$, where k is a constant, and transform to polar co-ordinates r, θ , we get

$$\frac{\partial^2 \psi}{\partial r^2} + \frac{1}{r} \frac{\partial \psi}{\partial r} + \frac{1}{r^2} \frac{\partial^2 \psi}{\partial \theta^2} + k^2 \psi = 0, \quad (7)$$

which is satisfied (Art. 101) by
$$\psi = C J_s(kr) \frac{\cos}{\sin} s\theta \quad (8)$$

This gives various solutions consistent with a fixed circular boundary of radius a , the admissible values of k being determined by

$$J_s(ka) = 0 \quad (9)$$

Suppose, for example, that in an unlimited mass of fluid the stream-function is

$$\psi = C J_1(kr) \sin \theta, \quad (10)$$

within the circle $r = a$, whilst outside this circle we have

$$\psi = U \left(r - \frac{a^2}{r} \right) \sin \theta \quad . \quad . \quad . \quad (11)$$

These two values of ψ agree for $r = a$, provided $J_1(ka) = 0$. Moreover, the tangential velocity at this circle will be continuous, provided the two values of $\partial\psi/\partial r$ are equal, i.e. if

$$C = \frac{2U}{kJ_1'(ka)} = -\frac{2U}{kJ_0(ka)} \quad . \quad (12)$$

If we now impress on everything a velocity U parallel to Ox , we get a species of cylindrical vortex travelling with velocity U through a liquid which is at rest at infinity. The smallest of the possible values of k is given by $ka/\pi = 1.2197$, the relative stream-lines *inside* the vortex are then given by the diagram on p. 272, provided the dotted circle be taken as the boundary ($r = a$). It is easily proved, by Art. 156 (1), that the 'impulse' of the vortex is represented by $2\pi\rho a^3 U$.

In the case of motion symmetrical about an axis (x), we have $q = 2\pi\omega\delta n$ constant along a stream-line, ω denoting as in Art. 94 the distance of any point from the axis of symmetry. The condition for steady motion then is that the ratio ω/ϖ must be constant along any stream-line. Hence, if ψ be the stream-function, we must have, by Art. 160 (2),

$$\frac{\partial^2 \psi}{\partial x^2} + \frac{\partial^2 \psi}{\partial \varpi^2} - \frac{1}{\varpi} \frac{\partial \psi}{\partial \varpi} = \varpi^2 f(\psi), \quad . \quad . \quad (13)$$

where $f(\psi)$ denotes an arbitrary function of ψ *

An interesting example is furnished by Hill's 'Spherical Vortex'†. If we assume

$$\psi = \frac{1}{2} A \varpi^2 (a^2 - r^2), \quad (14)$$

where $r^2 = x^2 + \varpi^2$, for all points within the sphere $r = a$, the formula (2) of Art. 160 makes

$$\omega = -\frac{5}{2} A \varpi,$$

so that the condition of steady motion is satisfied. Again it is evident, on reference to

* This result is due to Stokes, *l.c.*

† "On a Spherical Vortex," *Phil. Trans.*, A, t. clxxxv (1894)


Arts 96, 97, that the irrotational flow of a stream with the general velocity $-U$ parallel to the axis, past a fixed spherical surface $r=a$, is given by

$$\psi = \frac{1}{2} U a^2 \left(1 - \frac{a^3}{r^3} \right) \quad (15)$$

The two values of ψ agree when $r=a$, this makes the normal velocity zero on both sides. In order that the tangential velocity may be continuous, the values of $\partial\psi/\partial r$ must also agree. Remembering that $\varpi = r \sin \theta$, this gives $A = -\frac{3}{2} U/a^2$, and therefore

$$\omega = \frac{3}{4} U \varpi / a^2 \quad (16)$$

The sum of the strengths of the vortex-filaments composing the spherical vortex is $5Ua$



The figure shows the stream-lines, both inside and outside the vortex, they are drawn, as usual, for equidistant values of ψ

If we impress on everything a velocity U parallel to z , we get a spherical vortex advancing with constant velocity U through a liquid which is at rest at infinity

By the formulae of Art 161, we readily find that the square of the 'mean-radius' of the vortex is $\frac{2}{3} a^2$, the 'impulse' is $2\pi\rho a^3 U$, and the energy is $\frac{1}{2} \pi \rho a^3 U^2$

As explained in Art 146, it is quite unnecessary to calculate formulae for the pressure, in order to assure ourselves that this is continuous at the surface of the vortex. The continuity of the pressure is already secured by the continuity of the velocity, and the constancy of the circulation in any moving circuit

165 As already stated, the theory of vortex motion was originated by von Helmholtz in 1858. It acquired additional interest when, in 1867, Lord Kelvin suggested* the theory of vortex atoms. As a physical theory, this lies outside our province, but it has given rise to a great number of interesting investigations, to which some reference should be made. We may mention the investigations as to the stability and the periods of vibration of rectilinear† and annular‡ vortices, the similar investigations relating to hollow

* *l c ante* p 214

† Sir W Thomson, *l c ante* p 218

‡ J J Thomson, *l c ante* p 208, Dyson, *Phil. Trans A*, t clxxxiv. p 1041 (1893)

vortices (where the rotationally moving core is replaced by a vacuum*), and the calculations of the forms of boundary of a hollow vortex which are consistent with steady motion†. A summary of some of the leading results has been given by Love‡

Clebsch's Transformation

166 Another matter of some interest, which can only be briefly touched upon, is Clebsch's transformation of the hydrodynamical equations§

It is easily seen that the component velocities at any one instant can be expressed in the forms

$$u = -\frac{\partial\phi}{\partial x} + \lambda \frac{\partial\mu}{\partial x}, \quad v = -\frac{\partial\phi}{\partial y} + \lambda \frac{\partial\mu}{\partial y}, \quad w = -\frac{\partial\phi}{\partial z} + \lambda \frac{\partial\mu}{\partial z}, \quad (1)$$

where ϕ, λ, μ are functions of x, y, z , provided the component rotations can be put in the forms

$$2\xi = \frac{\partial(\lambda, \mu)}{\partial(y, z)}, \quad 2\eta = \frac{\partial(\lambda, \mu)}{\partial(z, x)}, \quad 2\zeta = \frac{\partial(\lambda, \mu)}{\partial(x, y)} \quad (2)$$

Now if the differential equations of the vortex-lines, viz

$$\frac{dx}{\xi} = \frac{dy}{\eta} = \frac{dz}{\zeta}, \quad . \quad . \quad . \quad (3)$$

be supposed integrated in the form

$$\alpha = \text{const}, \quad \beta = \text{const}, \quad . \quad . \quad . \quad (4)$$

where α, β are functions of x, y, z , we must have

$$2\xi = P \frac{\partial(\alpha, \beta)}{\partial(y, z)}, \quad 2\eta = P \frac{\partial(\alpha, \beta)}{\partial(z, x)}, \quad 2\zeta = P \frac{\partial(\alpha, \beta)}{\partial(x, y)}, \quad . \quad . \quad (5)$$

where P is some function of x, y, z || Substituting these expressions in the identity

$$\frac{\partial\xi}{\partial x} + \frac{\partial\eta}{\partial y} + \frac{\partial\zeta}{\partial z} = 0,$$

we find

$$\frac{\partial(P, \alpha, \beta)}{\partial(x, y, z)} = 0, \quad . \quad . \quad . \quad (6)$$

which shews that P is of the form $f(\alpha, \beta)$ If λ, μ be any two functions of α, β , we have

$$\frac{\partial(\lambda, \mu)}{\partial(y, z)} = \frac{\partial(\lambda, \mu)}{\partial(\alpha, \beta)} \times \frac{\partial(\alpha, \beta)}{\partial(y, z)}, \quad \&c, \quad \&c,$$

* Sir W Thomson, *l c*, Hicks, "On the Steady Motion and the Small Vibrations of a Hollow Vortex," *Phil Trans*, 1884, Pocklington, "The Complete System of the Periods of a Hollow Vortex Ring," *Phil Trans*, A, t clxxxvi p 603 (1895), Carslaw, "The Fluted Vibrations of a Circular Vortex-Ring with a Hollow Core," *Proc Lond Math Soc*, t xxviii p 97 (1896)

† Hicks, *l c*, Pocklington, "Hollow Straight Vortices," *Camb. Proc*, t. viii p 178 (1894)

‡ *l c ante* p. 182

§ "Ueber eine allgemeine Transformation d hydrodynamischen Gleichungen," *Crelle*, t liv (1857) and t lvi (1859). See also Hill, *Quart Journ Math*, t xvii (1881), and *Camb Trans*,

t xiv (1883)

|| Cf Forsyth, *Differential Equations*, Art 174

and the equations (5) will therefore reduce to the form (2), provided λ, μ be chosen so that

$$\frac{\partial(\lambda, \mu)}{\partial(\alpha, \beta)} = f(\alpha, \beta), \quad (7)$$

which can obviously be satisfied in an infinity of ways

It is evident from (2) that the intersections of the surfaces $\lambda = \text{const}$, $\mu = \text{const}$ are the vortex-lines. This suggests that the functions λ, μ which occur in (1) may be supposed to vary continuously with t in such a way that the surfaces in question move with the fluid*. Various analytical proofs of the possibility of this have been given, the simplest, perhaps, is by means of the equations (2) of Art 15, which give (as in Art 17)

$$u dx + v dy + w dz = u_0 da + v_0 db + w_0 dc - d\chi \quad (8)$$

It has been proved that we may assume, initially,

$$u_0 da + v_0 db + w_0 dc = -d\phi_0 + \lambda d\mu \quad (9)$$

Hence, considering space-variations at time t , we shall have

$$u dx + v dy + w dz = -d\phi + \lambda d\mu, \quad (10)$$

where $\phi = \phi_0 + \chi$, and λ, μ have the same values as in (9), but are now expressed in terms of x, y, z, t . Since, in the 'Lagrangian' method the independent space-variables relate to the individual particles, this proves the theorem

On this understanding the equations of motion can be integrated, provided the extraneous forces have a potential, and that p is a function of ρ only. We have

$$\begin{aligned} \frac{\partial u}{\partial t} - 2v\zeta + 2w\eta &= \frac{\partial u}{\partial t} + \left(u \frac{\partial \lambda}{\partial x} + v \frac{\partial \lambda}{\partial y} + w \frac{\partial \lambda}{\partial z} \right) \frac{\partial \mu}{\partial x} - \left(u \frac{\partial \mu}{\partial x} + v \frac{\partial \mu}{\partial y} + w \frac{\partial \mu}{\partial z} \right) \frac{\partial \lambda}{\partial x} \\ &= \frac{\partial}{\partial x} \left(-\frac{\partial \phi}{\partial t} + \lambda \frac{\partial \mu}{\partial t} \right) + \frac{D\lambda}{Dt} \frac{\partial \mu}{\partial x} - \frac{D\mu}{Dt} \frac{\partial \lambda}{\partial x}, \end{aligned} \quad (11)$$

and therefore, on the present assumption that $D\lambda/Dt = 0$, $D\mu/Dt = 0$,

$$\int \frac{d\rho}{\rho} + \frac{1}{2} q^2 + \Omega = \frac{\partial \phi}{\partial t} - \lambda \frac{\partial \mu}{\partial t}, \quad (12)$$

by Art 146 (5), (6). An arbitrary function of t is here supposed incorporated in $\partial \phi / \partial t$

If the above condition be not imposed on λ, μ , we have, writing

$$H = \int \frac{d\rho}{\rho} + \frac{1}{2} q^2 + \Omega - \frac{\partial \phi}{\partial t} + \lambda \frac{\partial \mu}{\partial t}, \quad (13)$$

$$\frac{D\lambda}{Dt} \frac{\partial \mu}{\partial x} - \frac{D\mu}{Dt} \frac{\partial \lambda}{\partial x} = -\frac{\partial H}{\partial x}, \quad \frac{D\lambda}{Dt} \frac{\partial \mu}{\partial y} - \frac{D\mu}{Dt} \frac{\partial \lambda}{\partial y} = -\frac{\partial H}{\partial y}, \quad \frac{D\lambda}{Dt} \frac{\partial \mu}{\partial z} - \frac{D\mu}{Dt} \frac{\partial \lambda}{\partial z} = -\frac{\partial H}{\partial z} \quad (14)$$

Hence

$$\frac{\partial(H, \lambda, \mu)}{\partial(x, y, z)} = 0, \quad (15)$$

shewing that H is of the form $f(\lambda, \mu, t)$; and

$$\frac{D\lambda}{Dt} = -\frac{\partial H}{\partial \mu}, \quad \frac{D\mu}{Dt} = \frac{\partial H}{\partial \lambda} \quad (16)$$

* It must not be overlooked that on account of the insufficient determinacy of λ, μ these functions may vary continuously with t without relating always to the same particles of fluid

CHAPTER VIII.

TIDAL WAVES

167 ONE of the most interesting and successful applications of hydrodynamical theory is to the small oscillations, under gravity, of a liquid having a free surface. In certain cases, which are somewhat special as regards the theory, but very important from a practical point of view, these oscillations may combine to form progressive waves travelling with (to a first approximation) no change of form over the surface

The term 'tidal,' as applied to waves, has been used in various senses, but it seems most natural to confine it to gravitational oscillations possessing the characteristic feature of the oceanic tides produced by the action of the sun and moon. We have therefore ventured to place it at the head of this Chapter, as descriptive of waves in which the motion of the fluid is mainly horizontal, and therefore (as will appear) sensibly the same for all particles in a vertical line. This latter circumstance greatly simplifies the theory

It will be convenient to recapitulate, in the first place, some points in the general theory of small oscillations which will receive constant exemplification in the investigations which follow*. The theory has reference in the first instance to a system of finite freedom, but the results, when properly interpreted, hold good without this restriction†

Let q_1, q_2, \dots, q_n be n generalized co-ordinates serving to specify the configuration of a dynamical system, and let them be so chosen as to vanish in the configuration of equilibrium. The kinetic energy T will be a homogeneous quadratic function of the generalized velocities $\dot{q}_1, \dot{q}_2, \dots, \dot{q}_n$, say

$$2T = a_{11}\dot{q}_1^2 + a_{22}\dot{q}_2^2 + \dots + 2a_{12}\dot{q}_1\dot{q}_2 + \dots, \quad \dots \quad (1)$$

where the coefficients are in general functions of the co-ordinates q_1, q_2, \dots, q_n ,

* For a fuller account of the general theory see Thomson and Tait, *Natural Philosophy*, Arts 337, , Lord Rayleigh, *Theory of Sound*, c iv., Routh, *Elementary Rigid Dynamics* (6th ed.), London, 1897, c ix, Whittaker, *Analytical Dynamics*, c vii

† The steps by which a rigorous transition can be made to the case of infinite freedom have recently been investigated by Hilbert, *Gott Nachr*, 1904, p 49

but may in the application to *small* motions, be supposed constant, and to have the values corresponding to $q_1, q_2, \dots, q_n = 0$. Again, if (as we shall suppose) the system is 'conservative,' the potential energy V of a small displacement is a homogeneous quadratic function of the component displacements q_1, q_2, \dots, q_n , with (on the same understanding) constant coefficients, say

$$2V = c_{11}q_1^2 + c_{22}q_2^2 + \dots + 2c_{12}q_1q_2 + \dots \quad (2)$$

By a real* linear transformation of the co-ordinates q_1, q_2, \dots, q_n it is possible to reduce T and V simultaneously to sums of squares, the new variables thus introduced are called the 'normal co-ordinates' of the system. In terms of these we have

$$2T = a_1q_1^2 + a_2q_2^2 + \dots + a_nq_n^2, \quad \dots \quad (3)$$

$$2V = c_1q_1^2 + c_2q_2^2 + \dots + c_nq_n^2 \quad \dots \quad (4)$$

The coefficients a_1, a_2, \dots, a_n are called the 'principal coefficients of inertia', they are necessarily positive. The coefficients c_1, c_2, \dots, c_n may be called the 'principal coefficients of stability', they are all positive when the undisturbed configuration is stable.

When given extraneous forces act on the system, the work done by these during an arbitrary infinitesimal displacement $\Delta q_1, \Delta q_2, \dots, \Delta q_n$ may be expressed in the form

$$Q_1\Delta q_1 + Q_2\Delta q_2 + \dots + Q_n\Delta q_n \quad \dots \quad (5)$$

The coefficients Q_1, Q_2, \dots, Q_n are then called the 'normal components of disturbing force'.

In terms of the normal co-ordinates, the equations of motion are given by Lagrange's equations

$$\frac{d}{dt} \frac{\partial T}{\partial q_r} - \frac{\partial T}{\partial q_r} = - \frac{\partial V}{\partial q_r} + Q_r \quad [r = 1, 2, \dots, n] \quad (6)$$

In the present application to infinitely small motions, these take the form

$$a_rq_1 + c_rq_r = Q_r. \quad \dots \quad (7)$$

It is easily seen from this that the dynamical characteristics of the normal co-ordinates are (1°) that an impulse of any normal type produces an initial motion of that type only, and (2°) that a steady disturbing force of any type maintains a displacement of that type only.

To obtain the *free* motions of the system we put $Q_r = 0$. Solving, we find

$$q_r = A_r \cos(\sigma_r t + \epsilon_r), \quad \dots \quad (8)$$

where

$$\sigma_r = \left(\frac{c_r}{a_r} \right)^{\frac{1}{2}}, \quad \dots \quad (9)$$

* The algebraic proof of this involves the assumption that one at least of the functions T, V is essentially positive. In the present case T of course fulfils this condition.

and A_i, ϵ_i are arbitrary constants*. Hence a mode of free motion is possible in which any normal co-ordinate q_i varies alone, and the motion of any particle of the system, since it depends linearly on q_i , will be simple-harmonic, of period $2\pi/\sigma_i$, moreover the particles will pass simultaneously through their equilibrium positions. The several modes of this character are called the 'normal modes' of vibration of the system, their number is equal to that of the degrees of freedom, and any free motion whatever of the system may be obtained from them by superposition, with a proper choice of the 'amplitudes' (A_i) and 'epochs' (ϵ_i).

In certain cases, viz when two or more of the free periods ($2\pi/\sigma$) of the system are equal, the normal co-ordinates are to a certain extent indeterminate, i.e. they can be chosen in an infinite number of ways. An instance of this is the spherical pendulum. Other examples will present themselves later, see Arts 189, 198.

If two (or more) normal modes have the same period, then by compounding them, with arbitrary amplitudes and epochs, we obtain a small oscillation in which the motion of each particle is the resultant of simple-harmonic vibrations in different directions, and is therefore, in general, elliptic-harmonic, with the same period. This is exemplified in the conical pendulum, an important instance in our own subject is that of progressive waves in deep water (Chap IX).

If any of the coefficients of stability (c_r) be negative, the value of σ_r is pure imaginary. The circular function in (8) is then replaced by real exponentials, and an arbitrary displacement will in general increase until the assumptions on which the approximate equation (7) is based become untenable. The undisturbed configuration is then reckoned as unstable. The necessary and sufficient condition of stability (in the present sense) is that the potential energy V should be a minimum in the configuration of equilibrium.

To find the effect of disturbing forces, it is sufficient to consider the case where Q_r varies as a simple-harmonic function of the time, say

$$Q_r = C_r \cos(\sigma t + \epsilon), \quad \dots \quad (10)$$

where the value of σ is now prescribed. Not only is this the most interesting case in itself, but we know from Fourier's Theorem that, whatever the law of variation of Q_r with the time, it can be expressed by a series of terms such as (10). A particular integral of (7) is then

$$q_r = \frac{C_r}{c_r - \sigma^2 a_r} \cos(\sigma t + \epsilon) \quad \dots \quad (11)$$

This represents the 'forced oscillation' due to the periodic force Q_r . In it

* The ratio $\sigma/2\pi$ measures the 'frequency' of the oscillation. It is convenient to have a name for the quantity σ itself, the term 'speed' has been used in this sense by Lord Kelvin and Prof G. H. Darwin in their researches on the Tides.

the motion of every particle is simple-harmonic, of the prescribed period $2\pi/\sigma$, and the extreme displacements coincide in time with the maxima and minima of the force

A constant force equal to the instantaneous value of the actual force (10) would maintain a displacement

$$\bar{q}_r = \frac{C_r}{c_r} \cos(\sigma t + \epsilon), \quad (12)$$

the same, of course, as if the inertia-coefficient a_r were null. Hence (11) may be written

$$q_r = \frac{1}{1 - \frac{\sigma^2}{\sigma_r^2}} \bar{q}_r, \quad (13)$$

where σ_r has the value (9). This very useful formula enables us to write down the effect of a periodic force when we know that of a steady force of the same type. It is to be noticed that q_r and Q_r have the same or opposite phases according as $\sigma \lesseqgtr \sigma_r$, that is, according as the period of the disturbing force is greater or less than the free period. A simple example of this is furnished by a simple pendulum acted on by a periodic horizontal force. Other important illustrations will present themselves in the theory of the tides*.

When σ is very great in comparison with σ_r , the formula (11) becomes

$$q_r = -\frac{C_r}{\sigma^2 a_r} \cos(\sigma t + \epsilon). \quad (14)$$

the displacement is now always in the opposite phase to the force, and depends only on the *inertia* of the system.

If the period of the impressed force be nearly equal to that of the normal mode of order r , the amplitude of the forced oscillation, as given by (13), is very great compared with \bar{q}_r . In the case of exact equality, the solution (11) fails, and must be replaced by

$$q_r = Bt \sin(\sigma t + \epsilon), \quad (15)$$

where, as is verified immediately on substitution, $B = C_r/2\sigma a_r$. This gives an oscillation of continually increasing amplitude, and can therefore only be accepted as a representation of the initial stages of the disturbance.

Another very important property of the normal modes may be noticed. If by the introduction of constraints the system be compelled to oscillate in any other prescribed manner, the configuration at any instant can be specified by one variable, which we will denote by θ . In terms of this we shall have

$$q_r = B_r \theta,$$

* Cf. T. Young, "A Theory of Tides," *Nicholson's Journal*, t. xxxv (1813) [*Miscellaneous Works*, London, 1854, t. ii p. 262].

where the quantities B_r are certain constants. This makes

$$2T = (B_1^2 a_1 + B_2^2 a_2 + \dots + B_n^2 a_n) \theta^2, \quad (16)$$

$$2V = (B_1^2 c_1 + B_2^2 c_2 + \dots + B_n^2 c_n) \theta^2. \quad (17)$$

If $\theta \propto \cos(\sigma t + \epsilon)$, the constancy of the energy ($T + V$) requires

$$\sigma^2 = \frac{B_1^2 c_1 + B_2^2 c_2 + \dots + B_n^2 c_n}{B_1^2 a_1 + B_2^2 a_2 + \dots + B_n^2 a_n} \quad (18)$$

Hence σ^2 is intermediate in value between the greatest and least of the quantities c_r/a_r , in other words, the frequency of the constrained oscillation is intermediate between the greatest and least frequencies corresponding to the normal modes of the system. In particular, when a system is modified by the introduction of a constraint, the frequency of the slowest natural oscillation is *increased*.

Moreover, if the constrained type differ but slightly from a normal type (1), σ^2 will differ from c_r/a_r by a small quantity of the *second order*. This gives a valuable method of estimating approximately the frequency in cases where the normal types cannot be accurately determined*.

It may further be shewn that in the case of a *partial* constraint, which merely reduces the degree of freedom from n to $n - 1$, the periods of the modified system separate those of the original one†.

The modifications which are introduced into the theory of small oscillations by the consideration of viscous forces will be noticed in Chapter XI.

Long Waves in Canals

168 Proceeding now to the special problem of this Chapter, let us begin with the case of waves travelling along a straight canal, with horizontal bed, and parallel vertical sides. Let the axis of x be parallel to the length of the canal, that of y vertical and upwards, and let us suppose that the motion takes place in these two dimensions x, y . Let the ordinate of the free surface, corresponding to the abscissa x , at time t , be denoted by $y_0 + \eta$, where y_0 is the ordinate in the undisturbed state.

As already indicated, we shall assume in all the investigations of this Chapter that the vertical acceleration of the fluid particles may be neglected, or, more precisely, that the pressure at any point (x, y) is sensibly equal to the statical pressure due to the depth below the free surface, viz

$$p - p_0 = g\rho(y_0 + \eta - y), \quad (1)$$

where p_0 is the (uniform) external pressure.

* Lord Rayleigh, "Some General Theorems relating to Vibrations," *Proc Lond Math Soc*, t. iv p. 357 (1878) [*Sc Papers*, t. i p. 170], and *Theory of Sound*, c. iv.

† Routh, *Elementary Rigid Dynamics*, Art. 67, Rayleigh, *Theory of Sound* (2nd ed.), Art. 92a, Whittaker, *Analytical Dynamics*, Art. 81.

free surface we have $y = h + \eta$, $v = \partial\eta/\partial t$, whence (neglecting a product of small quantities)

$$\frac{\partial\eta}{\partial t} = -h \frac{\partial^2\xi}{\partial x\partial t} \quad \dots \quad (8)$$

From this (5) follows by integration with respect to t .

Eliminating η between (4) and (5), we obtain

$$\frac{\partial^2\xi}{\partial t^2} = gh \frac{\partial^2\xi}{\partial x^2} \quad \dots \quad (9)$$

The elimination of ξ gives an equation of the same form, viz

$$\frac{\partial^2\eta}{\partial t^2} = gh \frac{\partial^2\eta}{\partial x^2} \quad \dots \quad (10)$$

The above investigation can readily be extended to the case of a uniform canal of any form of section*. If the sectional area of the undisturbed fluid be S , and the breadth at the free surface b , the equation of continuity is

$$-\frac{\partial}{\partial x}(\xi S) \delta x = \eta b \delta x, \quad \dots \quad (11)$$

whence
$$\eta = -h \frac{\partial\xi}{\partial x}, \quad \dots \quad (12)$$

as before, provided $h = S/b$, i.e. h now denotes the *mean* depth of the canal. The dynamical equation (4) is of course unaltered.

169. The equation (9) is of a well-known type which occurs in several physical problems, e.g. the transverse vibrations of strings, and the motion of sound-waves in one dimension.

To integrate it, let us write, for shortness,

$$c^2 = gh, \quad \dots \quad (13)$$

and
$$x - ct = x_1, \quad x + ct = x_2$$

In terms of x_1 and x_2 as independent variables, the equation takes the form

$$\frac{\partial^2\xi}{\partial x_1\partial x_2} = 0$$

The complete solution is therefore

$$\xi = F(x - ct) + f(x + ct), \quad \dots \quad (14)$$

where F, f are arbitrary functions

* Kelland, *Trans R S Edin*, t xiv (1839).

The corresponding values of the particle-velocity and of the surface-elevation are given by

$$\left. \begin{aligned} \frac{\xi}{c} &= -F''(x-ct) + f'(x+ct), \\ \frac{\eta}{h} &= -F''(x-ct) - f'(x+ct) \end{aligned} \right\}. \quad (15)$$

The interpretation of these results is simple. Take first the motion represented by the first term in (14), alone. Since $F(x-ct)$ is unaltered when t and x are increased by τ and $c\tau$, respectively, it is plain that the disturbance which existed at the point x at time t has been transferred at time $t+\tau$ to the point $x+c\tau$. Hence the disturbance advances unchanged with a constant velocity c in space. In other words we have a 'progressive wave' travelling with constant velocity c in the direction of x -positive. In the same way the second term of (14) represents a progressive wave travelling with velocity c in the direction of x -negative. And it appears, since (14) is the *complete* solution of (9), that any motion whatever of the fluid, which is subject to the conditions laid down in the preceding Art, may be regarded as made up of waves of these two kinds.

The velocity (c) of propagation is, by (13), that 'due to' half the depth of the undisturbed fluid*.

The following table, giving in round numbers the velocity of wave-propagation for various depths, will be of interest, later, in connection with the theory of the tides.

h (feet)	c (feet per sec)	c (sea-miles per hour)	$2\pi a/c$ (hours)
312½*	100	60	360
1250	200	120	180
5000	400	240	90
11250+	600	360	60
20000	800	480	45

The last column gives the time a wave would take to travel over a distance equal to the earth's circumference ($2\pi a$). In order that a 'long' wave should traverse this distance in 24 hours, the depth would have to be about 14 miles. It must be borne in mind that these numerical results are only applicable to waves satisfying the conditions above postulated. The meaning of these conditions will be examined more particularly in Art 171.

170 To trace the effect of an arbitrary initial disturbance, let us suppose that when $t=0$ we have

$$\frac{\xi}{c} = \phi(x), \quad \frac{\eta}{h} = \psi(x) \quad . \quad . \quad . \quad . \quad (16)$$

* Lagrange, *Nouv. mém. de l'Acad. de Berlin*, 1781 [*Oeuvres*, t. 1 p. 747].

† This is probably comparable in order of magnitude with the mean depth of the ocean.

The functions F', f' which occur in (15) are then given by

$$\begin{aligned} F'(x) &= -\frac{1}{2} \{ \phi(x) + \psi(x) \}, \\ f'(x) &= \frac{1}{2} \{ \phi(x) - \psi(x) \}. \end{aligned} \tag{17}$$

Hence if we draw the curves $y = \eta_1, y = \eta_2$, where

$$\begin{aligned} \eta_1 &= \frac{1}{2}h \{ \psi(x) + \phi(x) \}, \\ \eta_2 &= \frac{1}{2}h \{ \psi(x) - \phi(x) \}, \end{aligned} \tag{18}$$

the form of the wave-profile at any subsequent instant t is found by displacing these curves parallel to x , through spaces $\pm ct$, respectively, and adding (algebraically) the ordinates. If, for example, the original disturbance be confined to a length l of the axis of x , then after a time $l/2c$ it will have broken up into two progressive waves of length l , travelling in opposite directions

In the particular case where in the initial state $\xi = 0$, and therefore $\phi(x) = 0$, we have $\eta_1 = \eta_2$, the elevation in each of the derived waves is then exactly half what it was, at corresponding points, in the original disturbance

It appears from (16) and (17) that if the initial disturbance be such that $\xi = \pm \eta/h \cdot c$, the motion will consist of a wave system travelling in one direction only, since one or other of the functions F' and f' is then zero.

It is easy to trace the motion of a surface-particle as a progressive wave of either kind passes it. Suppose, for example, that

$$\xi = F(x - ct), \tag{19}$$

and therefore
$$\xi = c \frac{\eta}{h} \tag{20}$$

The particle is at rest until it is reached by the wave; it then moves forward with a velocity proportional at each instant to the elevation above the mean level, the velocity being in fact less than the wave-velocity c , in the ratio of the surface-elevation to the depth of the water. The total displacement at any time is given by

$$\xi = \frac{1}{h} \int \eta c dt.$$

This integral measures the volume, per unit breadth of the canal, of the portion of the wave which has up to the instant in question passed the particle. Finally, when the wave has passed away, the particle is left at rest in advance of its original position at a distance equal to the total volume of the elevated water divided by the sectional area of the canal

171 We can now examine under what circumstances the solution expressed by (14) will be consistent with the assumptions made provisionally in Art 168.

The exact equation of vertical motion, viz

$$\rho \frac{Dv}{Dt} = -\frac{\partial p}{\partial z} - g\rho,$$

gives, on integration with respect to y ,

$$p - p_0 = g\rho (y_0 + \eta - y) - \rho \int_y^{y_0+\eta} \frac{Dv}{Dt} dy \quad \dots \quad (21)$$

This may be replaced by the approximate equation (1), provided $\beta (h + \eta)$ be small compared with $g\eta$, where β denotes the maximum vertical acceleration. Now in a progressive wave, if λ denote the distance between two consecutive nodes (i.e. points at which the wave-profile meets the undisturbed level), the time which the corresponding portion of the wave takes to pass a particle is λ/c , and therefore the vertical velocity will be of the order $\eta c/\lambda^*$, and the vertical acceleration of the order $\eta c^2/\lambda^2$, where η is the maximum elevation (or depression). Hence the neglect of the vertical acceleration is justified, provided h^2/λ^2 is a small quantity.

Waves whose slope is gradual, and whose length λ is large compared with the depth h of the fluid, are called 'long waves'.

Again, the restriction to infinitely small motions, made in equation (3), consisted in neglecting $u\partial u/\partial x$ in comparison with $\partial u/\partial t$. In a progressive wave we have $\partial u/\partial t = \pm c\partial u/\partial x$, so that u must be small compared with c , and therefore, by (20), η must be small compared with h . It is to be observed that this condition is altogether distinct from the former one, which may be legitimate in cases where the motion cannot be regarded as infinitely small. See Art 185.

The preceding conditions will of course be satisfied in the general case represented by equation (14), provided they are satisfied for each of the two progressive waves into which the disturbance can be analysed.

172 There is another, although on the whole a less convenient, method of investigating the motion of 'long' waves, in which the Lagrangian plan is adopted, of making the co-ordinates refer to the individual particles of the fluid. For simplicity, we will consider only the case of a canal of rectangular section†. The fundamental assumption that the vertical acceleration may be neglected implies as before that the horizontal motion of all particles in a plane perpendicular to the length of the canal will be the same. We there-

* Hence, comparing with (20), we see that the ratio of the maximum vertical to the maximum horizontal velocity is of the order h/λ .

† Airy, *Encyc. Metrop.*, "Tides and Waves," Art 192 (1845), see also Stokes, "On Waves," *Camb. and Dub. Math. Journ.*, t. iv (1849) [*Math. and Phys. Papers*, t. ii p. 222]. The case of a canal with sloping sides has been treated by McCowan, "On the Theory of Long Waves," *Phil. Mag.* (5), t. xxxv p. 250 (1892).

fore denote by $x + \xi$ the abscissa at time t of the plane of particles whose undisturbed abscissa is x . If η denote the elevation of the free surface, in this plane, the equation of motion of unit breadth of a stratum whose thickness (in the undisturbed state) is δx , will be

$$\rho h \delta x \frac{\partial^2 \xi}{\partial t^2} = - \frac{\partial p}{\partial x} \delta x (h + \eta),$$

where the factor $(\partial p / \partial x) . \delta x$ represents the pressure-difference for any two opposite particles x and $x + \delta x$ on the two faces of the stratum, while the factor $h + \eta$ represents the area of the stratum. Since we assume that the pressure about any particle depends only on its depth below the free surface we may write

$$\frac{\partial p}{\partial x} = g \rho \frac{\partial \eta}{\partial x},$$

so that our dynamical equation is

$$\frac{\partial^2 \xi}{\partial t^2} = - g \left(1 + \frac{\eta}{h} \right) \frac{\partial \eta}{\partial x} . \quad \dots \dots \dots (1)$$

The equation of continuity is obtained by equating the volumes of a stratum, consisting of the same particles, in the disturbed and undisturbed conditions respectively, viz.

$$\left(\delta x + \frac{\partial \xi}{\partial x} \delta x \right) (h + \eta) = h \delta x,$$

or
$$1 + \frac{\eta}{h} = \left(1 + \frac{\partial \xi}{\partial x} \right)^{-1} . \quad \dots \dots \dots (2)$$

Between equations (1) and (2) we may eliminate either η or ξ ; the result in terms of ξ is the simpler, being

$$\frac{\partial^2 \xi}{\partial t^2} = g h \frac{\frac{\partial^2 \xi}{\partial x^2}}{\left(1 + \frac{\partial \xi}{\partial x} \right)^3} . \quad \dots \dots \dots (3)$$

This is the general equation of 'long' waves in a uniform canal with vertical sides*

So far the only assumption is that the vertical acceleration of the particles may be neglected in calculating the pressure. If we now assume, in addition, that η/h is a small quantity, the equations (2) and (3) reduce to

$$\eta = - h \frac{\partial \xi}{\partial x}, \quad \dots \dots \dots (4)$$

and
$$\frac{\partial^2 \xi}{\partial t^2} = g h \frac{\partial^2 \xi}{\partial x^2} . \quad \dots \dots \dots (5)$$

* Airy, l c.

The elevation η also satisfies the equation

$$\frac{\partial^2 \eta}{\partial t^2} = gh \frac{\partial^2 \eta}{\partial x^2}. \quad \dots \dots \dots (6)$$

These are in conformity with our previous results, for the smallness of $\partial \xi / \partial x$ means that the relative displacement of any two particles is never more than a minute fraction of the distance between them, so that it is (to a first approximation) now immaterial whether the variable x be supposed to refer to a plane fixed in space, or to one moving with the fluid

173. The potential energy of a wave, or system of waves, due to the elevation or depression of the fluid above or below the mean level is, per unit breadth, $g\rho \iint y dx dy$, where the integration with respect to y is to be taken between the limits 0 and η , and that with respect to x over the whole length of the waves. Effecting the former integration, we get

$$\frac{1}{2} g \rho \int \eta^2 dx \quad \dots \dots \dots (1)$$

$$\text{The kinetic energy is} \quad \frac{1}{2} \rho h \int \xi^2 dx \quad \dots \dots \dots (2)$$

In a system of waves travelling in one direction only we have

$$\xi = \pm \frac{c}{h} \eta,$$

so that the expressions (1) and (2) are equal, or the total energy is half potential, and half kinetic

This result may be obtained in a more general manner, as follows* Any progressive wave may be conceived as having been originated by the splitting up, into two waves travelling in opposite directions, of an initial disturbance in which the particle-velocity was everywhere zero, and the energy therefore wholly potential. It appears from Art 170 that the two derived waves are symmetrical in every respect, so that each must contain half the original store of energy. Since, however, the elevation at corresponding points is for each derived wave exactly half that of the original disturbance, the potential energy of each will by (1) be one-fourth of the original store. The remaining (kinetic) part of the energy of each derived wave must therefore also be one-fourth of the original quantity.

174 If in any case of waves travelling in one direction only, without change of form, we impress on the whole mass a velocity equal and opposite to that of propagation, the motion becomes *steady*, whilst the forces acting on any particle remain the same as before. With the help of this artifice, the

* Lord Rayleigh, "On Waves," *Phil Mag* (5), t 1 p 257 [*Sc Papers*, t 1 p 251]

laws of wave-propagation can be investigated with great ease* Thus, in the present case we shall have, by Art. 22 (4), at the free surface,

$$\frac{p}{\rho} = \text{const} - g(h + \eta) - \frac{1}{2}q^2, \quad \dots \quad (1)$$

where q is the velocity. If the slope of the wave-profile be everywhere gradual, and the depth h small compared with the length of a wave, the horizontal velocity may be taken to be uniform throughout the depth, and approximately equal to q . Hence the equation of continuity is

$$q(h + \eta) = ch,$$

c being the velocity, in the steady motion, at places where the depth of the stream is uniform and equal to h . Substituting for q in (1), we have

$$\frac{p}{\rho} = \text{const} - gh \left(1 + \frac{\eta}{h}\right) - \frac{1}{2}c^2 \left(1 + \frac{\eta}{h}\right)^{-2}$$

Hence if η/h be small, the condition for a free surface, viz $p = \text{const}$, is satisfied approximately, provided

$$c^2 = gh,$$

which agrees with our former result.

175. It appears from the linearity of our equations that, in the case of sufficiently low waves, any number of independent solutions may be superposed. For example, having given a wave of any form travelling in one direction, if we superpose its *image* in the plane $x=0$, travelling in the opposite direction, it is obvious that in the resulting motion the horizontal velocity will vanish at the origin, and the circumstances are therefore the same as if there were a fixed barrier at this point. We can thus understand the reflexion of a wave at a barrier, the elevations and depressions are reflected unchanged, whilst the horizontal velocity is reversed. The same results follow from the formula

$$\xi = F(ct - x) - F(ct + x), \quad \dots \quad (1)$$

which is evidently the most general value of ξ subject to the condition that $\xi = 0$ for $x = 0$.

We can further investigate without much difficulty the partial reflexion of a wave at a point where there is an abrupt change in the section of the canal. Taking the origin at the point in question, we may write, for the negative side,

$$\eta_1 = F\left(t - \frac{x}{c_1}\right) + f\left(t + \frac{x}{c_1}\right), \quad u_1 = \frac{g}{c_1} F\left(t - \frac{x}{c_1}\right) - \frac{g}{c_1} f\left(t + \frac{x}{c_1}\right), \quad \dots \quad (2)$$

and for the positive side

$$\eta_2 = \phi\left(t - \frac{x}{c_2}\right), \quad u_2 = \frac{g}{c_2} \phi\left(t - \frac{x}{c_2}\right), \quad (3)$$

* Lord Rayleigh, *l.c.*

where the function F represents the original wave, and f , ϕ the reflected and transmitted portions respectively. The constancy of mass requires that at the point $x=0$ we should have $b_1 h_1 u_1 = b_2 h_2 u_2$, where b_1 , b_2 are the breadths at the surface, and h_1 , h_2 are the mean depths. We must also have at the same point $\eta_1 = \eta_2$, on account of the continuity of pressure*. These conditions give

$$\frac{b_1 h_1}{c_1} \{F(t) - f(t)\} = \frac{b_2 h_2}{c_2} \phi(t), \quad F(t) + f(t) = \phi(t)$$

We thence find that the ratios of the elevations in corresponding parts of the reflected and incident waves, and of the transmitted and incident waves, are

$$\frac{f}{F} = \frac{b_1 c_1 - b_2 c_2}{b_1 c_1 + b_2 c_2}, \quad \frac{\phi}{F} = \frac{2b_1 c_1}{b_1 c_1 + b_2 c_2}, \quad (4)$$

respectively. The reader may easily verify that the energy contained in the reflected and transmitted waves is equal to that of the original incident wave.

176 Our investigations, so far, relate to cases of *free* waves. When, in addition to gravity, small disturbing forces X , Y act on the fluid, the equation of motion is obtained as follows

We assume that within distances comparable with the depth h these forces vary only by a small fraction of their total value. On this understanding we have, in place of Art 168 (1),

$$\frac{p - p_0}{\rho} = (g - Y)(y_0 + \eta - y), \quad \dots \dots (1)$$

and therefore
$$\frac{1}{\rho} \frac{\partial p}{\partial x} = (g - Y) \frac{\partial \eta}{\partial x} - (y_0 + \eta - y) \frac{\partial Y}{\partial x}$$

The last term may be neglected for the reason just stated, and if we further neglect the product of the small quantities Y and $\partial \eta / \partial x$, the equation reduces to

$$\frac{1}{\rho} \frac{\partial p}{\partial x} = g \frac{\partial \eta}{\partial x}, \quad \dots \dots \dots (2)$$

as before. The equation of horizontal motion then takes the form

$$\frac{\partial^2 \xi}{\partial t^2} = -g \frac{\partial \eta}{\partial x} + X, \quad \dots \dots (3)$$

where X may be regarded as a function of x and t only. The equation of continuity has the same form as in Art 168, viz

$$\eta = -h \frac{\partial \xi}{\partial x} \quad \dots \dots (4)$$

* It will be understood that the problem admits only of an approximate treatment, on account of the rapid change in the character of the motion near the point of discontinuity. The nature of the approximation implied in the above assumptions will become more evident if we suppose the suffixes to refer to two sections S_1 and S_2 , one on each side of the origin O , at distances from O which, though very small compared with the wave-length, are yet moderate multiples of the transverse dimensions of the canal. The motion of the fluid will be sensibly uniform over each of these sections, and parallel to the length. The condition in the text then expresses that there is no sensible change of level between S_1 and S_2 .

Hence, on elimination of η ,

$$\frac{\partial^2 \xi}{\partial t^2} = gh \frac{\partial^2 \xi}{\partial x^2} + X. \quad \dots \quad (5)$$

177 The oscillations of water in a canal of uniform section, closed at both ends, may, as in the corresponding problem of Acoustics, be obtained by superposition of progressive waves travelling in opposite directions. It is more instructive, however, with a view to subsequent more difficult investigations, to treat the problem as an example of the general theory sketched in Art 167

We have to determine ξ so as to satisfy

$$\frac{\partial^2 \xi}{\partial t^2} = c^2 \frac{\partial^2 \xi}{\partial x^2} + X, \quad \dots \quad (1)$$

together with the terminal conditions that $\xi = 0$ for $x = 0$ and $x = l$, say

To find the free oscillations we put $X = 0$, and assume that

$$\xi \propto \cos(\sigma t + \epsilon),$$

where σ is to be found. On substitution we obtain

$$\frac{\partial^2 \xi}{\partial x^2} + \frac{\sigma^2}{c^2} \xi = 0, \quad \dots \quad (2)$$

whence, omitting the time-factor,

$$\xi = A \sin \frac{\sigma x}{c} + B \cos \frac{\sigma x}{c}.$$

The terminal conditions give $B = 0$, and

$$\frac{\sigma l}{c} = r\pi, \quad \dots \quad (3)$$

where r is integral. Hence the normal mode of order r is given by

$$\xi = A, \sin \frac{r\pi x}{l} \cos \left(\frac{r\pi ct}{l} + \epsilon \right), \quad \dots \quad (4)$$

where the amplitude A , and epoch ϵ , are arbitrary.

In the slowest oscillation ($r=1$), the water sways to and fro, heaping itself up alternately at the two ends, and there is a node at the middle ($x=\frac{1}{2}l$). The period ($2l/c$) is equal to the time a progressive wave would take to traverse twice the length of the canal.

The periods of the higher modes are respectively $\frac{1}{2}$, $\frac{1}{3}$, $\frac{1}{4}$, .. of this, but it must be remembered, in this and in other similar problems, that our theory ceases to be applicable when the length l/r of a semi-undulation becomes comparable with the depth h .

On comparison with the general theory of Art. 167, it appears that the normal co-ordinates of the present system are quantities $q_1, q_2, \dots q_n$ such that when the system is displaced according to any one of them, say q_r , we have

$$\xi = q_r \sin \frac{r\pi x}{l},$$

and we infer that the most general displacement of which the system is capable (subject to the conditions presupposed) is given by

$$\xi = \sum q_r \sin \frac{r\pi x}{l}, \quad \dots \dots \dots (5)$$

where $q_1, q_2, \dots q_n$ are arbitrary. This is in accordance with Fourier's Theorem

When expressed in terms of the normal velocities and the normal co-ordinates, the expressions for T and V must reduce to sums of squares. This is easily verified, in the present case, from the formula (5). Thus if S denote the sectional area of the canal, we find

$$2T = \rho S \int_0^l \dot{\xi}^2 dx = \sum a_r q_r^2, \quad 2V = g\rho \frac{S}{h} \int_0^l \eta^2 dx = \sum c_r q_r^2, \quad \dots \dots (6)$$

where $a_r = \frac{1}{2} \rho S l, \quad c_r = \frac{1}{2} r^2 \pi^2 g \rho h \frac{S}{l}.$ (7)

It is to be noted that, on the present reckoning, the coefficients of stability (c_r) increase with the depth.

Conversely, if we assume from Fourier's theorem that (5) is a sufficiently general expression for the value of ξ at any instant, the calculation just indicated shews that the coefficients q_r are the normal co-ordinates, and the frequencies can then be found from the general formula (9) of Art. 167, viz we have

$$\sigma_r = \left(\frac{c_r}{a_r} \right)^{\frac{1}{2}} = r\pi \frac{(gh)^{\frac{1}{2}}}{l}, \quad \dots \dots (8)$$

in agreement with (3).

178 As an example of forced waves we take the case of a uniform horizontal force

$$X = f \cos(\sigma t + \epsilon) \quad \dots \dots \dots (9)$$

This will illustrate, to a certain extent, the generation of tides in a land-locked sea of small dimensions.

Assuming that ξ varies as $\cos(\sigma t + \epsilon)$, and omitting the time-factor, the equation (1) becomes

$$\frac{\partial^2 \xi}{\partial x^2} + \frac{\sigma^2}{c^2} \xi = -\frac{f}{c^2},$$

the solution of which is

$$\xi = -\frac{f}{\sigma^2} + D \sin \frac{\sigma x}{c} + E \cos \frac{\sigma x}{c}. \quad \dots \quad (10)$$

The terminal conditions give

$$E = \frac{f}{\sigma^2}, \quad D \sin \frac{\sigma l}{c} = \left(1 - \cos \frac{\sigma l}{c}\right) \frac{f}{\sigma^2}. \quad (11)$$

Hence, unless $\sin \sigma l/c = 0$, we have $D = f/\sigma^2 \tan \sigma l/2c$, so that

$$\left. \begin{aligned} \xi &= \frac{2f}{\sigma^2 \cos \frac{\sigma l}{2c}} \sin \frac{\sigma x}{2c} \sin \frac{\sigma(l-x)}{2c} \cos(\sigma t + \epsilon), \\ \eta &= \frac{hf}{\sigma c \cos \frac{\sigma l}{2c}} \sin \frac{\sigma(x - \frac{1}{2}l)}{c} \cos(\sigma t + \epsilon) \end{aligned} \right\} \dots \quad (12)$$

and

If the period of the disturbing force be large compared with that of the slowest free mode, $\sigma l/2c$ will be small, and the formula for the elevation becomes

$$\eta = \frac{f}{g} (x - \frac{1}{2}l) \cos(\sigma t + \epsilon), \quad \dots \quad (13)$$

approximately, exactly as if the water were devoid of inertia. The horizontal displacement of the water is always in the same phase with the force, so long as the period is greater than that of the slowest free mode, or $\sigma l/c < \pi$. If the period be diminished until it is less than the above value, the phase is reversed.

When the period is exactly equal to that of a free mode of *odd* order ($s = 1, 3, 5, \dots$), the above expressions for ξ and η become infinite, and the solution fails. As pointed out in Art 167, the interpretation of this is that, in the absence of dissipative forces, the amplitude of the motion becomes so great that our fundamental approximations are no longer justified.

If, on the other hand, the period coincide with that of a free mode of *even* order ($s = 2, 4, 6, \dots$), we have $\sin \sigma l/c = 0$, $\cos \sigma l/c = 1$, and the terminal conditions are satisfied independently of the value of D . The forced motion may then be represented by*

$$\xi = -\frac{2f}{\sigma^2} \sin^2 \frac{\sigma x}{2c} \cos(\sigma t + \epsilon) \quad \dots \quad (14)$$

This example illustrates the fact that the effect of a disturbing force may often be conveniently calculated without resolving the force into its 'normal components' (Art 167)

* In the language of the general theory, the impressed force has here no component of the particular type with which it synchronizes, so that a vibration of this type is not excited at all. In the same way a periodic pressure applied at any point of a stretched string will not excite any fundamental mode which has a *node* there, even though it synchronize with it.

Another very simple case of forced oscillations, of some interest in connection with tidal theory, is that of a canal closed at one end and communicating at the other with an open sea in which a periodic oscillation

$$\eta = a \cos(\sigma t + \epsilon) \quad \dots \dots \dots (15)$$

is maintained. If the origin be taken at the closed end, the solution is obviously

$$\eta = a \frac{\cos \frac{\sigma x}{c}}{\cos \frac{\sigma l}{c}} \cdot \cos(\sigma t + \epsilon), \quad \dots \dots (16)$$

l denoting the length. If $\sigma l/c$ be small the tide has sensibly the same amplitude at all points of the canal. For particular values of l , (determined by $\cos \sigma l/c = 0$), the solution fails through the amplitude becoming infinite

Canal Theory of the Tides

179 The theory of forced oscillations in canals, or on open sheets of water, owes most of its interest to its bearing on the phenomena of the tides. The 'canal theory,' in particular, has been treated very fully by Airy*. We will consider one or two of the more interesting problems.

The calculation of the disturbing effect of a distant body on the waters of the ocean is placed for convenience in an Appendix at the end of this Chapter. It appears that the disturbing effect of the moon, for example, at a point P of the earth's surface, may be represented by a potential Ω whose approximate value is

$$\Omega = \frac{3}{2} \frac{\gamma M a^2}{D^3} (\frac{1}{3} - \cos^2 \mathfrak{S}), \quad \dots \dots (1)$$

where M denotes the mass of the moon, D its distance from the earth's centre, a the earth's radius, γ the 'constant of gravitation,' and \mathfrak{S} the moon's zenith distance at the place P . This gives a horizontal acceleration $\partial \Omega / \partial \mathfrak{S}$, or

$$f \sin 2\mathfrak{S}, \quad \dots \dots (2)$$

towards the point of the earth's surface which is vertically beneath the moon, where

$$f = \frac{3}{2} \gamma \frac{M a}{D^3} \cdot \dots \dots (3)$$

* *Encycl. Metrop.*, "Tides and Waves," Section vi (1845). Several of the leading features of the theory had been made out, by very simple methods, by Young, in 1813 and 1823 [*Miscellaneous Works*, t. ii pp. 262, 291].

If E be the earth's mass, we may write $g = \gamma E/a^2$, whence

$$\frac{f}{g} = \frac{3}{2} \cdot \frac{M}{E} \left(\frac{a}{D} \right)^3$$

Putting $M/E = \frac{1}{81}$, $a/D = \frac{1}{60}$, this gives $f/g = 8.57 \times 10^{-8}$. When the sun is the disturbing body, the corresponding ratio is $f/g = 3.78 \times 10^{-8}$.

It is convenient, for some purposes, to introduce a linear magnitude H , defined by

$$\frac{H}{a} = \frac{f}{g} \quad \dots \dots \dots (4)$$

If we put $a = 21 \times 10^6$ feet, this gives, for the lunar tide, $H = 1.80$ ft., and for the solar tide $H = 79$ ft. It is shewn in the Appendix that H measures the maximum range of the tide, from high water to low water, on the 'equilibrium theory'.

180 Take now the case of a uniform canal coincident with the earth's equator, and let us suppose for simplicity that the moon describes a circular orbit in the same plane. Let ξ be the displacement, relative to the earth's surface, of a particle of water whose mean position is at a distance x , measured eastwards, from some fixed meridian. If n be the angular velocity of the earth's rotation, the actual displacement of the particle at time t will be $\xi + nat$, so that the tangential acceleration will be $\partial^2 \xi / \partial t^2$. If we suppose the 'centrifugal force' to be as usual allowed for in the value of g , the processes of Arts 168, 176 will apply without further alteration.

If n' denote the angular velocity of the moon relative to the fixed meridian*, we may write

$$S = n't + \frac{x}{a} + \epsilon,$$

so that the equation of motion is

$$\frac{\partial^2 \xi}{\partial t^2} = c^2 \frac{\partial^2 \xi}{\partial x^2} - f \sin 2 \left(n't + \frac{x}{a} + \epsilon \right) \quad \dots \dots \dots (1)$$

The *free* oscillations are determined by the consideration that ξ is necessarily a periodic function of x , its value recurring whenever x increases by $2\pi a$. It may therefore be expressed, by Fourier's Theorem, in the form

$$\xi = \sum_0^\infty \left(P_r \cos \frac{rx}{a} + Q_r \sin \frac{rx}{a} \right) \quad \dots \dots \dots (2)$$

Substituting in (1), with the last term omitted, it is found that P_r and Q_r must satisfy the equation

$$\frac{d^2 P_r}{dt^2} + \frac{r^2 c^2}{a^2} P_r = 0 \quad \dots \dots \dots (3)$$

* That is, $n' = n - n_1$, if n_1 be the angular velocity of the moon in her orbit

The motion, in any normal mode, is therefore simple-harmonic, of period $2\pi a/rc$

For the *forced* waves, or tides, we find

$$\xi = -\frac{1}{4} \frac{fa^2}{c^2 - n'^2 a^2} \sin 2 \left(n't + \frac{x}{a} + \epsilon \right), \quad (4)$$

whence
$$\eta = \frac{1}{2} \frac{c^2 H}{c^2 - n'^2 a^2} \cos 2 \left(n't + \frac{x}{a} + \epsilon \right) \quad (5)$$

The tide is therefore semi-diurnal (the *lunar* day being of course understood), and is 'direct' or 'inverted,' *i.e.* there is high or low water beneath the moon, according as $c \gtrless n'a$, in other words according as the velocity, relative to the earth's surface, of a point which moves so as to be always vertically beneath the moon, is less or greater than that of a free wave. In the actual case of the earth we have

$$\frac{c^2}{n'^2 a^2} = \frac{g}{n'^2 a} \frac{h}{a} = 311 \frac{h}{a},$$

so that unless the depth of the canal were to greatly exceed such depths as actually occur in the ocean, the tides would be inverted.

This result, which is sometimes felt as a paradox, comes under a general principle referred to in Art. 167. It is a consequence of the comparative slowness of the free oscillations in an equatorial canal of moderate depth. It appears from the rough numerical table on p. 242 that with a depth of 11250 feet a free wave would take about 30 hours to describe the earth's semi-circumference, whereas the period of the tidal disturbing force is only a little over 12 hours.

The formula (5) is, in fact, a particular case of Art. 167 (13), for it may be written

$$\eta = \frac{1}{1 - \sigma^2/\sigma_0^2} \bar{\eta}, \quad (6)$$

where $\bar{\eta}$ is the elevation given by the 'equilibrium theory,' *viz.*

$$\bar{\eta} = \frac{1}{2} H \cos 2 \left(n't + \frac{x}{a} + \epsilon \right), \quad (7)$$

and $\sigma = 2n'$, $\sigma_0 = 2c/a$

For such moderate depths as 10000 feet and under, $n'^2 a^2$ is large compared with gh , the amplitude of the horizontal motion, as given by (4), is then $f/4n'^2$, or $g/4n'^2 a$. H , nearly, being approximately independent of the depth. In the case of the lunar tide this amplitude is about 140 feet. The maximum elevation is obtained by multiplying by $2h/a$, this gives, for a depth of 10000 feet, a height of only '133 of a foot.

For greater depths the tides would be higher, but still inverted, until we reach the critical depth $n'^2 a^2/g$, which is about 13 miles. For depths

beyond this limit, the tides become direct, and approximate more and more to the value given by the equilibrium theory*

181 The case of a circular canal parallel to the equator can be worked out in a similar manner. If the moon's orbit be still supposed to lie in the plane of the equator, we find by spherical trigonometry

$$\cos \mathfrak{D} = \sin \theta \cos \left(n't + \frac{x}{a \sin \theta} + \epsilon \right), \quad (1)$$

where θ is the co-latitude, and x denotes the distance of any point P of the canal from the zero meridian. This leads to

$$X = -\frac{\partial \Omega}{\partial x} = -f \sin \theta \sin 2 \left(n't + \frac{x}{a \sin \theta} + \epsilon \right), \quad (2)$$

$$\text{and thence to} \quad \eta = \frac{1}{2} \frac{c^2 H \sin^2 \theta}{c^2 - n'^2 a^2 \sin^2 \theta} \cos 2 \left(n't + \frac{x}{a \sin \theta} + \epsilon \right). \quad (3)$$

Hence if $n'a > c$ the tide will be direct or inverted according as $\theta \lesseqgtr \sin^{-1} c/n'a$. If the depth be so great that $c > n'a$, the tides will be direct for all values of θ .

If the moon be not in the plane of the equator, but have a co-declination Δ , the formula (1) is replaced by

$$\cos \mathfrak{D} = \cos \theta \cos \Delta + \sin \theta \sin \Delta \cos \alpha, \quad \dots \quad (4)$$

where α is the hour-angle of the moon from the meridian of P . For simplicity, we will neglect the moon's motion in her orbit in comparison with the earth's angular velocity of rotation (n), thus we put

$$\alpha = nt + \frac{x}{a \sin \theta} + \epsilon,$$

and treat Δ as constant. The resulting expression for the component X of the disturbing force is found to be

$$\begin{aligned} X = -\frac{\partial \Omega}{\partial x} = & -f \cos \theta \sin 2\Delta \sin \left(nt + \frac{x}{a \sin \theta} + \epsilon \right) \\ & - f \sin \theta \sin^2 \Delta \sin 2 \left(nt + \frac{x}{a \sin \theta} + \epsilon \right) \end{aligned} \quad (5)$$

We thence obtain

$$\begin{aligned} \eta = & \frac{1}{2} \frac{c^2 H}{c^2 - n^2 a^2 \sin^2 \theta} \sin 2\theta \sin 2\Delta \cos \left(nt + \frac{x}{a \sin \theta} + \epsilon \right) \\ & + \frac{1}{2} \frac{c^2 H}{c^2 - n^2 a^2 \sin^2 \theta} \sin^2 \theta \sin^2 \Delta \cos 2 \left(nt + \frac{x}{a \sin \theta} + \epsilon \right) \end{aligned} \quad (6)$$

* Cf Young, *l c ante* p 252

The first term gives a 'diurnal' tide of period $2\pi/n$, this vanishes and changes sign when the moon crosses the equator, *i.e.* twice a month. The second term represents a semi-diurnal tide of period π/n , whose amplitude is now less than before in the ratio of $\sin^2 \Delta$ to 1.

182 In the case of a canal coincident with a meridian we should have to take account of the fact that the undisturbed figure of the free surface is one of relative equilibrium under gravity and centrifugal force, and is therefore not exactly circular. We shall have occasion later on to treat the question of displacements relative to a rotating globe somewhat carefully, for the present we will assume by anticipation that *in a narrow canal* the disturbances are sensibly the same as if the earth were at rest, and the disturbing body were to revolve round it with the proper relative motion.

If the moon be supposed to move in the plane of the equator, the hour-angle from the meridian of the canal may be denoted by $n't + \epsilon$, and if x be the distance of any point P on the canal from the equator, we find

$$\cos \vartheta = \cos \frac{x}{a} \cos (n't + \epsilon). \quad . \quad . \quad . \quad (1)$$

Hence

$$X = -\frac{\partial \Omega}{\partial x} = -f \sin 2 \frac{x}{a} \cdot \cos^2 (n't + \epsilon) = -\frac{1}{2} f \sin 2 \frac{x}{a} \{1 + \cos 2 (n't + \epsilon)\} \quad (2)$$

Substituting in the equation (5) of Art. 176, and solving, we find

$$\eta = \frac{1}{4} H \cos 2 \frac{x}{a} + \frac{1}{4} \frac{c^2 H}{c^2 - n'^2 a^2} \cos 2 \frac{x}{a} \cos 2 (n't + \epsilon) \quad (3)$$

The first term represents a permanent change of mean level to the extent

$$\eta = \frac{1}{4} H \cos 2 \frac{x}{a} \quad . \quad . \quad (4)$$

The fluctuations above and below the disturbed mean level are given by the second term in (3). This represents a semi-diurnal tide, and we notice that if, as in the actual case of the earth, c be less than $n'a$, there will be high water in latitudes above 45° , and low water in latitudes below 45° , when the moon is in the meridian of the canal, and *vice versa* when the moon is 90° from that meridian. These circumstances would be all reversed if c were greater than $n'a$.

When the moon is not on the equator, but has a given declination, the mean level, as indicated by the term corresponding to (4), has a coefficient depending on the declination, and the consequent variations in it indicate a fortnightly (or, in the case of the sun, a semi-annual) tide. There is also introduced a diurnal tide whose sign depends on the declination. The reader will have no difficulty in examining these points, by means of the general value of Ω given in the Appendix.

Wave-Motion in a Canal of Variable Section

183 When the section (S , say) of the canal is not uniform, but varies gradually from point to point, the equation of continuity is, as in Art. 168 (11),

$$\eta = -\frac{1}{b} \frac{\partial}{\partial x} (S\xi), \quad \dots \dots \dots (1)$$

where b denotes the breadth at the surface. If h denote the mean depth over the width b , we have $S=bh$, and therefore

$$\eta = -\frac{1}{b} \frac{\partial}{\partial x} (hb\xi), \quad \dots \dots \dots (2)$$

where h , b are now functions of x

The dynamical equation has the same form as before, viz

$$\frac{\partial^2 \xi}{\partial t^2} = -g \frac{\partial \eta}{\partial x} \quad \dots \dots \dots (3)$$

Between (2) and (3) we may eliminate either η or ξ , the equation in η is

$$\frac{\partial^2 \eta}{\partial t^2} = \frac{g}{b} \frac{\partial}{\partial x} \left(hb \frac{\partial \eta}{\partial x} \right) \quad \dots \dots \dots (4)$$

The laws of propagation of waves in a canal of gradually varying rectangular section were investigated by Green* His results, freed from the restriction to the special form of section, may be obtained as follows

If we introduce a variable θ defined by

$$\frac{dx}{d\theta} = (gh)^{\frac{1}{2}}, \quad \dots \dots \dots (5)$$

in place of x , the equation (4) transforms into

$$\frac{\partial^2 \eta}{\partial t^2} = \eta'' + \left(\frac{b'}{b} + \frac{1}{2} \frac{h'}{h} \right) \eta', \quad \dots \dots \dots (6)$$

where the accents denote differentiations with respect to θ If b and h were constants, the equation would be satisfied by $\eta = F(\theta - t)$, as in Art 169, in the present case we assume, for trial,

$$\eta = \Theta \quad F(\theta - t), \quad \dots \dots \dots (7)$$

where Θ is a function of θ only Substituting in (6), we find

$$2 \frac{\Theta'}{\Theta} \cdot \frac{F'}{F} + \frac{\Theta''}{\Theta} + \left(\frac{b'}{b} + \frac{1}{2} \frac{h'}{h} \right) \left(\frac{F'}{F} + \frac{\Theta'}{\Theta} \right) = 0 \quad \dots \dots \dots (8)$$

The terms of this which involve F' will cancel provided

$$2 \frac{\Theta'}{\Theta} + \frac{b'}{b} + \frac{1}{2} \frac{h'}{h} = 0, \quad \dots \dots \dots (9)$$

or

$$\Theta = C b^{-\frac{1}{2}} h^{-\frac{1}{4}}, \quad \dots \dots \dots (9)$$

C being a constant Hence, provided the remaining terms in (8) may be neglected, the equation (4) will be satisfied

* "On the Motion of Waves in a Variable Canal of small depth and width," *Camd. Trans.* t. vi. (1837) [*Math. Papers*, p 225], see also Airy, "Tides and Waves," Art 260

The above approximation is justified, provided we can neglect Θ''/Θ' and Θ'/Θ in comparison with F''/F . As regards Θ'/Θ , it appears from (9) and (7) that this is equivalent to neglecting $b^{-1} db/dx$ and $h^{-1} dh/dx$ in comparison with $\eta^{-1} \partial\eta/\partial x$. If, now, λ denote a wave-length, in the general sense of Art. 171, $\partial\eta/\partial x$ is of the order η/λ , so that the assumption in question is that $\lambda db/dx$ and $\lambda dh/dx$ are small compared with b and h , respectively. In other words, it is assumed that the transverse dimensions of the canal vary only by small fractions of themselves within the limits of a wave-length. It is easily seen, in like manner, that the neglect of Θ''/Θ' in comparison with F''/F implies a similar limitation to the rates of change of db/dx and dh/dx .

Since the equation (4) is unaltered when we reverse the sign of z , the complete solution, subject to the above restrictions, is

$$\eta = b^{-\frac{1}{2}} h^{-\frac{1}{2}} \{F'(\theta - z) + f'(\theta + z)\}, \quad (10)$$

where F' and f' are arbitrary functions

The first term in this represents a wave travelling in the direction of x -positive, the velocity of propagation is determined by the consideration that any particular phase is recovered when $\delta\theta$ and δz have equal values, and is therefore equal to $(gh)^{\frac{1}{2}}$, by (5), exactly as in the case of a uniform section. In like manner the second term in (10) represents a wave travelling in the direction of x -negative. In each case the elevation of any particular part of the wave alters, as it proceeds, according to the law $b^{-\frac{1}{2}} h^{-\frac{1}{2}}$.

The reflection of a progressive wave at a point where the section of a canal suddenly changes has been considered in Art. 175. The formulæ there given shew, as we should expect, that the smaller the change in the dimensions of the section, the smaller will be the amplitude of the reflected wave. The case where the change from one section to the other is continuous, instead of abrupt, has been investigated by Lord Rayleigh for a special law of transition*. It appears that if the space within which the transition is completed be a moderate multiple of a wave-length there is practically no reflection, whilst in the opposite extreme the results agree with those of Art. 175.

If we assume, on the basis of these results, that when the change of section within a wave-length may be neglected a progressive wave suffers no appreciable disintegration by reflection, the law of amplitude easily follows from the principle of energy†. It appears from Art. 173 that the energy of the wave varies as the length, the breadth, and the square of the height, and it is easily seen that the length of the wave, in different parts of the canal, varies as the corresponding velocity of propagation, and therefore as the square root of the mean depth. Hence, in the above notation, $\eta^2 b h^{\frac{1}{2}}$ is constant, or

$$\eta \propto b^{-\frac{1}{2}} h^{-\frac{1}{4}},$$

which is Green's law above found.

* "On Reflection of Vibrations at the Confines of two Media between which the Transition is gradual," *Proc. Lond. Math. Soc.*, t. xi p. 51 (1880) [*Sc. Papers*, t. i p. 460], *Theory of Sound*, 2nd ed., London, 1894, Art. 148 b.

† Lord Rayleigh, *l.c. ante* p. 246.

184. In the case of simple harmonic motion, where $\eta \propto \cos(\sigma t + \epsilon)$, the equation (4) of the preceding Art. becomes

$$\frac{g}{b} \frac{\partial}{\partial x} \left(h b \frac{\partial \eta}{\partial x} \right) + \sigma^2 \eta = 0 \quad \dots \dots \dots (1)$$

Some particular cases of considerable interest can be solved with ease

1° For example, let us take the case of a canal whose breadth varies as the distance from the end $x=0$, the depth being uniform, and let us suppose that at its mouth ($x=a$) the canal communicates with an open sea in which a tidal oscillation

$$\eta = C \cos(\sigma t + \epsilon), \quad \dots \dots \dots (2)$$

is maintained. Putting $h = \text{const.}$, $b \propto x$, in (1), we find

$$\frac{\partial^2 \eta}{\partial x^2} + \frac{1}{x} \frac{\partial \eta}{\partial x} + k^2 \eta = 0, \quad \dots \dots \dots (3)$$

provided
$$k^2 = \frac{\sigma^2}{gh}. \quad \dots \dots \dots (4)$$

Hence
$$\zeta = C \frac{J_0(kx)}{J_0(ka)} \cos(\sigma t + \epsilon). \quad \dots \dots \dots (5)$$

The curve $y = J_0(x)$ is figured on p 269, it indicates how the amplitude of the forced oscillation increases, whilst the wave-length is practically constant, as we proceed up the canal from the mouth

2° Let us suppose that the variation is in the *depth* only, and that this increases uniformly from the end $x=0$ of the canal to the mouth, the remaining circumstances being as before. If, in (1), we put $h = h_0 x/a$, $\kappa = \sigma^2 a / g h_0$, we obtain

$$\frac{\partial}{\partial x} \left(x \frac{\partial \eta}{\partial x} \right) + \kappa \eta = 0. \quad \dots \dots \dots (6)$$

The solution of this which is finite for $x=0$ is

$$\eta = A \left(1 - \frac{\kappa x}{1^2} + \frac{\kappa^2 x^2}{1^2 2^2} - \dots \right), \quad \dots \dots \dots (7)$$


or
$$\eta = A J_0(2\kappa^{\frac{1}{2}} x^{\frac{1}{2}}), \quad \dots \dots \dots (8)$$

whence finally, restoring the time-factor and determining the constant,

$$\eta = C \frac{J_0(2\kappa^{\frac{1}{2}} x^{\frac{1}{2}})}{J_0(2\kappa^{\frac{1}{2}} a^{\frac{1}{2}})} \cos(\sigma t + \epsilon) \quad \dots \dots \dots (9)$$

The annexed diagram of the curve $y = J_0(\sqrt{x})$, where, for clearness, the scale adopted for y is 200 times that of x , shews how the amplitude continually increases, and the wave-length diminishes, as we travel up the canal

These examples may serve to illustrate the exaggeration of oceanic tides which takes place in shallow seas and in estuaries.



We add one or two simple problems of free oscillations.

3°. Let us take the case of a canal of uniform breadth, of length $2a$, whose bed slopes uniformly from either end to the middle. If we take the origin at one end, the motion in the first half of the canal will be determined, as above, by

$$\eta = A J_0(2\kappa^{\frac{1}{2}}x^{\frac{1}{2}}), \quad \dots \dots \dots (10)$$

where $\kappa = \sigma^2 a / g h_0$, h_0 denoting the depth at the middle

It is evident that the normal modes will fall into two classes. In the first of these η will have opposite values at corresponding points of the two halves of the canal, and will therefore vanish at the centre ($x = a$). The values of σ are then determined by

$$J_0(2\kappa^{\frac{1}{2}}a^{\frac{1}{2}}) = 0, \quad \dots \dots \dots (11)$$

viz. κ being any root of this, we have

$$\sigma = \frac{(g h_0)^{\frac{1}{2}}}{a} (\kappa a)^{\frac{1}{2}} \quad \dots \dots \dots (12)$$

In the second class, the value of η is symmetrical with respect to the centre, so that $\partial\eta/\partial x = 0$ at the middle. This gives

$$J_0'(2\kappa^{\frac{1}{2}}a^{\frac{1}{2}}) = 0 \quad \dots \dots \dots (13)$$

It appears that the slowest oscillation is of the asymmetrical class, and corresponds to the smallest root of (11), which is $2\kappa^{\frac{1}{2}}a^{\frac{1}{2}} = 7655\pi$, whence

$$\frac{2\pi}{\sigma} = 1.306 \times \frac{4a}{(g h_0)^{\frac{1}{2}}}.$$

4°. Again, let us suppose that the depth of the canal varies according to the law

$$h = h_0 \left(1 - \frac{x^2}{a^2}\right), \quad \dots \dots \dots (14)$$

where x now denotes the distance from the middle. Substituting in (1), with $b = \text{const}$, we find

$$\frac{\partial}{\partial x} \left\{ \left(1 - \frac{x^2}{a^2} \right) \frac{\partial \eta}{\partial x} \right\} + \frac{\sigma^2}{gh_0} \eta = 0 \quad \dots \dots \dots (15)$$

If we put $\sigma^2 = n(n+1) \frac{gh_0}{a^2}$, $\dots \dots \dots (16)$

this is of the same form as the general equation of zonal harmonics, Art. 84 (1)

In the present problem n is determined by the condition that ζ must be finite for $x/a = \pm 1$. This requires (Art 85) that n should be integral, the normal modes are therefore of the types

$$\eta = CP_n \left(\frac{x}{a} \right) \cos(\sigma t + \epsilon), \quad \dots \dots \dots (17)$$

where P_n is a zonal harmonic, the value of σ being determined by (16)

In the slowest oscillation ($n=1$), the profile of the free surface is a straight line. For a canal of *uniform* depth h_0 , and of the same length ($2a$), the corresponding value of σ would be $\pi c/2a$, where $c = (gh_0)^{\frac{1}{2}}$. Hence in the present case the frequency is less, in the ratio $2\sqrt{2\pi}$, or $\cdot 9003^*$.

The forced oscillations due to a uniform disturbing force

$$X = f \cos(\sigma t + \epsilon), \quad \dots \dots \dots (18)$$

can be obtained by the rule of Art. 167 (13). The equilibrium form of the free surface is evidently

$$\bar{\eta} = \frac{f}{g} x \cos(\sigma t + \epsilon), \quad \dots \dots \dots (19)$$

and, since the given force is of the normal type $n=1$, we have

$$\eta = \frac{f}{g(1 - \sigma^2/\sigma_0^2)} x \cos(\sigma t + \epsilon), \quad \dots \dots \dots (20)$$

where

$$\sigma_0^2 = \frac{2gh_0}{a^2}.$$

Waves of Finite Amplitude

185. When the elevation η is not small compared with the mean depth h , waves, even in an uniform canal of rectangular section, are no longer propagated without change of type. The question was first investigated by Airy†, by methods of successive approximation. He found that in a pro-

* Other cases of free oscillation in canals of varying section are discussed by Chrystal, "Some Results in the Mathematical Theory of Seiches," *Proc. R. S. Edin*, t. xxv p 328 (1904).

† "Tides and Waves," Art 198.

gressive wave different parts will travel with different velocities, the wave-velocity corresponding to an elevation η being given approximately by

$$c\left(1 + \frac{3}{2}\frac{\eta}{h}\right),$$

where c is the velocity corresponding to infinitely small amplitude

A more complete view of the matter can be obtained by the method employed by Riemann in treating the analogous problem in Acoustics, to which reference will be made in Chapter X

The sole assumption on which we are now proceeding is that the vertical acceleration may be neglected. It follows, as explained in Art 168, that the horizontal velocity may be taken to be uniform over any section of the canal. The dynamical equation is

$$\frac{\partial u}{\partial t} + u \frac{\partial u}{\partial x} = -g \frac{\partial \eta}{\partial x}, \quad \dots \dots \dots (1)$$

as before, and the equation of continuity, in the case of a rectangular section, is easily seen to be

$$\frac{\partial}{\partial x} \{ (h + \eta) u \} = - \frac{\partial \eta}{\partial t}, \quad \dots \dots \dots (2)$$

where h is the depth. This may be written

$$\frac{\partial \eta}{\partial t} + u \frac{\partial \eta}{\partial x} = - (h + \eta) \frac{\partial u}{\partial x} \dots \dots \dots (3)$$

Let us now write

$$P = f(\eta) + u, \quad Q = f(\eta) - u, \quad \dots \dots \dots (4)$$

where the function $f(\eta)$ is as yet at our disposal. If we multiply (3) by $f'(\eta)$, and add to (1), we get

$$\frac{\partial P}{\partial t} + u \frac{\partial P}{\partial x} = - (h + \eta) f'(\eta) \frac{\partial u}{\partial x} - g \frac{\partial \eta}{\partial x}.$$

If we now determine $f(\eta)$ so that

$$(h + \eta) \{ f'(\eta) \}^2 = g, \quad \dots \dots \dots (5)$$

this may be written

$$\frac{\partial P}{\partial t} + u \frac{\partial P}{\partial x} = - (h + \eta) f'(\eta) \frac{\partial P}{\partial x} \dots \dots \dots (6)$$

In the same way we find

$$\frac{\partial Q}{\partial t} + u \frac{\partial Q}{\partial x} = (h + \eta) f'(\eta) \frac{\partial Q}{\partial x} \dots \dots \dots (7)$$

The condition (5) is satisfied by

$$f(\eta) = 2c \left\{ \left(1 + \frac{\eta}{h} \right)^{\frac{1}{2}} - 1 \right\}, \quad \dots \quad (8)$$

where $c = (gh)^{\frac{1}{2}}$. The arbitrary constant has been chosen so as to make P and Q vanish in the parts of the canal which are free from disturbance, but this is not essential.

Substituting in (6) and (7) we find

$$\begin{aligned} dP &= \left[dx - \left\{ c \left(1 + \frac{\eta}{h} \right)^{\frac{1}{2}} + u \right\} dt \right] \frac{\partial P}{\partial x}, \\ dQ &= \left[dx + \left\{ c \left(1 + \frac{\eta}{h} \right)^{\frac{1}{2}} - u \right\} dt \right] \frac{\partial Q}{\partial x} \end{aligned} \quad (9)$$

It appears, therefore, that $dP = 0$, i.e. P is constant, for a geometrical point moving with the velocity

$$\frac{dx}{dt} = c \left(1 + \frac{\eta}{h} \right)^{\frac{1}{2}} + u, \quad \dots \quad (10)$$

whilst Q is constant for a point moving with the velocity

$$\frac{dx}{dt} = -c \left(1 + \frac{\eta}{h} \right)^{\frac{1}{2}} + u \quad (11)$$

Hence any given value of P travels forwards, and any given value of Q travels backwards, with the velocities given by (10) and (11) respectively. The values of P and Q are determined by those of η and u , and conversely.

As an example, let us suppose that the initial disturbance is confined to the space for which $a < x < b$, so that P and Q are initially zero for $x < a$ and $x > b$. The region within which P differs from zero therefore advances, whilst that within which Q differs from zero recedes, so that after a time these regions separate, and leave between them a space within which $P = 0$, $Q = 0$, and the fluid is therefore at rest. The original disturbance has now been resolved into two progressive waves travelling in opposite directions.

In the advancing wave we have

$$Q = 0, \quad \frac{1}{2}P = u = 2c \left\{ \left(1 + \frac{\eta}{h} \right)^{\frac{1}{2}} - 1 \right\}, \quad \dots \quad (12)$$

so that the elevation and the particle-velocity are connected by a definite relation (cf Art 170). The wave-velocity is given by (10) and (12), viz it is

$$c \left\{ 3 \left(1 + \frac{\eta}{h} \right)^{\frac{1}{2}} - 2 \right\}. \quad \dots \quad (13)$$

To the first order of η/h , this is in agreement with Airy's result.

Similar conclusions can be drawn in regard to the receding wave*

* The above results can also be deduced from the equation (3) of Art 172, to which Riemann's method can readily be adapted.

Since the wave-velocity increases with the elevation, it appears that in a progressive wave-system the slopes will become continually steeper in front, and more gradual behind, until at length a state of things is reached in which we are no longer justified in neglecting the vertical acceleration. As to what happens after this point we have at present no guide from theory, observation shews, however, that the crests tend ultimately to curl over and break.

186 In the detailed application of the equations (1) and (3) to tidal phenomena, it is usual to follow the method of successive approximation. As an example, we will take the case of a canal communicating at one end ($x = 0$) with an open sea, where the elevation is given by

$$\eta = a \cos \sigma t \quad \dots \dots \dots \quad (14)$$

For a first approximation we have

$$\frac{\partial u}{\partial t} = -g \frac{\partial \eta}{\partial x}, \quad \frac{\partial \eta}{\partial t} = -h \frac{\partial u}{\partial x}, \quad \dots \dots \quad (15)$$

the solution of which, consistent with (14), is

$$\eta = a \cos \sigma \left(t - \frac{x}{c} \right), \quad u = \frac{ga}{c} \cos \sigma \left(t - \frac{x}{c} \right) \quad (16)$$


For a second approximation we substitute these values of η and u in (1) and (3), and obtain

$$\frac{\partial u}{\partial t} = -g \frac{\partial \eta}{\partial x} - \frac{g^2 \sigma a^2}{2c^3} \sin 2\sigma \left(t - \frac{x}{c} \right), \quad \frac{\partial \eta}{\partial t} = -h \frac{\partial u}{\partial x} - \frac{g \sigma a^2}{c^2} \sin 2\sigma \left(t - \frac{x}{c} \right) \quad (17)$$

Integrating these by the usual methods, we find, as the solution consistent with (14),

$$\left. \begin{aligned} \eta &= a \cos \sigma \left(t - \frac{x}{c} \right) - \frac{3}{4} \frac{g \sigma a^2}{c^3} x \sin 2\sigma \left(t - \frac{x}{c} \right), \\ u &= \frac{ga}{c} \cos \sigma \left(t - \frac{x}{c} \right) - \frac{1}{8} \frac{g^2 a^2}{c^3} \cos 2\sigma \left(t - \frac{x}{c} \right) - \frac{3}{4} \frac{g^2 \sigma a^2}{c^4} x \sin \sigma \left(t - \frac{x}{c} \right). \end{aligned} \right\} \quad (18)$$

The annexed figure shews, with, of course, exaggerated amplitude, the profile of the waves in a particular case, as determined by the first of these equations. It is to be noted that if we fix our attention on a particular point of the canal, the rise and fall of the water do not take place symmetrically, the fall occupying a longer time than the rise



The occurrence of the factor x outside trigonometrical terms in (18) shews that there is a limit beyond which the approximation breaks down. The condition for the success of the approximation is evidently that $g \sigma a x / c^3$ should be small. Putting $c^2 = gh$, $\lambda = 2\pi c / \sigma$, this fraction becomes equal to $2\pi (a/h) (x/\lambda)$. Hence however small the ratio of the original elevation (a) to the depth, the fraction ceases to be small when x is a sufficient multiple of the wave-length (λ).

It is to be noticed that the limit here indicated is already being overstepped in the right-hand portions of the figure, and that the peculiar features which are beginning to shew themselves on the rear slope are an indication rather of the imperfections of the analysis than of any actual property of the waves. If we were to trace the curve further, we should find a secondary maximum and minimum of elevation developing themselves on the rear slope. In this way Airy attempted to explain the phenomenon of a double high-water which is observed in some rivers, but, for the reason given, the argument cannot be sustained*.

The same difficulty does not necessarily present itself in the case of a canal closed by a fixed barrier at a distance from the mouth, or, again, in the case of the forced waves due to a periodic horizontal force in a canal closed at both ends (Art 178). Enough has, however, been given to shew the general character of the results to be expected in such cases. For further details we must refer to Airy's treatise†.

When analysed, as in (18), into a series of simple-harmonic functions of the time, the expression for the elevation of the water at any particular place (x) consists of two terms, of which the second represents an 'over-tide,' or 'tide of the second order,' being proportional to a^2 , its frequency is double that of the primary disturbance (14). If we were to continue the approximation we should obtain tides of higher orders, whose frequencies are 3, 4, . . . times that of the primary.

If, in place of (14), the disturbance at the mouth of the canal were given by

$$\zeta = a \cos \sigma t + a' \cos (\sigma' t + \epsilon),$$

it is easily seen that in the second approximation we should in like manner obtain tides of periods $2\pi/(\sigma + \sigma')$ and $2\pi/(\sigma - \sigma')$, these are called 'compound tides.' They are analogous to the 'combination-tones' in Acoustics which were first investigated by von Helmholtz‡.

Propagation in Two Dimensions.

187. Let us suppose, in the first instance, that we have a plane sheet of water of uniform depth h . If the vertical acceleration be neglected, the horizontal motion will as before be the same for all particles in the same vertical line. The axes of x, y being horizontal, let u, v be the component horizontal velocities at the point (x, y) , and let ζ be the corresponding elevation of the free surface above the undisturbed level. The equation of continuity may be obtained by calculating the flux of matter into the columnar space which stands on the elementary rectangle $\delta x \delta y$; viz we have, neglecting terms of the second order,

$$\frac{\partial}{\partial x} (u h \delta y) \delta x + \frac{\partial}{\partial y} (v h \delta x) \delta y = - \frac{\partial}{\partial t} \{ (\zeta + h) \delta x \delta y \},$$

$$\text{whence} \quad \frac{\partial \zeta}{\partial t} = -h \left(\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} \right) \quad . \dots . \dots . \dots . \quad (1)$$

* McCowan, *l.c. ante* p. 244.

† "Tides and Waves," Arts 198, and 308. See also G. H. Darwin, "Tides," *Encyc Britann* (9th ed.) t. xxiii. pp. 362, 363 (1888).

‡ "Ueber Combinationstone," *Beil Monatsber*, May 22, 1856 [*Ges Abh.*, t. i p. 256], and "Theorie der Luftschwingungen in Röhren mit offenen Enden," *Crelle*, t. lvi. p. 14 (1859) [*Ges Abh.*, t. i. p. 318].

The dynamical equations are, in the absence of disturbing forces,

$$\rho \frac{\partial u}{\partial t} = -\frac{\partial p}{\partial x}, \quad \rho \frac{\partial v}{\partial t} = -\frac{\partial p}{\partial y},$$

where we may write

$$p - p_0 = g\rho(z_0 + \zeta - z),$$

if z_0 denote the ordinate of the free surface in the undisturbed state. We thus obtain

$$\frac{\partial u}{\partial t} = -g \frac{\partial \zeta}{\partial x}, \quad \frac{\partial v}{\partial t} = -g \frac{\partial \zeta}{\partial y}. \quad \dots \dots \dots (2)$$

If we eliminate u and v , we find

$$\frac{\partial^2 \zeta}{\partial t^2} = c^2 \left(\frac{\partial^2 \zeta}{\partial x^2} + \frac{\partial^2 \zeta}{\partial y^2} \right), \quad \dots \dots \dots (3)$$

where $c^2 = gh$ as before

In the application to simple-harmonic motion, the equations are shortened if we assume a 'complex' time-factor $e^{i(\sigma t + \epsilon)}$, and reject, in the end, the imaginary parts of our expressions. This is legitimate so long as we have to deal solely with linear equations. We have then, from (2),

$$u = \frac{ig \partial \zeta}{\sigma \partial x}, \quad v = \frac{ig \partial \zeta}{\sigma \partial y}, \dots \dots \dots (4)$$

whilst (3) becomes

$$\frac{d^2 \zeta}{dx^2} + \frac{d^2 \zeta}{dy^2} + k^2 \zeta = 0, \quad \dots \dots \dots (5)$$

where

$$k^2 = \frac{\sigma^2}{c^2}. \quad \dots \dots \dots (6)$$

The condition to be satisfied at a vertical bounding wall is obtained at once from (4), viz it is

$$\frac{\partial \zeta}{\partial n} = 0, \quad \dots \dots \dots (7)$$

if δn denote an element of the normal to the boundary

When the fluid is subject to small disturbing forces whose variation within the limits of the depth may be neglected, the equations (2) are replaced by

$$\frac{\partial u}{\partial t} = -g \frac{\partial \zeta}{\partial x} - \frac{\partial \Omega}{\partial x}, \quad \frac{\partial v}{\partial t} = -g \frac{\partial \zeta}{\partial y} - \frac{\partial \Omega}{\partial y}, \quad \dots \dots \dots (8)$$

where Ω is the potential of these forces

$$\text{If we put} \quad \bar{\zeta} = -\frac{\Omega}{g}, \quad \dots \dots \dots (9)$$

so that $\bar{\zeta}$ denotes the equilibrium-elevation corresponding to the potential Ω , these may be written

$$\frac{\partial u}{\partial t} = -g \frac{\partial}{\partial x} (\zeta - \bar{\zeta}), \quad \frac{\partial v}{\partial t} = -g \frac{\partial}{\partial y} (\zeta - \bar{\zeta}). \quad \dots \quad (10)$$

In the case of simple-harmonic motion, these take the forms

$$u = \frac{vg}{\sigma} \frac{\partial}{\partial x} (\zeta - \bar{\zeta}), \quad v = \frac{vg}{\sigma} \frac{\partial}{\partial y} (\zeta - \bar{\zeta}), \quad \dots \quad ..(11)$$

whence, substituting in the equation of continuity (1), we obtain

$$(\nabla_1^2 + k^2) \zeta = \nabla_1^2 \bar{\zeta}, \quad \dots \dots \dots (12)$$

if
$$\nabla_1^2 = \frac{\partial^2}{\partial x^2} + \frac{\partial^2}{\partial y^2}, \quad \dots \dots \dots (13)$$

and $k^2 = \sigma^2/gh$, as before The condition to be satisfied at a vertical boundary is now

$$\frac{\partial}{\partial n} (\zeta - \bar{\zeta}) = 0 \quad \dots \dots \dots ..(14)$$

188 The equation (3) of Art 187 is identical in form with that which presents itself in the theory of the transverse vibrations of a uniformly stretched membrane A still closer analogy, when regard is had to the boundary conditions, is furnished by the theory of cylindrical waves of sound* Indeed many of the results obtained in this latter theory can be at once transferred to our present subject

Thus, to find the free oscillations of a sheet of water bounded by vertical walls, we require a solution of

$$(\nabla_1^2 + k^2) \zeta = 0, \quad \dots \dots \dots (1)$$

subject to the boundary condition

$$\frac{\partial \zeta}{\partial n} = 0 \quad \dots \dots \dots (2)$$

Just as in Art. 177 it will be found that such a solution is possible only for certain values of k , which accordingly determine the periods $(2\pi/kc)$ of the various normal modes

Thus, in the case of a *rectangular* boundary, if we take the origin at one corner, and the axes of x, y along two of the sides, the boundary conditions are that $\partial\zeta/\partial x = 0$ for $x = 0$ and $x = a$, and $\partial\zeta/\partial y = 0$ for $y = 0$ and $y = b$, where a, b are the lengths of the edges parallel to x, y respectively The general value of ζ subject to these conditions is given by the double Fourier's series

$$\zeta = \Sigma \Sigma A_{m,n} \cos \frac{m\pi x}{a} \cos \frac{n\pi y}{b}, \quad \dots \dots \dots (3)$$

* Lord Rayleigh, *Theory of Sound*, Art 339

where the summations include all integral values of m, n from 0 to ∞ . Substituting in (1) we find

$$k^2 = \pi^2 \left(\frac{m^2}{a^2} + \frac{n^2}{b^2} \right) \quad \dots \dots \dots (4)$$

If $a > b$, the component oscillation of longest period is got by making $m = 1, n = 0$, whence $ka = \pi$. The motion is then everywhere parallel to the longer side of the rectangle. Cf Art 177.

189 In the case of a *circular* sheet of water, it is convenient to take the origin at the centre, and to transform to polar co-ordinates, writing

$$x = r \cos \theta, \quad y = r \sin \theta.$$

The equation (1) of the preceding Art becomes

$$\frac{\partial^2 \zeta}{\partial r^2} + \frac{1}{r} \frac{\partial \zeta}{\partial r} + \frac{1}{r^2} \frac{\partial^2 \zeta}{\partial \theta^2} + k^2 \zeta = 0 \quad \dots \dots \dots (1)$$

This might of course have been established independently.

As regards dependence on θ , the value of ζ may, by Fourier's Theorem, be supposed expanded in a series of cosines and sines of multiples of θ , we thus obtain a series of terms of the form

$$f(r) \begin{matrix} \cos \\ \sin \end{matrix} s\theta \quad \dots \dots \dots (2)$$

It is found on substitution in (1) that each of these terms must satisfy the equation independently, and that

$$f''(r) + \frac{1}{r} f'(r) + \left(k^2 - \frac{s^2}{r^2} \right) f(r) = 0 \quad \dots \dots \dots (3)$$

This is of the same form as Art 101 (14). Since ζ must be finite for $r = 0$, the various normal modes are given by

$$\zeta = A_s J_s(kr) \begin{matrix} \cos \\ \sin \end{matrix} s\theta \cdot \cos(\sigma t + \epsilon), \quad \dots \dots \dots (4)$$

where s may have any of the values 0, 1, 2, 3, .., and A_s is an arbitrary constant. The admissible values of k are determined by the condition that $\partial \zeta / \partial r = 0$ at the boundary $r = a$, say, or

$$J'_s(ka) = 0. \quad \dots \dots \dots (5)$$


The corresponding 'speeds' (σ) of the oscillations are then given by $\sigma = k(gh)^{\frac{1}{2}}$.

In the case $s = 0$, the motion is symmetrical about the origin, so that the waves have annular ridges and furrows. The lowest roots of

$$J'_0(ka) = 0, \text{ or } J_1(ka) = 0, \quad \dots \dots \dots (6)$$

are given by

$$\frac{ka}{\pi} = 1.2197, \quad 2.2330, \quad 3.2383, \dots \dots \dots (7)$$



For the sake of clearness, the scale of the ordinates in this figure has been taken five times as great as that of the abscissae

these values tending ultimately to the form $ka/\pi = m + \frac{1}{2}$, where m is integral* In the m th mode of the symmetrical class there are m nodal circles whose radii are given by $\zeta = 0$ or

$$J_0(kr) = 0 \quad . \quad . \quad . \quad (8)$$

The roots of this† are

$$\frac{kr}{\pi} = 7.655, \quad 1.7571, \quad 2.7546, \quad \dots \quad (9)$$

For example, in the first symmetrical mode there is one nodal circle $r = 628a$. The form of the section of the free surface by a plane through the axis of z , in any of these modes, will be understood from the drawing of the curve $y = J_0(x)$, which is given on the preceding page

When $s > 0$ there are s equidistant nodal diameters, in addition to the nodal circles

$$J_s(kr) = 0 \quad . \quad . \quad . \quad \dots \quad (10)$$

It is to be noticed that, owing to the equality of the frequencies of the two modes represented by (4), the normal modes are now to a certain extent indeterminate, viz in place of $\cos s\theta$ or $\sin s\theta$ we might substitute $\cos s(\theta - \alpha_s)$, where α_s is arbitrary. The nodal diameters are then given by

$$\theta - \alpha_s = \frac{2m+1}{2s} \pi, \quad \dots \quad . \quad . \quad (11)$$

where $m = 0, 1, 2, \dots, s-1$. The indeterminateness disappears, and the frequencies become unequal, if the boundary deviate, however slightly, from the circular form

In the case of the circular boundary, we obtain by superposition of two fundamental modes of the same period, in different phases, a solution

$$\zeta = C_s J_s(kr) \cos(\sigma t \mp s\theta + \epsilon) \quad . \quad . \quad . \quad (12)$$

This represents a system of waves travelling unchanged round the origin with an angular velocity σ/s in the positive or negative direction of θ . The motion of the individual particles is easily seen from Art 187 (4) to be elliptic-harmonic, one principal axis of each elliptic orbit being along the radius vector. All this is in accordance with the general theory referred to in Art. 167

The most interesting modes of the unsymmetrical class are those corresponding to $s = 1$, e.g.

$$\zeta = A J_1(kr) \cos \theta \cdot \cos(\sigma t + \epsilon), \quad . \quad . \quad . \quad (13)$$

* Stokes, "On the Numerical Calculation of a class of Definite Integrals and Infinite Series," *Camb Trans*, t ix. (1850) [*Math and Phys Papers*, t ii p 355]

† It is to be noticed that ka/π is equal to τ_0/τ , where τ is the actual period, and τ_0 is the time a progressive wave would take to travel with the velocity $(gh)^{\frac{1}{2}}$ over a space equal to the diameter $2a$

† Stokes, l c


where k is determined by

$$J_1'(ka) = 0 \quad \dots\dots\dots(14)$$

The roots of this are*

$$\frac{ka}{\pi} = 586, \quad 1\,697, \quad 2\,717, \dots\dots\dots(15)$$

We have now one nodal diameter ($\theta = \frac{1}{2}\pi$), whose position is, however, indeterminate, since the origin of θ is arbitrary. In the corresponding modes for an elliptic boundary, the nodal diameter would be fixed, viz it would coincide with either the major or the minor axis, and the frequencies would be unequal.




The diagrams on this and on the next page shew the contour-lines of the free surface in the first two modes of the present species. These lines meet the boundary at right angles, in conformity with the general boundary condition (Art 188 (2)). The simple-harmonic vibrations of the individual particles take place in straight lines perpendicular to the contour-lines, by Art 187 (4). The form of the sections of the free surface by planes through the axis of z is given by the curve $y = J_1(x)$ on p. 269.

The first of the two modes here figured has the longest period of all the normal types. In it, the water sways from side to side, much as in the

* See Lord Rayleigh's treatise, Art 389. A general formula for calculating the roots of $J_s'(ka) = 0$, due to Prof. J. McMahon, is given by Gray and Mathews (*loc. cit.* p. 128), p. 241.

slowest mode of a canal closed at both ends (Art. 177) In the second mode there is a nodal circle, whose radius is given by the lowest root of $J_1(kr) = 0$, this makes $r = .719 a^*$.



A comparison of the preceding investigation with the general theory of small oscillations referred to in Art 167 leads to several important properties of Bessel's Functions

In the first place, since the total mass of water is unaltered, we must have

$$\int_0^{2\pi} \int_0^a \zeta r d\theta dr = 0, \quad \dots \quad (16)$$

where ζ has any one of the forms given by (4) For $s > 0$ this is satisfied in virtue of the trigonometrical factor $\cos s\theta$ or $\sin s\theta$, in the symmetrical case it gives

$$\int_0^a J_0(kr) r dr = 0 \quad \dots \quad (17)$$

Again, since the most general free motion of the system can be obtained by superposition of the normal modes, each with an arbitrary amplitude and epoch, it follows that any

* The oscillations of a liquid in a circular basin of any uniform depth were discussed by Poisson, "Sur les petites oscillations de l'eau contenue dans un cylindre," *Ann. de Gergonne*, t. xix p. 225 (1828-9), the theory of Bessel's Functions had not at that date been worked out, and the results were consequently not interpreted. The full solution of the problem, with numerical details, was given independently by Lord Rayleigh, *Phil. Mag.* (5), t. 1 p. 257 (1876) [*Sc. Papers*, t. 1. p. 25]

The investigation in the text is limited, of course, to the case of a depth small in comparison with the radius a . Poisson's and Lord Rayleigh's solution for the case of finite depth will be noticed in Chap. ix

value whatever of ζ , which is subject to the condition (16), can be expanded in a series of the form

$$\zeta = \Sigma \Sigma (A_s \cos s\theta + B_s \sin s\theta) J_s(kr), \quad \dots \dots (18)$$

where the summations embrace all integral values of s (including 0) and, for each value of s , all the roots k of (5). If the coefficients A_s, B_s be regarded as functions of t , the equation (18) may be regarded as giving the value of the surface-elevation at any instant. The quantities A_s, B_s are then the normal co-ordinates of the present system (Art 167), and in terms of them the formulæ for the kinetic and potential energies must reduce to sums of squares. Taking, for example, the potential energy

$$V = \frac{1}{2} g \rho \iint \zeta^2 dx dy, \quad \dots \dots \dots (19)$$

this requires that

$$\int_0^{2\pi} \int_0^a w_1 w_2 r d\theta dr = 0, \quad \dots \dots \dots (20)$$

where w_1, w_2 are any two terms of the expansion (18). If w_1, w_2 involve cosines or sines of different multiples of θ , this is verified at once by integration with respect to θ , but if we take

$$w_1 \propto J_s(k_1 r) \cos s\theta, \quad w_2 \propto J_s(k_2 r) \cos s\theta,$$

where k_1, k_2 are any two distinct roots of (5), we get

$$\int_0^a J_s(k_1 r) J_s(k_2 r) r dr = 0 \quad \dots \dots \dots (21)$$

The general results of which (17) and (21) are particular cases, are

$$\int_0^a J_0(kr) r dr = -\frac{a}{k} J_0'(ka) \dots \dots \dots (22)$$

(cf Art 102 (10)), and

$$\int_0^a J_s(k_1 r) J_s(k_2 r) r dr = \frac{1}{k_1^2 - k_2^2} \{k_2 a J_s'(k_2 a) J_s(k_1 a) - k_1 a J_s'(k_1 a) J_s(k_2 a)\}. \quad (23)$$

In the case of $k_1 = k_2$ the latter expression becomes indeterminate, the evaluation in the usual manner gives

$$\int_0^a \{J_s(ka)\}^2 r dr = \frac{1}{2k^2} [k^2 a^2 \{J_s'(ka)\}^2 + (k^2 a^2 - s^2) \{J_s(ka)\}^2] \quad (24)$$

For the analytical proofs of these formulæ we must refer to the treatises cited on p 128

The small oscillations of an *annular* sheet of water bounded by concentric circles are easily treated, theoretically, with the help of Bessel's Functions 'of the second kind.' The only case of any special interest, however, is when the two radii are nearly equal, we then have practically a re-entrant canal, and the solution follows more simply from Art 180.

The analysis can also be applied to the case of a *circular sector* of any angle*, or to a sheet of water bounded by two concentric circular arcs and two radii.

* See Lord Rayleigh, *Theory of Sound*, Art. 339.

190 As an example of *forced* vibrations, let us suppose that the disturbing forces are such that the equilibrium elevation would be

$$\bar{\zeta} = C \left(\frac{r}{a} \right)^s \cos s\theta \cos(\sigma t + \epsilon) \dots \dots \dots (25)$$

This makes $\nabla_1^2 \bar{\zeta} = 0$, so that the equation (12) of Art 187 reduces to the form (1), above, and the solution is

$$\zeta = A J_s(kr) \cos s\theta \cos(\sigma t + \epsilon), \dots \dots (26)$$

where A is an arbitrary constant The boundary-condition (Art 187 (14)) gives

$$A k a J_s'(ka) = sC,$$

whence
$$\zeta = C \frac{s J_s'(kr)}{k a J_s'(ka)} \cos s\theta \cos(\sigma t + \epsilon) \dots \dots \dots (27)$$

The case $s=1$ is interesting as corresponding to a *uniform* horizontal force, and the result may be compared with that of Art 178

From the case $s=2$ we could obtain a rough representation of the semi-diurnal tide in a polar basin bounded by a small circle of latitude, except that the rotation of the earth is not as yet taken into account

We notice that the expression for the amplitude of oscillation becomes infinite when $J_s'(ka) = 0$ This is in accordance with a general principle, of which we have already had several examples, the period of the disturbing force being now equal to that of one of the free modes investigated in the preceding Art.

191. When the sheet of water is of variable depth, the investigation at the beginning of Art 187 gives, as the equation of continuity,

$$\frac{\partial \zeta}{\partial t} = - \frac{\partial (hu)}{\partial x} - \frac{\partial (hv)}{\partial y} \dots \dots \dots (1)$$

The dynamical equations (Art 187 (2)) are of course unaltered Hence, eliminating ζ , we find, for the free oscillations,

$$\frac{\partial^2 \zeta}{\partial t^2} = g \left\{ \frac{\partial}{\partial x} \left(h \frac{\partial \zeta}{\partial x} \right) + \frac{\partial}{\partial y} \left(h \frac{\partial \zeta}{\partial y} \right) \right\} \dots \dots \dots (2)$$

If the time-factor be $e^{i(\sigma t + \epsilon)}$, we obtain

$$\frac{\partial}{\partial x} \left(h \frac{\partial \zeta}{\partial x} \right) + \frac{\partial}{\partial y} \left(h \frac{\partial \zeta}{\partial y} \right) + \frac{\sigma^2}{g} \zeta = 0 \dots \dots \dots (3)$$

When h is a function of r , the distance from the origin, only, this may be written

$$h \nabla_1^2 \zeta + \frac{dh}{dr} \frac{\partial \zeta}{\partial r} + \frac{\sigma^2}{g} \zeta = 0 \dots \dots \dots (4)$$

As a simple example we may take the case of a circular basin which shelves gradually from the centre to the edge, according to the law

$$h = h_0 \left(1 - \frac{r^2}{a^2} \right). \quad (5)$$

Introducing polar co-ordinates, and assuming that ζ varies as $\cos s\theta$ or $\sin s\theta$, the equation (4) takes the form

$$\left(1 - \frac{r^2}{a^2} \right) \left(\frac{\partial^2 \zeta}{\partial r^2} + \frac{1}{r} \frac{\partial \zeta}{\partial r} - \frac{s^2}{r^2} \zeta \right) - \frac{2}{a^2} r \frac{\partial \zeta}{\partial r} + \frac{\sigma^2}{gh_0} \zeta = 0 \quad \dots \quad (6)$$

That integral of this equation which is finite at the origin is easily found in the form of an ascending series. Thus, assuming

$$\zeta = \Sigma A_m \left(\frac{r}{a} \right)^m, \quad (7)$$

where the trigonometrical factors are omitted, for shortness, the relation between consecutive coefficients is found to be

$$(m^2 - s^2) A_m = \left\{ m(m-2) - s^2 - \frac{\sigma^2 a^2}{gh_0} \right\} A_{m-2},$$

or, if we write $\frac{\sigma^2 a^2}{gh_0} = n(n-2) - s^2, \quad \dots \quad (8)$

where n is not as yet assumed to be integral,

$$(m^2 - s^2) A_m = (m-n)(m+n-2) A_{m-2} \quad \dots \quad (9)$$

The equation is therefore satisfied by a series of the form (7), beginning with the term $A_s (r/a)^s$, the succeeding coefficients being determined by putting $m=s+2, s+4, \dots$ in (9). We thus find

$$\zeta = A_s \left(\frac{r}{a} \right)^s \left\{ 1 - \frac{(n-s-2)(n+s)}{2(2s+2)} \frac{r^2}{a^2} + \frac{(n-s-4)(n-s-2)(n+s)(n+s+2)}{2 \cdot 4(2s+2)(2s+4)} \frac{r^4}{a^4} - \dots \right\}, \quad (10)$$

or in the usual notation of hypergeometric series

$$\zeta = A_s \frac{r^s}{a^s} F \left(\alpha, \beta, \gamma, \frac{r^2}{a^2} \right), \quad \dots \quad (11)$$

where

$$\alpha = \frac{1}{2}n + \frac{1}{2}s, \quad \beta = 1 + \frac{1}{2}s - \frac{1}{2}n, \quad \gamma = s+1$$

Since these make $\gamma - \alpha - \beta = 0$, the series is not convergent for $r=a$, unless it terminate. This can only happen when n is integral, of the form $s+2j$. The corresponding values of σ are then given by (8)

In the symmetrical modes ($s=0$) we have

$$\zeta = A_0 \left\{ 1 - \frac{j(j-1)}{1^2} \frac{r^2}{a^2} + \frac{(j+1)j(j-1)(j-2)}{1^2 \cdot 2^2} \frac{r^4}{a^4} - \dots \right\}, \quad \dots \quad (12)$$

where j may be any integer greater than unity. It may be shown that this expression vanishes for $j-1$ values of r between 0 and a , indicating the existence of $j-1$ nodal circles. The value of σ is given by

$$\sigma^2 = 4j(j-1) \frac{gh_0}{a^2} \quad \dots \quad (13)$$

Thus the gravest symmetrical mode ($j=2$) has a nodal circle of radius $707a$, and its frequency is determined by $\sigma^2 = 8gh_0/a^2$

Of the unsymmetrical modes, the slowest, for any given value of s , is that for which $n=s+2$, in which case we have

$$\zeta = A_s \frac{r^s}{a^s} \cos s\theta \cos (\sigma t + \epsilon),$$

the value of σ being given by
$$\sigma^2 = 2s \frac{g h_0}{a^2} . \quad . \quad (14)$$

The slowest mode of all is that for which $s=1$, $n=3$, the free surface is then always *plane*. It is found on comparison with Art 189 (15) that the frequency is 768 of that of the corresponding mode in a circular basin of *uniform* depth h_0 , and of the same radius

As in Art 190 we could at once write down the formula for the tidal motion produced by a uniform horizontal periodic force, or, more generally, for the case when the disturbing potential is of the type

$$\Omega \propto r^s \cos s\theta \cos (\sigma t + \epsilon)$$

192 We may conclude this discussion of 'long' waves on plane sheets of water by an examination of the mode of propagation of disturbances from a centre in an unlimited sheet of uniform depth. For simplicity, we will consider only the case of symmetry, where the elevation ζ is a function of the distance r from the origin of disturbance. This will introduce us to some peculiar and rather important features which attend wave-propagation in two dimensions.

The investigation of a periodic disturbance involves the use of a Bessel's Function (of zero order) 'of the second kind,' as to which some preliminary notes may be useful.

To solve the equation
$$\frac{d^2\phi}{dz^2} + \frac{1}{z} \frac{d\phi}{dz} + \phi = 0 \quad \dots \dots \dots (1)$$

by definite integrals, we assume*
$$\phi = \int e^{-zt} T dt, \quad \dots \dots \dots (2)$$

where T is a function of the complex variable t , and the limits of integration are constants as yet unspecified. This makes

$$z \frac{d^2\phi}{dz^2} + \frac{d\phi}{dz} + z\phi = -[(1+t^2) e^{-zt} T] + \int \left(\frac{d}{dt} \{ (1+t^2) T \} - tT \right) e^{-zt} dt,$$

by a partial integration. The equation (1) is accordingly satisfied by

$$\phi = \int \frac{e^{-zt} dt}{\sqrt{(1+t^2)}}, \quad \dots \dots \dots (3)$$

provided the expression

$$\sqrt{(1+t^2)} e^{-zt}$$

vanish at each limit of integration. Hence, on the supposition that z is real and positive, or at all events has its real part positive, the integral in (3) may be taken along a path joining any two of the points i , $-i$, $+\infty$ in the plane of the variable t , but two distinct paths joining the same points will not necessarily give the same result if they include between them one of the branch-points ($t = \pm i$) of the function under the integral sign.

* Forsyth, *Differential Equations*, c vii. The systematic application of this method to the theory of Bessel's Functions is due to Hankel, "Die Cylinderfunktionen erster u zweiter Art," *Math Ann*, t 1 p 467 (1869). See Gray and Mathews, c vii.

Thus, for example, we have the solution

$$\phi_1 = \int_{-\infty}^{\infty} \frac{e^{-zt} dt}{\sqrt{(1+t^2)}},$$

where the path is the portion of the imaginary axis which lies between the limits, and that value of the radical is taken which becomes = 1 for $t=0$. If we write $t = \xi + i\eta$, we obtain


$$\phi_1 = i \int_{-1}^1 \frac{e^{-iz\eta} d\eta}{\sqrt{(1-\eta^2)}} = 2i \int_0^{\frac{1}{2}\pi} \cos(z \cos \theta) d\theta = i\pi J_0(z), \quad \dots \quad (4)$$

which is the solution already known (Art. 100)

An independent solution is obtained if we take the integral (3) along the axis of η from the point $(0, i)$ to the origin, and thence along the axis of ξ to the point $(\infty, 0)$. This gives, with the same determination of the radical,

$$\phi_2 = \int_i^0 \frac{e^{-iz\eta} d(i\eta)}{\sqrt{(1-\eta^2)}} + \int_0^\infty \frac{e^{-z\xi} d\xi}{\sqrt{(1+\xi^2)}} = \int_0^\infty \frac{e^{-z\xi} d\xi}{\sqrt{(1+\xi^2)}} - i \int_0^1 \frac{e^{-iz\eta} d\eta}{\sqrt{(1-\eta^2)}} \quad \dots \quad (5)$$

By adopting other pairs of limits, and other paths, we can obtain other forms of ϕ , but these must all be equivalent to ϕ_1 or ϕ_2 , or to linear combinations of these. In particular, some other forms of ϕ_2 are important. It is known that the value of the integral (3) taken round any closed contour which excludes the branch points ($t = \pm i$) is zero. Let us first take as our contour a rectangle, two of whose sides coincide with the positive portions of the axes of ξ and η , except for a small semicircular indentation about the point $t=i$, whilst the remaining sides are at infinity. It is easily seen that the parts of the integral due to the infinitely distant sides will vanish, either through the vanishing of the factor $e^{-z\xi}$ when ξ is infinite, or through the infinitely rapid fluctuation of the function $e^{-iz\eta}/\eta$ when η is infinite. Hence for the path which gave us (5) we may substitute that which extends along the axis of η from the point $(0, i)$ to $(0, i\infty)$, provided the continuity of the radical be attended to. Now as the variable t travels counter-clockwise round the small semicircle, the radical changes continuously from $\sqrt{(1-\eta^2)}$ to $i\sqrt{(\eta^2-1)}$. We have therefore



$$\phi_2 = \int_i^\infty \frac{e^{-iz\eta} d(i\eta)}{i\sqrt{(\eta^2-1)}} = \int_1^\infty \frac{e^{-iz\eta} d\eta}{\sqrt{(\eta^2-1)}} = \int_0^\infty e^{-iz \cosh u} du. \quad \dots \quad (6)$$

This solution is the one which is specially appropriate to the case of diverging waves. Another method of obtaining it will be given in Chap. X.

If we equate the imaginary parts of (5) and (6) we obtain

$$J_0(z) = \frac{2}{\pi} \int_0^\infty \sin(z \cosh u) du, \quad \dots \quad (7)$$

a form due to Mehler*

It is convenient to have a special notation for the function in (6), we write

$$D_0(z) = \frac{2}{\pi} \int_0^\infty e^{-iz \cosh u} du \quad \dots \quad (8)$$

* *Math Ann*, t. v. (1872)

This is equivalent to

$$D_0(z) = K_0(z) - \omega J_0(z), \quad \dots \quad (9)$$

where*

$$K_0(z) = \frac{2}{\pi} \int_0^\infty \cos(z \cosh u) du \quad \dots \quad (10)$$

Equating the real parts of (5) and (6) we have, also,

$$K_0(z) = \frac{2}{\pi} \int_0^\infty e^{-z \sinh u} du - \frac{2}{\pi} \int_0^{\frac{1}{2}\pi} \sin(z \cos \vartheta) d\vartheta \quad (11)$$

For a like reason, the path adopted for ϕ_2 may be replaced by the line drawn from the point $(0, \iota)$ parallel to the axis of ξ (viz the dotted line in the figure). To secure the continuity of $\sqrt{(1+t^2)}$, we note that as t describes the lower quadrant of the small semicircle, the value of the radical changes from $\sqrt{(1-\eta^2)}$ to $e^{\frac{1}{2}\pi} \sqrt{(2\xi)}$, approximately. Hence along the dotted line we have, putting $t = \iota + \xi$,

$$\sqrt{(1+t^2)} = e^{\frac{1}{2}\pi} \sqrt{(2\xi - \iota\xi^2)},$$

where that value of the radical is to be chosen which is real and positive when ξ is infinitesimal. Thus

$$\phi_2 = \int_{\iota}^{\infty + \iota} \frac{e^{-z(\xi + \iota)} d(\xi + \iota)}{e^{\frac{1}{2}\pi} \sqrt{(2\xi - \iota\xi^2)}} = \frac{1}{\sqrt{2}} e^{-\iota(z + \frac{1}{2}\pi)} \int_0^\infty \frac{e^{-z\xi}}{\xi^{\frac{1}{2}}} (1 - \frac{1}{2}\iota\xi)^{-\frac{1}{2}} d\xi \quad \dots \quad (12)$$

If we expand the binomial, and integrate term by term, we find

$$D_0(z) = \left(\frac{2}{\pi z}\right)^{\frac{1}{2}} e^{-\iota(z + \frac{1}{2}\pi)} \left\{ 1 + \frac{1^2}{1!} \left(\frac{\iota}{8z}\right) + \frac{1^2 \cdot 3^2}{2!} \left(\frac{\iota}{8z}\right)^2 + \dots \right\}, \quad \dots \quad (13)$$

where use has been made of the formulae

$$\left. \begin{aligned} \int_0^\infty e^{-z\xi} \xi^{-\frac{1}{2}} d\xi &= \frac{\Gamma(-\frac{1}{2})}{z^{\frac{1}{2}}} = \frac{\pi^{\frac{1}{2}}}{z^{\frac{1}{2}}}, \\ \int_0^\infty e^{-z\xi} \xi^{m-\frac{1}{2}} d\xi &= \frac{\Gamma(m-\frac{1}{2})}{z^{m+\frac{1}{2}}} = \frac{1 \cdot 3 \cdot (2m-1)}{2^m z^m} \frac{\pi^{\frac{1}{2}}}{z^{\frac{1}{2}}} \end{aligned} \right\} \quad \dots \quad (14)$$

If we isolate the imaginary part of (13) we have, on comparison with (9),

$$J_0(z) = \left(\frac{2}{\pi z}\right)^{\frac{1}{2}} \{R \sin(z + \frac{1}{4}\pi) - S \cos(z + \frac{1}{4}\pi)\}, \quad \dots \quad (15)$$

where

$$\left. \begin{aligned} R &= 1 - \frac{1^2 \cdot 3^2}{2! (8z)^2} + \frac{1^2 \cdot 3^2 \cdot 5^2 \cdot 7^2}{4! (8z)^4} - \dots, \\ S &= \frac{1^2}{1! (8z)} - \frac{1^2 \cdot 3^2 \cdot 5^2}{3! (8z)^3} + \dots \end{aligned} \right\} \quad \dots \quad (16)$$

A similar expression for $K_0(z)$ can easily be written down

* As regards K_0 , this is the notation employed by Heine (except as to the constant factor), and H. Weber. The reader should be warned, however, that the same symbol has been employed in at least two other distinct senses in connection with the theory of Bessel's Functions.

The choice of a standard solution 'of the second kind' is largely a matter of convention, since the differential equation (1) is still satisfied if we add any constant multiple of $J_0(z)$. In terms of the more usual notation,

$$K_0(z) = \frac{2}{\pi} \{-Y_0(z) + (\log 2 - \gamma) J_0(z)\},$$

where $\gamma = .5772$ (Euler's constant)

A table of the function $\frac{1}{2}\pi K_0(z)$ has been constructed by B. A. Smith, see *Phil. Mag.* (5), t. xlv p. 122 (1898).

The series in (13) and (16) are of the kind known as 'semi-convergent,' or 'asymptotic,' expansions, i.e. although for sufficiently large values of z the successive terms may for a while diminish, they ultimately increase again indefinitely, but if we stop at a small term we get an approximately correct result*. This may be established by an examination of the remainder after m terms in the process of evaluation of (12)

It follows from (15) that the large roots of the equation $J_0(z)=0$ approximate to those of

$$\sin(z + \frac{1}{4}\pi) = 0 \quad . \quad . \quad . \quad . \quad . \quad (17)$$

The series in (13) gives ample information as to the demeanour of the function $D_0(z)$ when z is large. When z is small, $D_0(z)$ is very great, as appears from (9) and (11). A complete formula suitable for this case can only be obtained by a somewhat indirect process, but an approximation may be conducted as follows. Referring to (11), we have

$$\begin{aligned} \int_0^\infty e^{-z \sinh v} dv &= \int_1^\infty e^{-\frac{1}{2}z(v - \frac{1}{v})} \frac{dv}{v} = \int_1^\infty \frac{e^{-\frac{1}{2}zv}}{v} \left\{ 1 + \frac{z}{2v} + \frac{1}{2!} \left(\frac{z}{2v} \right)^2 + \dots \right\} dv \\ &= \int_{\frac{1}{2}z}^\infty \frac{e^{-w}}{w} \left\{ 1 + \frac{z^2}{4w} + \frac{1}{2!} \left(\frac{z^2}{4w} \right)^2 + \dots \right\} dw. \quad . \quad . \quad . \quad . \quad . \quad (18) \end{aligned}$$

The first term gives†

$$\int_{\frac{1}{2}z}^\infty \frac{e^{-w}}{w} dw = -\gamma - \log \frac{1}{2}z + \dots \dots \dots (19)$$

and the remaining ones are small in comparison. Hence, by (9) and (11),

$$D_0(z) = -\frac{2}{\pi} (\log \frac{1}{2}z + \gamma + \frac{1}{2}i\pi + \dots) \quad . \quad . \quad . \quad . \quad . \quad (20)$$

It follows that

$$\lim_{z=0} z D_0'(z) = -\frac{2}{\pi} \dagger \quad . \quad . \quad . \quad . \quad . \quad (21)$$

193. We can now proceed to the wave-problem stated at the beginning of Art 192. For definiteness we will imagine the disturbance to be caused by a variable pressure p_0 applied to the surface. On this supposition the dynamical equations near the beginning of Art 187 are replaced by

$$\frac{\partial u}{\partial t} = -g \frac{\partial \xi}{\partial x} - \frac{1}{\rho} \frac{\partial p_0}{\partial x}, \quad \frac{\partial v}{\partial t} = -\frac{1}{\rho} \frac{\partial \xi}{\partial y} - \frac{1}{\rho} \frac{\partial p_0}{\partial y}, \quad . \quad . \quad . \quad . \quad . \quad (1)$$

whilst

$$\frac{\partial \xi}{\partial t} = -h \left(\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} \right), \quad . \quad . \quad . \quad . \quad . \quad (2)$$

as before.

* Cf Whittaker, *Modern Analysis*, c viii. The semi-convergent expansion of $J_0(z)$ is due to Poisson, *Journ de l'École Polyt*, cah 19, p 349 (1823), a rigorous investigation of this and other analogous expansions was given by Stokes, *l.c ante* p 270. The 'remainder' was examined by Lipschitz, *Crelle*, t lvi. p 189 (1859). Cf Hankel, *l.c ante* p 276.

† De Morgan, *Differential and Integral Calculus*, London, 1842, p 653.

‡ The Bessel's Functions of the second kind were first thoroughly investigated and made available for the solution of physical problems in an arithmetically intelligible form by Stokes, in a series of papers published in the *Camb Trans*. With the help of the modern Theory of Functions, some of the processes have been simplified by Lipschitz and others, and (especially from the physical point of view) by Lord Rayleigh. These later methods have been freely used in the text.

If we introduce the velocity-potential in (1), we have, on integration,

$$\frac{\partial \phi}{\partial t} = g\zeta + \frac{p_0}{\rho}. \quad \dots \dots \dots (3)$$

We may suppose that p_0 refers to the *change* of pressure, and that the arbitrary function of t which has been incorporated in ϕ is chosen so that $\partial \phi / \partial t = 0$ in the regions not affected by the disturbance. Eliminating ζ by means of (2), we have

$$\frac{\partial^2 \phi}{\partial t^2} = gh \nabla_1^2 \phi + \frac{1}{\rho} \frac{\partial p_0}{\partial t}. \quad \dots \dots \dots (4)$$

When ϕ has been determined, the value of ζ is given by (3).

We will now assume that p_0 is sensible only over a small* area about the origin. If we multiply both sides of (4) by $\delta x \delta y$, and integrate over the area in question, the term on the left-hand may be neglected (relatively), and we find

$$-\int \frac{\partial \phi}{\partial n} \delta s = \frac{1}{g\rho h} \frac{d}{dt} \iint p_0 dx dy, \quad \dots \dots \dots (5)$$

where δs is an element of the boundary of the area, and δn refers to the horizontal normal to δs , drawn outwards. Hence the origin may be regarded as a two-dimensional source, of strength

$$f(t) = \frac{1}{g\rho h} \frac{dP_0}{dt}, \quad \dots \dots \dots (6)$$

where P_0 is the integral disturbing pressure

Turning to polar co-ordinates, we have to satisfy

$$\frac{\partial^2 \phi}{\partial t^2} = c^2 \left(\frac{\partial^2 \phi}{\partial r^2} + \frac{1}{r} \frac{\partial \phi}{\partial r} \right), \quad \dots \dots \dots (7)$$

where $c^2 = gh$, subject to the condition

$$\lim_{r=0} \left(-2\pi r \frac{\partial \phi}{\partial r} \right) = f(t), \quad \dots \dots \dots (8)$$

where $f(t)$ is the strength of the source, as above defined.

In the case of a simple-harmonic source $e^{i\sigma t}$ the equation (7) takes the form

$$\frac{\partial^2 \phi}{\partial r^2} + \frac{1}{r} \frac{\partial \phi}{\partial r} + k^2 \phi = 0, \quad \dots \dots \dots (9)$$

where $k = \sigma/c$, and a solution is

$$\phi = \frac{1}{4} D_0(kr) e^{i\sigma t}, \quad \dots \dots \dots (10)$$

* That is, the dimensions of the area are small compared with the 'length' of the waves generated, this term being understood in the general sense of Art 171. On the other hand, the dimensions must be supposed large in comparison with h .

where the constant factor has been determined by Art 192 (21). Taking the real part we have

$$\phi = \frac{1}{4} \{K_0(kr) \cos \sigma t + J_0(kr) \sin \sigma t\}, \quad (11)$$

corresponding to $f(t) = \cos \sigma t$.

For large values of kr the result (10) takes the form

$$\phi = \frac{1}{\sqrt{(8\pi r)}} e^{i\sigma(t - \frac{r}{c}) - \frac{1}{2}i\pi} \dots \dots \dots (12)$$

The combination $t - r/c$ indicates that we have, in fact, obtained the solution appropriate to the representation of diverging waves.

It appears that the amplitude of the annular waves ultimately varies inversely as the square root of the distance from the origin

194 The solution we have obtained for the case of a simple-harmonic source $e^{i\sigma t}$ may be written

$$2\pi\phi = \int_0^\infty e^{i\sigma(t - \frac{r}{c} \cosh u)} du \dots \dots \dots (13)$$

This suggests generalization by Fourier's theorem; thus the formula

$$2\pi\phi = \int_0^\infty f\left(t - \frac{r}{c} \cosh u\right) du \dots \dots \dots (14)$$

should represent the disturbance due to a source $f(t)$ at the origin*. It is of course implied that the form of $f(t)$ must be such that the integral is convergent, this condition will as a matter of course be fulfilled whenever the source has been in action only for a finite time. A more complete formula, embracing both converging and diverging waves, is

$$2\pi\phi = \int_0^\infty f\left(t - \frac{r}{c} \cosh u\right) du + \int_0^\infty F\left(t + \frac{r}{c} \cosh u\right) du \dots \dots (15)$$

The solution (15) may be verified, subject to certain conditions, by substitution in the differential equation (7). Taking the first term alone, we find

$$\begin{aligned} 2\pi \left\{ c^2 \left(\frac{\partial^2 \phi}{\partial r^2} + \frac{1}{r} \frac{\partial \phi}{\partial r} \right) - \frac{\partial^2 \phi}{\partial t^2} \right\} \\ = \int_0^\infty \left\{ \sinh^2 u \cdot f''\left(t - \frac{r}{c} \cosh u\right) - \frac{c}{r} \cosh u \cdot f'\left(t - \frac{r}{c} \cosh u\right) \right\} du \\ = \frac{c^2}{r^2} \int_0^\infty \frac{\partial^2}{\partial u^2} f\left(t - \frac{r}{c} \cosh u\right) du = -\frac{c}{r} \left[\sinh u \cdot f'\left(t - \frac{r}{c} \cosh u\right) \right]_{u=0}^{u=\infty} \end{aligned}$$

This obviously vanishes whenever $f(t)=0$ for negative values of t exceeding a certain limit†

* The substance of Arts 194-196 is adapted from a paper "On Wave-Propagation in Two Dimensions," *Proc Lond Math Soc*, t xxxv p 141 (1902). A result equivalent to (14) was obtained (in a different manner) by Levi-Civita, *Nuovo Cimento* (4), t vi (1897).

† The verification is very similar to that given by Levi-Civita.

$$\begin{aligned}
 \text{Again,} \quad -2\pi r \frac{\partial \phi}{\partial t} &= \frac{r}{c} \int_0^\infty \cosh u \, f' \left(t - \frac{r}{c} \cosh u \right) du \\
 &= \frac{r}{c} \int_0^\infty (\sinh u + e^{-u}) f' \left(t - \frac{r}{c} \cosh u \right) du \\
 &= - \left[f \left(t - \frac{r}{c} \cosh u \right) \right]_{u=0}^{u=\infty} + \frac{r}{c} \int_0^\infty e^{-u} f' \left(t - \frac{r}{c} \cosh u \right) du \\
 &= f \left(t - \frac{r}{c} \right) + \frac{r}{c} \int_0^\infty e^{-u} f' \left(t - \frac{r}{c} \cosh u \right) du,
 \end{aligned}$$

under the same condition. The limiting value of this when $r=0$ is $f(t)$, and the statement made above as to the strength of the source in (14) is accordingly verified.

A similar process will apply to the second term of (15) provided $F(t)$ vanishes for positive values of t exceeding a certain limit.

195 We may apply (14) to trace the effect of a temporary source varying according to some simple prescribed law.

If we suppose that everything is quiescent until the instant $t=0$, so that $f(t)$ vanishes for negative values of t , we see from (14) or from the equivalent form

$$2\pi\phi = \int_{-\infty}^{t-\frac{r}{c}} \frac{f(\theta) d\theta}{\left\{ (t-\theta)^2 - \frac{r^2}{c^2} \right\}^{\frac{1}{2}}} \quad \dots \quad (16)$$

that ϕ will be zero everywhere so long as $t < r/c$. If, moreover, the source acts only for a finite time τ , so that $f(t) = 0$ for $t > \tau$, we have, for $t > \tau + r/c$,

$$2\pi\phi = \int_0^\tau \frac{f(\theta) d\theta}{\left\{ (t-\theta)^2 - \frac{r^2}{c^2} \right\}^{\frac{1}{2}}} \quad \dots \quad (17)^*$$

This expression does not as a rule vanish, the wave accordingly is not sharply defined in the rear, as it is in front, but has, on the contrary, a sort of 'tail'† whose form, when $t - r/c$ is large compared with τ , is determined by

$$2\pi\phi = \frac{1}{\left(t^2 - \frac{r^2}{c^2} \right)^{\frac{1}{2}}} \int_0^\tau f(\theta) d\theta. \quad \dots \quad (18)$$

* Analytically, it may be noticed that the equation (4), when $p_0=0$, may be written

$$\frac{\partial^2 \phi}{\partial x^2} + \frac{\partial^2 \phi}{\partial y^2} + \frac{\partial^2 \phi}{\partial (ict)^2} = 0,$$

and that (17) consists of an aggregate of solutions of the known type

$$\{x^2 + y^2 + (ict)^2\}^{-\frac{1}{2}}$$

† The existence of the 'tail' in the case of cylindrical electric waves, was noted by Heaviside, *Phil. Mag.* (5), t xxvi (1888) [*Electrical Papers*, t ii].

The elevation ζ at any point is given by (3), viz

$$\zeta = \frac{1}{g} \frac{\partial \phi}{\partial t} \quad \dots \quad \dots \quad \dots \quad \dots \quad (19)$$

It follows that

$$\int_{-\infty}^{\infty} \zeta dt = 0, \quad \dots \quad \dots \quad \dots \quad \dots \quad (20)$$

provided the initial and final values of ϕ vanish. It may be shewn that this will be the case whenever $f(t)$ is finite and the integral

$$\int_{-\infty}^{\infty} f(t) dt \quad \dots \quad \dots \quad \dots \quad \dots \quad (21)$$

is convergent. The meaning of these conditions appears from (6). It follows that even when P_0 is always positive, so that the flux of liquid in the neighbourhood of the origin is altogether outwards, the wave which passes any point does not consist solely of an elevation (as it would in the corresponding one-dimensional problem) but, in the simplest case, of an elevation followed by a depression.

196. 1° The simplest assumption we can make, free from awkward infinities, is that P_0 increases, during the interval from $t = -\tau$ to $t = +\tau$, from one constant value to another, according to the parabolic law

$$P_0 = A + B \left(t \pm \frac{t^2}{2\tau} \right),$$

where the upper or lower sign is to be taken according as t is negative or positive. This makes $f'(t) = \pm 1$, if a constant factor be omitted. The reduction of the formula


$$2\pi g \zeta = \int_0^{\infty} f' \left(t - \frac{r}{c} \cosh u \right) du = \int_{-\infty}^{t - \frac{r}{c}} \frac{f'(\theta) d\theta}{\left\{ (t - \theta)^2 - \frac{r^2}{c^2} \right\}^{\frac{1}{2}}} \quad (22)$$

is now very simple; we find

$$\left. \begin{aligned} 2\pi g \zeta &= 0, & \text{for } t < \frac{r}{c} - \tau, \\ &= \cosh^{-1} \frac{c(t + \tau)}{r}, & \text{for } \frac{r}{c} - \tau < t < \frac{r}{c}; \\ &= \cosh^{-1} \frac{c(t + \tau)}{r} - 2 \cosh^{-1} \frac{ct}{r}, & \text{for } \frac{r}{c} < t < \frac{r}{c} + \tau, \\ &= \cosh^{-1} \frac{c(t + \tau)}{r} - 2 \cosh^{-1} \frac{ct}{r} + \cosh^{-1} \frac{c(t - \tau)}{r}, & \text{for } t > \frac{r}{c} + \tau. \end{aligned} \right\} \dots \dots \dots (23)$$

The annexed figure, constructed with ζ as ordinate and t as abscissa, exhibits the variation of ζ at a particular point ($r = 100c\tau$) as the wave passes over it

Within the range shewn, the same curve also indicates very fairly the profile of the wave after a time t which is about equal to 100τ , it being understood, of course, in this interpretation, that the direction of propagation is from right to left. The change of sign, and the indefinite prolongation of the 'tail' will be observed.



2° The diagram shews certain peculiarities due to the abrupt changes in the rate of variation of the source. A solitary wave, free from discontinuity of every degree, is obtained if we assume

$$f(t) = \frac{\tau}{t^2 + \tau^2}, \quad \dots \dots \dots (24)$$

which makes P_0 increase from one constant value to another according to the law

$$P_0 = A + B \tan^{-1} \frac{t}{\tau} \quad \dots \dots \dots (25)$$

The disturbing pressure has now no definite epoch of beginning or ending, but the range of time within which it is sensible can be made as small as we please by diminishing τ . For purposes of calculation it is convenient to assume

$$f(t) = \frac{1}{t - i\tau} \quad \dots \dots \dots (26)$$

in place of (24), and to retain in the end only the imaginary part. We have then

$$2\pi\phi = \int_0^\infty \frac{du}{t - \frac{r}{c} \cosh u - i\tau} = 2 \int_0^1 \frac{dz}{t - \frac{r}{c} - i\tau - \left(t + \frac{r}{c} - i\tau\right) z^2}, \quad (27)$$

where $z = \tanh \frac{1}{2}u$. We now write

$$t - \frac{r}{c} - i\tau = a^2 e^{-2i\alpha}, \quad t + \frac{r}{c} - i\tau = b^2 e^{-2i\beta}, \quad \dots \dots \dots (28)$$

where we may suppose that a, b are positive, and that the angles α, β lie between 0 and $\frac{1}{2}\pi$. Since


$$\left. \begin{aligned} a^4 &= \left(t - \frac{r}{c}\right)^2 + \tau^2, & b^4 &= \left(t + \frac{r}{c}\right)^2 + \tau^2, \\ \tan 2\alpha &= \frac{c\tau}{ct - r}, & \tan 2\beta &= \frac{c\tau}{ct + r}, \end{aligned} \right\} \dots \dots \dots (29)$$

it appears that $a \leq b$ according as $t \geq 0$, and that $\alpha > \beta$ always. With this notation, we find

$$2\pi\phi = 2 \int_0^1 \frac{dz}{a^2 e^{-2i\alpha} - b^2 e^{-2i\beta} z^2} = -\frac{e^{i(\alpha+\beta)}}{ab} \log \frac{z + \frac{a}{b} e^{-i(\alpha-\beta)}}{z - \frac{a}{b} e^{-i(\alpha-\beta)}} \dots \dots (30)$$

To interpret the logarithms, let us mark, in the plane of a complex variable z , the points

$$I = +1, \quad P = -\frac{a}{b} e^{-i(\alpha-\beta)}, \quad Q = \frac{a}{b} e^{-i(\alpha-\beta)}.$$



Since the integrals in the second member of (30) are to be taken along the path OI , the proper value of the third member is

$$\frac{e^{i(\alpha+\beta)}}{ab} \left\{ \left(\log \frac{IP}{OP} + i \cdot OPI \right) - \left(\log \frac{IQ}{OQ} - i \cdot OQI \right) \right\},$$

where real logarithms and positive values of the angles are to be understood. Hence, rejecting all but the imaginary part, we find

$$2\pi\phi = \frac{\sin(\alpha+\beta)}{ab} \log \frac{IP}{IQ} + \frac{\cos(\alpha+\beta)}{ab} (\pi - PIQ) \dots (31)$$

as the solution corresponding to a source of the type (24). Here

$$\frac{IP}{IQ} = \left(\frac{a^2 + 2ab \cos(\alpha+\beta) + b^2}{a^2 - 2ab \cos(\alpha-\beta) + b^2} \right)^{\frac{1}{2}}, \quad \tan PIQ = \frac{2ab \sin(\alpha-\beta)}{b^2 - a^2}, \dots (32)$$

and the values of a, b, α, β in terms of r and t are to be found from (29)

It will be sufficient to trace the effect of the most important part of the wave as it passes a point whose distance r from the origin is large compared with $c\tau$. If we confine ourselves to times at which $t - r/c$ is small compared with r/c , a will be small compared with b , PIQ will be a small angle, and IP/IQ will = 1, nearly. If we put

$$t = \frac{r}{c} + \tau \tan \eta, \quad (33)$$

we shall have

$$\alpha = \frac{1}{4}\pi - \frac{1}{2}\eta, \quad a = \sqrt{(\tau \sec \eta)}, \quad \beta = \frac{1}{4} \frac{c\tau}{r}, \quad b = \left(\frac{2r}{c}\right)^{\frac{1}{2}}, \quad (34)$$


approximately, and the formula (31) will reduce to

$$2\pi\phi = \frac{\pi}{ab} \cos \alpha = \frac{\pi}{\sqrt{2}\tau} \left(\frac{c\tau}{r}\right)^{\frac{1}{2}} \cos\left(\frac{1}{4}\pi - \frac{1}{2}\eta\right) \sqrt{(\cos \eta)} \quad (35)$$

The elevation ζ is then given by

$$2\pi g\zeta = 2\pi g \frac{d\zeta}{d(\tau \tan \eta)} = \frac{1}{4\sqrt{2}\tau^2} \left(\frac{c\tau}{r}\right)^{\frac{1}{2}} \sin\left(\frac{1}{4}\pi - \frac{1}{2}\eta\right) \cos^3 \eta. \quad (36)$$

approximately. The annexed diagram shews the relation between ζ and t , as given by this formula*. The comparison with that on p 284 shews how the crudities have disappeared in consequence of the more natural suppositions now made as to the law of variation of the source



197 We proceed to consider the case of a spherical sheet, or ocean, of water, covering a solid globe. We will suppose for the present that the globe does not rotate, and we will also in the first instance neglect the mutual attraction of the particles of the water. The mathematical conditions of the

* The points marked -1, 0, +1 on the diagram correspond to the times $r/c - \tau$, r/c , $r/c + \tau$, respectively

question are then exactly the same as in the acoustical problem of the vibrations of spherical layers of air*

Let a be the radius of the globe, h the depth of the fluid, we assume that h is small compared with a , but not (as yet) that it is uniform. The position of any point on the sheet being specified by the angular co-ordinates θ, ω , let u be the component velocity of the fluid at this point along the meridian, in the direction of θ increasing, and v the component along the parallel of latitude, in the direction of ω increasing. Also let ζ denote the elevation of the free surface above the undisturbed level. The horizontal motion being assumed, for the reasons explained in Art. 171, to be the same at all points in a vertical line, the condition of continuity is

$$\frac{\partial}{\partial \theta} (uha \sin \theta \delta \omega) \delta \theta + \frac{\partial}{\partial \omega} (vha \delta \theta) \delta \omega = -a \sin \theta \delta \omega \ a \delta \theta \ \frac{\partial \zeta}{\partial t},$$

where the left-hand side measures the flux out of the columnar space standing on the element of area $a \sin \theta \delta \omega \ a \delta \theta$, whilst the right-hand member expresses the rate of diminution of the volume of the contained fluid, owing to fall of the surface. Hence

$$\frac{\partial \zeta}{\partial t} = -\frac{1}{a \sin \theta} \left\{ \frac{\partial (hu \sin \theta)}{\partial \theta} + \frac{\partial (hv)}{\partial \omega} \right\}. \quad \dots (1)$$

If we neglect terms of the second order in u, v , the dynamical equations are, on the same principles as in Arts 168, 187,

$$\frac{\partial u}{\partial t} = -g \frac{\partial \zeta}{a \partial \theta} - \frac{\partial \Omega}{a \partial \theta}, \quad \frac{\partial v}{\partial t} = -g \frac{\partial \zeta}{a \sin \theta \partial \omega} - \frac{\partial \Omega}{a \sin \theta \partial \omega}, \quad (2)$$

where Ω denotes the potential of the extraneous forces.

$$\text{If we put} \quad \bar{\zeta} = \frac{\Omega}{g}, \quad \dots \dots \dots (3)$$

these may be written

$$\frac{\partial u}{\partial t} = -\frac{g}{a} \frac{\partial}{\partial \theta} (\zeta - \bar{\zeta}), \quad \frac{\partial v}{\partial t} = -\frac{g}{a \sin \theta} \frac{\partial}{\partial \omega} (\zeta - \bar{\zeta}). \quad \dots (4)$$

Between (1) and (4) we can eliminate u, v , and so obtain an equation in ζ only.

In the case of simple-harmonic motion, the time-factor being $e^{i(\sigma t + e)}$, the equations take the forms

$$\zeta = \frac{i}{\sigma a \sin \theta} \left\{ \frac{\partial (hu \sin \theta)}{\partial \theta} + \frac{\partial (hv)}{\partial \omega} \right\}, \quad \dots (5)$$

$$u = i \frac{g}{\sigma a} \frac{\partial}{\partial \theta} (\zeta - \bar{\zeta}), \quad v = i \frac{g}{\sigma a \sin \theta} \frac{\partial}{\partial \omega} (\zeta - \bar{\zeta}). \quad \dots (6)$$

* Discussed in Lord Rayleigh's *Theory of Sound*, c. xviii.

198 We will now consider more particularly the case of *uniform* depth. To find the free oscillations we put $\zeta=0$, the equations (5) and (6) of the preceding Art then lead to

$$\frac{1}{\sin \theta} \frac{\partial}{\partial \theta} \left(\sin \theta \frac{\partial \zeta}{\partial \theta} \right) + \frac{1}{\sin^2 \theta} \frac{\partial^2 \zeta}{\partial \omega^2} + \frac{\sigma^2 a^2}{gh} \zeta = 0 \quad \dots \quad \dots (1)$$

This is identical in form with the general equation of spherical surface-harmonics (Art. 83 (2)) Hence, if we put

$$\frac{\sigma^2 a^2}{gh} = n(n+1), \quad \dots \dots \dots (2)$$

$$\text{a solution of (1) will be} \quad \zeta = S_n, \quad \dots \dots \dots (3)$$

where S_n is the general surface-harmonic of order n

It was pointed out in Art 86 that S_n will not be finite over the whole sphere unless n be integral. Hence, for an ocean covering the whole globe, the form of the free surface at any instant is, in any fundamental mode, that of a 'harmonic spheroid'

$$r = a + h + S_n \cos(\sigma t + \epsilon), \quad \dots \dots \dots (4)$$

and the speed of the oscillation is given by

$$\sigma = \{n(n+1)\}^{\frac{1}{2}} \frac{(gh)^{\frac{1}{2}}}{a}, \quad \dots \dots \dots (5)$$

the value of n being integral.

The characters of the various normal modes are best gathered from a study of the nodal lines ($S_n=0$) of the free surface. Thus, it is shown in treatises on Spherical Harmonics* that the zonal harmonic $P_n(\mu)$ vanishes for n real and distinct values of μ lying between ± 1 , so that in this case we have n nodal circles of latitude. When n is odd one of these coincides with the equator. In the case of the tesseral harmonic

$$(1 - \mu^2)^{\frac{1}{2}s} \frac{d^s P_n(\mu)}{d\mu^s} \frac{\cos}{\sin} \left\{ s\omega, \right.$$

the second factor vanishes for $n-s$ values of μ , and the trigonometrical factor for $2s$ equidistant values of ω . The nodal lines therefore consist of $n-s$ parallels of latitude and $2s$ meridians. Similarly the sectorial harmonic

$$(1 - \mu^2)^{\frac{1}{2}n} \frac{\cos}{\sin} \left\{ n\omega \right.$$

has as nodal lines $2n$ meridians

These are, however, merely special cases, for since there are $2n+1$ independent surface-harmonics of any integral order n , and since the

* For references, see p. 102.

frequency, determined by (5), is the same for each of these, there is a corresponding degree of indeterminateness in the normal modes, and in the configuration of the nodal lines

We can also, by superposition, build up various types of progressive waves, *e.g.* taking a sectorial harmonic we get a solution in which

$$\zeta \propto (1 - \mu^2)^{\frac{1}{2}n} \cos(n\omega - \sigma t + \epsilon), \quad . \quad . \quad . \quad . \quad . \quad (6)$$

this gives a series of meridional ridges and furrows travelling round the globe, the velocity of propagation, as measured at the equator, being

$$\frac{\sigma a}{n} = \left(\frac{n+1}{n}\right)^{\frac{1}{2}} \cdot (gh)^{\frac{1}{2}} \quad . \quad . \quad . \quad . \quad . \quad (7)$$

It is easily verified, on examination, that the orbits of the particles are now ellipses having their principal axes in the directions of the meridians and parallels, respectively. At the equator these ellipses reduce to straight lines

In the case $n=1$, the harmonic is always of the zonal type. The harmonic spheroid (4) is then, to our order of approximation, a sphere excentric to the globe. It is important to remark, however, that this case is, strictly speaking, not included in our dynamical investigation, unless we imagine a constraint applied to the globe to keep it at rest, for the deformation in question of the free surface would involve a displacement of the centre of mass of the ocean, and a consequent reaction on the globe. A corrected theory for the case where the globe is free could easily be investigated, but the matter is hardly important, first because in such a case as that of the Earth the inertia of the solid globe is so enormous compared with that of the ocean, and secondly because disturbing forces which can give rise to a deformation of the type in question do not as a rule present themselves in nature. It appears, for example, that the first term in the expression for the tide-generating potential of the sun or moon is a spherical harmonic of the *second* order (see the Appendix to this Chapter).

When $n=2$, the free surface at any instant is approximately ellipsoidal. The corresponding period, as found from (5), is then 816 of that belonging to the analogous mode in an equatorial canal (Art 180)

For large values of n the distance from one nodal line to another is small compared with the radius of the globe, and the oscillations then take place much as on a plane sheet of water. For example, the velocity, at the equator, of the sectorial waves represented by (6) tends with increasing n to the value $(gh)^{\frac{1}{2}}$, in agreement with Art. 169.

From a comparison of the foregoing investigation with the general theory of Art 167 we are led to infer, on physical grounds alone, the possibility of the expansion of any arbitrary value of ζ in a series of surface harmonics, thus

$$\zeta = \sum_0^{\infty} S_n,$$

the coefficients of the various independent harmonics being the normal coordinates of the system. Again, since the products of these coefficients must disappear from the expressions for the kinetic and potential energies, we are led to the 'conjugate' properties of spherical harmonics quoted in Art 87. The actual calculation of the energies will be given in the next Chapter, in connection with an independent treatment of the same problem.

The effect of a simple-harmonic disturbing force can be written down at once from the formula (13) of Art. 167. If the surface value of Ω be expanded in the form

$$\Omega = \sum \Omega_n, \quad \dots \dots \dots (8)$$

where Ω_n is a surface-harmonic of integral order n , the various terms are normal components of force, in the generalized sense of Art 135, and the equilibrium value of ζ corresponding to any one term Ω_n is

$$\zeta_n = -\frac{1}{g} \Omega_n \dots \dots \dots (9)$$

Hence, for the forced oscillation due to this term, we have

$$\zeta_n = -\frac{1}{1 - \frac{\sigma^2}{\sigma_n^2}} \frac{\Omega_n}{g}, \quad \dots \dots \dots (10)$$

where σ measures the 'speed' of the disturbing force, and σ_n that of the corresponding free oscillation, as given by (5). There is no difficulty, of course, in deducing (10) directly from the equations of the preceding Art.

199 We have up to this point neglected the mutual attraction of the parts of the liquid. In the case of an ocean covering the globe, and with such relations of density as we meet with in the actual earth and ocean, this is not insensible. To investigate its effect in the case of the free oscillations, we have only to substitute for Ω_n , in the last formula, the gravitation-potential of the displaced water. If the density of this be denoted by ρ , whilst ρ_0 represents the mean density of the globe and liquid combined, we have*

$$\Omega_n = -\frac{4\pi\gamma\rho a}{2n+1} \zeta_n, \quad \dots \dots \dots (11)$$

and

$$g = \frac{4}{3}\gamma\pi a\rho_0, \quad \dots \dots \dots (12)$$

γ denoting the gravitation-constant, whence

$$\Omega_n = -\frac{3}{2n+1} \cdot \frac{\rho}{\rho_0} \cdot g \zeta_n \dots \dots \dots (13)$$

* See, for example, Routh, *Analytical Statics*, 2nd ed., Cambridge, 1902, t. II pp. 146-7

Substituting in (10) we find

$$\frac{\sigma_n^2}{\sigma_n'^2} = \left(1 - \frac{3}{2n+1} \frac{\rho}{\rho_0}\right), \quad \dots \dots (14)$$

where σ_n is now used to denote the actual speed of the oscillation, and σ_n' the speed calculated on the former hypothesis of no mutual attraction. Hence the corrected speed is given* by

$$\sigma_n^2 = n(n+1) \left(1 - \frac{3}{2n+1} \frac{\rho}{\rho_0}\right) \frac{gh}{a^2} \quad \dots \dots (15)$$

For an ellipsoidal oscillation ($n=2$), and for $\rho/\rho_0 = .18$ (as in the case of the Earth), we find from (14) that the effect of the mutual attraction is to lower the frequency in the ratio of 94 to 1

The slowest oscillation would correspond to $n=1$, but, as already indicated, it would be necessary, in this mode, to imagine a constraint applied to the globe to keep it at rest. This being premised, it appears from (15) that if $\rho > \rho_0$ the value of σ_1^2 is negative. The circular function of t is then replaced by real exponentials, this shews that the configuration in which the surface of the sea is a sphere concentric with the globe is one of unstable equilibrium. Since the introduction of a constraint tends in the direction of stability, we infer that when $\rho > \rho_0$ the equilibrium is *a fortiori* unstable when the globe is free. In the extreme case where the globe itself is supposed to have no gravitative power at all, it is obvious that the water, if disturbed, would tend ultimately, under the influence of dissipative forces, to collect itself into a spherical mass, the nucleus being expelled.

It is obvious from Art 167, or it may easily be verified independently, that the forced vibrations due to a given periodic disturbing force, when the gravitation of the water is taken into account, will be given by the formula (10), provided Ω_n now denote the potential of the extraneous forces only, and σ_n have the value given by (15)

200. The oscillations of a sea bounded by meridians, or parallels of latitude, or both, can also be treated by the same method†. The spherical harmonics involved are however, as a rule, no longer of integral order, and it is accordingly difficult to deduce numerical results

In the case of a zonal sea bounded by two parallels of latitude, we assume

$$\zeta = \{A p(\mu) + B q(\mu)\} \begin{matrix} \cos \\ \sin \end{matrix} s\omega, \quad \dots \dots (1)$$

* This result was given by Laplace, *Mécanique Céleste*, Livre 1^{er}, Art 1 (1799). The free and the forced oscillations of the type $n=2$ had been previously investigated in his "Recherches sur quelques points du système du monde," *Mém de l'Acad roy des Sciences*, 1775 [1778] [*Oeuvres Complètes*, t. ix pp. 109,]

† Cf Lord Rayleigh, *loc ante* p 287

where $\mu = \cos \theta$, and $p(\mu)$, $q(\mu)$ are the two functions of μ , containing $(1 - \mu^2)^{\frac{1}{2}s}$ as a factor, which are given by the formula (2) of Art 86. It will be noticed that $p(\mu)$ is an *even*, and $q(\mu)$ an *odd* function of μ .

If we distinguish the limiting parallels by suffixes, the boundary conditions are that $u=0$ for $\mu=\mu_1$ and $\mu=\mu_2$. For the free oscillations this gives, by Art 197 (6),

$$Ap'(\mu_1) + Bq'(\mu_1) = 0, \quad Ap'(\mu_2) + Bq'(\mu_2) = 0, \quad (2)$$

whence
$$\begin{vmatrix} p'(\mu_1) & q'(\mu_1) \\ p'(\mu_2) & q'(\mu_2) \end{vmatrix} = 0, \quad \dots \quad (3)$$

which is the equation to determine the admissible values of n . The speeds (σ) corresponding to the various roots are given as before by Art 198 (5).

If the two boundaries are equidistant from the equator, we have $\mu_2 = -\mu_1$. The above solutions then break up into two groups, viz for one of these we have

$$B=0, \quad p'(\mu_1)=0, \quad (4)$$

and for the other
$$A=0, \quad q'(\mu_1)=0 \quad (5)$$

In the former case ζ has the same value at two points symmetrically situated on opposite sides of the equator, in the latter the values at these points are numerically equal, but opposite in sign.

If we imagine one of the boundaries to be contracted to a point (say $\mu_2=1$), we pass to the case of a circular basin. The values of $p'(1)$ and $q'(1)$ are infinite, but their ratio can be evaluated by means of formulae given in Art 84. This gives, by (3), the ratio A/B , and substituting in (2) we get the equation to determine n . A simpler method of treating this case consists, however, in starting with a solution which is known to be finite, whatever the value of n , at the pole $\mu=1$. This involves a change of variable, as to which there is some latitude of choice.

We might take, for instance, the expression for $P_n^s(\cos \theta)$ in Art. 86 (6), and seek to determine n from the condition that

$$\frac{\partial}{\partial \theta} P_n^s(\cos \theta) = 0 \quad \dots \quad (6)$$

for $\theta = \theta_1^*$

By making the radius of the sphere infinite, we can pass to the plane problem of Art 189†. The steps of the transition will be understood from Art 100.

If the sheet of water considered have as boundaries two meridians (with or without parallels of latitude), say $\omega=0$ and $\omega=\alpha$, the condition that $v=0$ at these restricts us to the factor $\cos s\omega$, and gives $s\alpha = m\pi$, where m is integral. This determines the admissible values of s , which are not in general integral‡.

* This question has been discussed by Macdonald, *Proc Lond Math Soc*, t xxxi p 264 (1899).

† Cf Lord Rayleigh, *Theory of Sound*, Arts 336, 338.

‡ The reader who wishes to carry the study of the problem further in this direction is referred to Thomson and Tait, *Natural Philosophy* (2nd ed.), Appendix B, "Spherical Harmonic Analysis."

Tidal Oscillations of a Rotating Sheet of Water

201. The theory of the tides on an open sheet of water is seriously complicated by the fact of the earth's rotation. If, indeed, we could assume that the periods of the free oscillations, and of the disturbing forces, were small compared with a day, the preceding investigations would apply as a first approximation, but these conditions are far from being fulfilled in the actual circumstances of the Earth.

The difficulties which arise when we attempt to take the rotation into account have their origin in this, that a particle having a motion in latitude tends to keep its angular momentum about the earth's axis unchanged, and so to alter its motion in longitude. This point is of course familiar in connection with Hadley's theory of the trade-winds*. Its bearing on tidal theory seems to have been first recognised by Maclaurin†

Owing to the enormous inertia of the solid body of the earth compared with that of the ocean, the effect of tidal reactions in producing periodic changes of the angular velocity is quite insensible. This angular velocity will therefore for the present be treated as constant‡

The theory of the small oscillations of a dynamical system about a state of equilibrium relative to a solid body which rotates with constant angular velocity about a fixed axis differs in some important particulars from the theory of small oscillations about a state of absolute equilibrium, of which some account was given in Art 167. It is therefore worth while to devote a little space to it before entering on the consideration of special problems.

202 Let us take rectangular axes x, y, z fixed relatively to the solid, of which the axis of z coincides with the axis of rotation, and let ω be the angular velocity of the rotation. The equations of motion of a particle m relative to these moving axes are known to be

$$m(x - 2\omega y - \omega^2 x) = X, \quad m(\ddot{y} + 2\omega \dot{x} - \omega^2 y) = Y, \quad mz = Z, \dots (1)$$

where X, Y, Z are the impressed forces. From these we derive

$$\begin{aligned} \Sigma m(\dot{x}\Delta x + \dot{y}\Delta y + z\Delta z) + 2\omega \Sigma m(x\Delta y - y\Delta x) \\ - \omega^2 \Sigma m(x\Delta x + y\Delta y) = \Sigma (X\Delta x + Y\Delta y + Z\Delta z), \dots (2) \end{aligned}$$

where the symbol Δ has the same meaning as in Art 135

* "The Cause of the General Trade Winds," *Phil. Trans.*, 1735

† *De Causâ Physicâ Fluxus et Refluxus Maris*, Prop. vii. "Motus aquæ turbatur ex inæquali velocitate quâ corpora circa axem Terræ motu diurno deferuntur" (1740)

‡ The secular effect of tidal friction in this respect will be noticed later (Chap. xi.)

The conditions for relative equilibrium, in the absence of disturbing forces, are found by putting $q_1, \dot{q}_2, \dots \dot{q}_n = 0$ in (10), or more simply from (2). In either way we obtain

$$\frac{\partial}{\partial q_i} (V - T_0) = 0, \quad . \quad . \quad . \quad . \quad . \quad (11)$$

which shews that the equilibrium value of the expression $V - T_0$ is 'stationary.'

If T denote the total kinetic energy of the system, we have

$$T = \frac{1}{2} \Sigma m \{(\dot{x} - \omega y)^2 + (\dot{y} + \omega x)^2 + \dot{z}^2\} = \mathcal{T} + T_0 + \omega \Sigma m (xy - y\dot{x}), \quad (12)$$

whence, on reference to (1),

$$\begin{aligned} \frac{d}{dt} (T + V) &= \frac{d}{dt} (\mathcal{T} + T_0 + V) + \omega \Sigma m (x\dot{y} - y\dot{x}) \\ &= \frac{d}{dt} (\mathcal{T} + V - T_0) + \omega \Sigma (xY - yX) \quad \dots \quad (13) \end{aligned}$$

This is to be equated to the rate at which the disturbing forces do work, *viz* to

$$\omega \Sigma (xY - yX) + Q_1 q_1 + Q_2 q_2 + \dots + Q_n q_n$$

$$\text{Hence} \quad \frac{d}{dt} (\mathcal{T} + V - T_0) = Q_1 \dot{q}_1 + Q_2 \dot{q}_2 + \dots + Q_n \dot{q}_n. \quad \dots \dots \dots (14)$$

This might also be deduced from the equations (10)

When there are no disturbing forces, we have

$$\mathcal{T} + V - T_0 = \text{const} \quad \dots \dots \dots (15)$$

203 We will now suppose the coordinates q_i to be chosen so as to vanish in the undisturbed state. In the case of a *small* disturbance, we may then write

$$2\mathcal{T} = a_{11}\dot{q}_1^2 + a_{22}\dot{q}_2^2 + \dots + 2a_{12}q_1\dot{q}_2 + \dots \dots \dots (1)$$

$$2(V - T_0) = c_{11}q_1^2 + c_{22}q_2^2 + \dots + 2c_{12}q_1q_2 + \dots \dots \dots (2)$$

where the coefficients may be treated as constants. The terms of the first degree in $V - T_0$ have been omitted, on account of the 'stationary' property.

In order to simplify the equations as much as possible, we will further suppose that, by a linear transformation, each of these expressions is reduced, as in Art 167, to a sum of squares, *viz*

$$2\mathcal{T} = a_1 q_1^2 + a_2 q_2^2 + \dots + a_n q_n^2, \quad \dots \dots \dots (3)$$

$$2(V - T_0) = c_1 q_1^2 + c_2 q_2^2 + \dots + c_n q_n^2 \quad \dots \dots \dots (4)$$

The determinant $\Delta(\lambda)$ comes under the class called by Cayley 'skew-determinants,' in virtue of the relations (8) of Art. 202. If we reverse the sign of λ , the rows and columns are simply interchanged, and the value of the determinant is therefore unaltered. Hence, when expanded, the equation (9) will involve only *even* powers of λ , and the roots will be in pairs of the form

$$\lambda = \pm (\rho + i\sigma).$$

In order that the configuration of relative equilibrium should be stable it is essential that the values of ρ should all be zero, for otherwise terms of the forms $e^{\pm\rho t} \cos \sigma t$ and $e^{\pm\rho t} \sin \sigma t$ would present themselves in the realized expression for any coordinate q_r . This would indicate the possibility of an oscillation of continually increasing amplitude.

In the theory of absolute equilibrium, sketched in Art. 167, the necessary and sufficient condition of stability (in the above sense) was simply that the potential energy must be a minimum in the configuration of equilibrium. In the present case the conditions are more complicated*, but it is easily seen that if the expression for $V - T_0$ be essentially positive, in other words if the coefficients c_1, c_2, \dots, c_n in (4) be all positive, the equilibrium must be stable. This follows at once from the equation

$$\mathcal{T} + (V - T_0) = \text{const}, \quad \dots \quad \dots \quad (11)$$

proved in Art. 202, which shews that under the present supposition neither \mathcal{T} nor $V - T_0$ can increase beyond a certain limit depending on the initial circumstances. It will be observed that this argument does not involve the use of approximate equations†.

Hence stability is assured if $V - T_0$ is a minimum in the configuration of relative equilibrium. But this condition is not essential, and there may even be stability (from the present point of view) with $V - T_0$ a maximum, as will be shewn presently in the particular case of two degrees of freedom. It is to be remarked, however, that if the system be subject to dissipative forces, however slight, affecting the relative coordinates q_1, q_2, \dots, q_n , the equilibrium will be permanently or 'secularly' stable only if $V - T_0$ is a minimum. It is the characteristic of such forces that the work done by them on the system is always negative. Hence by (6) the expression $\mathcal{T} + (V - T_0)$ will, so long as there is any relative motion of the system, continually diminish, in the algebraical sense. Hence if the system be started from relative rest in a configuration such that $V - T_0$ is negative, the above expression, and therefore

* They have been investigated by Routh, *On the Stability of a Given State of Motion*; see also his *Advanced Rigid Dynamics*, c. vi.

† The argument was originally applied to the theory of oscillations about a configuration of absolute equilibrium (Art. 167) by Dirichlet, "Ueber die Stabilität des Gleichgewichts," *Crelle*, t. xxxii (1846) [*Werke*, Berlin, 1889-97, t. ii p. 3].

* The theory of the free modes has been further developed by Lord Rayleigh, "On the Free Vibrations of Systems affected with Small Rotatory Terms," *Phil Mag* (6), t v p 293 (1903), for the case where the rotatory coefficients β_{rs} are relatively small

The most important point of contrast with the theory of the 'normal modes' in the case of no rotation is that the displacement of any one type is no longer affected solely by the disturbing force of that type. As a consequence, the motions of the individual particles are, as is easily seen from (14), now in general elliptic-harmonic. Again, there are in general differences of phase, variable with the frequency, between the displacements and the force

As in Art 167, the displacement becomes very great when $\Delta(i\sigma)$ is very small, i.e. whenever the 'speed' σ of the disturbing force approximates to that of one of the natural modes of free oscillation.

When the period of the disturbing forces is infinitely long, the displacements tend to the 'equilibrium-values'

$$q_1 = \frac{Q_1}{c_1}, \quad q_2 = \frac{Q_2}{c_2}, \quad \dots \quad q_n = \frac{Q_n}{c_n}, \quad \dots \quad (18)$$

as is found by putting $\sigma = 0$ in (17), or more simply from the fundamental equations (5). This conclusion must be modified, however, when one or more of the coefficients of stability c_1, c_2, \dots, c_n is zero. If, for example, $c_1 = 0$, the first row and column of the determinant $\Delta(\lambda)$ are both divisible by λ , so that the determinantal equation (10) has a pair of zero roots. In other words we have a possible free motion of infinitely long period. The coefficients of Q_2, Q_3, \dots, Q_n on the right-hand side of (17) then become indeterminate for $\sigma = 0$, and the evaluated results do not as a rule coincide with (18). This point is of some importance, because in the hydrodynamical applications, as we shall see, steady circulatory motions of the fluid, with a constant deformation of the free surface, are possible when no extraneous forces act, and as a consequence forced tidal oscillations of long period do not necessarily approximate to the values given by the equilibrium theory of the tides. Cf Arts 213, 216

In order to elucidate the foregoing statements we may consider more in detail the case of two degrees of freedom. The equations of motion are then of the forms

$$a_1 q_1 + c_1 q_1 + \beta q_2 = Q_1, \quad a_2 q_2 + c_2 q_2 - \beta q_1 = Q_2 \quad (19)$$

The equation determining the periods of the free oscillations is

$$a_1 a_2 \lambda^4 + (a_1 c_2 + a_2 c_1 + \beta^2) \lambda^2 + c_1 c_2 = 0 \quad \dots \quad (20)$$

For 'ordinary' stability it is sufficient that the roots of this quadratic in λ^2 should be real and negative. Since a_1, a_2 are essentially positive, it is easily seen that this condition is in any case fulfilled if c_1, c_2 are both positive, and that it will also be satisfied even when c_1, c_2 are both negative, provided β^2 be sufficiently great. It will be shewn later, however, that in the latter case the equilibrium is rendered unstable by the introduction of dissipative forces.

To find the forced oscillations when Q_1, Q_2 vary as $e^{i\sigma t}$, we have, omitting the time-factor,

$$(c_1 - \sigma^2 a_1) q_1 + i\sigma \beta q_2 = Q_1, \quad -i\sigma \beta q_1 + (c_2 - \sigma^2 a_2) q_2 = Q_2, \quad (21)$$

whence
$$q_1 = \frac{(c_2 - \sigma^2 a_2) Q_1 - \sigma \beta Q_2}{(c_1 - \sigma^2 a_1)(c_2 - \sigma^2 a_2) - \sigma^2 \beta^2}, \quad q_2 = \frac{\sigma \beta Q_1 + (c_1 - \sigma^2 a_1) Q_2}{(c_1 - \sigma^2 a_1)(c_2 - \sigma^2 a_2) - \sigma^2 \beta^2}. \quad (22)$$

Let us now suppose that $c_2=0$, or, in other words, that the displacement q_2 does not affect the value of $V-T_0$. We will also suppose that $Q_2=0$, i.e. that the extraneous forces do no work during a displacement of the type q_2 . The above formulae then give

$$q_1 = \frac{a_2}{a_2(c_1 - \sigma^2 a_1) + \beta^2} Q_1, \quad q_2 = \frac{\beta}{a_2(c_1 - \sigma^2 a_1) + \beta^2} Q_1. \quad (23)$$

In the case of a disturbance of long period we have $\sigma=0$, approximately, and therefore

$$q_1 = \frac{1}{c_1 + \beta^2/a_2} Q_1, \quad q_2 = \frac{\beta}{a_2 c_1 + \beta^2} Q_1. \quad (24)$$

The displacement q_1 is therefore *less* than its equilibrium-value, in the ratio $1/(1 + \beta^2/a_2 c_1)$, and it is accompanied by a motion of the type q_2 although there is no extraneous force of the latter type (cf Art 216). We pass, of course, to the case of absolute equilibrium, considered in Art 167, by putting $\beta=0$.

It should be added that the determination of the 'principal coordinates' of Art 203 depends on the original forms of \mathcal{T} and $V-T_0$, and is therefore affected by the value of ω^2 , which enters as a factor of T_0 . The system of equations there given is accordingly not altogether suitable for a discussion of the question how the character and the frequencies of the respective principal modes of free vibration vary with ω . One remarkable point which is thus overlooked is that types of circulatory motion, which are of infinitely long period in the case of no rotation, may be converted by the slightest degree of rotation into oscillatory modes of periods comparable with that of the rotation. Cf Arts 211, 221.

To illustrate the matter in its simplest form, we may take the case of two degrees of freedom. If c_2 vanishes for $\omega=0$, and so contains ω^2 as a factor in the general case, the two roots of equation (20) are

$$\lambda^2 = -\frac{c_1}{a_1}, \quad \lambda^2 = -\frac{c_2}{a_2},$$

approximately, when ω^2 is small. The latter root makes $\lambda \propto \omega$, ultimately

206. Proceeding to the hydrodynamical examples, we begin with the case of a plane horizontal sheet of water having in the undisturbed state a motion of uniform rotation about a vertical axis*. The results will apply without serious qualification to the case of a polar or other basin, of not too great dimensions, on a rotating globe.

Let the axis of rotation be taken as axis of z . The axes of x and y being now supposed to rotate in their own plane with the prescribed angular velocity ω , let us denote by u, v, w the velocities at time t , *relative to these axes*,

* Sir W. Thomson, "On Gravitational Oscillations of Rotating Water," *Proc R S Edin*, t x p 92 (1879) [*Phil. Mag*, (5) t x p 109 (1880)]

of the particle which then occupies the position (x, y, z) The actual velocities of the same particle, parallel to the instantaneous positions of the axes, will be $u - \omega y$, $v + \omega x$, w , and the accelerations in the same directions will be

$$\frac{Du}{Dt} - 2\omega v - \omega^2 x, \quad \frac{Dv}{Dt} + 2\omega u - \omega^2 y, \quad \frac{Dw}{Dt}$$

In the present application, the relative motion is assumed to be infinitely small, so that we may replace D/Dt by $\partial/\partial t$

Now let z_0 be the ordinate of the free surface when there is relative equilibrium under gravity alone, so that

$$z_0 = \frac{1}{2} \frac{\omega^2}{g} (x^2 + y^2) + \text{const}, \quad \dots \quad (1)$$

as in Art 26 For simplicity we will suppose that the slope of this surface is everywhere very small, in other words, if r be the greatest distance of any part of the sheet from the axis of rotation, $\omega^2 r/g$ is assumed to be small

If $z_0 + \zeta$ denote the ordinate of the free surface when disturbed, then on the usual assumption that the vertical acceleration of the water is small compared with g , the pressure at any point (x, y, z) will be given by

$$p - p_0 = g\rho (z_0 + \zeta - z) \quad \dots \quad (2)$$

whence
$$-\frac{1}{\rho} \frac{\partial p}{\partial x} = -\omega^2 x - g \frac{\partial \zeta}{\partial x}, \quad -\frac{1}{\rho} \frac{\partial p}{\partial y} = -\omega^2 y - g \frac{\partial \zeta}{\partial y}$$

The equations of horizontal motion are therefore

$$\frac{\partial u}{\partial t} - 2\omega v = -g \frac{\partial \zeta}{\partial x} - \frac{\partial \Omega}{\partial x}, \quad \frac{\partial v}{\partial t} + 2\omega u = -g \frac{\partial \zeta}{\partial y} - \frac{\partial \Omega}{\partial y}, \quad \dots \quad (3)$$

where Ω denotes the potential of the disturbing forces

If we write
$$\bar{\zeta} = -\frac{\Omega}{g}, \quad \dots \quad (4)$$

these become

$$\frac{\partial \zeta}{\partial t} - 2\omega v = -g \frac{\partial}{\partial x} (\zeta - \bar{\zeta}), \quad \frac{\partial v}{\partial t} + 2\omega u = -g \frac{\partial}{\partial y} (\zeta - \bar{\zeta}) \quad \dots \quad (5)$$

The equation of continuity has the same form as in Art 191, viz

$$\frac{\partial \zeta}{\partial t} = -\frac{\partial (hu)}{\partial x} - \frac{\partial (hv)}{\partial y}, \quad \dots \quad (6)$$

where h denotes the depth, from the free surface to the bottom, in the undisturbed condition This depth will not, of course, be uniform unless the bottom follows the curvature of the free surface as given by (1)

If we eliminate $\zeta - \bar{\zeta}$ from the equations (5), by cross-differentiation, we find

$$\frac{\partial}{\partial t} \left(\frac{\partial v}{\partial x} - \frac{\partial u}{\partial y} \right) + 2\omega \left(\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} \right) = 0, \quad (7)$$

or, writing $u = \partial \xi / \partial t$, $v = \partial \eta / \partial t$, and integrating with respect to t ,

$$\frac{\partial v}{\partial x} - \frac{\partial u}{\partial y} + 2\omega \left(\frac{\partial \xi}{\partial x} + \frac{\partial \eta}{\partial y} \right) = \text{const.} \quad \dots \quad (8)$$

This is merely the expression of von Helmholtz' theorem that the product of the angular velocity

$$\omega + \frac{1}{2} \left(\frac{\partial v}{\partial x} - \frac{\partial u}{\partial y} \right) \quad \text{and the cross-section} \quad \left(1 + \frac{\partial \xi}{\partial x} + \frac{\partial \eta}{\partial y} \right) \delta x \delta y,$$

of a vortex-filament, is constant

In the case of a simple-harmonic disturbance, the time-factor being $e^{i\sigma t}$, the equations (5) and (6) become

$$i\sigma u - 2\omega v = -g \frac{\partial}{\partial x} (\zeta - \bar{\zeta}), \quad i\sigma v + 2\omega u = -g \frac{\partial}{\partial y} (\zeta - \bar{\zeta}), \quad \dots (9)$$

$$\text{and} \quad i\sigma \zeta = -\frac{\partial (hu)}{\partial x} - \frac{\partial (hv)}{\partial y}. \quad \dots \dots \dots (10)$$

From (9) we find

$$u = \frac{g}{\sigma^2 - 4\omega^2} \left(i\sigma \frac{\partial}{\partial x} + 2\omega \frac{\partial}{\partial y} \right) (\zeta - \bar{\zeta}), \quad v = \frac{g}{\sigma^2 - 4\omega^2} \left(i\sigma \frac{\partial}{\partial y} - 2\omega \frac{\partial}{\partial x} \right) (\zeta - \bar{\zeta}), \quad \dots (11)$$

and if we substitute from these in (10), we obtain an equation in ζ only

In the case of *uniform* depth the result takes the form

$$\nabla_1^2 \zeta + \frac{\sigma^2 - 4\omega^2}{gh} \zeta = \nabla_1^2 \bar{\zeta}, \quad \dots (12)$$

where $\nabla_1^2 = \partial^2 / \partial x^2 + \partial^2 / \partial y^2$, as before

When $\bar{\zeta} = 0$, the equations (5) and (6) can be satisfied by *constant* values of u , v , ζ provided certain conditions are fulfilled. We must have

$$u = -\frac{g}{2\omega} \frac{\partial \zeta}{\partial y}, \quad v = \frac{g}{2\omega} \frac{\partial \zeta}{\partial x}, \quad \dots (13)$$

and therefore

$$\frac{\partial (h, \zeta)}{\partial (x, y)} = 0 \quad \dots \quad (14)$$

The latter condition shews that the contour-lines of the free surface must be everywhere parallel to the contour-lines of the bottom, but that the value of ζ is otherwise arbitrary. The flow of the fluid is everywhere parallel to the contour-lines, and it is therefore further necessary for the possibility of such steady motions that the depth should be uniform along the boundary (supposed to be a vertical wall). When the depth is everywhere the same, the condition (14) is satisfied identically, and the only limitation on the value of ζ is that it should be constant along the boundary.

whilst the equation of continuity (10) becomes

$$\zeta = -\frac{\partial(hRr)}{r\partial r} - \frac{\partial(h\Theta)}{r\partial\theta} \quad \dots \quad (2)$$

Hence

$$R = \frac{g}{\sigma^2 - 4\omega^2} \left(\frac{\partial}{\partial r} - \frac{2i\omega}{\sigma} \frac{\partial}{r\partial\theta} \right) (\zeta - \bar{\zeta}), \quad \Theta = \frac{ig}{\sigma^2 - 4\omega^2} \left(\frac{2\omega}{\sigma} \frac{\partial}{\partial r} - i \frac{\partial}{r\partial\theta} \right) (\zeta - \bar{\zeta}), \quad \dots \quad (3)$$

and substituting in (2) we get the differential equation in ζ .

In the case of *uniform* depth we find

$$(\nabla_1^2 + \kappa^2) \zeta = \nabla_1^2 \bar{\zeta}, \quad \dots \quad (4)$$

where

$$\nabla_1^2 = \frac{\partial^2}{\partial r^2} + \frac{1}{r} \frac{\partial}{\partial r} + \frac{1}{r^2} \frac{\partial^2}{\partial \theta^2}, \quad \dots \quad (5)$$

and

$$\kappa^2 = \frac{\sigma^2 - 4\omega^2}{gh} \quad \dots \quad (6)$$

This might have been written down at once from Art 206 (12)

The condition to be satisfied at the boundary ($r = a$, say) is $R = 0$, or

$$\left(r \frac{\partial}{\partial r} - \frac{2i\omega}{\sigma} \frac{\partial}{\partial \theta} \right) (\zeta - \bar{\zeta}) = 0 \quad \dots \quad (7)$$

209 In the case of the *free* oscillations we have $\bar{\zeta} = 0$. The way in which the imaginary i enters into the above equations, taken in conjunction with Fourier's theorem, suggests that θ occurs in the form of a factor $e^{is\theta}$, where s is integral. On this supposition, the differential equation (4) becomes

$$\frac{\partial^2 \zeta}{\partial r^2} + \frac{1}{r} \frac{\partial \zeta}{\partial r} + \left(\kappa^2 - \frac{s^2}{r^2} \right) \zeta = 0, \quad \dots \quad (8)$$

and the boundary-condition (7) gives

$$r \frac{\partial \zeta}{\partial r} + \frac{2s\omega}{\sigma} \zeta = 0, \quad \dots \quad (9)$$

for $r = a$.

The equation (8) is of Bessel's form, and the solution which is finite for $r = 0$ may therefore be written

$$\zeta = A J_s(\kappa r) e^{i(\sigma t + s\theta)}, \quad \dots \quad (10)$$

but it is to be noted that κ^2 is not, in the present problem, necessarily positive. When κ^2 is negative, we may replace $J_s(\kappa r)$ by $I_s(\kappa' r)$, where κ' is the positive square root of $(4\omega^2 - \sigma^2)/gh$, and

$$I_s(z) = \frac{z^s}{2^s \cdot s!} \left\{ 1 + \frac{z^2}{2(2s+2)} + \frac{z^4}{2 \cdot 4(2s+2)(2s+4)} + \dots \right\}^* \quad (11)$$

* The functions $I_s(z)$ have been tabulated by Prof A. Lodge, *Brit Ass Rep* 1889.

In the case of symmetry about the axis ($s = 0$), we have, in real form,

$$\zeta = AJ_0(\kappa r) \cos(\sigma t + \epsilon), \quad \dots \dots (12)$$

where κ is determined by

$$J_0'(\kappa a) = 0 \quad \dots \dots (13)$$

The corresponding values of σ are then given by (6). The free surface has, in the various modes, the same forms as in Art 189, but the frequencies are now greater, viz we have

$$\sigma^2 = \sigma_0^2 + 4\omega^2, \quad \dots \dots (14)$$

where σ_0 is the corresponding value of σ when there is no rotation. It is easily seen, moreover, on reference to (3), that the relative motions of the fluid particles are no longer purely radial, the particles describe, in fact, ellipses whose major axes are in the direction of the radius vector.

For $s > 0$ we have

$$\zeta = AJ_s(\kappa r) \cos(\sigma t + s\theta + \epsilon), \quad \dots \dots (15)$$

where the admissible values of κ , and thence of σ , are determined by (9), which gives

$$\kappa a J_s'(\kappa a) + \frac{2s\omega}{\sigma} J_s(\kappa a) = 0 \quad \dots \dots (16)$$

The formula (15) represents a wave rotating relatively to the water with an angular velocity σ/s , the rotation of the wave being in the same direction with that of the water, or the opposite, according as σ/ω is negative or positive

Some indications as to the values of σ may be gathered from a graphical construction. If we write $\kappa^2 a^2 = x$, we have, from (6),

$$\frac{\sigma}{2\omega} = \pm \left(1 + \frac{x}{\beta}\right)^{\frac{1}{2}}, \quad \dots \dots (17)$$

where

$$\beta = \frac{4\omega^2 a^2}{gh} \quad \dots \dots (18)$$

If we further put

$$\frac{sJ_s(\kappa a)}{\kappa a J_s'(\kappa a)} = \phi(\kappa^2 a^2),$$

the equation (16) may be written

$$\phi(x) \pm \left(1 + \frac{x}{\beta}\right)^{\frac{1}{2}} = 0 \quad \dots \dots (19)$$

The curve

$$y = -\phi(x). \quad (20)$$


can be readily traced by means of the tables of the functions $J_s(z)$, $I_s(z)$, and its intersections with the parabola

$$y^2 = 1 + \frac{x}{\beta}. \quad (21)$$

will give, by their ordinates, the values of $\sigma/2\omega$. The constant β , on which the positions of the roots depend, is equal to the square of the ratio $2\omega a/(gh)^{\frac{1}{2}}$ which the period of

a wave travelling round a circular canal of depth h and perimeter $2\pi a$ bears to the half-period (π/ω) of the rotation of the water

The accompanying figures indicate the relative magnitudes of the lower roots, in the cases $s=1$ and $s=2$, when β has the values 2, 6, 40, respectively*



With the help of these figures we can trace, in a general way, the changes in the character of the free modes as β increases from zero. The results may be interpreted as due either to a continuous increase of ω , or to a continuous diminution of h . We will use the terms 'positive' and 'negative' to distinguish waves which travel, relatively to the water, in the same direction as the rotation and the opposite.


When β is infinitely small, the values of x are given by $J'_s(x^{\frac{1}{2}})=0$, these correspond to the vertical asymptotes of the curve (20). The values of σ then occur in pairs of equal and oppositely-signed quantities, indicating that there is now no difference between the velocity of positive and negative waves. The case is, in fact, that of Art 189 (12).

As β increases, the two values of σ forming a pair become unequal in magnitude, and the corresponding values of x separate, that being the greater for which $\sigma/2\omega$ is positive. When $\beta=s(s+1)$ the curve (20) and the parabola (21) touch at the point $(0, -1)$, the corresponding value of σ being -2ω . As β increases beyond this critical value, one value of x becomes negative, and the corresponding (negative) value of $\sigma/2\omega$ becomes smaller and smaller.

Hence, as β increases from zero, the relative angular velocity becomes greater for a negative than for a positive wave of (approximately) the same type, moreover the value of σ for a negative wave is always greater than 2ω . As the rotation increases, the two

* For clearness the scale of y has been taken to be 10 times that of x .

kinds of wave become more and more distinct in character as well as in 'speed'. With a sufficiently great value of β we may have one, but never more than one, positive wave for which σ is numerically less than 2ω . Finally, when β is very great, the value of σ corresponding to this wave becomes very small compared with ω , whilst the remaining values tend all to become more and more nearly equal to $\pm 2\omega$.



If we use a zero suffix to distinguish the case of $\omega=0$, we find

$$\frac{\sigma^2}{\sigma_0^2} = \frac{\kappa^2 + 4\omega^2/g\hbar}{\kappa_0^2} = \frac{x+\beta}{x_0}, \quad \dots \quad (22)$$

where x_0 refers to the proper asymptote of the curve (20). This gives the 'speed' of any free mode in terms of that of the corresponding mode when there is no rotation.

210 As a sufficient example of *forced* oscillations we may assume

$$\zeta = C \left(\frac{r}{a} \right)^s e^{i(\sigma t + s\theta + \epsilon)}, \quad \dots \quad (23)$$

where the value of σ is now prescribed

This makes $\nabla^2 \zeta = 0$, and the equation (4) then gives

$$\zeta = A J_s(\kappa r) e^{i(\sigma t + s\theta + \epsilon)}, \quad \dots \quad (24)$$

where A is to be determined by the boundary-condition (7), viz

$$A = \frac{s \left(1 + \frac{2\omega}{\sigma} \right)}{\kappa \alpha J_s'(\kappa \alpha) + \frac{2s\omega}{\sigma} J_s(\kappa \alpha)} \quad C \quad \dots \dots \dots (25)$$

This becomes very great when the frequency of the disturbance is nearly coincident with that of a free mode of corresponding type.

From the point of view of tidal theory the most interesting cases are those of $s=1$ with $\sigma=\omega$, and $s=2$ with $\sigma=2\omega$, respectively. These would represent the diurnal and semidiurnal tides due to a distant disturbing body whose proper motion may be neglected in comparison with the rotation ω .

In the case of $s=1$ we have a *uniform* horizontal disturbing force. Putting, in addition, $\sigma=\omega$, we find without difficulty that the amplitude of the tide-elevation at the edge ($r=\alpha$) of the basin has to its 'equilibrium-value' the ratio

$$\frac{3I_1(z)}{I_1(z) + zI_0(z)}, \quad \dots \dots \dots (26)$$

where $z = \frac{1}{2}\sqrt{(3\beta)}$. With the help of Lodge's tables we find that this ratio has the values

		1 000,	638,	396,	
for	$\beta =$	0,	12,	48,	respectively

When $\sigma=2\omega$, we have $\kappa=0$, and thence, by (23), (24), (25),

$$\zeta = \bar{\zeta}, \quad \dots \dots \dots (27)$$

i.e. the tidal elevation has exactly the equilibrium-value

This remarkable result can be obtained in a more general manner; it holds whenever the disturbing force is of the type

$$\zeta = \chi(r) e^{i(2\omega t + s\theta + \epsilon)} \dots \dots \dots (28)$$

provided the depth h be a function of r only. If we revert to the equations (1), we notice that when $\sigma=2\omega$ they are satisfied by $\zeta = \bar{\zeta}$, $\Theta = iR$. To determine R as a function of r , we substitute in the equation of continuity (2), which gives

$$\frac{\partial(hR)}{\partial r} - \frac{s-1}{r} hR = -\chi(r) \dots \dots \dots (29)$$

The arbitrary constant which appears on integration of this equation is to be determined by the boundary-condition

In the present case we have $\chi(r) = Cr^s/\alpha^s$. Integrating, and making $R=0$ for $r=\alpha$, we find

$$hR = \frac{Cr^{s-1}}{2\alpha^s} (\alpha^2 - r^2) e^{i(2\omega t + s\theta + \epsilon)} \dots \dots \dots (30)$$

The relation $\Theta = iR$ shows that the amplitudes of R and Θ are equal, while their phases differ by 90° , the relative orbits of the fluid particles are in fact circles of radii

$$r = \frac{Cr^{s-1}}{2h\alpha^s} (\alpha^2 - r^2), \quad \dots \dots \dots (31)$$

described each about its centre with angular velocity 2ω in the negative direction. We may easily deduce that the path of any particle in space is an ellipse of semi-axes $r \pm r$

described about the origin with harmonic motion in the positive direction, the period being $2\pi/\omega$. This accounts for the peculiar features of the case. For if ζ have always the equilibrium-value, the horizontal forces due to the elevation exactly balance the disturbing force, and there remain only the forces due to the undisturbed form of the free surface (Art 206 (1)). These give an acceleration gdz_0/dr , or $\omega^2 r$, to the centre, where r is the radius-vector of the particle in its actual position. Hence all the conditions of the problem are satisfied by elliptic-harmonic motion of the individual particles, provided the positions, the dimensions, and the 'epochs' of the orbits can be adjusted so as to satisfy the condition of continuity, with the assumed value of ζ . The investigation just given resolves this point.

211 We may also briefly notice the case of a circular basin of variable depth, the law of depth being the same as in Art 191, viz

$$h = h_0 \left(1 - \frac{r^2}{a^2}\right). \quad \dots \dots \dots (1)$$

Assuming that R , Θ , ζ all vary as $e^{i(\sigma t + s\theta + \epsilon)}$, and that h is a function of r only, we find, from Art 208 (2), (3),

$$(\sigma^2 - 4\omega^2)\zeta + g \frac{dh}{dr} \left(\frac{\partial}{\partial r} + \frac{2\omega s}{\sigma r}\right) (\zeta - \bar{\zeta}) + g h \left(\frac{\partial^2}{\partial r^2} + \frac{1}{r} \frac{\partial}{\partial r} - \frac{s^2}{r^2}\right) (\zeta - \bar{\zeta}) = 0 \quad \dots (2)$$

Introducing the value of h from (1), we have, for the *free* oscillations

$$\left(1 - \frac{r^2}{a^2}\right) \left(\frac{\partial^2 \zeta}{\partial r^2} + \frac{1}{r} \frac{\partial \zeta}{\partial r} - \frac{s^2}{r^2} \zeta\right) - \frac{2}{a^2} \left(r \frac{\partial \zeta}{\partial r} + \frac{2\omega s}{\sigma} \zeta\right) + \frac{\sigma^2 - 4\omega^2}{g h_0} \zeta = 0 \quad \dots \dots (3)$$

This is identical with Art 191 (6), except that we now have

$$\frac{\sigma^2 - 4\omega^2}{g h_0} - \frac{4\omega s}{\sigma a^2}$$

in place of $\sigma^2/g h_0$. The solution can therefore be written down from the results of that Art, viz if we put

$$\frac{(\sigma^2 - 4\omega^2)a^2}{g h_0} - \frac{4\omega s}{\sigma} = n(n-2) - s^2, \quad \dots \dots (4)$$

we have

$$\zeta = A_s \left(\frac{r}{a}\right)^s F\left(a, \beta, \gamma, \frac{r^2}{a^2}\right) e^{i(\sigma t + s\theta + \epsilon)}, \quad \dots \dots (5)$$

where

$$\alpha = \frac{1}{2}n + \frac{1}{2}s, \quad \beta = 1 + \frac{1}{2}s - \frac{1}{2}n, \quad \gamma = s + 1,$$

and the condition of convergence at the boundary $r=a$ requires that

$$n = s + 2j, \quad \dots \dots \dots (6)$$

where j is some positive integer. The values of σ are then given by (4)

The forms of the free surface are therefore the same as in the case of no rotation, but the motion of the water-particles is different. The relative orbits are in fact now ellipses having their principal axes along and perpendicular to the radius vector, this follows easily from Art 208 (3).

In the symmetrical modes ($s=0$), the equation (4) gives

$$\sigma^2 = \sigma_0^2 + 4\omega^2, \quad \dots \dots \dots (7)$$

where σ_0 denotes the 'speed' of the corresponding mode in the case of no rotation, as found in Art 191.

For any value of s other than zero, the most important modes are those for which $n=s+2$. The equation (4) is then divisible by $\sigma+2\omega$, but this is an extraneous factor; discarding it, we have the quadratic

$$\sigma^2 - 2\omega\sigma = 2s \frac{gh_0}{a^2}, \quad (8)$$

whence

$$\sigma = \omega \pm \left(\omega^2 + 2s \frac{gh_0}{a^2} \right)^{\frac{1}{2}} \quad \dots \quad (9)$$

This gives two waves rotating round the origin, the relative wave-velocity being greater for the negative than for the positive wave, as in the case of uniform depth (Art 209). With the help of (8) the formulae reduce to

$$\zeta = A_s \left(\frac{r}{a} \right)^s, \quad R = \frac{1}{2} \frac{a}{h_0} A_s \left(\frac{r}{a} \right)^{s-1}, \quad \Theta = \frac{1}{2} i \frac{a}{h_0} A_s \left(\frac{r}{a} \right)^{s-1}, \quad \dots \quad (10)$$

the factor $e^{i(\sigma t + s\theta + \epsilon)}$ being of course understood in each case. Since $\Theta = iR$, the relative orbits are all circles. The case $s=1$ is noteworthy, the free surface is then always *plane*, and the circular orbits have all the same radius.

When $n > s+2$, we have nodal circles. The equation (4) is then a *cubic* in $\sigma/2\omega$, it is easily seen that its roots are all real, lying between $-\infty$ and -1 , -1 and 0 , and $+1$ and $+\infty$, respectively. As a numerical example, in the case of $s=1$, $n=5$, corresponding to the values

2,	6,	40
of $4\omega^2 a^2 / gh_0$, we find		
$\frac{\sigma}{2\omega} = \begin{cases} +2.889 \\ -0.125 \\ -2.764 \end{cases}$	$\begin{cases} +1.874 \\ -0.100 \\ -1.774 \end{cases}$	$\begin{cases} +1.180 \\ -0.037 \\ -1.143 \end{cases}$

The first and the last root of each triad give positive and negative waves of a somewhat similar character to those already obtained in the case of uniform depth. The smaller negative root gives a comparatively slow oscillation which, when the angular velocity ω is infinitely small, becomes a *steady* rotational motion, without elevation or depression of the surface*.

The most important type of *forced* oscillations is such that

$$\bar{\zeta} = C \left(\frac{r}{a} \right)^s e^{i(\sigma t + s\theta + \epsilon)} \quad \dots \quad (11)$$

We readily verify, on substitution in (3), that

$$\bar{\zeta} = \frac{2sg h_0}{2sg h_0 - (\sigma^2 - 2\omega\sigma)a^2} \bar{\zeta} \quad \dots \quad (12)$$

We notice that when $\sigma=2\omega$ the tide-height has exactly the equilibrium-value, in agreement with Art 210.

If σ_1, σ_2 denote the two roots of (8), the last formula may be written

$$\bar{\zeta} = \frac{\bar{\zeta}}{(1 - \sigma/\sigma_1)(1 - \sigma/\sigma_2)} \quad (13)$$

* The possibility of oscillations of this type has been pointed out in Art 205, *ad fi*.

Tides on a Rotating Globe.

212. We proceed to give some account of Laplace's problem of the tidal oscillations of an ocean of (comparatively) small depth covering a rotating globe*. In order to bring out more clearly the nature of the approximations which are made on various grounds, we adopt a method of establishing the fundamental equations somewhat different from that usually followed

When in relative equilibrium, the free surface is of course a level-surface with respect to gravity and centrifugal force, we shall assume it to be a surface of revolution about the polar axis, but the ellipticity will not in the first instance be taken to be small

We adopt this equilibrium-form of the free surface as a surface of reference, and denote by θ and ϕ the co-latitude (*i.e.* the angle which the normal makes with the polar axis) and the longitude, respectively, of any point upon it. We shall further denote by z the altitude, measured outwards along a normal, of any point above this surface

The relative position of any particle of the fluid being specified by the three orthogonal coordinates θ , ϕ , z , the kinetic energy of unit mass is given by

$$2T = (R + z)^2 \dot{\theta}^2 + \omega^2 (\omega + \phi)^2 + \dot{z}^2, \quad \dots \dots \dots (1)$$

where R is the radius of curvature of the meridian-section of the surface of reference, and ω is the distance of the particle from the polar axis. It is to be noticed that R is a function of θ only, whilst ω is a function of both θ and z , and it easily follows from geometrical considerations that

$$\frac{\partial \omega}{(R + z) \partial \theta} = \cos \theta, \quad \frac{\partial \omega}{\partial z} = \sin \theta. \quad \dots \dots (2)$$

The component accelerations are obtained at once from (1) by Lagrange's formula. Omitting terms of the second order, on account of the restriction to infinitely small motions, we have

$$\left. \begin{aligned} \frac{1}{R + z} \left(\frac{d}{dt} \frac{\partial T}{\partial \dot{\theta}} - \frac{\partial T}{\partial \theta} \right) &= (R + z) \ddot{\theta} - \frac{1}{R + z} (\omega^2 + 2\omega \phi) \omega \frac{\partial \omega}{\partial \theta}, \\ \frac{1}{\omega} \left(\frac{d}{dt} \frac{\partial T}{\partial \dot{\phi}} - \frac{\partial T}{\partial \phi} \right) &= \ddot{\phi} + 2\omega \left(\frac{\partial \omega}{\partial \theta} \dot{\theta} + \frac{\partial \omega}{\partial z} \dot{z} \right), \\ \frac{d}{dt} \frac{\partial T}{\partial \dot{z}} - \frac{\partial T}{\partial z} &= \ddot{z} - (\omega^2 + 2\omega \phi) \omega \frac{\partial \omega}{\partial z} \end{aligned} \right\} \dots (3)$$

* "Recherches sur quelques points du système du monde," *Mém. de l'Acad. roy. des Sciences*, 1775 [1778] and 1776 [1779]; *Oeuvres Complètes*, t. ix pp 88, 187. The investigation is reproduced, with various modifications, in the *Mécanique Céleste*, Livre 4^{me}, c 1 (1799).

Hence, if we write u, v, w for the component relative velocities of a particle, viz

$$u = (R + z) \dot{\theta}, \quad v = \varpi \phi, \quad w = z, \quad \dots \dots \dots (4)$$

and make use of (2), the hydrodynamical equations may be put in the forms

$$\left. \begin{aligned} \frac{\partial u}{\partial t} - 2\omega v \cos \theta &= -\frac{1}{R+z} \frac{\partial}{\partial \theta} \left(\frac{p}{\rho} + \Psi - \frac{1}{2} \omega^2 \varpi^2 + \Omega \right), \\ \frac{\partial v}{\partial t} + 2\omega u \cos \theta + 2\omega w \sin \theta &= -\frac{1}{\varpi} \frac{\partial}{\partial \phi} \left(\frac{p}{\rho} + \Psi - \frac{1}{2} \omega^2 \varpi^2 + \Omega \right), \\ \frac{\partial w}{\partial t} - 2\omega v \sin \theta &= -\frac{\partial}{\partial z} \left(\frac{p}{\rho} + \Psi - \frac{1}{2} \omega^2 \varpi^2 + \Omega \right), \end{aligned} \right\} \quad (5)$$

where Ψ is the gravitation-potential due to the earth's attraction, whilst Ω denotes the potential of the disturbing forces

So far the only approximation has consisted in the omission of terms of the second order in u, v, w . In the present application, the depth of the sea being small compared with the dimensions of the globe, we may replace $R + z$ by R . We will further assume that the effect of the *relative* vertical acceleration on the pressure may be neglected, and that the vertical velocity is small compared with the horizontal velocity. The last of the equations (5) then reduces to

$$\frac{\partial}{\partial z} \left(\frac{p}{\rho} + \Psi - \frac{1}{2} \omega^2 \varpi^2 + \Omega \right) = 0. \quad \dots \dots \dots (6)$$

Let us integrate this between the limits z and ζ , where ζ denotes the elevation of the disturbed surface above the surface of reference. At the surface of reference ($z = 0$) we have

$$\Psi - \frac{1}{2} \omega^2 \varpi^2 = \text{const.},$$

by hypothesis, and therefore at the free surface ($z = \zeta$)

$$\Psi - \frac{1}{2} \omega^2 \varpi^2 = \text{const.} + g\zeta,$$

provided

$$g = \left[\frac{\partial}{\partial z} (\Psi - \frac{1}{2} \omega^2 \varpi^2) \right]_{z=0}. \quad \dots \dots \dots (7)$$

Here g denotes the value of *apparent* gravity at the surface of reference, it is of course, in general, a function of θ . The integration in question then gives

$$\frac{p}{\rho} + \Psi - \frac{1}{2} \omega^2 \varpi^2 + \Omega = \text{const.} + g\zeta + \Omega, \quad \dots \dots \dots (8)$$

the variation of Ω with z being neglected. Substituting from (8) in the first two of equations (5), we obtain, with the approximations above indicated,

$$\frac{\partial u}{\partial t} - 2\omega v \cos \theta = -g \frac{\partial}{R \partial \theta} (\zeta - \bar{\zeta}), \quad \frac{\partial v}{\partial t} + 2\omega u \cos \theta = -g \frac{\partial}{\varpi \partial \phi} (\zeta - \bar{\zeta}), \quad \dots (9)$$

where
$$\bar{\xi} = -\frac{\Omega}{g}. \quad \dots \dots \dots (10)$$

These equations are independent of z , so that the horizontal motion may be assumed to be sensibly the same for all particles in the same vertical line

As in Art 197, this last result greatly simplifies the equation of continuity. In the present case we find without difficulty

$$\frac{\partial \xi}{\partial t} = -\frac{1}{\varpi} \left\{ \frac{\partial (h\varpi u)}{R\partial \theta} + \frac{\partial (hv)}{\partial \phi} \right\} \quad \dots \quad (11)$$

It is important to notice that these equations involve no assumptions beyond those expressly laid down, in particular, there is no restriction as to the ellipticity of the meridian, which may be of any degree of oblateness

213 In order, however, to simplify the question as far as possible, without sacrificing any of its essential features, we now take advantage of the circumstance that in the actual case of the earth the ellipticity is a small quantity, being in fact comparable with the ratio $(\omega^2 a/g)$ of centrifugal force to gravity at the equator, which ratio is known to be about $\frac{1}{289}$. Subject to an error of this order of magnitude, we may put $R = a$, $\varpi = a \sin \theta$, $g = \text{const}$, where a is the earth's mean radius. We thus obtain*

$$\frac{\partial u}{\partial t} - 2\omega v \cos \theta = -\frac{g}{a} \frac{\partial}{\partial \theta} (\xi - \bar{\xi}), \quad \frac{\partial v}{\partial t} + 2\omega u \cos \theta = -\frac{g}{a \sin \theta} \frac{\partial}{\partial \phi} (\xi - \bar{\xi}), \quad (1)$$

with
$$\frac{\partial \xi}{\partial t} = -\frac{1}{a \sin \theta} \left\{ \frac{\partial (hu \sin \theta)}{\partial \theta} + \frac{\partial (hv)}{\partial \phi} \right\}, \quad \dots \dots \dots (2)$$

this last equation being identical with Art 197 (1).

Two conclusions of some interest in connection with our previous work follow at once from the *form* of the equations (1). In the first place, if \mathbf{u} , \mathbf{v} denote the velocities along and perpendicular to *any* horizontal direction s , we easily find, by transformation of coordinates

$$\frac{\partial \mathbf{u}}{\partial t} - 2\omega \mathbf{v} \cos \theta = -g \frac{\partial}{\partial s} (\xi - \bar{\xi}) \quad \dots \dots \dots (3)$$

In the case of a narrow canal, the transverse velocity \mathbf{v} is zero, and the equation (3) takes the same form as in the case of no rotation, this has been assumed by anticipation in Art 182. The only effect of the rotation in such cases is to produce a slight slope of the wave-crests and furrows in the direction *across* the canal, as investigated in Art 207.

Again, by comparison of (1) with Art 206 (5), we see that the oscillations of a sheet of water of relatively small dimensions, in colatitude θ , will take

* Laplace, *l c ante* p 312

place according to the same laws as those of a *plane* sheet rotating about a normal to its plane with angular velocity $\omega \cos \theta$.

As in Art 206, free steady motions are possible, subject to certain conditions. Putting $\bar{\xi}=0$, we find that the equations (1) and (2) are satisfied by constant values of u , v , ζ , provided

$$u=-\frac{g}{2\omega a \sin \theta \cos \theta} \frac{\partial \zeta}{\partial \phi}, \qquad v=\frac{g}{2\omega a \cos \theta} \frac{\partial \zeta}{\partial \theta}, \quad \dots \quad \dots (4)$$

and
$$\frac{\partial (h \sec \theta, \zeta)}{\partial (\theta, \phi)}=0 \quad \dots \quad \dots \quad \dots (5)$$

The latter condition is satisfied by any assumption of the form
$$\zeta=f(h \sec \theta), \quad \dots \quad \dots \quad \dots (6)$$

and the equations (4) then give the values of u, v . It appears from (4) that the velocity in these steady motions is everywhere parallel to the contour-lines of the disturbed surface.

If h is constant, or a function of the latitude only, the only condition imposed on ζ is that it should be independent of ϕ ; in other words the elevation must be symmetrical about the polar axis.

214 We shall suppose henceforward that the depth h is a function of θ only, and that the barriers to the sea, if any, coincide with parallels of latitude

We take first the cases where the disturbed form of the water-surface is one of revolution about the polar axis. When the terms involving ϕ are omitted, the equations (1) and (2) of the preceding Art take the forms

$$\frac{\partial u}{\partial t}-2\omega v \cos \theta=-\frac{g}{a} \frac{\partial}{\partial \theta} (\zeta-\bar{\xi}), \qquad \frac{\partial v}{\partial t}+2\omega u \cos \theta=0, \quad \dots (1)$$

with
$$\frac{\partial \zeta}{\partial t}=-\frac{\partial (hu \sin \theta)}{a \sin \theta \partial \theta} \quad \dots \quad \dots (2)$$

Assuming a time-factor $e^{i\sigma t}$, and solving for u, v , we find

$$u=\frac{i\sigma g}{\sigma^2-4\omega^2 \cos^2 \theta} \frac{\partial}{a \partial \theta} (\zeta-\bar{\xi}), \qquad v=-\frac{2\omega g \cos \theta}{\sigma^2-4\omega^2 \cos^2 \theta} \frac{\partial}{a \partial \theta} (\zeta-\bar{\xi}), \quad (3)$$

with
$$i\sigma \zeta=-\frac{\partial (hu \sin \theta)}{a \sin \theta \partial \theta} \quad \dots \quad \dots (4)$$

The formulae for the component displacements (ξ, η , say) can be written down from the relations $u=\dot{\xi}$, $v=\dot{\eta}$, or $u=i\sigma \xi$, $v=i\sigma \eta$. It appears that the fluid particles describe ellipses having their principal axes along the meridians and the parallels of latitude, respectively, the ratio of the axes being $\sigma/2\omega \sec \theta$. In the *forced* oscillations of the present type the ratio $\sigma/2\omega$ is

very small, so that the ellipses are very elongated, with the greatest length from E. to W., except in the neighbourhood of the equator.

Eliminating u and v between (3) and (4), and writing, for shortness,

$$\zeta - \bar{\zeta} = \zeta', \quad \frac{\sigma}{2\omega} = f, \quad \frac{\omega^2 a}{g} = m, \quad \dots \dots (5)$$

we find
$$\frac{\partial}{\sin \theta \partial \theta} \left(\frac{h \sin \theta}{f^2 - \cos^2 \theta} \frac{\partial \zeta'}{\partial \theta} \right) + 4m\zeta' = -4m\bar{\zeta} \dots \dots (6)$$

In the case of uniform depth, this becomes

$$\frac{\partial}{\partial \mu} \left(\frac{1 - \mu^2}{f^2 - \mu^2} \frac{\partial \zeta'}{\partial \mu} \right) + \beta \zeta' = -\beta \bar{\zeta}, \quad \dots \dots (7)$$

where $\mu = \cos \theta$, and
$$\beta = \frac{4ma}{h} = \frac{4\omega^2 a^2}{gh} \dots \dots (8)$$

215 First, as regards the *free* oscillations Putting $\bar{\zeta} = 0$, we have

$$\frac{\partial}{\partial \mu} \left(\frac{1 - \mu^2}{f^2 - \mu^2} \frac{\partial \zeta'}{\partial \mu} \right) + \beta \zeta' = 0, \quad \dots \dots (9)$$

and we notice that in the case of no rotation this is included in (1) of Art 198, as may be seen by putting $\beta f^2 = \sigma^2 a^2 / gh$, $f = \infty$ The general solution of (9) is necessarily of the form

$$\zeta = AF(\mu) + Bf(\mu), \quad \dots \dots (10)$$

where $F(\mu)$ is an even, and $f(\mu)$ an odd, function of μ , and the constants A, B are arbitrary In the case of a zonal sea bounded by two parallels of latitude, the ratio A/B , and the admissible values of f (and thence of the frequency $\sigma/2\pi$) are determined by the conditions that $u = 0$ at each of these parallels If the boundaries are symmetrically situated on opposite sides of the equator, the oscillations fall into two classes, viz. in one of these $B = 0$, and in the other $A = 0$. By supposing the boundaries to contract to points at the poles, we pass to the case of an unlimited ocean, and the admissible values of f are now determined by the condition that u must be finite for $\mu = \pm 1$. The argument is, in principle, exactly that of Art 200, but the application of the last-mentioned condition is now more difficult, owing to the less familiar form in which the solution of the differential equation is obtained

In the case of symmetry with respect to the equator, we assume, following the method of Lord Kelvin* and Prof G H Darwin†,

$$\frac{1}{\mu^2 - f^2} \frac{\partial \zeta'}{\partial \mu} = B_1 \mu + B_3 \mu^3 + \dots + B_{2y+1} \mu^{2y+1} + \dots \dots (11)$$

* Sir W Thomson, "Note on the 'Oscillations of the First Species' in Laplace's Theory of the Tides," *Phil Mag* (4), t. 1 p 279 (1875)

† "On the Dynamical Theory of the Tides of Long Period," *Proc Roy Soc.*, t. xli p. 337 (1886), *Encyc Britann*, Art "Tides"

This leads to

$$\zeta' = A - \frac{1}{2} f^2 B_1 \mu^2 + \frac{1}{4} (B_1 - f^2 B_3) \mu^4 + \dots + \frac{1}{2j} (B_{2j-3} - f^2 B_{2j-1}) \mu^{2j} + \dots \dots (12)$$

where A is arbitrary, and makes

$$\frac{\partial}{\partial \mu} \left(\frac{1 - \mu^2}{\mu^2 - f^2} \frac{\partial \zeta'}{\partial \mu} \right) = B_1 + 3 (B_3 - B_1) \mu^2 + \dots + (2j + 1) (B_{2j+1} - B_{2j-1}) \mu^{2j} + \dots \dots (13)$$

Substituting in (9), and equating coefficients of the several powers of μ , we find

$$B_1 - \beta A = 0, \quad \dots \dots \dots (14)$$

$$B_3 - \left(1 - \frac{\beta f^2}{2} \right) B_1 = 0, \quad \dots \dots \dots (15)$$

and thenceforward

$$B_{2j+1} - \left(1 - \frac{\beta f^2}{2j(2j+1)} \right) B_{2j-1} - \frac{\beta}{2j(2j+1)} B_{2j-3} = 0 \quad \dots \dots (16)$$

These equations determine $B_1, B_3, \dots B_{2j+1}, \dots$ in succession, in terms of A , and the solution thus obtained would be appropriate, as already explained, to the case of a zonal sea bounded by two parallels in equal N and S latitudes. In the case of an ocean covering the globe, it would, as we shall prove, give infinite velocities at the poles, except for certain definite values of f .

Let us write $B_{2j+1}/B_{2j-1} = N_{j+1}; \quad \dots \dots \dots (17)$

we shall shew, in the first place, that as j increases N_j must tend either to the limit 0 or to the limit 1. The equation (16) may be written

$$N_{j+1} = 1 - \frac{\beta f^2}{2j(2j+1)} + \frac{\beta}{2j(2j+1)} \frac{1}{N_j} \dots \dots (18)$$

Hence, when j is large, either

$$N_j = - \frac{\beta}{2j(2j+1)}, \quad \dots \dots \dots (19)$$

approximately, or N_{j+1} is not small, in which case N_{j+2} will be nearly equal to 1, and the values of N_{j+3}, N_{j+4}, \dots will tend more and more nearly to 1, the approximate formula being

$$N_{j+1} = 1 - \frac{\beta(f^2 - 1)}{2j(2j+1)} \dots \dots \dots (20)$$

Hence, with increasing j , N_j tends to one or other of the forms (19) and (20).

In the former case (19), the series (11) will be convergent for $\mu = \pm 1$, and the solution is valid over the whole globe

In the other event (20), the product $N_3 N_4 \dots N_{j+1}$, and therefore the coefficient B_{2j+1} , tends with increasing j to a finite limit other than zero. The series (11) will then, after some finite number of terms, become comparable with $1 + \mu^2 + \mu^4 + \dots$, or $(1 - \mu^2)^{-1}$, so that we may write

$$\frac{1}{\mu^2 - f^2} \frac{\partial \zeta'}{\partial \mu} = L + \frac{M}{1 - \mu^2}, \quad \dots \quad (21)$$

where L and M are functions of μ which remain finite when $\mu = \pm 1$. Hence from (3),

$$u = -\frac{i\sigma}{4m} \frac{(1 - \mu^2)^{\frac{1}{2}}}{\mu^2 - f^2} \frac{\partial \zeta'}{\partial \mu} = -\frac{i\sigma}{4m} \{ (1 - \mu^2)^{\frac{1}{2}} L + (1 - \mu^2)^{-\frac{1}{2}} M \}, \quad (22)$$

which makes u infinite at the poles

It follows that the conditions of our problem can be satisfied only if N_j tends to the limit zero, and this consideration, as we shall see, restricts us to a determinate series of values of f

The relation (18) may be put in the form

$$N_j = \frac{-\frac{\beta}{2j(2j+1)}}{1 - \frac{\beta f^2}{2j(2j+1)} - N_{j+1}}, \quad \dots \quad (23)$$

and by successive applications of this we obtain N_j in the form of a convergent continued fraction

$$N_j = \frac{-\frac{\beta}{2j(2j+1)}}{1 - \frac{\beta f^2}{2j(2j+1)} + \frac{\frac{\beta}{(2j+2)(2j+3)}}{1 - \frac{\beta f^2}{(2j+2)(2j+3)} + \frac{\frac{\beta}{(2j+4)(2j+5)}}{1 - \frac{\beta f^2}{(2j+4)(2j+5)} + \dots}}, \quad (24)$$

on the present supposition that N_{j+k} tends with increasing k to the limit 0, in the manner indicated by (19). In particular, this formula determines the value of N_2 . Now from (15) we must have

$$N_2 = 1 - \frac{\beta f^2}{2 \cdot 3}, \quad \dots \quad (25)$$

whence

$$1 - \frac{\beta f^2}{2 \cdot 3} + \frac{\frac{\beta}{4 \cdot 5}}{1 - \frac{\beta f^2}{4 \cdot 5} + \frac{\frac{\beta}{6 \cdot 7}}{1 - \frac{\beta f^2}{6 \cdot 7} + \dots}} = 0, \quad \dots \quad (26)$$

which is equivalent to $N_1 = \infty$. This equation determines the admissible value of $f (= \sigma/2\omega)$. The constants in (11) are then given by

$$B_1 = \beta A, \quad B_3 = N_2 \beta A, \quad B_5 = N_2 N_3 \beta A, \quad \dots \quad (27)$$

where A is arbitrary.

It is easily seen that when β is infinitesimal the roots of (26) are given by

$$\frac{\sigma^2 a^2}{gh} = \beta f^2 = n(n+1), \quad \dots \quad (28)$$

where n is an even integer, cf Art 198

One arithmetically remarkable point remains to be noticed. It might appear at first sight that when a value of f has been found from (26) the coefficients B_3, B_5, B_7, \dots could be found in succession from (15) and (16), or by means of the equivalent formula (18). But this would require us to start with *exactly* the right value of f and to observe absolute accuracy in the subsequent stages of the work. The above argument shews, in fact, that any other value, differing by however little, if adopted as a starting point for the calculation will inevitably lead at length to values of N , which approximate to the limit 1*.

216 It is shewn in the Appendix to this Chapter that the tide-generating potential, when expanded in simple-harmonic functions of the time, consists of terms of three distinct types

The first type is such that the equilibrium tide-height would be given by

$$\bar{\zeta} = H' \left(\frac{1}{3} - \cos^2 \theta \right) \cdot \cos(\sigma t + \epsilon)^\dagger \quad \dots \quad (29)$$

The corresponding forced waves are called by Laplace the 'Oscillations of the First Species', they include the lunar fortnightly and the solar semi-annual tides, and generally all the tides of long period. Their characteristic is symmetry about the polar axis, and they form accordingly the most important case of forced oscillations of the present type.

If we substitute from (29) in (7), and assume for

$$\frac{1 - \mu^2}{\mu^2 - f^2} \frac{\partial \zeta'}{\partial \mu} \quad \text{and} \quad \zeta'$$

expressions of the forms (11) and (12), we have, in place of (14), (15),

$$B_1 - \frac{1}{3}\beta H' - \beta A = 0, \quad \dots \quad (30)$$

$$B_3 - \left(1 - \frac{\beta f^2}{2} \right) B_1 + \frac{1}{3}\beta H' = 0, \quad \dots \quad (31)$$

whilst (16) and its consequences hold for all the higher coefficients. It may be noticed that (31) may be included under the general formula (16), provided we write $B_{-1} = -2H'$. It appears by the same argument as before that the only admissible solution for an ocean covering the globe is the one that makes

* Sir W. Thomson, *loc. ante* p. 316

† In strictness, θ here denotes the *geocentric* latitude, but the difference between this and the geographical latitude may be neglected consistently with the assumptions introduced in Art 213

$N_\infty = 0$, and that accordingly N_j must have the value given by the continued fraction in (24), where f is now prescribed by the frequency of the disturbing forces

In particular, this formula determines the value of N_1 . Now

$$B_1 = N_1 B_{-1} = -2N_1 H',$$

and the equation (30) then gives

$$A = -\frac{1}{3}H' - \frac{2}{\beta}N_1 H', \quad . \quad . \quad . \quad (32)$$

in other words, this is the only value of A which is consistent with a zero limit of N_j , and therefore with a finite velocity at the poles. Any other value of A , if adopted as a starting point for the calculation of B_1, B_2, B_3, \dots in succession, by means of (30), (31), and (16), would lead ultimately to values of N_j approximating to the limit 1. Moreover, since *absolute* accuracy in the initial choice of A and in the subsequent computations would be essential to avoid this, the only practical method of calculating the coefficients is to use the formulae

$$B_1/H' = -2N_1, \quad B_3 = N_2 B_1, \quad B_5 = N_3 B_3, \quad . \quad ,$$

$$\text{or} \quad B_1/H' = -2N_1, \quad B_3/H' = -2N_1 N_2, \quad B_5/H' = -2N_1 N_2 N_3, \\ . \quad . \quad . \quad (33)$$

where the values of N_1, N_2, N_3, \dots are to be computed from the continued fraction (24). It is evident *à posteriori* that the solution thus obtained will satisfy all the conditions of the problem, and that the series (12) will converge with great rapidity. The most convenient plan of conducting the calculation is to assume a roughly approximate value, suggested by (19), for one of the ratios N_j of sufficiently high order, and thence to compute

$$N_{j-1}, N_{j-2}, \dots, N_2, N_1$$

in succession by means of the formula (23). The values of the constants A, B_1, B_3, \dots , in (12), are then given by (32) and (33). For the tidal elevation we find

$$\zeta/H' = -2N_1/\beta - (1 - f^2 N_1) \mu^2 - \frac{1}{2} N_1 (1 - f^2 N_2) \mu^4 - \\ - \frac{1}{j} N_1 N_2 \dots N_{j-1} (1 - f^2 N_j) \mu^{2j} - \dots \dots \dots (34)$$

In the case of the lunar fortnightly tide, f is the ratio of a sidereal day to a lunar month, and is therefore equal to about $\frac{1}{28}$, or more precisely 0.0365. This makes $f^2 = 0.0133$. It is evident that a fairly accurate representation of this tide, and *à fortiori* of the solar semi-annual tide, and of the remaining tides of long period, will be obtained by putting $f = 0$, this materially shortens the calculations.

The results will involve the value of β , $= 4\omega^2 a^2 / gh$. For $\beta = 40$, which corresponds to a depth of 7260 feet, we find in this way

$$\begin{aligned} \zeta/H' = & 1515 - 1\,0000\mu^2 + 1\,5153\mu^4 - 1\,2120\mu^6 + \cdot 6063\mu^8 - 2076\mu^{10} \\ & + 0516\mu^{12} - 0097\mu^{14} + 0018\mu^{16} - 0002\mu^{18}, \quad \dots \quad (35)^* \end{aligned}$$

whence, at the poles ($\mu = \pm 1$),

$$\zeta = -\frac{2}{3}H' \times 154,$$

and, at the equator ($\mu = 0$),

$$\zeta = \frac{1}{3}H' \times \cdot 455$$

Again, for $\beta = 10$, or a depth of 29040 feet, we get

$$\begin{aligned} \zeta/H = & 2359 - 1\cdot 0000\mu^2 + 5898\mu^4 - 1623\mu^6 \\ & + 0258\mu^8 - 0026\mu^{10} + 0002\mu^{12} \quad \dots \quad (36) \end{aligned}$$

This makes, at the poles,

$$\zeta = -\frac{2}{3}H' \times 470,$$

and, at the equator,

$$\zeta = \frac{1}{3}H' \times 708$$

For $\beta = 5$, or a depth of 58080 feet, we find

$$\begin{aligned} \zeta/H' = & 2723 - 1\,0000\mu^2 + 3404\mu^4 \\ & - 0509\mu^6 + \cdot 0043\mu^8 - \cdot 0004\mu^{10} \quad \dots \dots \dots (37) \end{aligned}$$

This gives, at the poles,

$$\zeta = -\frac{2}{3}H' \times 651,$$

and, at the equator,

$$\zeta = \frac{1}{3}H' \times 817$$

Since the polar and equatorial values of the equilibrium tide are $-\frac{2}{3}H'$ and $\frac{1}{3}H'$, respectively, these results shew that for the depths in question the long-period tides are, on the whole, *direct*, though the nodal circles will, of course, be shifted more or less from the positions assigned by the equilibrium theory. It appears, moreover, that, for depths comparable with the actual depth of the sea, the tide has less than half the equilibrium value. It is easily seen from the form of equation (5) that with increasing depth, and consequent diminution of β , the tide height will approximate more and more closely to the equilibrium value. This tendency is illustrated by the above numerical results

* The coefficients in (35) and (36) differ only slightly from the numerical values obtained by Prof. Darwin for the case $f = 0365$.

It is to be remarked that the kinetic theory of the long-period tides was passed over by Laplace, under the impression that practically, owing to the operation of dissipative forces, they would have the values given by the equilibrium theory. He proved, indeed, that the tendency of frictional forces must be in this direction, but it has been pointed out by Darwin* that in case of the fortnightly tide, at all events, it is doubtful whether the effect would be nearly so great as Laplace supposed. We shall return to this point later.

217 When the disturbance is no longer restricted to be symmetrical about the polar axis, we must recur to the general equations (1) and (2) of Art 213. We retain, however, the assumptions as to the law of depth and the nature of the boundaries introduced in Art 214.

If we assume that Ω, u, v, ζ all vary as $e^{i(\sigma t + s\phi + \epsilon)}$, where s is integral, the equations referred to give

$$i\sigma u - 2\omega v \cos \theta = -\frac{g}{a} \frac{\partial}{\partial \theta} (\zeta - \bar{\zeta}), \quad i\sigma v + 2\omega u \cos \theta = -\frac{isg}{a \sin \theta} (\zeta - \bar{\zeta}), \quad (1)$$

$$\text{with} \quad i\sigma \zeta = -\frac{1}{a \sin \theta} \left\{ \frac{\partial (hu \sin \theta)}{\partial \theta} + ish v \right\} \quad \dots \quad (2)$$

Solving for u, v , we find

$$\left. \begin{aligned} u &= \frac{i\sigma}{4m(f^2 - \cos^2 \theta)} \left(\frac{\partial \zeta'}{\partial \theta} + \frac{s}{f} \zeta' \cot \theta \right), \\ v &= -\frac{\sigma}{4m(f^2 - \cos^2 \theta)} \left(\frac{\cos \theta}{f} \frac{\partial \zeta'}{\partial \theta} + s \zeta' \operatorname{cosec} \theta \right), \end{aligned} \right\} \quad \dots \dots (3)$$

where we have written

$$\zeta - \bar{\zeta} = \zeta', \quad \frac{\sigma}{2\omega} = f, \quad \frac{\omega^2 a}{g} = m, \quad \dots \dots \dots (4)$$

as before

It appears that in all cases of simple-harmonic oscillation the fluid particles describe ellipses having their principal axes along the meridians and parallels of latitude, respectively.

Substituting from (3) in (2) we obtain the differential equation in ζ'

$$\begin{aligned} & \frac{\partial}{\sin \theta \partial \theta} \left\{ \frac{h \sin \theta}{f^2 - \cos^2 \theta} \left(\frac{\partial \zeta'}{\partial \theta} + \frac{s}{f} \zeta' \cot \theta \right) \right\} \\ & - \frac{h}{f^2 - \cos^2 \theta} \left(\frac{s}{f} \cot \theta \frac{\partial \zeta'}{\partial \theta} + s^2 \zeta' \operatorname{cosec}^2 \theta \right) + 4ma\zeta' = -4ma\bar{\zeta}. \quad (5) \end{aligned}$$

* *l c. ante* p. 316

218 The case $s = 1$ includes, as forced oscillations, Laplace's 'Oscillations of the Second Species,' where the disturbing potential is a tesseral harmonic of the second order, viz

$$\bar{\xi} = H'' \sin \theta \cos \theta \cos (\sigma t + \phi + \epsilon), \quad \dots \dots (1)$$

where σ differs not very greatly from ω . This includes the lunar and solar diurnal tides

In the case of a disturbing body whose proper motion could be neglected, we should have $\sigma = \omega$, exactly, and therefore $f = \frac{1}{2}$. In the case of the moon, the orbital motion is so rapid that the actual period of the principal lunar diurnal tide is very appreciably longer than a sidereal day*, but the supposition that $f = \frac{1}{2}$ simplifies the formulae so materially that we adopt it in the following investigation†. We find that it enables us to calculate the forced oscillations when the depth follows the law

$$h = (1 - q \cos^2 \theta) h_0, \quad \dots \dots (2)$$

where q is any given constant

Taking an exponential factor $e^{i(\omega t + \phi + \epsilon)}$, and therefore putting $s = 1$, $f = \frac{1}{2}$, in Art 217 (3), and assuming

$$\xi' = C \sin \theta \cos \theta, \quad \dots \dots (3)$$

we find

$$u = -i\sigma \frac{C}{m}, \quad v = \sigma \frac{C}{m} \cos \theta \quad \dots \dots (4)$$

Substituting in the equation of continuity (Art. 217 (2)), we get

$$\xi' + \bar{\xi} = \frac{C}{ma} \frac{dh}{d\theta}, \quad \dots \dots (5)$$

which is consistent with the law of depth (2), provided

$$C = -\frac{1}{1 - 2qh_0/ma} H'' \quad \dots \dots (6)$$

This gives

$$\xi = -\frac{2qh_0/ma}{1 - 2qh_0/ma} \bar{\xi} \quad \dots \dots (7)$$

One remarkable consequence of this formula is that in the case of uniform depth ($q = 0$) there is no diurnal tide, so far as the rise and fall of the surface is concerned. This result was first established (in a different manner) by Laplace, who attached great importance to it as shewing that his kinetic theory was able to account for the relatively small values of the diurnal tide which are given by observation, in striking contrast to what would be demanded by the equilibrium-theory

* It is to be remarked, however, that there is an important term in the harmonic development of Ω for which $\sigma = \omega$ exactly, provided we neglect the changes in the plane of the disturbing body's orbit. This period is the same for the sun as for the moon, and the two partial tides thus produced combine into what is called the 'luni-solar' diurnal tide

† Taken with very slight alteration from Airy ("Tides and Waves," Arts. 95), and Darwin (*Encyc Brit.*, t xxiii p 359)

But, although with a uniform depth there is no rise and fall, there are tidal currents. It appears from (4) that every particle describes an ellipse whose major axis is in the direction of the meridian, and of the same length in all latitudes. The ratio of the minor to the major axis is $\cos \theta$, and so varies from 1 at the poles to 0 at the equator, where the motion is wholly N and S.

219 In the case $s=2$, the forced oscillations of most importance are where the disturbing potential is a sectorial harmonic of the second order. These constitute Laplace's 'Oscillations of the Third Species,' for which

$$\bar{\xi} = H''' \sin^2 \theta \cdot \cos(\sigma t + 2\phi + \epsilon), \quad \dots \dots (1)$$

where σ is nearly equal to 2ω . This includes the most important of all the tidal oscillations, viz. the lunar and solar semi-diurnal tides.

If the orbital motion of the disturbing body were infinitely slow we should have $\sigma = 2\omega$, and therefore $f=1$, for simplicity we follow Laplace in making this approximation, although it is a somewhat rough one in the case of the principal lunar tide*.

A solution similar to that of the preceding Art can be obtained for the special law of depth†

$$h = h_0 \sin^2 \theta \quad \dots \dots \dots (2)$$

Adopting an exponential factor $e^{i(2\omega t + 2\phi + \epsilon)}$, and putting therefore $f=1$, $s=2$, we find that if we assume

$$\zeta' = C \sin^2 \theta, \quad \dots \dots (3)$$

the equations (3) of Art 217 give

$$u = \frac{2\sigma}{m} C \cot \theta, \quad v = -\frac{\sigma}{2m} C \frac{\sin \theta}{1 + \cos^2 \theta}, \quad \dots \dots (4)$$

whence, substituting in Art 217 (2),

$$\zeta = \frac{2h_0}{ma} C \sin^2 \theta \quad \dots \dots \dots (5)$$

Putting $\zeta = \zeta' + \bar{\xi}$, and substituting from (1) and (3), we find

$$C = -\frac{1}{1 - 2h_0/ma} H''', \quad \dots \dots \dots (6)$$

and therefore

$$\zeta = -\frac{2h_0/ma}{1 - 2h_0/ma} \bar{\xi}. \quad \dots \dots \dots (7)$$

For such depths as actually occur in the ocean $2h_0 < ma$, and the tide is therefore inverted. It may be noticed that the formulae (4) make the velocity infinite at the poles, as was to be expected, since the depth there is zero.

* There is, however, a 'luni-solar' semi-diurnal tide whose speed is exactly 2ω if we neglect the changes in the planes of the orbits. Cf p 323, first footnote.

† Cf Airy and Darwin, *ll cc*

220 For any other law of depth a solution can only be obtained in the form of a series. In the case of *uniform* depth we find, putting $s = 2, f = 1, 4ma/h = \beta$ in Art 217 (5),

$$(1 - \mu^2)^2 \frac{d^2 \zeta'}{d\mu^2} + \{\beta(1 - \mu^2)^2 - 2\mu^2 - 6\} \zeta' = -\beta(1 - \mu^2)^2 \bar{\zeta}, \quad (8)$$

where μ is written for $\cos \theta$. In this form the equation is somewhat intractable, since it contains terms of four different dimensions in μ . It simplifies a little, however, if we transform to

$$\nu, = (1 - \mu^2)^{\frac{1}{2}}, = \sin \theta,$$

as independent variable, viz we find

$$\nu^2(1 - \nu^2) \frac{d^2 \zeta'}{d\nu^2} - \nu \frac{d\zeta'}{d\nu} - (8 - 2\nu^2 - \beta\nu^4) \zeta' = -\beta\nu^4 \zeta = -\beta H''' \nu^6, \quad (9)$$

which is of *three* different dimensions in ν

To obtain a solution for the case of an ocean covering the globe, we assume

$$\zeta' = B_0 + B_2\nu^2 + B_4\nu^4 + \dots + B_{2j}\nu^{2j} + \dots \quad (10)$$

Substituting in (9), and equating coefficients, we find

$$B_0 = 0, \quad B_2 = 0, \quad 0 \quad B_4 = 0, \quad \dots \quad (11)$$

$$16B_6 - 10B_4 + \beta H''' = 0, \quad \dots \quad (12)$$

and thenceforward

$$2j(2j + 6) B_{2j+4} - 2j(2j + 3) B_{2j+2} + \beta B_{2j} = 0 \quad \dots \quad (13)$$

These equations give B_6, B_8, B_{10}, \dots in succession, in terms of B_4 , which is so far undetermined. It is obvious, however, from the nature of the problem, that, except for certain special values of h (and therefore of β), which are such that there is a free oscillation of corresponding type ($s = 2$) having the speed 2ω , the solution must be unique. We shall see, in fact, that unless B_4 have a certain definite value the solution above indicated will make the meridian component (u) of the velocity discontinuous at the equator*.

The argument is in some respects similar to that of Art 216. If we denote by N_j the ratio B_{2j+2}/B_{2j} of consecutive coefficients, we have, from (13),

$$N_{j+1} = \frac{2j + 3}{2j + 6} - \frac{\beta}{2j(2j + 6)} \frac{1}{N_j}, \quad \dots \quad (14)$$

from which it appears that, with increasing j , N_j must tend to one or other of the limits 0 and 1. More precisely, unless the limit of N_j be zero, the limiting form of N_{j+1} will be

$$(2j + 3)/(2j + 6), \text{ or } 1 - \frac{3}{2j},$$

* In the case of a polar sea bounded by a small circle of latitude whose angular radius is $< \frac{1}{2}\pi$, the value of B_4 is determined by the condition that $u = 0$, or $\partial \zeta' / \partial \nu = 0$, at the boundary

approximately The latter is identical with the limiting form of the ratio of the coefficients of ν^{2j} and ν^{2j-2} in the expansion of $(1 - \nu^2)^{\frac{1}{2}}$ We infer that, unless B_4 have such a value as to make $N_\infty = 0$, the terms of the series (10) will become ultimately comparable with those of $(1 - \nu^2)^{\frac{1}{2}}$, so that we may write

$$\zeta' = L + (1 - \nu^2)^{\frac{1}{2}} M, \dots \dots \dots (15)$$

where L, M are functions of ν which do not vanish for $\nu = 1$ Near the equator ($\nu = 1$) this makes

$$\frac{d\zeta'}{d\theta} = \mp (1 - \nu^2)^{\frac{1}{2}} \frac{d\zeta'}{d\nu} = \pm M \dots \dots \dots (16)$$

Hence, by Art 217 (3), u would change from a certain finite value to an equal but opposite value as we cross the equator

It is therefore essential, for our present purpose, to choose the value of B_4 so that $N_\infty = 0$ This is effected by the same method as in Art. 216 Writing (13) in the form

$$N_j = \frac{\frac{\beta}{2j(2j+6)}}{\frac{2j+3}{2j+6} - N_{j+1}}, \dots \dots \dots (17)$$

we see that N_j must be given by the converging continued fraction

$$N_j = \frac{\frac{\beta}{2j(2j+6)}}{\frac{2j+3}{2j+6} - \frac{\frac{\beta}{(2j+2)(2j+8)}}{\frac{2j+5}{2j+8} - \frac{\frac{\beta}{(2j+4)(2j+10)}}{\frac{2j+7}{2j+10} - \&c}} \dots \dots (18)$$

This holds from $j = 2$ upwards, but it appears from (12) that it will give also the value of N_1 (not hitherto defined), provided we use this symbol for B_4/H''' We have then

$$B_4 = N_1 H''', \quad B_6 = N_2 B_4, \quad B_8 = N_3 B_6, \dots$$

Finally, writing $\zeta = \bar{\zeta} + \zeta'$, we obtain

$$\zeta/H''' = \nu^2 + N_1 \nu^4 + N_1 N_2 \nu^6 + N_1 N_2 N_3 \nu^8 + \dots \dots \dots (19)$$

As in Art. 216, the practical method of conducting the calculation is to assume an approximate value for N_{j+1} , where j is a moderately large number, and then to deduce $N_j, N_{j-1}, \dots N_2, N_1$ in succession by means of the formula (17)

The above investigation is taken substantially from the very remarkable paper written by Lord Kelvin* in vindication of Laplace's treatment of the problem, as given in the *Mécanique Céleste*. In the passage more especially in question, Laplace determines the constant B_4 by means of the continued fraction for N_1 , without, it must be allowed, giving any adequate justification of the step, and the soundness of this procedure had been disputed by Airy†, and after him by Ferrel‡.

Laplace, unfortunately, was not in the habit of giving specific references, so that few of his readers appear to have become acquainted with the original presentment§ of the kinetic theory, where the solution for the case in question is put in a very convincing, though somewhat different, form. Aiming in the first instance at an approximate solution by means of a *finite* series, thus

$$\zeta' = B_4\nu^4 + B_6\nu^6 + \dots + B_{2k+2}\nu^{2k+2}, \quad \dots (20)$$

Laplace remarks|| that in order to satisfy the differential equation, the coefficients would have to fulfil the conditions

$$\left. \begin{aligned} 16B_0 - 10B_4 + \beta H''' &= 0, \\ 40B_8 - 28B_6 + \beta B_4 &= 0, \\ (2k-2)(2k+4)B_{2k+2} - (2k-2)(2k+1)B_{2k} + \beta B_{2k-2} &= 0, \\ -2k(2k+3)B_{2k+2} + \beta B_{2k} &= 0, \\ \beta B_{2k+2} &= 0, \end{aligned} \right\} \dots \dots (21)$$

as is seen at once by putting $B_{2k+4}=0$, $B_{2k+6}=0$, in the general relation (13)

We have here $k+1$ equations between k constants. The method followed is to determine the constants by means of the first k relations, we thus obtain an exact solution, not of the proposed differential equation (9), but of the equation as modified by the addition of a term $\beta B_{2k+2}\nu^{2k+2}$ to the right-hand side. This is equivalent to an alteration of the disturbing force, and if we can obtain a solution such that the required alteration is very small, we may accept it as an approximate solution of the problem in its original form¶.

Now, taking the first k relations of the system (21) in reverse order, we obtain B_{2k+2} in terms of B_{2k} , thence B_{2k} in terms of B_{2k-1} , and so on, until, finally, B_4 is expressed in terms of H''' , and it is obvious that if k be large enough the value of B_{2k+2} , and the consequent adjustment of the disturbing force which is required to make the solution exact, will be very small. This will be illustrated presently, after Laplace, by a numerical example.

The process just given is plainly equivalent to the use of the continued fraction (17) in the manner already explained, starting with $j+1=k$, and $N_k = \beta/2k(2k+3)$. The continued fraction, as such, does not, however, make its appearance in the memoir here referred to, but was introduced in the *Mécanique Céleste*, probably as an after-thought, as a condensed expression of the method of computation originally employed.

* Sir W. Thomson, "On an Alleged Error in Laplace's Theory of the Tides," *Phil. Mag.* (4), t 1 p 227 (1875).

† "Tides and Waves," Art. 111.

‡ "Tidal Researches," *U S Coast Survey Rep*, 1874, p 154.

§ "Recherches sur quelques points du système du monde," *Mém de l'Acad roy des Sciences*, 1776 [1779] [*Oeuvres Complètes*, t ix, pp 187].

|| *Oeuvres*, t ix p 218. The notation has been altered.

¶ It is remarkable that this argument is of a kind constantly employed by Airy himself in his researches on waves.

The following table gives the numerical values of the coefficients of the several powers of ν in the formula (19) for ζ/H''' , in the cases $\beta = 40, 20, 10, 5, 1$, which correspond to depths of 7260, 14520, 29040, 58080, 290400, feet, respectively*. The last line gives the value of ζ/H''' for $\nu = 1$, i.e. the ratio of the amplitude at the equator to its equilibrium-value. At the poles ($\nu = 0$), the tide has in all cases the equilibrium-value zero

	$\beta = 40$	$\beta = 20$	$\beta = 10$	$\beta = 5$	$\beta = 1$
ν^2	+ 1 0000	+1 0000	+ 1 0000	+1 0000	+1 0000
ν^4	+20 1862	- 0 2491	+6 1915	+0 7504	+0 1062
ν^6	+10 1164	-1 4056	+3 2447	+0 1566	+0 0039
ν^8	-13 1047	- 0 8594	+0 7234	+0 0157	+0 0001
ν^{10}	-15 4488	- 0 2541	+ 0 0919	+0 0009	
ν^{12}	- 7 4581	-0 0462	+0 0076		
ν^{14}	- 2 1975	-0 0058	+0 0004		
ν^{16}	- 0 4501	-0 0006			
ν^{18}	- 0 0687				
ν^{20}	- 0 0082				
ν^{22}	- 0 0008				
ν^{24}	- 0 0001				
	- 7 434	-1 821	+11 259	+1 924	+1 110

We may use the above results to estimate the closeness of the approximation in each case. For example, when $\beta = 40$, Laplace finds $B_{26} = -000004H'''$, the addition to the disturbing force which is necessary to make the solution exact would then be $-00002H'''\nu^{30}$, and would therefore bear to the actual force the ratio $-00002\nu^{28}$.

It appears from (19) that near the poles, where ν is small, the tides are in all cases direct. For sufficiently great depths, β will be very small, and the formulae (17) and (19) then shew that the tide has everywhere sensibly the equilibrium-value, all the coefficients being small except the first, which is unity. As h is diminished, β increases, and the formula (17) shews that each of the ratios N_j will continually increase, except when it changes sign from + to - by passing through the value ∞ . No singularity in the solution attends this passage of N_j through ∞ , except in the case of N_1 , since, as is easily seen, the product $N_{j-1}N_j$ remains finite, and the coefficients in (19) are therefore all finite. But when $N_1 = \infty$, the expression for ζ becomes infinite, shewing that the depth has then one of the critical values already referred to.

The table above given indicates that for depths of 29040 feet, and upwards, the tides are everywhere direct, but that there is some critical depth between 29040 feet and 14520 feet, for which the tide at the equator

* The first three cases were calculated by Laplace, *loc. ante* p. 312, the last by Lord Kelvin. The numbers relating to the third case have been slightly corrected, in accordance with the computations of Hough; see p. 329.

changes from direct to inverted. The largeness of the second coefficient in the case $\beta = 40$ indicates that the depth could not be reduced much below 7260 feet before reaching a second critical value

Whenever the equatorial tide is inverted, there must be one or more pairs of nodal circles ($\xi = 0$), symmetrically situated on opposite sides of the equator. In the case of $\beta = 40$, the position of the nodal circles is given by $\nu = 95$, or $\theta = 90^\circ \pm 18^\circ$, approximately*

221 The dynamical theory of the tides, in the case of an ocean covering the globe, with depth uniform along each parallel of latitude, has in recent times been greatly improved and developed by Hough†, who, taking up an abandoned attempt of Laplace, has substituted expansions in spherical harmonics for the series of powers of μ (or ν). This has the advantage of more rapid convergence, especially, as might be expected, in cases where the influence of the rotation is relatively small, and it also enables us to take account of the mutual attraction of the particles of water, which, as we have seen in the simpler problem of Art. 199, is by no means insignificant.

If the surface-elevation ξ , and the conventional equilibrium tide-height $\bar{\xi}$ (in which the effect of mutual attraction is not included), be expanded in series of spherical harmonics, thus

$$\xi = \Sigma \xi_n, \quad \bar{\xi} = \Sigma \bar{\xi}_n, \quad \dots \dots \dots (1)$$

the complete expression for the disturbing potential will be

$$\Omega = -g\Sigma \left(\bar{\xi}_n + \frac{3}{2n+1} \frac{\rho}{\rho_0} \xi_n \right),$$

cf Art 199. The factor $-g$ is to be substituted for $\bar{\xi}$ in the equations of Arts 213, this will be allowed for if we write

$$\xi' = \Sigma (\alpha_n \xi_n - \bar{\xi}_n), \quad \dots \dots \dots (2)$$

where

$$\alpha_n = 1 - \frac{3}{2n+1} \frac{\rho}{\rho_0}, \quad \dots \dots \dots (3)$$

in modification of the notation of Art 214 (5) or Art. 217 (4)

In the oscillations of the 'First Species,' the differential equation may be written

$$\frac{\partial}{\partial \mu} \left(\frac{1-\mu^2}{f^2-\mu^2} \frac{\partial \xi'}{\partial \mu} \right) + \beta \xi = 0. \quad \dots \dots \dots (4)$$

If we assume

$$\xi = \Sigma C_n P_n(\mu), \quad \bar{\xi} = \Sigma \gamma_n P_n(\mu), \quad \dots \dots \dots (5)$$

we have

$$\xi' = \Sigma (\alpha_n C_n - \gamma_n) P_n(\mu). \quad \dots \dots \dots (6)$$

* For a fuller discussion of these points reference may be made to the original investigation of Laplace, and to Lord Kelvin's papers

† "On the Application of Harmonic Analysis to the Dynamical Theory of the Tides," *Phil. Trans.*, A t clxxxix p 201, and t cxci p 139 (1897)

Substituting in (4), and integrating between the limits -1 and μ , we find

$$\Sigma (\alpha_n C_n - \gamma_n) (1 - \mu^2) \frac{dP_n}{d\mu} + \Sigma \beta C_n \{ (f^2 - 1) + (1 - \mu^2) \} \int_{-1}^{\mu} P_n d\mu = 0 \quad (7)$$

Now, by known formulae of zonal harmonics*,

$$\int_{-1}^{\mu} P_n d\mu = -\frac{1}{n(n+1)} (1 - \mu^2) \frac{dP_n}{d\mu}, \quad \dots \quad (8)$$

$$\begin{aligned} \text{and } \int_{-1}^{\mu} P_n d\mu &= \frac{1}{2n+1} (P_{n+1} - P_{n-1}) \\ &= \frac{1}{2n+1} \left\{ \frac{1}{2n+3} \left(\frac{dP_{n+2}}{d\mu} - \frac{dP_n}{d\mu} \right) - \frac{1}{2n-1} \left(\frac{dP_n}{d\mu} - \frac{dP_{n-2}}{d\mu} \right) \right\} \\ &= \frac{1}{(2n+1)(2n+3)} \frac{dP_{n+2}}{d\mu} - \frac{2}{(2n-1)(2n+3)} \frac{dP_n}{d\mu} \\ &\quad + \frac{1}{(2n-1)(2n+1)} \frac{dP_{n-2}}{d\mu} \end{aligned} \quad (9)$$

Substituting in (7), and equating to zero the coefficient of $(1 - \mu^2) \frac{dP_n}{d\mu}$, we find

$$\frac{1}{(2n+3)(2n+5)} C_{n+2} - L_n C_n + \frac{1}{(2n-3)(2n-1)} C_{n-2} = \frac{\gamma_n}{\beta}, \quad \dots \quad (10)$$

$$\text{where } L_n = \frac{f^2 - 1}{n(n+1)} + \frac{2}{(2n-1)(2n+3)} - \frac{\alpha_n}{\beta} \quad \dots \quad (11)$$

The relation (10) will hold from $n=1$ onwards, provided we put

$$C_{-1} = 0, \quad C_0 = 0.$$

The further theory is based substantially on the argument of Laplace, given in Art. 220, and the work follows much the same lines as in Arts 215, 216, 220.

In the *free* oscillations we have $\gamma_n = 0$, and the admissible values of f are determined by the transcendental equation

$$L_2 - \frac{1}{\frac{5 \cdot 7^2}{L_4} - 9} \frac{1}{\frac{9}{L_6} - \frac{11 \cdot 13}{\&c}} = 0, \quad \dots \quad (12)$$

$$\text{or } L_1 - \frac{1}{\frac{3 \cdot 5^2}{L_3} - 7} \frac{1}{\frac{7}{L_5} - \frac{9 \cdot 11}{\&c}} = 0, \quad \dots \quad (13)$$

* See Todhunter, *Functions of Laplace, &c*, c v., Whittaker, *Modern Analysis*, Art 117.

according as the mode is symmetrical or asymmetrical with respect to the equator. Alternative forms of the period equations are given by Hough, suitable for computation of the higher roots, and it is shewn that close approximations are given by the equations $L_n = 0$ or

$$\frac{\sigma^2}{4\omega^2} = 1 + n(n+1) \left\{ \left(1 - \frac{3}{2n+1} \frac{\rho}{\rho_0} \right) \frac{gh}{4\omega^2 a^2} - \frac{2}{(2n-1)(2n+3)} \right\}, \tag{14}$$

except for the first two or three values of n

The following table gives the periods (in sidereal time) of the slowest symmetrical oscillation (*i.e.* the one in which the surface-elevation would vary as $P_2(\mu)$ if there were no rotation), corresponding to various depths*

β	Depth (feet)	$\frac{\sigma^2}{4\omega^2}$	Period		Period when $\omega=0$	
			h	m	h	m.
40	7260	44155	18	35	32	49
20	14520	62473	15	110	23	12
10	29040	92506	12	286	16	25
5	58080	14785	9	521	11	35

The results obtained for the *forced* oscillations of the 'First Species' are very similar to those of Art 216. The limiting form of the long-period tides when $\sigma = 0$ shews the following results

β	$\rho/\rho_0 = 181$		$\rho/\rho_0 = 0$	
	Pole	Equator	Pole	Equator
40	140	426	154	455
20	266	551		
10	443	681	470	708
5	628	796	651	817

The second and third columns give the ratio of the polar and equatorial tides to the respective equilibrium-values†. The numbers in the fourth and fifth columns are repeated from Art 216. The comparison shews the effect of the mutual gravitation of the water in reducing the amplitude.

* The slowest asymmetrical mode has a much longer period. It involves a displacement of the centre of mass of the water, so that a correction would be necessary if the nucleus were free, cf Art 198.

† The numbers are deduced from Hough's results. The paper referred to includes a discussion of many other interesting points, including an examination of cases of varying depth, with numerical illustrations.

222 In the more general case, where symmetry about the axis is not imposed, the surface-elevation ζ is expanded by Hough in a series of tesseral harmonics of the type

$$P_n^s(\mu) e^{i(\sigma t + s\phi + \epsilon)} \quad . \quad . \quad . \quad (1)$$

In relation to tidal theory the most important cases are where the disturbing potential is of the form (1), with $n = 2$ and $s = 1$ or $s = 2$

The calculations are necessarily somewhat intricate, and it must suffice here to mention a few of the more interesting results, which will indicate how the gaps in the previous investigations have been filled.

To understand the nature of the *free* oscillations, it is best to begin with the case of no rotation ($\omega = 0$) As ω is increased, the pairs of numerically equal, but oppositely-signed, values of σ which were obtained in Art 198 begin to diverge in absolute value, that being the greater which has the same sign with ω The character of the fundamental modes is also gradually altered These oscillations are distinguished as ‘of the First Class’

At the same time certain steady motions which are possible, without change of level, when there is no rotation, are converted into long-period oscillations with change of level, the speeds being initially comparable with ω The corresponding modes are designated as ‘of the Second Class’*; cf. Art. 205

The following table gives the speeds of those modes of the First Class which are of most importance in relation to the diurnal and semi-diurnal tides, respectively, and the corresponding periods, in sidereal time. The last column repeats the corresponding periods in the case of no rotation, as calculated from the formula (15) of Art. 199

Depth (feet)	Second Species [$s = 1$]		Third Species [$s = 2$]		Period when $\omega = 0$ h m
	$\frac{\sigma}{\omega}$	Period h m	$\frac{\sigma}{\omega}$	Period h m	
7260	1 6337	14 41	1 3347	17 59	} 32 49
	-0 9834	24 24	-0 6221	38 34	
14520	1 8677	12 51	1 6133	14 52	} 23 12
	-1 2450	19 16	-0 8922	26 54	
29040	2 1641	11 5	1 9968	12 1	} 16 25
	-1 6170	14 50	-1 2855	18 40	
58080	2 6288	9 8	2 5535	9 24	} 11 35
	-2 1611	11 6	-1 8575	12 55	

* These two classes of oscillations have been already encountered in the plane problem of Art 211

The quickest oscillation of the Second Class has in each case a period of over a day, and the periods of the remainder are very much longer

As regards the *forced* oscillations of the 'Second Species,' Laplace's conclusion that when $\sigma = \omega$, exactly, the diurnal tide vanishes in the case of uniform depth, still holds. The computation for the most important lunar diurnal tide, for which $\sigma/\omega = 92700$, shews that with such depths as we have considered the tides are small compared with the equilibrium heights, and are in the main inverted

Of the forced oscillations of the 'Third Species,' we may note first the case of the solar semi-diurnal tide, for which $\sigma = 2\omega$ with sufficient accuracy. For the four depths given in our tables, the ratio of the dynamical tide-height to the conventional equilibrium tide-height at the equator is found to be

$$+ 7\ 9548, \quad - 1\ 5016, \quad - 234\ 87, \quad + 2\ 1389,$$

respectively

"The very large coefficients which appear when $hg/4\omega^2a^2 = \frac{1}{10}$ indicate that for this depth there is a period of free oscillation of semi-diurnal type whose period differs but slightly from half-a-day. On reference to the tables it will be seen that we have, in fact, evaluated this period as 12 hours 1 minute, while for the case $hg/4\omega^2a^2 = \frac{1}{40}$ we have found a period of 12 hours 5 minutes*. We see then that though, when the period of forced oscillation differs from that of one of the types of free oscillation by as little as one minute, the forced tide may be nearly 250 times as great as the corresponding equilibrium tide, a difference of 5 minutes between these periods will be sufficient to reduce the tide to less than ten times the corresponding equilibrium tide. It seems then that the tides will not tend to become excessively large unless there is very close agreement with the period of one of the free oscillations

"The critical depths for which the forced tides here treated of become infinite are those for which a period of free oscillation coincides exactly with 12 hours. They may be ascertained by putting $[\sigma = 2\omega]$ in the period-equation for the free oscillations and treating this equation as an equation for the determination of h . The two largest roots are , and the corresponding critical depths are about 29,182 feet and 7375 feet ..

"It will be seen that in three cases out of the four here considered the effect of the mutual gravitation of the waters is to increase the ratio of the tide to the equilibrium tide [cf Art 220]. In two of the cases the sign is also reversed. This of course results from the fact that when $[\rho/\rho_1 = 0.18093]$ one of the periods of free oscillation is rather greater than 12 hours, when $[\rho/\rho_1 = 0]$ the corresponding period will be less than 12 hours†."

* [Belonging to a mode which comes next in sequence to the one having a period of 17h. 59m.]

† Hough, *Phil. Trans.*, A. t. cxci. pp 178, 179.

Hough has also computed the lunar semi-diurnal tides for which

$$\frac{\sigma}{2\omega} = 0.96350$$

For the four depths aforesaid the ratios of the equatorial tide-heights to their equilibrium values are found to be

$$-2.4187, \quad -1.8000, \quad +11.0725, \quad +1.9225,$$

respectively

"On comparison of these numbers with those obtained for the solar tides, we see that for a depth of 7260 feet the solar tides will be direct while the lunar tides will be inverted, the opposite being the case when the depth is 29,040 feet. This is of course due to the fact that in each of these cases there is a period of free oscillation intermediate between twelve solar (or, more strictly, sidereal) hours and twelve lunar hours. The critical depths for which the lunar tides become infinite are found to be 26,044 feet and 6448 feet

"Consequently this phenomenon will occur if the depth of the ocean be between 29,182 feet and 26,044 feet, or between 7375 feet and 6448 feet. An important consequence would be that for depths lying between these limits the usual phenomena of spring and neap tides would be reversed, the higher tides occurring when the moon is in quadrature, and the lower at new and full moon*"

223 It is not easy to estimate, in any but the most general way, the extent to which the foregoing conclusions of the dynamical theory would have to be modified if account could be taken of the actual configuration of the ocean, with its irregular boundaries and irregular variation of depth†. One or two points may however be noticed

In the first place, the formulae (17) of Art. 205 would lead us to expect for any given tide a phase-difference, variable from place to place, between the tide-height and the disturbing force. Thus, in the case of the lunar semi-diurnal tides, for example, high-water or low-water need not synchronize with the transit of the moon or 'anti-moon'‡ across the meridian. More precisely, in the case of a disturbing force of given type for which the equilibrium tide-height at a particular place would be

$$\bar{\xi} = \alpha \cos \sigma t, \quad \dots \dots \dots (1)$$

the dynamical tide-height will be

$$\xi = A \cos (\sigma t - \epsilon), \quad \dots \dots \dots (2)$$

where the ratio A/α , and the phase-difference ϵ , will be functions of the speed σ .

* Hough, *l.c.*, where reference is made to Lord Kelvin's *Popular Lectures and Addresses*, London, 1894, t. II p. 22 (1868)

† As to the general mathematical problem reference may be made to Poincaré, "Sur l'équilibre et les mouvements des mers," *Liouville* (5), t. II pp. 57, 217 (1896)

‡ This term is explained in the Appendix to this Chapter (p. 340)

Again, consider the superposition of two oscillations of the same type but of slightly different speeds, *eg* the lunar and solar semi-diurnal tides. If the origin of t be taken at a syzygy, we have

$$\zeta = \alpha \cos \sigma t + \alpha' \cos \sigma' t, \quad \dots \dots \dots (3)$$

and
$$\zeta = A \cos (\sigma t - \epsilon) + A' \cos (\sigma' t - \epsilon') \quad \dots \dots \dots (4)$$

This may be written

$$\zeta = (A + A' \cos \phi) \cos (\sigma t - \epsilon) + A' \sin \phi \sin (\sigma t - \epsilon), \quad \dots \dots (5)$$

where
$$\phi = (\sigma - \sigma') t - \epsilon + \epsilon'. \quad \dots \dots \dots (6)$$

If the first term in the second member of (4) represents the lunar, and the second the solar tide, we shall have $\sigma < \sigma'$, and $A > A'$. If we write

$$A + A' \cos \phi = C \cos \alpha, \quad A' \sin \phi = C \sin \alpha, \quad \dots \dots (7)$$

we get
$$\zeta = C \cos (\sigma t - \epsilon - \alpha), \quad \dots \dots \dots (8)$$

where
$$C = (A^2 + 2AA' \cos \phi + A'^2)^{\frac{1}{2}}, \quad \alpha = \tan^{-1} \frac{A' \sin \phi}{A + A' \cos \phi}. \quad \dots (9)$$

This may be described as a simple-harmonic vibration of slowly varying amplitude and phase. The amplitude ranges between the limits $A \pm A'$, whilst α may be supposed to lie always between $\pm \frac{1}{2}\pi$. The 'speed' must also be regarded as variable, *viz.* we find

$$\sigma - \frac{d\alpha}{dt} = \frac{\sigma A^2 + (\sigma + \sigma') AA' \cos \phi + \sigma' A'^2}{A^2 + 2AA' \cos \phi + A'^2} \quad \dots \dots (10)$$

This ranges between*

$$\frac{A\sigma + A'\sigma'}{A + A'} \quad \text{and} \quad \frac{A\sigma - A'\sigma'}{A - A'} \quad \dots \dots \dots (11)$$

The above is the well-known explanation of the phenomena of the spring- and neap-tides†, but we are now concerned further with the question of phase. On the equilibrium theory, the maxima of the amplitude C would occur whenever

$$(\sigma' - \sigma) t = 2n\pi,$$

where n is integral. On the dynamical theory the corresponding times of maximum are given by

$$(\sigma' - \sigma) t - (\epsilon' - \epsilon) = 2n\pi,$$

i.e. the dynamical maxima follow the statical by an interval‡

$$(\epsilon' - \epsilon)/(\sigma' - \sigma).$$

If the difference between σ' and σ were infinitesimal, this would be equal to $d\epsilon/d\sigma$

* Helmholtz, *Lehre von den Tonempfindungen* (2^e Aufl.), Braunschweig, 1870, p. 622.

† Cf. Thomson and Tait, *Natural Philosophy*, Art 60.

‡ This interval may of course be negative

The fact that the time of high-water, even at syzygy, may follow or precede the transit of the moon or anti-moon by an interval of several hours is well known*. The interval, when reckoned as a retardation, is, moreover, usually greater for the solar than for the lunar semi-diurnal tide, with the result that the spring-tides are in many places highest a day or two after the corresponding syzygy. The latter circumstance has been usually ascribed to the operation of Tidal Friction (for which see Chap XI), but it is evident that the phase-differences which are incidental to a complete dynamical theory, even in the absence of friction, cannot be ignored in this connection. There is reason to believe that they are, indeed, far more important than those due to friction.

Lastly, it was shewn in Arts 205, 216, that the long-period tides may deviate very considerably from the values given by the equilibrium theory, owing to the possibility of certain *steady* motions in the absence of disturbance. It has been pointed out by Lord Rayleigh† that these steady motions may be impossible in certain cases where the ocean is limited by perpendicular barriers. Referring to Art. 213 (6), it appears that if the depth h be constant, ζ must (in the steady motion) be a function of the co-latitude θ only, and therefore by (4) of the same Art, the eastward velocity must be a function of the latitude. This is inconsistent with the existence of a perpendicular barrier extending along a meridian. The objection would not apply to the case of a sea shelving gradually from the central parts to the edge.

224 We may complete the investigation of Art 199 by a brief notice of the question of the stability of the ocean, in the case of rotation.

It has been shewn in Art. 204 that the condition of secular stability is that $V - T_0$ should be a minimum in the equilibrium configuration. If we neglect the mutual attraction of the elevated water, the application to the present problem is very simple. The excess of the quantity $V - T_0$ over its undisturbed value is evidently

$$\iiint \left\{ \int_0^{\zeta} (\Psi - \tfrac{1}{2} \omega^2 \varpi^2) dz \right\} \delta S, \quad \dots \dots \dots (1)$$

where Ψ denotes the potential of the earth's attraction, δS is an element of the oceanic surface, and the rest of the notation is as before. Since $\Psi - \tfrac{1}{2} \omega^2 \varpi^2$ is constant over the undisturbed level ($z = 0$), its value at a small altitude z may be taken to be $gz + \text{const}$, where, as in Art 212,

$$g = \left[\frac{\partial}{\partial z} (\Psi - \tfrac{1}{2} \omega^2 \varpi^2) \right]_{z=0} \dots \dots \dots (2)$$

* The values of the retardations (which we have denoted by ϵ) for the various tidal components, at a number of ports, are given by Baird and Darwin, "Results of the Harmonic Analysis of Tidal Observations," *Proc R S*, t xxxix p 135 (1885), and Darwin, "Second Series of Results," *Proc R S*, t xlv p 556 (1889).

† "Note on the Theory of the Fortnightly Tide," *Phil Mag* (6), t v. p 136 (1903)

Since $\iint \xi dS = 0$, on account of the constancy of volume, we find from (1) that the increment of $V - T_0$ is

$$\frac{1}{2} \iint g \xi^2 dS \quad \dots \dots \dots (3)$$

This is essentially positive, and the equilibrium is therefore secularly stable*.

It is to be noticed that this proof does not involve any restriction as to the depth of the fluid, or as to smallness of the ellipticity, or even as to symmetry of the undisturbed surface with respect to the axis of rotation

If we wish to take into account the mutual attraction of the water, the problem can only be solved without difficulty when the undisturbed surface is nearly spherical, and we neglect the variation of g . The question (as to secular stability) is then exactly the same as in the case of no rotation. The calculation for this case will find an appropriate place in the next chapter. The result, as we might anticipate from Art 199, is that the necessary and sufficient condition of stability of the ocean is that its density should be less than the mean density of the earth*.

225 This is perhaps the most suitable occasion for a few additional remarks on the general question of stability of dynamical systems. We have in the main followed the ordinary usage which pronounces a state of equilibrium, or of steady motion, to be stable or unstable according to the character of the solution of the approximate equations of disturbed motion. If the solution consist of series of terms of the type $Ce^{\pm \lambda t}$, where all the values of λ are pure imaginary (*i.e.* of the form $i\sigma$), the undisturbed state is usually reckoned as stable, whilst if any of the λ 's are real, it is accounted unstable. In the case of disturbed *equilibrium*, this leads algebraically to the usual criterion of a minimum value of V as a necessary and sufficient condition of stability.

It has in recent times been questioned whether this conclusion is, from a practical point of view, altogether warranted. It is pointed out that since Lagrange's equations become less and less accurate as the deviation from the equilibrium configuration increases, it is a matter for examination how far rigorous conclusions as to the ultimate extent of the deviation can be drawn from them†.

The argument of Dirichlet, which establishes that the occurrence of a minimum value of V is a *sufficient* condition of stability, in any practical sense, has already been referred to. No such simple proof is available to shew without qualification that this condition is *necessary*. If, however, we recognize the existence of dissipative forces, which are called into play by any motion whatever of the system, the conclusion can be drawn as in Art 204.

* Cf Laplace, *Mécanique Céleste*, Livre 4^me, Arts 13, 14.

† See papers by Liapounoff and Hadamard, *Liouville* (5), t. III (1897).

A little consideration will shew that a good deal of the obscurity which attaches to the question arises from the want of a sufficiently precise mathematical definition of what is meant by 'stability.' The difficulty is encountered in an aggravated form when we pass to the question of stability of motion. The various definitions which have been propounded by different writers are examined critically by Klein and Sommerfeld in their book on the theory of the top*. Rejecting previous definitions, they base their criterion on the character of the changes produced in the *path* of the system by small arbitrary disturbing impulses. If the undisturbed path be the *limiting form* of the disturbed path when the impulses are indefinitely diminished, it is said to be stable, but not otherwise. For instance, the vertical fall of a particle under gravity is reckoned as stable, although for a *given* impulsive disturbance, however small, the deviation of the particle's position at any time t from the position which it occupied in the original motion increases indefinitely with t . Even this criterion, as the writers referred to themselves recognize, is not free from ambiguity unless the phrase 'limiting form,' as applied to a path, be strictly defined. It appears moreover that a definition which is analytically precise may not in all cases be easy to reconcile with geometrical prepossessions†

The foregoing considerations have reference, of course, to the question of 'ordinary' stability. The more important theory of 'secular' stability (Art 204) is not affected. We shall meet with the criterion for this, under a somewhat modified form, at a later stage in our subject‡

* *Ueber die Theorie des Kreisels*, Leipzig, 1897, p. 342.

† Some good illustrations are furnished by Particle Dynamics. Thus a particle moving in a circle about a centre of force varying inversely as the cube of the distance will if slightly disturbed either fall into the centre, or recede to infinity, after describing in either case a spiral with an infinite number of convolutions. Each of these spirals has, analytically, the circle as its 'limiting form,' although the motion in the latter is most naturally described as unstable. Cf. Korteweg, *Wiener Ber.*, May 20, 1886.

A narrower definition has been given by Love, and applied by Bromwich to several dynamical and hydrodynamical problems, see *Proc Lond Math Soc*, t xxxiii p. 325 (1901).


‡ This summary is taken substantially from the Art "Dynamics, Analytical," in *Encyc. Brit.*, t xxvii (1902).

APPENDIX

TO CHAPTER VIII

ON TIDE-GENERATING FORCES.

a. If, in the annexed figure, O and C be the centres of the earth and of the disturbing body (say the moon), the potential of the moon's attraction at a point P near the earth's surface will be $-\gamma M/CP$, where M denotes the moon's mass, and γ the gravitation-



constant. If we put $OC=D$, $OP=r$, and denote the moon's (geocentric) zenith-distance at P , viz the angle POC , by θ , this potential is equal to

$$-\frac{\gamma M}{(D^2 - 2rD \cos \theta + r^2)^{\frac{1}{2}}}$$

We require, however, not the absolute accelerative effect at P , but the acceleration relative to the earth. Now the moon produces in the whole mass of the earth an acceleration $\gamma M/D^2$ * parallel to OC , and the potential of a uniform field of force of this intensity is evidently

$$-\frac{\gamma M}{D^2} r \cos \theta$$

Subtracting this from the former result we get, for the potential of the relative attraction at P ,

$$\Omega = -\frac{\gamma M}{(D^2 - 2rD \cos \theta + r^2)^{\frac{1}{2}}} + \frac{\gamma M}{D^2} r \cos \theta. \quad \dots \quad (1)$$

This function Ω is identical with the 'disturbing-function' of planetary theory

Expanding in powers of r/D , which is in our case a small quantity, and retaining only the most important term, we find

$$\Omega = \frac{1}{2} \frac{\gamma M r^2}{D^3} (1 - \cos^2 \theta) \quad \dots \quad (2)$$

Considered as a function of the position of P , this is a zonal harmonic of the second degree, with OC as axis

* The effect of this is to produce a monthly inequality in the motion of the earth's centre about the sun. The amplitude of the inequality in radius vector is about 3000 miles, that of the inequality in longitude is about 7"; see Laplace, *Mécanique Céleste*, Livre 6^{me}, Art 30, and Livre 13^{me}, Art 10

The reader will easily verify that, to the order of approximation adopted, Ω is equal to the joint potential of two masses, each equal to $\frac{1}{2}M$, placed, one at C , and the other at a point C' in CO produced such that $OC' = OC^*$.

b. In the 'equilibrium-theory' of the tides it is assumed that the free surface takes at each instant the equilibrium-form which might be maintained if the disturbing body were to retain unchanged its actual position relative to the rotating earth. In other words, the free surface is assumed to be a level-surface under the combined action of gravity, of centrifugal force, and of the disturbing force. The equation to this level-surface is

$$\Psi - \frac{1}{2}\omega^2\varpi^2 + \Omega = \text{const}, \quad (3)$$

where ω is the angular velocity of the rotation, ϖ denotes the distance of any point from the earth's axis, and Ψ is the potential of the earth's attraction. If we use square brackets [] to distinguish the values of the enclosed quantities at the undisturbed level, and denote by $\bar{\zeta}$ the elevation of the water above this level due to the disturbing potential Ω , the above equation is equivalent to

$$[\Psi - \frac{1}{2}\omega^2\varpi^2] + \left[\frac{\partial}{\partial z} (\Psi - \frac{1}{2}\omega^2\varpi^2) \right] \bar{\zeta} + \Omega = \text{const}, \quad (4)$$

approximately, where $\partial/\partial z$ is used to indicate a space-differentiation along the normal outwards. The first term is of course constant, and we therefore have

$$\bar{\zeta} = -\frac{\Omega}{g} + C, \quad (5)$$

where, as in Art 212,

$$g = \left[\frac{\partial}{\partial z} (\Psi - \frac{1}{2}\omega^2\varpi^2) \right]. \quad (6)$$

Evidently, g denotes the value of 'apparent gravity', it will of course vary more or less with the position of P on the earth's surface.

It is usual, however, in the theory of the tides, to ignore the slight variations in the value of g , and the effect of the ellipticity of the undisturbed level on the surface-value of Ω . Putting, then, $r = a$, $g = \gamma E/a^2$, where E denotes the earth's mass, and a the mean radius of the surface, we have, from (2) and (5),

$$\bar{\zeta} = H(\cos^2 \vartheta - \frac{1}{3}) + C, \quad (7)$$

where

$$H = \frac{3}{2} \frac{M}{E} \left(\frac{a}{D} \right)^3 a, \quad (8)$$

as in Art 179. Hence the equilibrium-form of the free surface is a harmonic spheroid of the second order, of the zonal type, having its axis passing through the disturbing body.

c. Owing to the diurnal rotation, and also to the orbital motion of the disturbing body, the position of the tidal spheroid relative to the earth is continually changing, so that the level of the water at any particular place will continually rise and fall. To analyse the character of these changes, let θ be the co-latitude, and ϕ the longitude, measured eastward from some fixed meridian, of any place P , and let Δ be the north-polar-distance, and α the hour-angle west of the same meridian, of the disturbing body. We have, then,

$$\cos \vartheta = \cos \Delta \cos \theta + \sin \Delta \sin \theta \cos(\alpha + \phi), \quad (9)$$

* Thomson and Tait, Art 804. These two fictitious bodies are designated as 'moon' and 'anti-moon,' respectively.

and thence, by (7),

$$\begin{aligned}\zeta = & \frac{3}{2}H(\cos^2 \Delta - \frac{1}{3})(\cos^2 \theta - \frac{1}{3}) \\ & + \frac{1}{2}H \sin 2\Delta \sin 2\theta \cos(a + \phi) \\ & + \frac{1}{2}H \sin^2 \Delta \sin^2 \theta \cos 2(a + \phi) + C \quad \dots \quad (10)\end{aligned}$$

Each of these terms may be regarded as representing a partial tide, and the results superposed.

Thus, the *first* term is a zonal harmonic of the second order, and gives a tidal spheroid symmetrical with respect to the earth's axis, having as nodal lines the parallels for which $\cos^2 \theta = \frac{1}{3}$, or $\theta = 90^\circ \pm 35^\circ 16'$. The amount of the tidal elevation in any particular latitude varies as $\cos^2 \Delta - \frac{1}{3}$. In the case of the moon the chief fluctuation in this quantity has a period of about a fortnight, we have here the origin of the 'lunar fortnightly' or 'declinational' tide. When the sun is the disturbing body, we have a 'solar semi-annual' tide. It is to be noticed that the mean value of $\cos^2 \Delta - \frac{1}{3}$ with respect to the time is not zero, so that the inclination of the orbit of the disturbing body to the equator involves as a consequence a permanent change of mean level. Cf. Art. 182.

The *second* term in (10) is a spherical harmonic of the type obtained by putting $n=2$, $s=1$ in Art. 86 (7). The corresponding tidal spheroid has as nodal lines the meridian which is distant 90° from that of the disturbing body, and the equator. The disturbance of level is greatest in the meridian of the disturbing body, at distances of 45° N and S of the equator. The oscillation at any one place goes through its period with the hour-angle a , i.e. in a lunar or solar day. The amplitude is, however, not constant, but varies slowly with Δ , changing sign when the disturbing body crosses the equator. This term accounts for the lunar and solar 'diurnal' tides.

The *third* term is a sectorial harmonic ($n=2$, $s=2$), and gives a tidal spheroid having as nodal lines the meridians which are distant 45° E and W from that of the disturbing body. The oscillation at any place goes through its period with $2a$, i.e. in half a (lunar or solar) day, and the amplitude varies as $\sin^2 \Delta$, being greatest when the disturbing body is on the equator. We have here the origin of the lunar and solar 'semi-diurnal' tides.

The 'constant' C is to be determined by the consideration that, on account of the invariability of volume, we must have

$$\iint \zeta dS = 0, \quad \dots \quad (11)$$

where the integration extends over the surface of the ocean. If the ocean cover the whole earth we have $C=0$, by the general property of spherical surface-harmonics quoted in Art. 87. It appears from (7) that the greatest elevation above the undisturbed level is then at the points $\vartheta=0$, $\vartheta=180^\circ$, i.e. at the points where the disturbing body is in the zenith or nadir, and the amount of this elevation is $\frac{3}{2}H$. The greatest depression is at places where $\vartheta=90^\circ$, i.e. the disturbing body is on the horizon, and is $\frac{1}{2}H$. The greatest possible range is therefore equal to H .

In the case of a limited ocean, C does not vanish, but has at each instant a definite value depending on the position of the disturbing body relative to the earth. This value may be easily written down from equations (10) and (11), it is a sum of spherical harmonic functions of Δ , a , of the second order, with constant coefficients in the form of surface-integrals whose values depend on the distribution of land and water over the globe. The changes in the value of C , due to relative motion of the disturbing body, give a *general* rise and fall of the free surface, with (in the case of the moon) fortnightly, diurnal, and semi-diurnal periods. This 'correction to the equilibrium-theory' as usually

presented, was first fully investigated by Thomson and Tait* The necessity for a correction of the kind, in the case of a limited sea, had however been recognized by D Bernoulli†

d. We have up to this point neglected the mutual attraction of the particles of the water To take this into account, we must add to the disturbing potential Ω the gravitation-potential of the elevated water In the case of an ocean covering the earth, the correction can be easily applied, as in Art 199 If we put $n=2$ in the formulæ of that Art, the addition to the value of Ω is $-\frac{2}{3}\rho/\rho_0 g\bar{\zeta}$, and we thence find without difficulty

$$\bar{\zeta} = \frac{H}{1 - \frac{2}{3}\rho/\rho_0} (\cos^2 \theta - \frac{1}{3}) \quad \dots \quad (12)$$

It appears that all the tides are *increased*, in the ratio $(1 - \frac{2}{3}\rho/\rho_0)^{-1}$ If we assume $\rho/\rho_0 = 18$, this ratio is 1.12

e. So much for the equilibrium-theory For the purposes of the kinetic theory of Arts 212—223, it is necessary to suppose the value (10) of $\bar{\zeta}$ to be expanded in a series of simple-harmonic functions of the time The actual expansion, taking account of the variations of Δ and a , and of the distance D of the disturbing body, (which enters into the value of H), is a somewhat complicated problem of Physical Astronomy, into which we do not enter‡.

Disregarding the constant C , which disappears in the dynamical equations (1) of Art 214, the constancy of volume being now secured by the equation of continuity (2), it is easily seen that the terms in question will be of three distinct types

First, we have the tides of long period, for which

$$\bar{\zeta} = H' (\cos^2 \theta - \frac{1}{3}) \cos(\sigma t + \epsilon) \quad \dots \quad (13)$$

The most important tides of this class are the ‘lunar fortnightly’ for which, in degrees per mean solar hour, $\sigma = 1^\circ 098$, and the ‘solar semi-annual’ for which $\sigma = 0^\circ 082$.

Secondly, we have the diurnal tides, for which

$$\bar{\zeta} = H'' \sin \theta \cos \theta \cos(\sigma t + \phi + \epsilon), \quad \dots \quad (14)$$

where σ differs but little from the angular velocity ω of the earth’s rotation. These include the ‘lunar diurnal’ ($\sigma = 13^\circ 943$), the ‘solar diurnal’ ($\sigma = 14^\circ 959$), and the ‘luni-solar diurnal’ ($\sigma = \omega = 15^\circ 041$)

* *Natural Philosophy*, Art 808, see also Prof G H Darwin, “On the Connection to the Equilibrium Theory of the Tides for the Continents,” *Proc Roy Soc*, April 1, 1886 It appears as the result of a numerical calculation by Prof H H Turner, appended to this paper, that with the actual distribution of land and water the correction is of little importance

† *Traité sur le Flux et Reflux de la Mer*, c xi (1740) This essay, as well as the one by Maclaurin cited on p 293, and another on the same subject by Euler, is reprinted in Le Seur and Jacquier’s edition of Newton’s *Principia*

‡ Reference may be made to Laplace, *Mécanique Céleste*, Livre 13^{me}, Art 2, to the investigations of Lord Kelvin and Prof G H Darwin in the *Brit Ass Reports* for 1868, 1872, 1876, 1883, 1885, and to the Arts on “Tides,” by the latter author, in the *Encyc Britann* (9th ed.), tt xxiii, xxxiii

Lastly, we have the semi-diurnal tides, for which

$$\bar{\zeta} = H''' \sin^2 \theta \cos(\sigma t + 2\phi + \epsilon), \quad (15)^*$$

where σ differs but little from 2ω . These include the 'lunar semi-diurnal' ($\sigma = 28^\circ 984$), the 'solar semi-diurnal' ($\sigma = 30^\circ$), and the 'luni-solar semi-diurnal' ($\sigma = 2\omega = 30^\circ 082$)

For a complete enumeration of the more important partial tides, and for the values of the coefficients H' , H'' , H''' in the several cases, we must refer to the papers by Lord Kelvin and Prof G H Darwin, already cited. In the Harmonic Analysis of Tidal Observations, which is the special object of these investigations, the only result of dynamical theory which is made use of is the general principle that the tidal elevation at any place must be equal to the sum of a series of simple-harmonic functions of the time, whose periods are the same as those of the several terms in the development of the disturbing potential, and are therefore known *à priori*. The amplitudes and phases of the various partial tides, for any particular port, are then determined by comparison with tidal observations extending over a sufficiently long period†. We thus obtain a practically complete expression which can be used for the systematic prediction of the tides at the port in question.

f. One point of special interest in the Harmonic Analysis is the determination of the long-period tides. It has been already stated that owing to the influence of dissipative forces these must tend to approximate more or less closely to their equilibrium values. Unfortunately, the only long-period tide, whose coefficient can be inferred with any certainty from the observations, is the lunar fortnightly, and it is at least doubtful whether the dissipative forces are sufficient to produce in this case any great effect in the direction indicated. Hence the observed fact that the fortnightly tide has less than its equilibrium value does not entitle us to make any inference as to elastic yielding of the solid body of the earth to the tidal distorting forces exerted by the moon‡.

* It is evident that over a small area, near the poles, which may be treated as sensibly plane, the formulae (14) and (15) make

$$\bar{\zeta} \propto r \cos(\sigma t + \phi + \epsilon), \quad \text{and} \quad \bar{\zeta} \propto r^2 \cos(\sigma t + 2\phi + \epsilon),$$

respectively, where r , ω are plane polar coordinates. These forms have been used by anticipation in Arts 190, 210.

† It is of interest to note, in connection with Art 185, that the tide-gauges, being situated in relatively shallow water, are sensibly affected by certain tides of the second order, which therefore have to be taken account of in the general scheme of Harmonic Analysis.

‡ Prof G H Darwin, *l.c. ante* p 316. See, however, the paper by Lord Rayleigh cited on p. 336 *ante*.

CHAPTER IX.

SURFACE WAVES

226 WE have now to investigate, as far as possible, the laws of wave-motion in liquids when the vertical acceleration is no longer neglected. The most important case not covered by the preceding theory is that of waves on relatively deep water, where, as will be seen, the agitation rapidly diminishes in amplitude as we pass downwards from the surface, but it will be understood that there is a continuous transition to the state of things investigated in the preceding chapter, where the horizontal motion of the fluid was sensibly the same from top to bottom.

We begin with the oscillations of a horizontal sheet of water, and we will confine ourselves in the first instance to cases where the motion is in two dimensions, of which one (x) is horizontal, and the other (y) vertical. The elevations and depressions of the free surface will then present the appearance of a series of parallel straight ridges and furrows, perpendicular to the plane xy .

The motion, being assumed to have been generated originally from rest by the action of ordinary forces, will necessarily be irrotational, and the velocity-potential ϕ will satisfy the equation

$$\frac{\partial^2 \phi}{\partial x^2} + \frac{\partial^2 \phi}{\partial y^2} = 0, \quad \dots \dots \dots (1)$$

with the condition
$$\frac{\partial \phi}{\partial n} = 0 \quad \dots \dots \dots (2)$$

at a fixed boundary

To find the condition which must be satisfied at the free surface ($p = \text{const}$), let the origin O be taken at the undisturbed level, and let Oy be drawn vertically upwards. The motion being assumed to be infinitely small, we find, putting $\Omega = gy$ in the formula (4) of Art. 20, and neglecting the square of the velocity (q),

$$\frac{p}{\rho} = \frac{\partial \phi}{\partial t} - gy + F(t) \quad \dots \dots \dots (3)$$

Hence if η denote the elevation of the surface at time t above the point $(x, 0)$, we shall have, since the pressure there is uniform,

$$\eta = \frac{1}{g} \left[\frac{\partial \phi}{\partial t} \right]_{y=\eta}, \quad \dots \dots \dots (4)$$

provided the function $F(t)$, and the additive constant, be supposed merged in the value of $\partial \phi / \partial t$. Subject to an error of the order already neglected, this may be written

$$\eta = \frac{1}{g} \left[\frac{\partial \phi}{\partial t} \right]_{y=0} \dots \dots \dots (5)$$

Since the normal to the free surface makes an infinitely small angle $(\partial \eta / \partial x)$ with the vertical, the condition that the normal component of the fluid velocity at the free surface must be equal to the normal velocity of the surface itself gives, with sufficient approximation,

$$\frac{\partial \eta}{\partial t} = - \left[\frac{\partial \phi}{\partial y} \right]_{y=0} \dots \dots \dots (6)$$

This is in fact what the general surface condition (Art 10 (3)) becomes, if we put $F(x, y, z, t) \equiv y - \eta$, and neglect small quantities of the second order

Eliminating η between (5) and (6), we obtain the condition

$$\frac{\partial^2 \phi}{\partial t^2} + g \frac{\partial \phi}{\partial y} = 0, \quad \dots \dots \dots (7)$$

to be satisfied when $y = 0$

In the case of simple-harmonic motion, the time-factor being $e^{i(\sigma t + \epsilon)}$, this condition becomes

$$\sigma^2 \phi = g \frac{\partial \phi}{\partial y} \dots \dots \dots (8)$$

227 Let us apply this to the free oscillations of a sheet of water, or a straight canal, of uniform depth h , and let us suppose for the present that there are no limits to the fluid in the direction of x , the fixed boundaries, if any, being vertical planes parallel to xy

Since the conditions are uniform in respect to x , the simplest supposition we can make is that ϕ is a simple-harmonic function of x , the most general case consistent with the above assumptions can be derived from this by superposition, in virtue of Fourier's Theorem

We assume then

$$\phi = P \cos kx \ e^{i(\sigma t + \epsilon)}, \quad \dots \dots \dots (1)$$

where P is a function of y only. The equation (1) of Art 226 gives

$$\frac{d^2 P}{dy^2} - k^2 P = 0, \quad \dots \dots \dots (2)$$

whence

$$P = A e^{ky} + B e^{-ky} \dots \dots \dots (3)$$

The condition of no vertical motion at the bottom is $\partial\phi/\partial y=0$ for $y=-h$, whence

$$Ae^{-kh}=Be^{kh}, =\frac{1}{2}C, \text{ say.}$$

This leads to $\phi = C \cosh k(y+h) \cos kx \cdot e^{i(\sigma t + \epsilon)}$ (4)

The value of σ is then determined by Art 226 (8), which gives

$$\sigma^2 = gk \tanh kh \quad \dots \dots \dots (5)$$

Substituting from (4) in Art. 226 (5), we find

$$\eta = \frac{i\sigma C}{g} \cosh kh \cos kx \cdot e^{i(\sigma t + \epsilon)}, \quad \dots \dots (6)$$

or, writing

$$a = -\frac{\sigma C}{g} \cosh kh,$$

and retaining only the real part of the expression,

$$\eta = a \cos kx \sin (\sigma t + \epsilon). \quad \dots \dots (7)$$

This represents a system of 'standing waves,' of wave-length $\lambda = 2\pi/k$, and vertical amplitude a . The relation between the period ($2\pi/\sigma$) and the wave-length is given by (5). Some numerical examples of this dependence are given on p. 350

In terms of a we have

$$\phi = -\frac{ga \cosh k(y+h)}{\sigma \cosh kh} \cos kx \cos (\sigma t + \epsilon), \quad \dots (8)$$

and it is easily seen from Art 62 that the corresponding value of the stream-function is

$$\psi = \frac{ga \sinh k(y+h)}{\sigma \cosh kh} \sin kx \cos (\sigma t + \epsilon) \quad \dots \dots \dots (9)$$

If \mathbf{x}, \mathbf{y} be the co-ordinates of a particle relative to its mean position (x, y), we have

$$\frac{d\mathbf{x}}{dt} = -\frac{\partial\phi}{\partial x}, \quad \frac{d\mathbf{y}}{dt} = -\frac{\partial\phi}{\partial y}, \quad \dots \dots \dots (10)$$

if we neglect the differences between the component velocities at the points (x, y) and ($x + \mathbf{x}, y + \mathbf{y}$), as being small quantities of the second order

Substituting from (8), and integrating with respect to t , we find

$$\left. \begin{aligned} \mathbf{x} &= -a \frac{\cosh k(y+h)}{\sinh kh} \sin kx \sin (\sigma t + \epsilon), \\ \mathbf{y} &= a \frac{\sinh k(y+h)}{\sinh kh} \cos kx \sin (\sigma t + \epsilon), \end{aligned} \right\} \dots \dots (11)$$

where a slight reduction has been effected by means of (5). The motion of each particle is rectilinear, and simple-harmonic, the direction of motion varying from vertical, beneath the crests and hollows ($kx = m\pi$), to horizontal,


beneath the nodes ($kx = (m + \frac{1}{2}) \pi$). As we pass downwards from the surface to the bottom the amplitude of the vertical motion diminishes from $a \cos kx$ to 0, whilst that of the horizontal motion diminishes in the ratio $\cosh kh$ 1.

When the wave-length is very small compared with the depth, kh is large, and therefore $\tanh kh = 1$ * The formulae (11) then reduce to

$$x = -ae^{ky} \sin kx \sin (\sigma t + \epsilon), \quad y = ae^{ky} \cos kx \sin (\sigma t + \epsilon), \dots \quad (12)$$

with
$$\sigma^2 = gk \quad \dots \dots \dots (13)$$

The motion now diminishes rapidly from the surface downwards, thus at a depth of a wave-length the diminution of amplitude is in the ratio $e^{-2\pi}$ or 1/535 The forms of the lines of (oscillatory) motion ($\psi = \text{const}$), for this case, are shewn in the annexed figure



In the above investigation the fluid is supposed to extend to infinity in the direction of x , and there is consequently no restriction to the value of k The formulae also, give, however, the longitudinal oscillations in a canal of finite length, provided k have the proper values If the fluid be bounded by the vertical planes $x = 0, x = l$ (say), the condition $\partial\phi/\partial x = 0$ is satisfied at both ends provided $\sin kl = 0$, or $kl = m\pi$, where $m = 1, 2, 3, \dots$ The wave-lengths of the normal modes are therefore given by the formula $\lambda = 2l/m$. Cf Art 177

228 The investigation of the preceding Art relates to the case of ‘standing’ waves, it naturally claimed the first place, as a straightforward application of the usual method of treating the free oscillations of a system about a state of equilibrium

In the case, however, of a sheet of water, or a canal, of uniform depth, extending horizontally to infinity in both directions, we can, by superposition of two systems of standing waves of the same wave-length, obtain a system of progressive waves which advance unchanged with constant velocity For this, it is necessary that the crests and troughs of one component system should coincide (horizontally) with the nodes of the other,

* This case may of course be more easily investigated independently

that the amplitudes of the two systems should be equal, and that their phases should differ by a quarter-period

$$\text{Thus if we put} \quad \eta = \eta_1 \pm \eta_2, \quad . \quad . \quad . \quad . \quad . \quad (1)$$

$$\text{where} \quad \eta_1 = a \sin kx \cos \sigma t, \quad \eta_2 = a \cos kx \sin \sigma t, \quad . \quad . \quad (2)$$

$$\text{we get} \quad \eta = a \sin (kx \pm \sigma t), \quad . \quad . \quad . \quad . \quad (3)$$

which represents an infinite train of waves travelling in the negative or positive direction of x , respectively, with the velocity c given by

$$c = \frac{\sigma}{k} = \left(\frac{g}{k} \tanh kh \right)^{\frac{1}{2}}, \quad . \quad . \quad . \quad . \quad (4)$$

where the value of σ has been substituted from Art 227 (5) In terms of the wave-length (λ) we have

$$c = \left(\frac{g\lambda}{2\pi} \tanh \frac{2\pi h}{\lambda} \right)^{\frac{1}{2}} \quad . \quad . \quad . \quad . \quad (5)$$

When the wave-length is anything less than double the depth, we have $\tanh kh = 1$, sensibly, and therefore *

$$c = \left(\frac{g}{k} \right)^{\frac{1}{2}} = \left(\frac{g\lambda}{2\pi} \right)^{\frac{1}{2}} \quad . \quad . \quad . \quad . \quad (6)$$

On the other hand when λ is moderately large compared with h we have $\tanh kh = kh$, nearly, so that the velocity is independent of the wave-length, being given by

$$c = (gh)^{\frac{1}{2}}, \quad . \quad . \quad . \quad . \quad (7)$$

as in Art 169 This result is here obtained on the assumption that the wave-profile is a curve of sines, but Fourier's theorem shews that the restriction is now to a great extent unnecessary

It appears, on tracing the curve $y = (\tanh x)/x$, or from the numerical table to be given presently, that for a given depth h the wave-velocity increases constantly with the wave-length, from zero to the asymptotic value (7)

Let us now fix our attention, for definiteness, on a train of simple-harmonic waves travelling in the positive direction, *i.e.* we take the lower sign in (1) and (3). It appears, on comparison with Art 227 (7), that the value of η_1 is deduced by putting $\epsilon = \frac{1}{2}\pi$, and subtracting $\frac{1}{2}\pi$ from the value of kx †, and that of η_2 by putting $\epsilon = 0$, simply. This proves a statement made above as to the relation between the component systems of standing waves, and also enables us to write down at once the proper modifications of the remaining formulae of the preceding Art

* Green, "Note on the Motion of Waves in Canals," *Camb Trans*, t. vii (1839) [*Math. Papers*, p 279].

† This is merely equivalent to a change of the origin from which x is measured.

Thus, we find, for the component displacements of a particle,

$$\left. \begin{aligned} x &= x_1 - x_2 = a \frac{\cosh k(y+h)}{\sinh kh} \cos(kx - \sigma t), \\ y &= y_1 - y_2 = a \frac{\sinh k(y+h)}{\sinh kh} \sin(kx - \sigma t) \end{aligned} \right\} \quad (8)$$

This shews that the motion of each particle is elliptic-harmonic, the period ($2\pi/\sigma$, $=\lambda/c$) being that in which the disturbance travels over a wave-length. The semi-axes, horizontal and vertical, of the elliptic orbits are

$$a \frac{\cosh k(y+h)}{\sinh kh} \quad \text{and} \quad a \frac{\sinh k(y+h)}{\sinh kh},$$

respectively. These both diminish from the surface to the bottom ($y=-h$), where the latter vanishes. The distance between the foci is the same for all the ellipses, being equal to $a \operatorname{cosech} kh$. It easily appears, on comparison of (8) with (3), that a surface-particle is moving in the direction of wave-propagation when it is at a crest, and in the opposite direction when it is in a trough*.

When the depth exceeds half a wave-length, e^{-kh} is very small, and the formulae (8) reduce to

$$x = ae^{ky} \cos(kx - \sigma t), \quad y = ae^{ky} \sin(kx - \sigma t), \quad \dots \dots \dots (9)$$

so that each particle describes a circle, with constant angular velocity σ , $= (2\pi g/\lambda)^{\frac{1}{2}}$ †. The radii of these circles are given by the formula ae^{ky} , and therefore diminish rapidly downwards.

In the first table on the next page, the second column gives the values of $\operatorname{sech} kh$ corresponding to various values of the ratio h/λ . This quantity measures the ratio of the horizontal motion at the bottom to that at the surface. The third column gives the ratio of the vertical to the horizontal diameter of the elliptic orbit of a surface particle. The fourth and fifth columns give the ratios of the wave-velocity to that of waves of the same length on water of infinite depth, and to that of 'long' waves on water of the actual depth, respectively.

The tables of *absolute* values of periods and wave-velocities, which are also given on p. 350, are abridged from Airy's treatise‡. The value of g adopted by him is 32.16 f.s.s.

The possibility of progressive waves advancing with unchanged form is limited, theoretically, to the case of uniform depth, but the numerical results shew that a variation in the depth will have no appreciable influence, provided the depth everywhere exceeds (say) half the wave-length.

* The results of Arts 227, 228, for the case of finite depth, were given, substantially, by Airy, "Tides and Waves," Arts 160 (1845).

† Green, *loc. ante* p. 348.

‡ "Tides and Waves," Arts 169, 170.

h/λ	$\operatorname{sech} kh$	$\tanh kh$	$c/(gk^{-1})^{\frac{1}{2}}$	$c/(gh)^{\frac{1}{2}}$
0.00	1.000	0.000	0.000	1.000
01	998	063	250	999
02	992	125	354	997
03	983	186	432	994
04	969	246	496	990
05	953	304	552	984
06	933	360	600	977
07	911	413	643	970
08	886	464	681	961
09	859	512	715	951
10	831	557	746	941
20	527	850	922	823
30	297	955	977	712
40	161	987	993	627
50	086	996	998	563
60	046	999	999	515
70	025	1.000	1.000	477
80	013	1.000	1.000	446
90	007	1.000	1.000	421
1.00	004	1.000	1.000	399
∞	000	1.000	1.000	000

Depth of water, in feet	Length of wave, in feet				
	1	10	100	1000	10,000
Period of wave, in seconds					
1	0.442	1.873	17.645	176.33	1763.3
10	0.442	1.398	5.923	55.80	557.62
100	0.442	1.398	4.420	18.73	176.45
1000	0.442	1.398	4.420	13.98	59.23
10,000	0.442	1.398	4.420	13.98	44.20

Depth of water, in feet	Length of wave, in feet					
	1	10	100	1000	10,000	∞
Wave-velocity, in feet per second						
1	2 262	5 339	5 667	5 671	5 671	5 671
10	2 262	7 154	16 88	17 92	17 93	17 93
100	2 262	7 154	22 62	53 39	56 67	56 71
1000	2 262	7 154	22 62	71 54	168 8	179 3
10,000	2 262	7 154	22 62	71 54	226 2	567 1

We remark, finally, that the theory of progressive waves may be obtained, without the intermediary of standing waves, by assuming at once, in place of Art. 227 (1),

$$\phi = Pe^{i(\sigma t - kx)} \quad . \quad . \quad . \quad . \quad (10)$$

whence

$$\left. \begin{aligned} \frac{\phi}{c} &= -x - (\alpha e^{-ky} - \beta e^{ky}) \sin kx, \\ \frac{\psi}{c} &= -y + (\alpha e^{-ky} + \beta e^{ky}) \cos kx \end{aligned} \right\} \quad \dots \dots (1)$$

This represents a motion which is periodic in respect to x , superposed on a uniform current of velocity c . We shall suppose that $k\alpha$ and $k\beta$ are small quantities, in other words, that the amplitude of the disturbance is small compared with the wave-length.

The profile of the free surface must be a stream-line, we will take it to be the line $\psi = 0$. Its form is then given by (1), viz to a first approximation we have

$$y = (\alpha + \beta) \cos kx, \quad \dots \dots (2)$$

showing that the origin is at the mean level of the surface. Again, at the bottom ($y = -h$) we must also have $\psi = \text{const}$, this requires

$$\alpha e^{kh} + \beta e^{-kh} = 0$$

The equations (1) may therefore be put in the forms

$$\left. \begin{aligned} \frac{\phi}{c} &= -x + C \cosh k(y+h) \sin kx, \\ \frac{\psi}{c} &= -y + C \sinh k(y+h) \cos kx \end{aligned} \right\} \quad \dots \dots (3)$$

The formula for the pressure is

$$\begin{aligned} \frac{p}{\rho} &= \text{const} - gy - \frac{1}{2} \left\{ \left(\frac{\partial \phi}{\partial x} \right)^2 + \left(\frac{\partial \phi}{\partial y} \right)^2 \right\} \\ &= \text{const} - gy - \frac{c^2}{2} \{ 1 - 2kC \cosh k(y+h) \cos kx \}, \end{aligned}$$

if we neglect $k^2 C^2$. Since the equation to the stream-line $\psi = 0$ is

$$y = C \sinh kh \cos kx, \quad \dots \dots (4)$$

approximately, we have, along this line,

$$\frac{p}{\rho} = \text{const} + (kc^2 \coth kh - g)y.$$

The condition for a free surface is therefore satisfied, provided

$$c^2 = gh \cdot \frac{\tanh kh}{kh} \quad \dots \dots (5)$$

This determines the wave-length ($2\pi/k$) of possible stationary undulations on a stream of given uniform depth h , and velocity c . It is easily seen that the value of kh is real or imaginary according as c is less or greater than $(gh)^{\frac{1}{2}}$.

If we impress on everything the velocity $-c$ parallel to x , we get progressive waves on still water, and (5) is then the formula for the wave-velocity, as in Art 228

When the ratio of the depth to the wave-length is sufficiently great, the formulae (1) become

$$\frac{\phi}{c} = -x + \beta e^{ky} \sin kx, \quad \frac{\psi}{c} = -y + \beta e^{ky} \cos kx, \quad . \quad . \quad (6)$$

leading to
$$\frac{p}{\rho} = \text{const.} - gy - \frac{c^2}{2} \{1 - 2k\beta e^{ky} \cos kx + k^2 \beta^2 e^{2ky}\} \quad . \quad . \quad (7)$$

If we neglect $k^2 \beta^2$, the latter equation may be written

$$\frac{p}{\rho} = \text{const.} + (kc^2 - g)y + kc\psi. \quad . \quad . \quad . \quad (8)$$

Hence if

$$c^2 = \frac{g}{k}, \quad . \quad . \quad . \quad . \quad . \quad . \quad (9)$$

the pressure will be uniform not only at the upper surface, but along *every* stream-line $\psi = \text{const.}$ * This point is of some importance, for it shews that the solution expressed by (6) and (9) can be extended to the case of any number of liquids of different densities, arranged one over the other in horizontal strata, provided the uppermost surface be free, and the total depth infinite. And, since there is no limitation to the thinness of the strata, we may even include the case of a heterogeneous liquid whose density varies continuously with the depth.

231 The method of the preceding Art can be readily adapted to a number of other problems

1° For example, to find the velocity of propagation of waves over the common horizontal boundary of two masses of fluid which are otherwise unlimited, we may assume

$$\frac{\psi}{c} = -y + \beta e^{ky} \cos kx, \quad \frac{\psi'}{c} = -y + \beta e^{-ky} \cos kx, \quad . \quad . \quad (1)$$

where the accent relates to the upper fluid. For these satisfy the condition of irrotational motion, $\nabla^2 \psi = 0$, and they give a uniform velocity c at a great distance above and below the common surface, at which we have $\psi = \psi' = 0$, say, and therefore $y = \beta \cos kx$, approximately

The pressure-equations are

$$\left. \begin{aligned} \frac{p}{\rho} &= \text{const.} - gy - \frac{c^2}{2} (1 - 2k\beta e^{ky} \cos kx), \\ \frac{p'}{\rho'} &= \text{const.} - gy - \frac{c^2}{2} (1 + 2k\beta e^{-ky} \cos kx), \end{aligned} \right\} \quad . \quad . \quad . \quad (2)$$

* This conclusion, it must be noted, is limited to the case of infinite depth. It was first remarked by Poisson, *l.c. post p. 364*

which give, at the common surface,

$$\left. \begin{aligned} \frac{p}{\rho} &= \text{const} - (g - kc^2)y, \\ \frac{p'}{\rho'} &= \text{const} - (g + kc^2)y, \end{aligned} \right\} \dots \dots (3)$$

the usual approximations being made. The condition $p = p'$ thus leads to

$$c^2 = \frac{g}{k} \frac{\rho - \rho'}{\rho + \rho'}, \quad \dots \dots (4)$$

a result first obtained by Stokes

The presence of the upper fluid has therefore the effect of diminishing the velocity of propagation of waves of any given length in the ratio $\{(1-s)/(1+s)\}^{\frac{1}{2}}$, where s is the ratio of the density of the upper to that of the lower fluid. This diminution has a two-fold cause, the potential energy of a given deformation of the common surface is diminished in the ratio $1-s$, whilst the inertia is increased in the ratio $1+s$ *. As a numerical example, in the case of water over mercury ($s^{-1} = 13.6$) the wave-velocity is diminished in the ratio .929

It is to be noticed, in this and in other problems of the kind, that there is a discontinuity of motion at the common surface. The normal velocity ($\partial\psi/\partial x$) is of course continuous, but the tangential velocity ($-\partial\psi/\partial y$) changes from $c(1 - k\beta \cos kx)$ to $c(1 + k'\beta \cos kx)$ as we cross the surface, in other words we have (Art 151) a *vortex-sheet* of strength $-2k\beta \cos kx$. This is an extreme illustration of the remark, made in Art 17, that the free oscillations of a liquid of variable density are not necessarily irrotational.

If $\rho < \rho'$, the value of c is imaginary. The undisturbed equilibrium-arrangement is then unstable.

2° The case where the two fluids are confined between rigid horizontal planes $y = -h$, $y = h'$, is almost equally simple. We have, in place of (1),

$$\frac{\psi}{c} = -y + \beta \frac{\sinh k(y+h)}{\sinh kh} \cos kx, \quad \frac{\psi'}{c} = -y - \beta' \frac{\sinh k(y-h')}{\sinh kh'} \cos kx, \quad \dots (5)$$

leading to
$$c^2 = \frac{g}{k} \frac{\rho - \rho'}{\rho \coth kh + \rho' \coth kh'} \quad \dots \dots (6)$$

* This explains why the natural periods of oscillation of the common surface of two liquids of very nearly equal density are very long compared with those of a free surface of similar extent. The fact was noticed by Benjamin Franklin in the case of oil over water, see a letter dated 1762 (*Complete Works*, London, n d, t ii. p 142).

Again, near the mouths of some of the Norwegian fiords there is a layer of fresh over salt water. Owing to the comparatively small potential energy involved in a given deformation of the common boundary, waves of considerable height in this boundary are easily produced. To this cause is ascribed the abnormal resistance occasionally experienced by ships in those waters. See Ekman, "On Dead-Water," *Scientific Results of the Norwegian North Polar Expedition*, pt xv, Christiania, 1904.

When kh and kh' are both very great, this reduces to the form (2). When kh' is large, and kh small, we have

$$c^2 = \left(1 - \frac{\rho'}{\rho}\right) gh, \quad \dots \dots \dots (7)$$

the main effect of the presence of the upper fluid being now the change in the potential energy of a given deformation

3° When the upper surface of the upper fluid is *free*, we may assume

$$\left. \begin{aligned} \frac{\psi}{c} &= -y + \beta \frac{\sinh k(y+h)}{\sinh kh} \cos kx, \\ \frac{\psi'}{c'} &= -y + (\beta \cosh ky + \gamma \sinh ky) \cos kx, \end{aligned} \right\} \dots \dots (8)$$

and the conditions to be satisfied at the common boundary, and at the free surface, then lead to the equation

$$c^4 (\rho \coth kh \coth kh' + \rho') - c^2 \rho (\coth kh' + \coth kh) \frac{g}{k} + (\rho - \rho') \frac{g^2}{k^2} = 0 \quad \dots (9)$$

Since this is a quadratic in c^2 , there are *two* possible systems of waves of any given length ($2\pi/k$). This is as we should expect, since when the wave-length is prescribed the system has virtually two degrees of freedom, so that there are two independent modes of oscillation about the state of equilibrium. For example, in the extreme case where ρ'/ρ is small, one mode consists mainly in an oscillation of the upper fluid which is almost the same as if the lower fluid were solidified, whilst the other mode may be described as an oscillation of the lower fluid which is almost the same as if its upper surface were free.

The ratio of the amplitudes at the upper and lower surfaces is found to be

$$\frac{kc^2}{kh^2 \cosh kh' - g \sinh kh'} \dots \dots \dots (10)$$

Of the various special cases that may be considered, the most interesting is that in which kh is large, *i.e.* the depth of the lower fluid is great compared with the wave-length. Putting $\coth kh = 1$, we see that one root of (9) is now

$$c^2 = \frac{g}{k}, \quad \dots \dots \dots (11)$$

exactly as in the case of a single fluid of infinite depth, and that the ratio of the amplitudes is $e^{kh'}$. This is merely a particular case of the general result stated at the end of Art 230, it will in fact be found on examination that there is now no slipping at the common boundary of the two fluids. The second root of (9) is

$$c^2 = \frac{\rho - \rho'}{\rho \coth kh' + \rho'} \frac{g}{k}, \quad \dots \dots \dots (12)$$

and for this the ratio (10) assumes the value

$$-\left(\frac{\rho}{\rho'} - 1\right) e^{-kh'} \quad \dots \dots \dots (13)$$

If in (12) and (13) we put $kh' = \infty$, we fall back on a former case, whilst if we make kh' small, we find

$$c^2 = \left(1 - \frac{\rho'}{\rho}\right) gh', \dots \dots \dots (14)$$

and the ratio of the amplitudes is

$$-\left(\frac{\rho}{\rho'} - 1\right). \dots \dots \dots (15)$$

These problems were first investigated by Stokes* The case of any number of superposed strata of different densities has been treated by Webb† and Greenhill‡ For investigations of the possible *rotational* oscillations in a heterogeneous liquid the reader may consult the papers cited below§

232 As a further example of the method of Art 230 let us suppose that two fluids of densities ρ, ρ' , one beneath the other, are moving parallel to x with velocities U, U' , respectively, the common surface (when undisturbed) being of course plane and horizontal This is virtually a problem of small oscillations about a state of steady motion

The fluids being supposed unlimited vertically, we assume, for the lower fluid

$$\psi = -U \{y - \beta e^{ky} \cos kx\}, \dots \dots (1)$$

and for the upper fluid

$$\psi' = -U' \{y - \beta e^{-ky} \cos kx\}, \dots \dots \dots (2)$$

the origin being at the mean level of the common surface, which is assumed to be stationary, and to have the form

$$y = \beta \cos kx \dots \dots \dots (3)$$

The pressure-equations give

$$\left. \begin{aligned} \frac{p}{\rho} &= \text{const} - gy - \frac{1}{2} U^2 (1 - 2k\beta e^{ky} \cos kx), \\ \frac{p'}{\rho'} &= \text{const} - gy - \frac{1}{2} U'^2 (1 + 2k\beta e^{-ky} \cos kx), \end{aligned} \right\} \dots \dots (4)$$

* "On the Theory of Oscillatory Waves," *Camb Trans*, t viii (1847) [*Math and Phys. Papers*, t i p 212]

† *Math Tripos Papers*, 1884

‡ 'Wave Motion in Hydrodynamics,' *Amer Journ Math*, t ix (1887)

§ Lord Rayleigh, "Investigation of the Character of the Equilibrium of an Incompressible Heavy Fluid of Variable Density," *Proc Lond Math Soc.*, t xiv p 170 (1883) [*Sc Papers*, t ii p 200], Burnside, "On the small Wave-Motions of a Heterogeneous Fluid under Gravity," *Proc Lond Math Soc*, t xx p 392 (1889), Love, "Wave-Motion in a Heterogeneous Heavy Liquid," *Proc Lond Math Soc*, t xxii p 307 (1891).

whence, at the common surface,

$$\left. \begin{aligned} \frac{p}{\rho} &= \text{const} + (kU^2 - g)y, \\ \frac{p'}{\rho'} &= \text{const} - (kU'^2 + g)y \end{aligned} \right\} \dots\dots (5)$$

Since we must have $p = p'$ over this surface, we get

$$\rho U^2 + \rho' U'^2 = \frac{g}{k}(\rho - \rho') \dots\dots\dots (6)$$

This is the condition for stationary waves on the common surface of the two currents U, U' . It may be written

$$\left(\frac{\rho U + \rho' U'}{\rho + \rho'} \right)^2 = \frac{g}{k} \frac{\rho - \rho'}{\rho + \rho'} - \frac{\rho \rho'}{(\rho + \rho')^2} (U - U')^2 \dots\dots (7)$$

The quantity
$$\frac{\rho U + \rho' U'}{\rho + \rho'}$$

may be called the mean velocity of the two currents, and it appears that relatively to this the waves have velocities $\pm c$, given by

$$c^2 = c_0^2 - \frac{\rho \rho'}{(\rho + \rho')^2} (U - U')^2, \dots\dots\dots (8)$$

where c_0 denotes the wave-velocity in the absence of currents (Art 231)

If the relative velocity $|U - U'|$ of the currents exceed a certain limit, given by

$$(U - U')^2 = \frac{g}{k} \frac{\rho^2 - \rho'^2}{\rho \rho'}, \dots\dots\dots (9)$$

the value of c is imaginary, indicating instability. This upper limit diminishes indefinitely with the wave-length

This result would indicate that, if there were no modifying circumstances, the slightest breath of wind would be sufficient to ruffle the surface of water. We shall give, later, a more complete investigation of the present problem, taking account of capillary forces, which act in the direction of stability.

It appears from (7) that if $\rho = \rho'$, or if $g = 0$, the plane form of the surface is unstable for *all* wave-lengths. This result illustrates the statement, as to the instability of surfaces of discontinuity in a liquid, made in Art 79*

When the currents are confined by fixed horizontal planes $y = -h, y = h'$, we assume

$$\psi = -U \left\{ y - \beta \frac{\sinh k(y+h)}{\sinh kh} \cos kx \right\}, \quad \psi' = -U' \left\{ y + \beta \frac{\sinh k(y-h')}{\sinh kh'} \cos kx \right\} \dots\dots (10)$$

* The instability was first remarked by Helmholtz, *l. c. ante* p 20

The condition for stationary waves on the common surface is then found to be

$$\rho U^2 \coth kh + \rho' U'^2 \coth kh' = \frac{g}{k} (\rho - \rho') \quad \dots \quad (11)^*$$

It appears on examination that the undisturbed motion is stable or unstable, according as

$$|U - U'| < \frac{\rho \coth kh + \rho' \coth kh'}{(\rho \rho' \coth kh \coth kh')^{\frac{1}{2}}} c_0, \quad \dots \quad (12)$$

where c_0 is the wave-velocity in the absence of currents. When h and h' both exceed half the wave-length, this reduces practically to the former result (9).

233 These questions of stability are so important that it is worth while to give the more direct method of treatment†

If ϕ be the velocity-potential of a slightly disturbed stream flowing with the general velocity U parallel to x , we may write

$$\phi = -Ux + \phi_1, \quad \dots \quad (1)$$

where ϕ_1 is small. The pressure-formula is, to the first order,

$$\frac{p}{\rho} = \frac{\partial \phi_1}{\partial t} - gy + U \frac{\partial \phi_1}{\partial x} + \dots, \quad \dots \dots \dots (2)$$

and the condition to be satisfied at a bounding surface $y = \eta$, where η is small, is

$$\frac{\partial \eta}{\partial t} + U \frac{\partial \eta}{\partial x} = - \frac{\partial \phi_1}{\partial y} \quad \dots \quad (3)$$

To apply this to the problem stated at the beginning of Art. 232, we assume, for the lower and upper fluids, respectively,

$$\phi_1 = C e^{ky + iz(kx - \sigma t)}, \quad \phi_1' = C' e^{-ky + iz(kx - \sigma t)}, \quad \dots \dots \dots (4)$$

with, as the equation of the common surface,

$$\eta = a e^{iz(kx - \sigma t)} \quad \dots \quad (5)$$

The continuity of the pressure at this surface requires, by (2),

$$\rho \{i(\sigma - kU)C + ga\} = \rho' \{i(\sigma - kU')C' + ga\}, \quad \dots \quad (6)$$

whilst the surface-condition (3) gives

$$i(\sigma - kU)a = kC, \quad i(\sigma - kU')a = -kC' \quad \dots \dots \dots (7)$$

Eliminating a , C , C' , we get

$$\rho(\sigma - kU)^2 + \rho'(\sigma - kU')^2 = gk(\rho - \rho'), \quad \dots \dots \dots (8)$$

whence
$$\frac{\sigma}{k} = \frac{\rho U + \rho' U'}{\rho + \rho'} \pm \sqrt{\left\{ \frac{g}{k} \frac{\rho - \rho'}{\rho + \rho'} - \frac{\rho \rho'}{(\rho + \rho')^2} (U - U')^2 \right\}}, \quad \dots (9)$$

* Greenhill, *l c ante* p 356

† Sir W Thomson, "Hydrokinetic Solutions and Observations," *Phil Mag* (4), t xli (1871) [*Baltimore Lectures*, p 590], Lord Rayleigh, "On the Instability of Jets," *Proc Lond. Math. Soc*, t x p 4 (1878) [*Sc. Papers*, t i p 361]

leading to the same conclusions as in Art 232 If

$$(U - U')^2 > \frac{(\rho + \rho')^2}{\rho\rho'} c_0^2, \quad \dots \dots \dots (10)$$

where c_0 is the wave-velocity in the absence of currents, σ is imaginary, of the form $\alpha \pm i\beta$. The complete solution then contains a term with $e^{\sigma t}$ as a factor, indicating indefinite increase of amplitude

If $\rho = \rho'$, it is evident from (8) that σ will be imaginary for all values of k . Putting $U' = -U$, we get

$$\sigma = \pm ikU \quad \dots \dots (11)$$

Hence, taking the real part of (5), we find

$$\eta = ae^{\pm ikU t} \cos kx \quad \dots \dots (12)$$

The upper sign gives a system of standing waves whose height continually increases with the time, the rate of increase being greater, the shorter the wave-length.

The case of $\rho = \rho'$, with $U = U'$, is of some interest, as illustrating the flapping of sails and flags*. We may conveniently simplify the question by putting $U = U' = 0$, any common velocity may be superposed afterwards if desired. On these suppositions, the equation (8) reduces to $\sigma^2 = 0$. On account of the double root the solution has to be completed by the method explained in books on Differential Equations. In this way we obtain the two independent solutions

$$\eta = ae^{ikx}, \quad \phi_1 = 0, \quad \phi_1' = 0, \quad \dots (13)$$

$$\text{and} \quad \eta = ate^{ikx}, \quad \phi_1 = -\frac{\alpha}{k} e^{k y} e^{ikx}, \quad \phi_1' = \frac{\alpha}{k} e^{-k y} e^{ikx} \dots (14)$$

The former solution represents a state of equilibrium, the latter gives a system of stationary waves with amplitude increasing proportionally to the time. In this form of the problem there is no physical surface of separation to begin with, but if a slight discontinuity of motion be artificially produced, *e.g.* by impulses applied to a thin membrane which is afterwards dissolved, the discontinuity will persist, and, as we have seen, the height of the corrugations will continually increase.

The above method, when applied to the case where the fluids are confined between two rigid horizontal planes $y = -h$, $y = h'$, leads to

$$\rho (\sigma - kU)^2 \coth kh + \rho' (\sigma - kU')^2 \coth kh' = gk (\rho - \rho'), \quad \dots (15)$$

which is equivalent to Art 232 (11)

* Lord Rayleigh, *l.c.*

234 The investigations of the preceding Arts relate to a special type of waves, the profile is simple-harmonic, and the train extends to infinity in both directions. But since all our equations are linear (so long as we confine ourselves to a first approximation), we can, with the help of Fourier's theorem, build up by superposition a solution which shall represent the effect of arbitrary initial conditions. Since the subsequent motion is in general made up of systems of waves, of all possible lengths, travelling in either direction, each with the velocity proper to its own wave-length, the form of the free surface will continually alter. The only exception is when the wave-length of every system which is present in sensible amplitude is large compared with the depth of the fluid. The velocity of propagation $(gh)^{\frac{1}{2}}$ is then independent of the wave-length, so that in the case of waves travelling in one direction only, the wave-profile remains unchanged in form as it advances (Art. 169).

The effect of a local disturbance of the surface, in the case of infinite depth, will be considered presently, but it is convenient to introduce in the first place the very important conception of 'group-velocity,' which has application, not only to water-waves, but to every case of wave-motion where the velocity of propagation of a simple-harmonic train varies with the wave-length.

It has often been noticed that when an isolated group of waves, of sensibly the same length, is advancing over relatively deep water, the velocity of the group as a whole is less than that of the waves composing it. If attention be fixed on a particular wave, it is seen to advance through the group, gradually dying out as it approaches the front, whilst its former place in the group is occupied in succession by other waves which have come forward from the rear*.

The simplest analytical representation of such a group is obtained by the superposition of two systems of waves of the same amplitude, and of nearly but not quite the same wave-length. The corresponding equation of the free surface will be of the form

$$\begin{aligned}\eta &= a \sin(kx - \sigma t) + a \sin(k'x - \sigma' t) \\ &= 2a \cos\left\{\frac{1}{2}(k - k')x - \frac{1}{2}(\sigma - \sigma')t\right\} \sin\left\{\frac{1}{2}(k + k')x - \frac{1}{2}(\sigma + \sigma')t\right\} \\ &\quad \dots\dots\dots (1)\end{aligned}$$

If k, k' be very nearly equal, the cosine in this expression varies very slowly with x , so that the wave-profile at any instant has the form of a curve of sines in which the amplitude alternates gradually between the values 0 and $2a$. The surface therefore presents the appearance of a series of groups of waves, separated at equal intervals by bands of nearly smooth water. The motion of each group is then sensibly independent of the presence of the

* Scott Russell, "Report on Waves," *Brit Ass Rep* 1844, p 369.

others. Since the distance between the centres of two successive groups is $2\pi/(k-k')$, and the time occupied by the system in shifting through this space is $2\pi/(\sigma-\sigma')$, the group-velocity (U , say) is $=(\sigma-\sigma')/(k-k')$, or

$$U = \frac{d\sigma}{dk}, \dots \dots \dots (2)$$

ultimately In terms of the wave-length λ ($=2\pi/k$), we have

$$U = \frac{d(kc)}{dk} = c - \lambda \frac{dc}{d\lambda}, \dots \dots (3)$$

where c is the wave-velocity.

This result holds for any case of waves travelling through a uniform medium In the present application we have

$$c = \left(\frac{g}{k} \tanh kh\right)^{\frac{1}{2}}, \dots \dots \dots (4)$$

and therefore, for the group-velocity,

$$\frac{d(kc)}{dk} = \frac{1}{2}c \left(1 + \frac{\sinh 2kh}{2kh}\right) \dots \dots \dots (5)$$

The ratio which this bears to the wave-velocity c increases as kh diminishes, being $\frac{1}{2}$ when the depth is very great, and unity when it is very small, compared with the wave-length.

The above explanation seems to have been first given by Stokes*. The extension to a more general type of group was made by Rayleigh† and Gouy‡ The argument of these writers admits of being put very concisely Assuming a disturbance

$$y = \Sigma C \cos(\sigma t - kx + \epsilon), \dots \dots \dots (6)$$

where the summation (which may of course be replaced by an integration) embraces a series of terms in which the values of σ , and therefore also of k , vary very slightly, we remark that the phase of the typical term at time $t + \Delta t$ and place $x + \Delta x$ differs from the phase at time t and place x by the amount $\sigma \Delta t - k \Delta x$ Hence if the variations of σ and k from term to term be denoted by $\delta\sigma$ and δk , the change of phase will be sensibly the same for all the terms, provided

$$\delta\sigma \Delta t - \delta k \Delta x = 0 \dots \dots \dots (7)$$

The group as a whole therefore travels with the velocity

$$U = \frac{\Delta x}{\Delta t} = \frac{d\sigma}{dk} \dots \dots \dots (8)$$

* Smith's Prize Examination, 1876 [*Math. and Phys. Papers*, t. v. p. 362] See also Lord Rayleigh, *Theory of Sound*, Art. 191.

† *Nature*, t. xxv. p. 52 (1881) [*Sc. Papers*, t. i. p. 540]

‡ "Sur la vitesse de la lumière," *Ann. de Chim. et de Phys.*, t. xvi. p. 262 (1889)

Another derivation of (3) can be given which is, perhaps, more intuitive. In a medium such as we are considering, where the wave-velocity varies with the frequency, a limited initial disturbance gives rise in general to a wave-system in which the different wave-lengths, travelling with different velocities, are gradually sorted out (Arts 236, 237). If we regard the wave-length λ as a function of x and t , we have


$$\frac{\partial \lambda}{\partial t} + U \frac{\partial \lambda}{\partial x} = 0, \quad \dots \dots \dots (9)$$

since λ does not vary in the neighbourhood of a geometrical point travelling with velocity U , this is, in fact, the definition of U . Again, if we imagine another geometrical point to travel with the waves, we have

$$\frac{\partial \lambda}{\partial t} + c \frac{\partial \lambda}{\partial x} = \lambda \frac{\partial c}{\partial x} = \lambda \frac{dc}{d\lambda} \frac{\partial \lambda}{\partial x}, \quad \dots \dots \dots (10)$$

the second member expressing the rate at which two consecutive wave-crests are separating from one another. Combining (9) and (10), we are led, again, to the formula (3)*

The formula (3) admits of a simple geometrical representation†. If a curve be constructed with λ as abscissa and c as ordinate, the group-velocity will be represented by the intercept made by the tangent on the



axis of c . Thus, in the figure, PN represents the wave-velocity for the wave-length ON , and OT represents the group-velocity. The frequency of vibration, it may be noted, is represented by the tangent of the angle PON .

In the case of gravity-waves on deep water, $c \propto \lambda^{\frac{1}{2}}$, the curve has the form of the parabola $y^2 = 4ax$, and $OT = \frac{1}{2}PN$, i.e., the group-velocity is one-half the wave-velocity.

* See a paper "On Group-Velocity," *Proc. Lond. Math. Soc.* (2), t. 1 p. 473 (1904).

† *Manch. Mem.*, t. xlv No. 6 (1900).

235 The group-velocity has moreover a dynamical, as well as a geometrical, significance. This was first shewn by Prof Osborne Reynolds*, in the case of deep-water waves, by a calculation of the energy propagated across a vertical plane. In the case of infinite depth, the velocity-potential corresponding to a simple-harmonic train

$$\eta = a \sin k(x - ct), \quad . \quad . \quad (11)$$

$$\text{is} \quad \phi = ac e^{ky} \cos k(x - ct), \quad . \quad . \quad (12)$$

as may be verified by the consideration that for $y=0$ we must have $\partial\eta/\partial t = -\partial\phi/\partial y$. The variable part of the pressure is $\rho\partial\phi/\partial t$, if we neglect terms of the second order, so that the rate at which work is being done on the fluid to the right of the plane x is

$$\begin{aligned} - \int_{-\infty}^0 p \frac{\partial\phi}{\partial x} dy &= \rho a^2 k^2 c^2 \sin^2 k(x - ct) \int_{-\infty}^0 e^{2ky} dy \\ &= \frac{1}{2} g \rho a^2 c \sin^2 k(x - ct), \quad . \quad . \quad (13) \end{aligned}$$

since $c^2 = g/k$. The mean value of this expression is $\frac{1}{4} g \rho a^2 c$. It appears on reference to Art. 229 that this is exactly one-half of the energy of the waves which cross the plane in question per unit time. Hence in the case of an isolated group the supply of energy is sufficient only if the group advance with *half* the velocity of the individual waves.

It is readily proved in the same manner that in the case of a finite depth h the average energy transmitted per unit time is†

$$\frac{1}{4} g \rho a^2 c \left(1 + \frac{2kh}{\sinh 2kh} \right), \quad . \quad . \quad . \quad . \quad (14)$$

which is, by (4), the same as

$$\frac{1}{4} g \rho a^2 \times \frac{d(kc)}{dk} \quad . \quad . \quad . \quad . \quad . \quad . \quad (15)$$

Hence the rate of transmission of energy is equal to the group-velocity, $d(kc)/dk$, found independently by the former line of argument.

This identification of the kinematical group-velocity of the preceding Art. with the rate of transmission of energy has been extended to all kinds of waves by Lord Rayleigh (*lc*)

From a physical point of view the group-velocity is perhaps even more

* "On the Rate of Progression of Groups of Waves, and the Rate at which Energy is Transmitted by Waves," *Nature*, t xvi p 343 (1877) [*Sc Papers*, t i p 198]. Professor Reynolds has also constructed a model which exhibits in a very striking manner the distinction between wave-velocity and group-velocity in the case of the transverse oscillations of a row of equal pendulums whose bobs are connected by a string.

† Lord Rayleigh, "On Progressive Waves," *Proc Lond. Math. Soc*, t ix. p 21 (1877) [*Sc Papers*, t i p 322], *Theory of Sound*, t i, Appendix

important and significant than the wave-velocity. The latter may be greater or less than the former, and it is even possible to imagine mechanical media in which it would have the opposite direction, *i.e.* a disturbance might be propagated outwards from a centre in the form of a group, whilst the individual waves composing the group were themselves travelling backwards, coming into existence at the front, and dying out as they approach the rear*. Moreover, it may be urged that even in the more familiar phenomena of Acoustics and Optics the wave-velocity is of importance chiefly so far as it coincides with the group-velocity.

236 The theory of the waves produced in deep water by a local disturbance of the surface was investigated in two classical memoirs by Cauchy† and Poisson‡. The problem was long regarded as difficult, and even obscure, but in its two-dimensional form, at all events, it can be presented in a comparatively simple aspect.

It appears from Arts 40, 41 that the initial state of the fluid is determinate when we know the form of the boundary, and the boundary-values of the velocity-potential ϕ , or of the normal velocity $\partial\phi/\partial n$. Hence two forms of the problem naturally present themselves, we may start with an initial elevation of the free surface, without initial velocity, or we may start with the surface undisturbed (and therefore horizontal) and an initial distribution of surface-impulse ($\rho\phi_0$).

If the origin be in the undisturbed surface, and the axis of y be drawn vertically upwards, the typical solution for the case of initial rest is

$$\eta = \cos \sigma t \cos kx, \quad \dots \dots \dots (1)$$

$$\phi = g \frac{\sin \sigma t}{\sigma} e^{ky} \cos kx, \quad \dots \dots \dots (2)$$

provided

$$\sigma^2 = gk, \quad \dots \dots \dots (3)$$

in accordance with the ordinary theory of "standing" waves of simple-harmonic profile (Art 227)

If we generalize this by Fourier's double-integral theorem

$$f(x) = \frac{1}{\pi} \int_0^\infty dk \int_{-\infty}^\infty f(\alpha) \cos k(x-\alpha) d\alpha, \quad \dots \dots \dots (4)$$

then, corresponding to the initial conditions

$$\eta = f(x), \quad \phi_0 = 0, \quad \dots \dots \dots (5)$$

* *Proc Lond Math Soc* (2), t 1 p 473

† *l.c. ante*, p 15

‡ "Mémoire sur la théorie des ondes," *Mém de l'Acad Roy des Sciences*, t 1 (1816)

where the zero suffix indicates surface-value ($y = 0$), we have

$$\eta = \frac{1}{\pi} \int_0^\infty \cos \sigma t dk \int_{-\infty}^\infty f(\alpha) \cos k(x - \alpha) d\alpha, \quad \dots \quad (6)$$

$$\phi = \frac{g}{\pi} \int_0^\infty \frac{\sin \sigma t}{\sigma} e^{ky} dk \int_{-\infty}^\infty f(\alpha) \cos k(x - \alpha) d\alpha \quad \dots \quad (7)$$

If the initial elevation be confined to the immediate neighbourhood of the origin, so that $f(\alpha)$ vanishes for all but infinitesimal values of α , we have, assuming

$$\int_{-\infty}^\infty f(\alpha) d\alpha = 1, \quad \dots \quad (8)$$

$$\phi = \frac{g}{\pi} \int_0^\infty \frac{\sin \sigma t}{\sigma} e^{ky} \cos kx dk. \quad \dots \quad (9)$$

This may be expanded in the form

$$\phi = \frac{gt}{\pi} \int_0^\infty \left\{ 1 - \frac{gt^2}{3!} k + \frac{(gt^2)^2}{5!} k^2 - \dots \right\} e^{ky} \cos kx dk, \quad \dots \quad (10)$$

where use is made of (3) If we write

$$-y = r \cos \theta, \quad x = r \sin \theta, \quad \dots \quad (11)$$

we have, y being negative*,

$$\int_0^\infty e^{ky} \cos kx k^n dk = \frac{n!}{r^{n+1}} \cos(n+1)\theta, \quad \dots \quad (12)$$

so that (10) becomes

$$\phi = \frac{gt}{\pi} \left\{ \frac{\cos \theta}{r} - \frac{1}{3} \left(\frac{1}{2} gt^2 \right) \frac{\cos 2\theta}{r^2} + \frac{1}{3} \frac{1}{5} \left(\frac{1}{2} gt^2 \right)^2 \frac{\cos 3\theta}{r^3} - \dots \right\}, \quad \dots \quad (13)$$

a result which is easily verified From this the value of η is obtained by Art 226 (5), putting $\theta = \pm \frac{1}{2}\pi$ Thus, for $x > 0$,

$$\eta = \frac{1}{\pi x} \left\{ \frac{gt^2}{2x} - \frac{1}{3} \frac{1}{5} \left(\frac{gt^2}{2x} \right)^3 + \frac{1}{3} \frac{1}{5 \cdot 7 \cdot 9} \left(\frac{gt^2}{2x} \right)^5 - \dots \right\}. \quad \dots \quad (14)$$

It is evident at once that any particular phase of the surface disturbance, *e.g.*, a zero or a maximum or a minimum of η , is associated with a definite value of $gt^2/2x$, and therefore that the phase in question travels over the surface with a constant *acceleration* The meaning of this somewhat remarkable result will appear presently (Art 238)

* This formula may be dispensed with It is sufficient to calculate the value of ϕ at points on the vertical axis of symmetry, its value at other points can then be written down at once by a property of harmonic functions (cf Thomson and Tait, Art 498)

The series in (14) is virtually identical with one (usually designated by M^*) which occurs in the theory of Fresnel's diffraction-integrals. In its present form it is convenient only when we are dealing with the initial stages of the disturbance, it converges very slowly when $gt^2/2x$ is no longer small. The series may, however, be summed as follows. Writing, with a slight change from the usual convention,

$$\left. \begin{aligned} M &= \omega - \frac{\omega^3}{3 \cdot 5} + \frac{\omega^5}{3 \cdot 5 \cdot 7 \cdot 9} - \dots, \\ N &= \frac{\omega^2}{1 \cdot 3} - \frac{\omega^4}{1 \cdot 3 \cdot 5 \cdot 7} + \frac{\omega^6}{1 \cdot 3 \cdot 5 \cdot 7 \cdot 9 \cdot 11} - \dots, \end{aligned} \right\} \quad (15)$$

$$\text{and} \quad \chi = iM - N = \frac{i\omega}{1} + \frac{i^2\omega^2}{1 \cdot 3} + \frac{i^3\omega^3}{1 \cdot 3 \cdot 5} + \frac{i^4\omega^4}{1 \cdot 3 \cdot 5 \cdot 7} + \dots, \quad (16)$$

we find

$$2\omega \frac{d\chi}{d\omega} = \chi + i\omega(1 + \chi),$$

or

$$\frac{d}{d\omega} \left(\frac{\chi}{\sqrt{\omega}} \right) - \frac{1}{2} \left(\frac{\chi}{\sqrt{\omega}} \right) = \frac{i}{2\sqrt{\omega}} \quad (17)$$

The solution of this equation, subject to the condition that χ must ultimately vary as ω , when ω is small, is

$$\chi = \frac{1}{2}i\sqrt{\omega} e^{\frac{1}{2}i\omega} \int_0^\omega \frac{e^{-\frac{1}{2}iu}}{\sqrt{u}} du \quad (18)$$

Hence, equating separately imaginary and real parts, we obtain

$$\left. \begin{aligned} M &= \frac{1}{2}\sqrt{\omega} \left\{ \cos \frac{1}{2}\omega \int_0^\omega \cos \frac{1}{2}u \frac{du}{\sqrt{u}} + \sin \frac{1}{2}\omega \int_0^\omega \sin \frac{1}{2}u \frac{du}{\sqrt{u}} \right\}, \\ N &= \frac{1}{2}\sqrt{\omega} \left\{ \sin \frac{1}{2}\omega \int_0^\omega \cos \frac{1}{2}u \frac{du}{\sqrt{u}} - \cos \frac{1}{2}\omega \int_0^\omega \sin \frac{1}{2}u \frac{du}{\sqrt{u}} \right\}, \end{aligned} \right\} \quad (19)$$

which are, virtually, well-known results†

The equation (14) is equivalent to

$$\eta = \frac{\sqrt{\omega}}{2\pi x} \left\{ \cos \frac{1}{2}\omega \int_0^\omega \cos \frac{1}{2}u \frac{du}{\sqrt{u}} + \sin \frac{1}{2}\omega \int_0^\omega \sin \frac{1}{2}u \frac{du}{\sqrt{u}} \right\}, \quad (20)$$

where

$$\omega = \frac{gt^2}{2x}. \quad (21)$$


This agrees with a result given by Poisson. The definite integrals are practically of Fresnel's forms, and may be considered as known functions, so that the present problem may be regarded as completely solved. Moreover, Lommel, in his researches on Diffraction‡, has given a table of the function M/ω . We are thus enabled to delineate the first nine or ten waves with great ease. The fig. on the next page shews the variation of η with the time, at a particular place, for different places the intervals between assigned phases

* Cf Rayleigh, *Sc Papers*, t iii p. 129

† Cf Rayleigh, *l c*

‡ "Die Beugungsscheinungen geradliniger begrenzter Schirme," *Abh. d. k. Bayer. Akad. d. Wiss.*, 2^o Cl, t xv (1886)

vary as \sqrt{x} , whilst the corresponding elevations vary inversely as x . The diagrams on p 368, on the other hand, shew the wave-profile at a particular instant, at different times, the horizontal distances between corresponding points vary as the square of the time that has elapsed since the beginning of the disturbance, whilst corresponding elevations vary inversely as the square of this time



[The unit of the horizontal scale is $\sqrt{(2x/g)}$. That of the vertical scale is $Q/\pi x$, if Q be the sectional area of the initially elevated fluid.]

When $gt^2/2x$ is large, the definite integrals in (19) approximate to the limit $\sqrt{\pi^*}$, and we then have

$$\eta = \frac{g^{\frac{1}{2}}t}{2^{\frac{1}{2}}\pi^{\frac{1}{2}}x^{\frac{1}{2}}} \left(\cos \frac{gt^2}{4x} + \sin \frac{gt^2}{4x} \right), \quad . \quad . \quad (22)$$

in agreement with a result of Poisson and Cauchy

Expressions for the remainder are also given by these writers. Thus Poisson obtains (virtually) the semi-convergent expansion



$$M = \frac{1}{2}\sqrt{(\pi\omega)} (\cos \frac{1}{2}\omega + \sin \frac{1}{2}\omega) - \left\{ \frac{1}{\omega} - \frac{1}{\omega^3} \frac{3}{5} + \frac{1}{\omega^5} \frac{3}{5} \frac{5}{7} \frac{7}{9} - \dots \right\} \quad (23)$$

This is readily obtained from (18). Thus

$$\begin{aligned} \int_0^\omega e^{-\frac{1}{2}iu} \frac{du}{\sqrt{u}} &= (1-i)\sqrt{\pi} - \int_\omega^\infty e^{-\frac{1}{2}iu} \frac{du}{\sqrt{u}} \\ &= (1-i)\sqrt{\pi} + 2e^{-\frac{1}{2}i\omega} \left\{ \frac{i}{\omega^{\frac{1}{2}}} + \frac{1}{\omega^{\frac{3}{2}}} \frac{3}{5} + \frac{1}{\omega^{\frac{5}{2}}} \frac{3}{5} \frac{5}{7} + \dots \right\}, \quad \dots \quad (24) \end{aligned}$$

by a series of partial integrations. Since M is the real part of $-i\chi$, the result (23) follows

* Thus
$$\int_0^\infty \cos \frac{1}{2}u \frac{du}{\sqrt{u}} = 2\sqrt{2} \int_0^\infty \cos v^2 dv = \sqrt{\pi}.$$



[The unit of the horizontal scales is $\frac{1}{2}gt^2$ That of the vertical scales is $2Q/\pi gt^2$]

237 In the case of initial *impulses* applied to the surface, supposed horizontal, the typical solution is

$$\rho \phi = \cos \sigma t e^{k y} \cos k x, \dots \dots \dots (25)$$

$$\eta = -\frac{1}{g} \sigma \sin \sigma t \cos k x, \dots \dots \dots (26)$$

with $\sigma^2 = gk$ as before. Hence, if the initial conditions be

$$\rho \phi_0 = F(x), \quad \eta = 0, \dots \dots \dots (27)$$

we have
$$\phi = \frac{1}{\pi \rho} \int_0^\infty \cos \sigma t e^{k y} dk \int_{-\infty}^\infty F(\alpha) \cos k(x - \alpha) d\alpha, \dots (28)$$

$$\eta = -\frac{1}{\pi g \rho} \int_0^\infty \sigma \sin \sigma t dk \int_{-\infty}^\infty F(\alpha) \cos k(x - \alpha) d\alpha. (29)$$

For a concentrated impulse acting at the point $x = 0$ of the surface, we have, putting


$$\int_{-\infty}^\infty F(\alpha) d\alpha = 1, \dots \dots \dots (30)$$

$$\phi = \frac{1}{\pi \rho} \int_0^\infty \cos \sigma t e^{k y} \cos k x dk \dots \dots \dots (31)$$



This integral may be treated in the same manner as (9), but it is evident that the results may be obtained immediately by performing the operation $1/g\rho \cdot \partial/\partial t$ upon those of Art 236 Thus from (13) and (14) we derive

$$\phi = \frac{1}{\pi \rho} \left\{ \frac{\cos \theta}{r} - \frac{1}{2} g t^2 \frac{\cos 2\theta}{r^2} + \frac{1}{1 \cdot 3} \left(\frac{1}{2} g t^2 \right)^2 \frac{\cos 3\theta}{r^3} - \dots \right\}, (32)$$

$$\eta = \frac{t}{\pi \rho x^2} \left\{ \frac{1}{1} - \frac{3}{1 \cdot 3} \frac{g t^2}{2x} + \frac{5}{1 \cdot 3 \cdot 5 \cdot 7} \frac{(g t^2)^2}{9 (2x)^2} - \dots \right\} . (33)$$



[The unit of the horizontal scale is $\sqrt{(2x/g)}$ That of the vertical scale is $\frac{P}{\pi \rho x} \sqrt{\frac{2}{gx}}$, where P represents the total initial impulse]



[The unit of the horizontal scales is $\frac{1}{2}gt^2$ That of the vertical scales is $\frac{4P}{\pi\rho g^2 t^3}$.

The upper curve, if continued to the right, would cross the axis of x and would thereafter be indistinguishable from it on the present scale]

The formula (33) may also be written

$$\eta = \frac{t}{\pi \rho x^2} \frac{dM}{d\omega} = \frac{t}{2\pi \rho x^2} \left(1 + \frac{M}{\omega} - N \right), \quad \dots \dots (34)$$

where M and N are defined by (15), and $\omega = gt^2/2x$, as before. The function N/ω has also been tabulated by Lommel, so that the forms of the first few waves can be traced without difficulty. The fig. on p. 369 shews the rise and fall of the surface at a particular place, for different places the time-intervals between assigned phases vary as \sqrt{x} , as in the former case, but the corresponding elevations now vary inversely as $x^{\frac{3}{2}}$. In the diagrams on p. 370, which give an instantaneous view of the wave-profile, the horizontal distances between corresponding points vary as the square of the time, whilst corresponding ordinates vary inversely as the cube of the time.

For large values of $gt^2/2x$, we find, performing the operation $1/g\rho \partial/\partial t$ upon (22),

$$\eta = \frac{g^{\frac{1}{2}} t^{\frac{3}{2}}}{2^{\frac{5}{2}} \pi^{\frac{1}{2}} \rho x^{\frac{5}{2}}} \left(\cos \frac{gt^2}{4x} - \sin \frac{gt^2}{4x} \right), \quad \dots \dots (35)$$

approximately.

238 It remains to examine the meaning and the consequences of the results above obtained. It will be sufficient to consider, chiefly, the case of Art. 236, where an initial *elevation* is supposed to be concentrated in a line of the surface.

At any subsequent time t the surface is occupied by a wave-system whose advanced portions are delineated on p. 368. For sufficiently small values of x the form of the waves is given by (22), hence as we approach the origin the waves are found to diminish continually in length, and to increase continually in height, in both respects without limit.

As t increases, the wave-system is stretched out horizontally, proportionally to the square of the time, whilst the vertical ordinates are correspondingly diminished, in such a way that the area

$$\int \eta dx$$

included between the wave profile, the axis of x , and the ordinates corresponding to any two assigned phases (i.e., two assigned values of ω) is constant*. The latter statement may be verified immediately from the mere form of (14) or (20).

* This statement does not apply to the case of an initial *impulse*. The corresponding proposition then is that

$$\int \phi_0 dx,$$

taken between assigned values of ω , is constant. This appears from (32)

The oscillations of level, on the other hand, at any particular place, are represented on p 367. These follow one another more and more rapidly, with ever increasing amplitude. For sufficiently great values of t , the course of these oscillations is given by (22)

In the region where this formula holds, at any assigned epoch, the changes in length and height from wave to wave are very gradual, so that a considerable number of consecutive waves may be represented approximately by a curve of sines. The circumstances are, in fact, all approximately reproduced when

$$\Delta \frac{gt^2}{4x} = 2\pi \quad \dots \dots \dots (36)$$

Hence, if we vary t alone, we have, putting $\Delta t = \tau$, the period of oscillation,

$$\tau = \frac{4\pi x}{gt}; \quad \dots \dots \dots (37)$$

whilst, if we vary x alone, putting $\Delta x = -\lambda$, where λ is the wave-length, we find

$$\lambda = \frac{8\pi x^2}{gt^2} \quad \dots \dots \dots (38)$$

The wave-velocity is to be found from

$$\Delta \frac{gt^2}{4x} = 0, \quad \dots \dots \dots (39)$$

this gives

$$\frac{\Delta x}{\Delta t} = \frac{2x}{t} = \sqrt{\frac{g\lambda}{2\pi}}, \quad \dots \dots \dots (40)$$

by (38), as in the case of an infinitely long train of simple harmonic waves of length λ .

We can now see something of a reason why each wave should be continually accelerated. The waves in front are longer than those behind, and are accordingly moving faster. The consequence is that all the waves are continually being drawn out in length, so that their velocities of propagation continually increase as they advance. But the higher the rank of a wave in the sequence, the smaller is its acceleration.

So far, we have been considering the progress of individual waves. But, if we fix our attention on a *group* of waves, characterized as having (approximately) a given wave-length λ , the position of this group is regulated according to (40) by the formula

$$\frac{x}{t} = \frac{1}{2} \sqrt{\frac{g\lambda}{2\pi}}, \quad \dots \dots \dots (41)$$

i.e., the group advances with a constant velocity equal to *half* that of the component waves. The group does not, however, maintain a constant amplitude as it proceeds, it is easily seen from (22) that for a given value of λ the amplitude varies inversely as \sqrt{x} .

It appears that the region in the immediate neighbourhood of the origin may be regarded as a kind of source, emitting on each side an endless succession of waves of continually increasing amplitude and frequency, whose subsequent careers are governed by the laws above explained. This persistent activity of the source is not paradoxical, for our assumed initial accumulation of a finite volume of elevated fluid on an infinitely narrow base implies an unlimited store of energy.

In any practical case, however, the initial elevation is distributed over a band of finite breadth, we will denote this breadth by l . The disturbance at any point P is made up of parts due to the various elements, $\delta\alpha$, say, of the breadth l , these are to be calculated by the preceding formulae, and integrated over the breadth of the band. In the result, the mathematical infinity and other perplexing peculiarities, which we meet with in the case of a concentrated line-source, disappear. It would be easy to write down the requisite formulae, but, as they are not very tractable, and contain nothing not implied in the preceding statement, they may be passed over. It is more instructive to examine, in a general way, how the previous results will be modified.

The initial stages of the disturbance at a distance x , such that l/x is small, will evidently be much the same as on the former hypothesis, the parts due to the various elements $\delta\alpha$ will simply reinforce one another, and the result will be sufficiently expressed by (14) or (22) provided we multiply by

$$\int_{-\infty}^{\infty} f(\alpha) d\alpha,$$

i.e., by the sectional area of the initially elevated fluid. The formula (22), in particular, will hold when $gt^2/2x$ is large, so long as the wave-length λ at the point considered is large compared with l , i.e., by (38), so long as $gt^2/2x \cdot l/x$ is small. But when, as t increases, the length of the waves at x becomes comparable with or smaller than l , the contributions from the different parts of l are no longer sensibly in the same phase, and we have something analogous to 'interference' in the optical sense. The result will, of course, depend on the special character of the initial distribution of the values of $f(\alpha)$ over the space l^* , but it is plain that the increase of amplitude must at length be arrested, and that ultimately we shall have a gradual dying out of the disturbance.

There is one feature generally characteristic of the later stages which must be more particularly adverted to, as it has been the cause of some perplexity, viz. a fluctuation in the amplitude of the waves. This is readily accounted for on 'interference' principles. As a sufficient illustration, let

* Cf Burnside, "On Deep-water Waves resulting from a Limited Original Disturbance," *Proc Lond Math Soc*, t xx p 22 (1888)

which is due solely to the given disturbing force, we may avail ourselves of an artifice due to Lord Rayleigh, viz. we introduce a small frictional force proportional to the velocity. This law of resistance does not profess to be altogether a natural one, but it serves to represent in a rough way the effect of small dissipative forces, and it has the great mathematical convenience that it does not interfere with the irrotational character of the motion. For if we write, in the equations of Art. 6,

$$X = -\mu u, \quad Y = -g - \mu v, \quad Z = -\mu w, \quad \dots \dots (1)$$

the investigation of Art. 33, when applied to a closed circuit, gives

$$\left(\frac{D}{Dt} + \mu\right) \int (u dx + v dy + w dz) = 0, \quad \dots \dots (2)$$

whence
$$\int (u dx + v dy + w dz) = C e^{-\mu t}. \quad \dots \dots (3)$$

Hence the circulation in a circuit moving with the fluid, if once zero, is always zero

If ϕ be the velocity-potential, the equations of motion have now the integral

$$p = \rho \left(\frac{\partial \phi}{\partial t} - g y + \mu \phi \right), \quad \dots \dots (4)$$

this gives
$$\eta = \frac{1}{g} \frac{\partial \phi_0}{\partial t} + \frac{\mu}{g} \phi_0 - \frac{p_0}{g \rho}, \quad \dots \dots (5)$$

where the suffixes indicate surface-values, as before. The kinematical relation (6) of Art. 226 holds as always

Hence, corresponding to an applied surface-pressure

$$p_0 = e^{i \sigma t} \cos k(x - \alpha), \quad \dots \dots (6)$$

we find
$$g \rho \eta = - \frac{g k}{g k - \sigma^2 + i \mu \sigma} e^{i \sigma t} \cos k(x - \alpha), \quad \dots \dots (7)$$

or, writing
$$\kappa = \frac{\sigma^2}{g}, \quad \mu_1 = \frac{\mu \sigma}{g}, \quad \dots \dots (8)$$

$$g \rho \eta = - \frac{h}{k - (\kappa - i \mu_1)} e^{i \sigma t} \cos k(x - \alpha) \quad \dots \dots (9)$$

It will be noticed that $2\pi/\kappa$ would be the length of *free* waves having the imposed period $2\pi/\sigma$.

Generalizing (9) by Fourier's method, we find that a surface-pressure

$$p_0 = f(x) e^{i \sigma t} \quad \dots \dots (10)$$

produces a surface-elevation given by

$$g \rho \eta = - \frac{1}{\pi} e^{i \sigma t} \int_0^\infty \frac{k dk}{k - (\kappa - i \mu_1)} \int_{-\infty}^\infty f(\alpha) \cos k(x - \alpha) d\alpha, \dots \dots (11)$$

or, as it may conveniently be written,

$$g\rho\eta = -\frac{1}{2\pi i} e^{i\sigma t} \frac{\partial}{\partial x} \int_0^\infty \frac{dk}{k - (\kappa - i\mu_1)} \int_{-\infty}^\infty \{e^{ik(x-\alpha)} - e^{-ik(x-\alpha)}\} f(\alpha) d\alpha \quad (12)$$

We shall suppose, for the most part, that $f(\alpha)$ is sensible only for values of α lying between certain finite limits. At points of the surface beyond these limits, to the right of the origin, $x - \alpha$ will be positive, and we then have

$$\int_0^\infty \frac{e^{-ik(x-\alpha)} dk}{k - (\kappa - i\mu_1)} = -2\pi i e^{-i(\kappa - i\mu_1)(x-\alpha)} + \int_0^\infty \frac{e^{-m(x-\alpha)} dm}{m - i\kappa - \mu_1}, \quad (13)$$

$$\int_0^\infty \frac{e^{ik(x-\alpha)} dk}{k - (\kappa - i\mu_1)} = \int_0^\infty \frac{e^{-m(x-\alpha)} dm}{m + i\kappa + \mu_1}, \quad \dots \quad (14)$$

as will be shewn presently (Art. 241) in connection with a related problem

Substituting in (12), and putting $\mu_1 = 0$, since the frictional term in (4) has now served its purpose, we find

$$g\rho\eta = -e^{i\sigma t} \frac{\partial}{\partial x} \int_{-\infty}^\infty \left\{ e^{-i\kappa(x-\alpha)} - \frac{\kappa}{\pi} \int_0^\infty \frac{e^{-m(x-\alpha)} dm}{m^2 + \kappa^2} \right\} f(\alpha) d\alpha \quad \dots (15)$$

At distances from the seat of the applied pressure which are great compared with $2\pi/\kappa$, the definite integral with respect to m is negligible, and we have

$$g\rho\eta = i\kappa \int_{-\infty}^\infty e^{i[\sigma t - \kappa(x-\alpha)]} f(\alpha) d\alpha = i(A + iB) e^{i(\sigma t - \kappa x)}, \quad \dots (16)$$

provided

$$A = \kappa \int_{-\infty}^\infty f(\alpha) \cos \kappa \alpha d\alpha, \quad B = \kappa \int_{-\infty}^\infty f(\alpha) \sin \kappa \alpha d\alpha. \quad \dots (17)$$

Hence, taking the real parts of our expressions, we find that the waves produced by an applied surface-pressure

$$p_0 = f(x) \cos \sigma t \dots \dots \dots (18)$$

are represented, at a sufficiently great distance on the positive side of the origin, by

$$g\rho\eta = -A \sin(\sigma t - \kappa x) - B \cos(\sigma t - \kappa x) \dots \dots (19)^*$$

This represents a train of progressive waves whose wave-length and wave-velocity are related in the usual way to the imposed period. If the pressure p_0 be symmetrical with respect to the origin, $B = 0$.

When the surface-pressure (18) is concentrated at the origin, so that $f(\alpha)$ vanishes for all but infinitesimal values of α , we write

$$\int_{-\infty}^\infty f(\alpha) d\alpha = P, \quad \dots \dots (20)$$

* Cambridge Mathematical Tripos, Part II, 1901.

and obtain from (15)

$$g\rho\eta = \imath\kappa P e^{\imath(\sigma t - \kappa x)} - \frac{\kappa P e^{\imath\sigma t}}{\pi} \int_0^\infty \frac{e^{-mx} m dm}{m^2 + \kappa^2} \\ = \imath\kappa P e^{\imath(\sigma t - \kappa x)} - \frac{\kappa P}{\pi} e^{\imath\sigma t} \left\{ \frac{1}{\kappa^2 x^2} - \frac{3}{\kappa^4 x^4} + \frac{5}{\kappa^6 x^6} - \dots \right\}, \quad \dots\dots(21)$$

where the series in $\{ \}$ is semi-convergent

In the case of an integral pressure $P e^{\imath\sigma t}$ uniformly distributed over the space between $x = \pm a$, we should obtain

$$g\rho\eta = \imath P \frac{\sin \kappa a}{a} e^{\imath(\sigma t - \kappa x)} - \frac{\kappa P}{\pi a} e^{\imath\sigma t} \int_0^\infty \frac{e^{-mx} \sinh ma}{m^2 + \kappa^2} dm \quad (22)$$

This is on the supposition that x is positive and greater than a . If x lie between 0 and a , the details of the work require some modification, it will be found that

$$g\rho\eta = -\frac{P}{a} e^{\imath(\sigma t - \kappa a)} \cos \kappa x + \frac{\kappa P}{\pi a} e^{\imath\sigma t} \int_0^\infty \frac{e^{-ma} \cosh mx}{m^2 + \kappa^2} dm \quad (23)$$

At the point $x = a$ the values of η given by (22) and (23) differ by

$$\frac{P}{2g\rho a} e^{\imath\sigma t},$$

the amplitude of this discontinuity being exactly that which would be caused by a statical difference of pressure $P/2a$

Again, if

$$p_0 = \frac{P}{\pi} \frac{b}{b^2 + x^2} e^{\imath\sigma t} = \frac{P}{\pi} e^{\imath\sigma t} \int_0^\infty e^{-kb} \cos kx dk, \quad \dots\dots\dots(24)$$

we should find

$$g\rho\eta = \imath\kappa P e^{-\kappa b} e^{\imath(\sigma t - \kappa x)} - \frac{P}{\pi} e^{\imath\sigma t} \int_0^\infty \frac{\kappa \cos mb + m \sin mb}{m^2 + \kappa^2} e^{-mx} m dm. \quad \dots\dots(25)$$

It is of some interest to calculate the mean rate at which an integral pressure $P \cos \sigma t$ does work in generating waves. In the case of a concentrated pressure, taking the real part of (21), we have, at the origin ($x = 0$),

$$-\frac{\partial \eta}{\partial t} = \frac{\kappa \sigma P}{g\rho} \cos \sigma t + \text{a term in } \sin \sigma t \quad \dots \dots \dots (26)$$

The required mean rate is therefore

$$\frac{\kappa \sigma P^2}{2g\rho} \quad \text{or} \quad \frac{\sigma^3 P^2}{2g^2\rho}, \quad \dots\dots\dots(27)$$

varying as the *cube* of the frequency. The circumstance that the ineffectual term involving $\sin \sigma t$, in (26), is infinite need not dismay us. The difficulty does not occur when the pressure is diffused. Thus, in the case of a uniform

pressure distributed over the space between $x = \pm a$, we easily find from (23) that the mean rate of work is

$$\frac{\sigma^2 P^2}{2g^2 \rho} \left(\frac{\sin \kappa a}{\kappa a} \right)^2 \cdot \dots \dots \dots (28)$$

This agrees with (27) when κa is infinitely small*.

240. We may next calculate the effect of an arbitrary, but steady, application of pressure to the surface of a stream. We shall consider only the state of steady motion which, under the influence of dissipative forces, however small, will ultimately establish itself†.

In the absence of such forces, the problem is, like that of Art 239, indeterminate, for we can always superpose a train of free waves, of arbitrary amplitude, and of wave-length such that their velocity relative to the water is equal and opposite to that of the stream, in which case they will maintain a fixed position in space.

To avoid this indeterminateness, we will assume that the deviation of any particle of the fluid from the state of uniform flow is resisted by a force proportional to the *relative* velocity, so that

$$X = -\mu(u - c), \quad Y = -g - \mu v, \quad \dots \dots \dots (1)$$

where c denotes the velocity of the stream in the direction of x -positive. We now have

$$\frac{p}{\rho} = \text{const} - gy + \mu(cx + \phi) - \frac{1}{2}q^2, \quad \dots \dots \dots (2)$$

this being, in fact, the form assumed by Art. 21 (2) when we write

$$\Omega = gy - \mu(cx + \phi), \quad \dots \dots \dots (3)$$

in accordance with (1) above

To calculate, in the first place, the effect of a simple-harmonic distribution of pressure we assume

$$\frac{\phi}{c} = -x + \beta e^{ky} \sin kx, \quad \frac{\psi}{c} = -y + \beta e^{ky} \cos kx. \quad \dots (4)$$

* The substance of Arts 236—239 is taken from a paper "On Deep-Water Waves," *Proc Lond Math Soc* (2), t. ii p. 371 (1904)

† The first steps of the following investigation are adapted from a paper by Lord Rayleigh, "The Form of Standing Waves on the Surface of Running Water," *Proc Lond Math Soc*, t. xv p. 69 (1883) [*Sci Papers*, t. ii p. 258], being simplified by the omission, for the present, of all reference to Capillarity. The definite integrals involved are treated, however, in a somewhat more general manner, and the discussion of the results necessarily follows a different course.

The problem had been treated by Popoff, "Solution d'un problème sur les ondes permanentes," *Liouville* (2) t. iii p. 251 (1858), his analysis is correct, but regard is not had to the indeterminate character of the problem (in the absence of friction), and the results are consequently not pushed to a practical interpretation.

The equation (2) becomes, on neglecting the square of $k\beta$,

$$\frac{p}{\rho} = -gy + \beta e^{ky} (kc^2 \cos kx + \mu c \sin kx) \quad . \quad . \quad (5)$$

This gives for the variable part of the pressure at the upper surface ($\psi = 0$)

$$p_0 = \rho\beta \{(kc^2 - g) \cos kx + \mu c \sin kx\}, \quad . \quad . \quad (6)$$

which is equal to the real part of

$$\rho\beta (kc^2 - g - i\mu c) e^{ikx}$$

If we equate the coefficient to C , we may say that to the pressure

$$p_0 = C e^{ikx} \quad . \quad . \quad . \quad (7)$$

corresponds the surface-form

$$gpy = \frac{\kappa}{k - \kappa - i\mu_1} C e^{ikx}, \quad . \quad . \quad . \quad (8)$$

where we have written κ for g/c^2 , so that $2\pi/\kappa$ is the wave-length of the free waves which could maintain their position against the flow of the stream. We have also put $\mu/c = \mu_1$, for shortness.

Hence, taking the real parts, we find that the surface-pressure

$$p_0 = C \cos kx \quad . \quad . \quad . \quad . \quad . \quad (9)$$

produces the wave-form

$$gpy = \kappa C \frac{(k - \kappa) \cos kx - \mu_1 \sin kx}{(k - \kappa)^2 + \mu_1^2} \quad . \quad . \quad . \quad (10)$$

This shews that if μ be small the wave-crests will coincide in position with the maxima, and the troughs with the minima, of the applied pressure, when the wave-length is less than $2\pi/\kappa$, whilst the reverse holds in the opposite case. This is in accordance with a general principle. If we impress on everything a velocity $-c$ parallel to x , the result obtained by putting $\mu_1 = 0$ in (10) is seen to be merely a special case of Art 167 (13).

In the critical case of $k = \kappa$, we have

$$gpy = -\frac{\kappa C}{\mu_1} \sin kx, \quad . \quad . \quad . \quad (11)$$

shewing that the excess of pressure is now on the slopes which face down the stream. This explains roughly how a system of progressive waves may be maintained against our assumed dissipative forces by a properly adjusted distribution of pressure over their slopes.

241 The solution expressed by (10) may be generalized, in the first place by the addition of an arbitrary constant to x , and secondly by a sum-

mation with respect to k . In this way we may construct the effect of any arbitrary distribution of pressure, say

$$p_0 = f(x), \quad . \quad . \quad . \quad . \quad . \quad (12)$$

with the help of Fourier's theorem (Art 236 (4))

We will suppose, in the first instance, that $f(x)$ vanishes for all but infinitely small values of x , for which it becomes infinite in such a way that

$$\int_{-\infty}^{\infty} f(x) dx = P, \quad . \quad . \quad . \quad . \quad (13)$$

this will give us the effect of an integral pressure P concentrated on an infinitely narrow band of the surface at the origin. Replacing C in (10) by $P/\pi \delta k$, and integrating with respect to k between the limits 0 and ∞ , we obtain

$$gpy = \frac{\kappa P}{\pi} \cdot \int_0^{\infty} \frac{(k - \kappa) \cos kx - \mu_1 \sin kx}{(k - \kappa)^2 + \mu_1^2} dk \quad . \quad . \quad . \quad (14)$$

If we put $\zeta = k + im$, where k, m are taken to be the rectangular coordinates of a variable point in a plane, the properties of the expression (14) are contained in those of the complex integral

$$\int \frac{e^{i\zeta x}}{\zeta - c} d\zeta \quad . \quad . \quad . \quad . \quad (15)$$

It is known that the value of this integral, taken round the boundary of any area which does not include the singular point ($\zeta = c$), is zero. In the present case we have $c = \kappa + i\mu_1$, where κ and μ_1 are both positive.

Let us first suppose that x is positive, and let us apply the above theorem to the region which is bounded externally by the line $m=0$ and by an infinite semicircle, described with the origin as centre on the side of this line for which m is positive, and internally by a small circle surrounding the point (κ, μ_1) . The part of the integral due to the infinite semicircle obviously vanishes, and it is easily seen, putting $\zeta - c = re^{i\theta}$, that the part due to the small circle is

$$-2\pi i e^{i(\kappa + i\mu_1)x},$$

if the direction of integration be chosen in accordance with the rule of Art 32. We thus obtain

$$\int_{-\infty}^0 \frac{e^{ikx}}{k - (\kappa + i\mu_1)} dk + \int_0^{\infty} \frac{e^{ikx}}{k - (\kappa + i\mu_1)} dk - 2\pi i e^{i(\kappa + i\mu_1)x} = 0,$$

which is equivalent to

$$\int_0^{\infty} \frac{e^{ikx}}{k - (\kappa + i\mu_1)} dk = 2\pi i e^{i(\kappa + i\mu_1)x} + \int_0^{\infty} \frac{e^{-ikx}}{k + (\kappa + i\mu_1)} dk \quad . \quad . \quad . \quad (16)$$

On the other hand, when x is negative we may take the integral (15) round the contour made up of the line $m=0$ and an infinite semicircle lying on the side for which m is negative. This gives the same result as before, with the omission of the term due to the singular point, which is now external to the contour. Thus, for x negative,

$$\int_0^{\infty} \frac{e^{ikx}}{k - (\kappa + i\mu_1)} dk = \int_0^{\infty} \frac{e^{-ikx}}{k + (\kappa + i\mu_1)} dk \quad . \quad . \quad . \quad (17)$$

An alternative form of the last term in (16) may be obtained by integrating round the contour made up of the negative portion of the axis of k , and the positive portion of the axis of m , together with an infinite quadrant. We thus find

$$\int_{-\infty}^0 \frac{e^{ikx}}{k - (\kappa + i\mu_1)} dk + \int_0^{\infty} \frac{e^{-mx}}{m - (\kappa + i\mu_1)} dm = 0,$$

which is equivalent to

$$\int_{-\infty}^0 \frac{e^{-ikx}}{k + (\kappa + i\mu_1)} dk = \int_0^{\infty} \frac{e^{-mx}}{m - \mu_1 - i\kappa} dm \quad \dots \quad (18)$$

This is for x positive. In the case of x negative, we must take as our contour the negative portions of the axes of k , m , and an infinite quadrant. This leads to

$$\int_0^{\infty} \frac{e^{-ikx}}{k + (\kappa + i\mu_1)} dk = \int_0^{\infty} \frac{e^{mx}}{m + \mu_1 - i\kappa} dm, \quad \dots \quad (19)$$

as the transformation of the second member of (17)

In the foregoing argument μ_1 is positive. The corresponding results for the integral

$$\int_{\zeta} \frac{e^{i\zeta x}}{\zeta - (\kappa - i\mu_1)} d\zeta \quad \dots \quad (20)$$

are not required for our immediate purpose, but it will be convenient to state them for future reference. For x positive, we find

$$\int_0^{\infty} \frac{e^{ikx}}{k - (\kappa - i\mu_1)} dk = \int_0^{\infty} \frac{e^{-ikx}}{k + (\kappa - i\mu_1)} dk = \int_0^{\infty} \frac{e^{-mx}}{m + \mu_1 + i\kappa} dm, \quad \dots \quad (21)$$

whilst, for x negative,

$$\begin{aligned} \int_0^{\infty} \frac{e^{ikx}}{k - (\kappa - i\mu_1)} dk &= -2\pi i e^{(\kappa - i\mu_1)x} + \int_0^{\infty} \frac{e^{-ikx}}{k + (\kappa - i\mu_1)} dk \\ &= -2\pi i e^{(\kappa - i\mu_1)x} + \int_0^{\infty} \frac{e^{mx}}{m - \mu_1 - i\kappa} dm \quad \dots \quad (22) \end{aligned}$$

The verification is left to the reader*

If we take the real parts of the formulae (16), (18), and (17), (19), respectively, we obtain the results which follow

The formula (14) is equivalent, for x positive, to

$$\begin{aligned} \frac{\pi g \rho}{\kappa P} \cdot y &= -2\pi e^{-\mu_1 x} \sin \kappa x + \int_0^{\infty} \frac{(k + \kappa) \cos kx - \mu_1 \sin kx}{(k + \kappa)^2 + \mu_1^2} dk \\ &= -2\pi e^{-\mu_1 x} \sin \kappa x + \int_0^{\infty} \frac{(m - \mu_1) e^{-mx} dm}{(m - \mu_1)^2 + \kappa^2}, \quad \dots \quad (23) \end{aligned}$$

and, for x negative, to

$$\frac{\pi g \rho}{\kappa P} \cdot y = \int_0^{\infty} \frac{(m + \mu_1) e^{mx} dm}{(m + \mu_1)^2 + \kappa^2} \quad \dots \quad (24)$$

The interpretation of these results is simple. The first term of (23) represents a train of simple-harmonic waves, on the down-stream side of the

* For another treatment of these integrals, see Dini, *Vorlesungen ueber d. Lehre v. d. einfachen u. mehrfachen bestimmten Integralen* (ed. Arendt), Braunschweig, 1904, p. 170.

origin, of wave-length $2\pi c^2/g$, with amplitudes gradually diminishing according to the law $e^{-\mu_1 x}$. The remaining part of the deformation of the free-surface, expressed by the definite integrals in (23) and (24), though very great for small values of x , diminishes very rapidly as x increases, however small the value of the frictional coefficient μ_1 .

When μ_1 is infinitesimal, our results take the simpler forms

$$\begin{aligned} \frac{\pi g \rho}{\kappa P} y &= -2\pi \sin \kappa x + \int_0^\infty \frac{\cos kx}{k + \kappa} dk \\ &= -2\pi \sin \kappa x + \int_0^\infty \frac{me^{-mx}}{m^2 + \kappa^2} dm, \quad \dots \quad (25) \end{aligned}$$

for x positive, and

$$\frac{\pi g \rho}{\kappa P} \cdot y = \int_0^\infty \frac{\cos kx}{k + \kappa} dk = \int_0^\infty \frac{me^{mx}}{m^2 + \kappa^2} dm, \quad \dots \quad (26)$$

for x negative. The part of the disturbance of level which is represented by the definite integrals in these expressions is now symmetrical with respect to the origin, and diminishes constantly as the distance from the origin increases. When κx is moderately large we have, as in Art. 239, the semi-convergent expansion

$$\int_0^\infty \frac{me^{-mx}}{m^2 + \kappa^2} dm = \frac{1}{\kappa^2 x^2} - \frac{3!}{\kappa^4 x^4} + \frac{5!}{\kappa^6 x^6} - \dots \quad (27)$$

It appears that at a distance of about half a wave-length from the origin, on the down-stream side, the simple-harmonic wave-profile is fully established.

The definite integrals in (25) and (26) can be reduced to known functions as follows. If we put $(k + \kappa)x = u$, we have, for x positive,

$$\begin{aligned} \int_0^\infty \frac{\cos kx}{k + \kappa} dk &= \int_{\kappa x}^\infty \frac{\cos(\kappa x - u)}{u} du \\ &= -\text{Ci } \kappa x \cos \kappa x + \left(\frac{1}{2}\pi - \text{Si } \kappa x\right) \sin \kappa x, \quad \dots \quad (28) \end{aligned}$$

where, in conformity with the usual notation,

$$\text{Ci } u = - \int_u^\infty \frac{\cos u}{u} du, \quad \text{Si } u = \int_0^u \frac{\sin u}{u} du \quad \dots \quad (29)$$

The functions $\text{Ci } u$ and $\text{Si } u$ have been tabulated by Glaisher*. It appears that as u

* "Tables of the Numerical Values of the Sine-Integral, Cosine-Integral, and Exponential-Integral," *Phil. Trans.*, 1870. The expression of the last integral in (26) in terms of the sine- and cosine-integrals, was obtained, in a different manner from the above, by Schlömilch, "Sur l'intégrale définie $\int_0^\infty \frac{d\theta}{\theta^2 + a^2} e^{-x\theta}$," *Crelle*, t. xxxiii. (1846), see also De Morgan, *Differential and Integral Calculus*, London, 1842, p. 654, and Dirichlet, *Vorlesungen*, p. 208.

increases from zero they tend very rapidly to their asymptotic values 0 and $\frac{1}{2}\pi$, respectively. For small values of u we have

$$\left. \begin{aligned} \text{Ci } u &= \gamma + \log u - \frac{u^2}{2 \cdot 2!} + \frac{u^4}{4 \cdot 4!} - \dots, \\ \text{Si } u &= u - \frac{u^3}{3 \cdot 3!} + \frac{u^5}{5 \cdot 5!} - \dots, \end{aligned} \right\} \dots \dots \dots (30)$$

where γ is Euler's constant .5772.

It is easily found from (23) and (24) that when μ_1 is infinitesimal, the integral depression of the surface is

$$-\int_{-\infty}^{\infty} y dx = \frac{P}{g\rho}, \quad \dots \dots \dots (31)$$

exactly as if the fluid were at rest

242 The expressions (23), (24) and (25), (26) alike make the elevation infinite at the origin, but this difficulty disappears when the pressure, which we have supposed concentrated on a mathematical line of the surface, is diffused over a band of finite breadth.

To calculate the effect of a distributed pressure

$$p_0 = f(x), \quad \dots \dots \dots (32)$$

it is only necessary to write $x - \alpha$ for x in (25) and (26), to replace P by $f(\alpha) \delta \alpha$, and to integrate the resulting value of y with respect to α between the proper limits. It follows from known principles of the Integral Calculus that if p_0 be finite the integrals will be finite for all values of x .

In the case of a uniform pressure p_0 , applied to the part of the surface extending from $-\infty$ to the origin, we easily find by integration of (23), for $x > 0$,


$$g\rho y = -2p_0 \cos \kappa x + \frac{\kappa p_0}{\pi} \int_0^{\infty} \frac{e^{-m x} dm}{m^2 + \kappa^2}, \quad \dots \dots \dots (33)$$

where μ_1 has been put = 0. Again, if the pressure p_0 be applied to the part of the surface extending from 0 to $+\infty$, we find, for $x < 0$,

$$g\rho y = \frac{\kappa p_0}{\pi} \int_0^{\infty} \frac{e^{m x} dm}{m^2 + \kappa^2} \quad \dots \dots \dots (34)$$

From these results we can easily deduce the requisite formulae for the case of a uniform pressure acting on a band of finite breadth. The definite integral in (33) and (34) can be evaluated in terms of the functions $\text{Ci } u$, $\text{Si } u$, thus in (33)

$$\kappa \int_0^{\infty} \frac{e^{-m x} dm}{m^2 + \kappa^2} = \int_0^{\infty} \frac{\sin kx}{k + \kappa} dk = \left(\frac{1}{2}\pi - \text{Si } \kappa x\right) \cos \kappa x + \text{Ci } \kappa x \sin \kappa x. \dots (35)$$



In this way the diagram on p 384 was constructed, it represents the case where the band (AB) has a breadth κ^{-1} , or 159 of the length of a standing wave

The circumstances in any such case might be realized approximately by dipping the edge of a slightly inclined board into the surface of a stream, except that the pressure on the wetted area of the board would not be uniform, but would diminish from the central parts towards the edges. To secure a uniform pressure, the board would have to be curved towards the edges, to the shape of the portion of the wave-profile included between the points A , B in the figure.

It will be noticed that if the breadth of the band be an exact multiple of the wave-length ($2\pi/\kappa$), we have zero elevation of the surface at a distance, on the down-stream as well as on the up-stream side of the source of disturbance.

The diagram shews certain peculiarities at the points A , B due to the discontinuity in the applied pressure. A more natural representation of a local pressure is obtained if we assume

$$p_0 = \frac{P}{\pi} \frac{b}{b^2 + x^2} \quad \dots \dots \dots (36)$$

We may write this in the form

$$p_0 = \frac{P}{\pi} \frac{1}{b - ix} = \frac{P}{\pi} \int_0^\infty e^{-kb + i kx} dk, \quad \dots (37)$$

provided it is understood that, in the end, only the real part is to be retained. On reference to Art 240 (7), (8) we see that the corresponding elevation of the free surface is given by

$$g\rho y = \frac{\kappa P}{\pi} \int_0^\infty \frac{e^{-kb + i kx}}{k - \kappa - i\mu_1} dk \quad \dots \dots (38)$$

By the method of Art. 241, we find that this is equivalent, for $x > 0$, to

$$g\rho y = \frac{\kappa P}{\pi} \left\{ 2\pi i e^{(\kappa + i\mu_1)(ix - b)} + \int_0^\infty \frac{e^{-mb - m\alpha}}{m - \mu_1 + i\kappa} dm \right\}, \quad \dots (39)$$

and, for $x < 0$, to

$$g\rho y = \frac{\kappa P}{\pi} \int_0^\infty \frac{e^{mb + m\alpha}}{m + \mu_1 - i\kappa} dm \quad \dots \dots (40)$$

Hence, taking real parts, and putting $\mu_1 = 0$, we find

$$g\rho y = -2\kappa P e^{-\kappa b} \sin \kappa x + \frac{P}{\pi} \int_0^\infty \frac{m \cos mb - \kappa \sin mb}{m^2 + \kappa^2} e^{-m\alpha} dm, \quad [x > 0], \quad (41)$$

$$g\rho y = \frac{\kappa P}{\pi} \int_0^\infty \frac{m \cos mb - \kappa \sin mb}{m^2 + \kappa^2} e^{m\alpha} dm, \quad [x < 0]. \quad (42)$$

The factor $e^{-\kappa b}$ in the first term of (41) shews the effect of diffusing the pressure. It is easily proved that the values of y and dy/dx given by these formulae agree when $x = 0^*$.

243 If in the problem of Art 240 we suppose the depth to be finite and equal to h , there will be, in the absence of dissipation, indeterminateness or not, according as the velocity c of the stream is less or greater than $(gh)^{\frac{1}{2}}$, the maximum wave-velocity for the given depth, see Art. 230. The difficulty presented by the former case can be evaded by the introduction of small frictional forces, but it may be anticipated from the preceding investigation that the main effect of these will be to annul the elevation of the surface at a distance on the up-stream side of the region of disturbed pressure, and if we assume this at the outset we need not complicate our equations by retaining the frictional terms†.

For the case of a simple-harmonic distribution of pressure we assume

$$\left. \begin{aligned} \frac{\phi}{c} &= -x + \beta \cosh k(y+h) \sin kx, \\ \frac{\psi}{c} &= -y + \beta \sinh k(y+h) \cos kx, \end{aligned} \right\} \dots \dots \dots (1)$$

as in Art 230 (3) Hence, at the surface

$$y = \beta \sinh kh \cos kx, \quad \dots \dots \dots (2)$$

we have

$$\frac{p_0}{\rho} = -gy - \frac{1}{2}(q^2 - c^2) = \beta(kc^2 \cosh kh - g \sinh kh) \cos kx, \quad (3)$$

so that to the imposed pressure

$$p_0 = C \cos kx, \quad \dots \dots \dots (4)$$

will correspond the surface-form

$$y = \frac{C}{\rho} \cdot \frac{\sinh kh}{kc^2 \cosh kh - g \sinh kh} \cos kx. \quad \dots \dots \dots (5)$$

As in Art. 240, the pressure is greatest over the troughs, and least over the crests, of the waves, or *vice versa*, according as the wave-length is greater or less than that corresponding to the velocity c , in accordance with general theory

The generalization of (5) by Fourier's method gives

$$y = \frac{P}{\pi \rho} \int_0^\infty \frac{\sinh kh \cos kx}{kc^2 \cosh kh - g \sinh kh} dk, \quad \dots \dots \dots (6)$$

* A different treatment of the problem of Arts 241, 242, is given in a recent paper by Lord Kelvin, "Deep Water Ship-Waves," *Proc. R. S. Edin.*, t xxv p 562 (1905) [*Phil. Mag.* (6), t ix p 733]

† There is no difficulty in so modifying the investigation as to take the frictional forces into account, when these are very small.

as the representation of the effect of a pressure of integral amount P applied to a narrow band of the surface at the origin This may be written

$$\frac{\pi \rho c^2}{P} \cdot y = \int_0^\infty \frac{\cos(xu/h)}{u \coth u - gh/c^2} du \quad \dots \dots \dots (7)$$

Now consider the complex integral

$$\int \frac{e^{i\omega\zeta/h}}{\zeta \coth \zeta - gh/c^2} d\zeta, \dots \dots \dots (8)$$

where $\zeta = u + iv$ The function under the integral sign has a singular point at $\zeta = \mp i\omega$, according as x is positive or negative, and the remaining singular points are given by the roots of

$$\frac{\tanh \zeta}{\zeta} = \frac{c^2}{gh} \quad \dots \dots \dots (9)$$

Since (6) is an even function of x , it will be sufficient to take the case of x positive

Let us first suppose that $c^2 > gh$ The roots of (9) are then all pure imaginaries, viz they are of the form $\pm i\beta$, where β is a root of

$$\frac{\tan \beta}{\beta} = \frac{c^2}{gh} \quad \dots \dots \dots (10)$$

The smallest positive root of this lies between 0 and $\frac{1}{2}\pi$, and the higher roots approximate with increasing closeness to the values $(s + \frac{1}{2})\pi$, where s is integral. We will denote these roots in order by $\beta_0, \beta_1, \beta_2, \dots$ Let us now take the integral (8) round the contour made up of the axis of u , an infinite semicircle on the positive side of this axis, and a series of small circles surrounding the singular points $\zeta = i\beta_0, i\beta_1, i\beta_2, \dots$ The part due to the infinite semicircle obviously vanishes Again, it is known that if a be a simple root of $f(\zeta) = 0$ the value of the integral

$$\int \frac{F(\zeta)}{f(\zeta)} d\zeta$$

taken in the positive direction round a small circle enclosing the point $\zeta = a$ is equal to*

$$2\pi i \frac{F(a)}{f'(a)} \quad \dots \dots \dots (11)$$

Now in the case of (8) we have

$$f'(a) = \coth a - a(\coth^2 a - 1) = \frac{1}{a} \left\{ \frac{gh}{c^2} \left(1 - \frac{gh}{c^2} \right) + a^2 \right\}, \quad \dots \dots (12)$$

whence, putting $a = i\beta_s$, the expression (11) takes the form

$$2\pi B_s e^{-\beta_s x/h}, \quad \dots \dots \dots (13)$$

where

$$B_s = \frac{\beta_s}{\beta_s^2 - \frac{gh}{c^2} \left(1 - \frac{gh}{c^2} \right)} \quad \dots \dots \dots (14)$$

The theorem in question then gives

$$\int_{-\infty}^0 \frac{e^{ixu/h}}{u \coth u - gh/c^2} du + \int_0^\infty \frac{e^{ixu/h}}{u \coth u - gh/c^2} du - 2\pi \sum_0^\infty B_s e^{-\beta_s x/h} = 0. \quad \dots (15)$$

If in the former integral we write $-u$ for u , this becomes

$$\int_0^\infty \frac{\cos(xu/h)}{u \coth u - gh/c^2} du = \pi \sum_0^\infty B_s e^{-\beta_s x/h} \quad \dots \dots \dots (16)$$

* Forsyth, *Theory of Functions*, Art 24.

The surface-form is then given by

$$y = \frac{P}{\rho c^2} \sum_0^\infty B_s e^{-\beta_s x/h} \quad . \quad . \quad . \quad (17)$$

It appears that the surface-elevation (which is symmetrical with respect to the origin) is insensible beyond a certain distance from the seat of disturbance

When, on the other hand, $c^2 < gh$, the equation (9) has a pair of real roots ($\pm a$, say), the lowest roots ($\pm \beta_0$) of (10) having now disappeared. The integral (7) is then indeterminate, owing to the function under the integral sign becoming infinite within the range of integration. One of its values, viz the 'principal value,' in Cauchy's sense, can however be found by the same method as before, provided we exclude the points $\zeta = \pm a$ from the contour by drawing semicircles of small radius ϵ round them, on the side for which v is positive. The parts of the complex integral (8) due to these semicircles will be

$$-2\pi \frac{e^{\pm i a x/h}}{f'(\pm a)},$$

where $f'(a)$ is given by (12), and their sum is therefore equal to

$$2\pi A \sin \frac{ax}{h}, \quad . \quad . \quad . \quad (18)$$

where

$$A = \frac{a}{a^2 - \frac{gh}{c^2} \left(\frac{gh}{c^2} - 1 \right)} \quad . \quad . \quad . \quad (19)$$

The equation corresponding to (16) now takes the form

$$\left\{ \int_0^{a-\epsilon} + \int_{a+\epsilon}^\infty \right\} \frac{\cos xu/h}{u \coth u - gh/c^2} du = -\pi A \sin \frac{ax}{h} + \pi \sum_1^\infty B_s e^{-\beta_s x/h}, \quad (20)$$

so that, if we take the principal value of the integral in (7), the surface-form on the side of x -positive is

$$y = -\frac{P}{\rho c^2} A \sin \frac{ax}{h} + \frac{P}{\rho c^2} \sum_1^\infty B_s e^{-\beta_s x/h} \quad . \quad . \quad . \quad (21)$$

Hence at a distance from the origin the deformation of the surface consists of the simple-harmonic train of waves indicated by the first term, the wave-length $2\pi h/a$ being that corresponding to a velocity of propagation c relative to still water

Since the function (7) is symmetrical with respect to the origin, the corresponding result for negative values of x is

$$y = \frac{P}{\rho c^2} A \sin \frac{ax}{h} + \frac{P}{\rho c^2} \sum_1^\infty B_s e^{\beta_s x/h} \quad . \quad . \quad . \quad (22)$$

The general solution of our indeterminate problem is completed by adding to (21) and (22) terms of the form

$$C \cos \frac{ax}{h} + D \sin \frac{ax}{h} \quad . \quad . \quad . \quad (23)$$

The practical solution, including the effect of infinitely small dissipative forces, is obtained by so adjusting these terms as to make the deformation of the surface insensible at a distance on the up-stream side. We thus get, finally, for positive values of x ,

$$y = -\frac{2P}{\rho c^2} A \sin \frac{ax}{h} + \frac{P}{\rho c^2} \sum_1^\infty B_s e^{-\beta_s x/h}, \quad . \quad . \quad . \quad (24)$$

and, for negative values of x ,

$$y = \frac{P}{\rho c^2} \sum_1^\infty B_s e^{\beta_s x/h} \quad . \quad . \quad . \quad . \quad . \quad (25)$$

For a different method of reducing the definite integral in this problem we must refer to the paper by Lord Kelvin cited below

244 The same method can be employed to investigate the effect on a uniform stream of slight inequalities in the bed*

Thus, in the case of a simple-harmonic corrugation given by

$$y = -h + \gamma \cos kx, \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

the origin being as usual in the undisturbed surface, we assume

$$\left. \begin{aligned} \frac{\phi}{c} &= -x + (\alpha \cosh ky + \beta \sinh ky) \sin kx, \\ \frac{\psi}{c} &= -y + (\alpha \sinh ky + \beta \cosh ky) \cos kx \end{aligned} \right\} \quad . \quad . \quad . \quad . \quad (2)$$

The condition that (1) should be a stream-line is

$$\gamma = -\alpha \sinh kh + \beta \cosh kh. \quad . \quad . \quad . \quad . \quad (3)$$

The pressure-formula is

$$\frac{p}{\rho} = \text{const} - gy + kc^2 (\alpha \cosh ky + \beta \sinh ky) \cos kx, \quad . \quad . \quad . \quad (4)$$

approximately, and therefore along the stream-line $\psi = 0$

$$\frac{p}{\rho} = \text{const} + (kc^2 \alpha - g\beta) \cos kx,$$

so that the condition for a free surface gives

$$kc^2 \alpha - g\beta = 0 \quad . \quad . \quad . \quad . \quad . \quad (5)$$

The equations (3) and (5) determine α and β The profile of the free surface is given by

$$y = \beta \cos kx \\ = \frac{\gamma}{\cosh kh - g/kc^2 \cdot \sinh kh} \cos kx \quad . \quad . \quad . \quad . \quad (6)$$

If the velocity of the stream be less than that of waves in still water of uniform depth h , of the same length as the corrugations, as determined by Art. 228 (4), the denominator is negative, so that the undulations of the free surface are inverted relatively to those of the bed In the opposite case, the undulations of the surface follow those of the bed, but with a different vertical

* Sir W Thomson, "On Stationary Waves in Flowing Water," *Phil Mag* (5), t. xxii pp 353, 445, 517 (1886), and t xxiii. p 52 (1887)

scale When c has precisely the value given by Art. 228 (4), the solution fails, as we should expect, through the vanishing of the denominator To obtain an intelligible result in this case we should be compelled to take special account of dissipative forces.

The above solution may be generalized, by Fourier's Theorem, so as to apply to the case where the inequalities of the bed follow any arbitrary law Thus, if the profile of the bed be given by

$$y = -h + f(x) = -h + \frac{1}{\pi} \int_0^\infty dk \int_{-\infty}^\infty f(\xi) \cos k(x-\xi) d\xi, \quad \dots \quad (7)$$

that of the free surface will be obtained by superposition of terms of the type (6) due to the various elements of the Fourier-integral, thus

$$y = \frac{1}{\pi} \int_0^\infty dk \int_{-\infty}^\infty \frac{f(\xi) \cos k(x-\xi)}{\cosh kh - g/kc^2 \sinh kh} d\xi \quad \dots \quad (8)$$

In the case of a single isolated inequality at the point of the bed vertically beneath the origin, this reduces to

$$\begin{aligned} y &= \frac{Q}{\pi} \int_0^\infty \frac{\cos kx}{\cosh kh - g/kc^2 \sinh kh} dk \\ &= \frac{Q}{\pi h} \int_0^\infty \frac{u \cos(xu/h)}{u \cosh u - gh/c^2 \sinh u} du, \quad \dots \quad (9) \end{aligned}$$

where Q represents the area included by the profile of the inequality above the general level of the bed For a depression Q will of course be negative

The discussion of the integral

$$\int \frac{\zeta e^{ix\zeta/h} d\zeta}{\zeta \cosh \zeta - gh/c^2 \sinh \zeta} \quad \dots \quad (10)$$

can be conducted exactly as in Art. 243 The function to be integrated differs only by the factor $\zeta/(\sinh \zeta)$, the singular points therefore are the same as before, and we can at once write down the results

Thus when $c^2 > gh$ we find, for the surface-form,

$$y = \frac{Q}{h} \sum_0^\infty B_s \frac{\beta_s}{\sin \beta_s} e^{\mp \beta_s x/h}, \quad \dots \quad (11)$$

the upper or the lower sign being taken according as x is positive or negative

When $c^2 < gh$, the 'practical' solution is, for x positive,

$$y = -\frac{2Q}{h} A \frac{a}{\sinh a} \sin \frac{ax}{h} + \frac{Q}{h} \sum_1^\infty B_s \frac{\beta_s}{\sin \beta_s} e^{-\beta_s x/h}, \quad \dots \quad (12)$$

and, for x negative,

$$y = \frac{Q}{h} \sum_1^\infty B_s \frac{\beta_s}{\sin \beta_s} e^{\beta_s x/h}. \quad \dots \quad (13)$$

The symbols a , β_s , A , B_s have here exactly the same meanings as in Art. 243*.

* A very interesting drawing of the wave-profile produced by an isolated inequality in the bed is given in Lord Kelvin's paper, *Phil Mag* (5), t xxii p. 529 The effect of an abrupt change of level in the bed has been discussed by Wien, *Hydrodynamik*, p. 201

245. If in the problems of Arts 241, 243 we impress on everything a velocity — c parallel to x , we get the case of a pressure-disturbance advancing with constant velocity c over the surface of otherwise still water. In this form of the question it is not difficult to understand, in a general way, the origin of the train of waves following the disturbance.

If, for example, equal impulses be applied in succession to a series of equidistant parallel lines of the surface, at equal intervals of time, each impulse will produce on its own account a system of waves of the character investigated in Art. 237. The systems due to the different impulses will be superposed, with the obvious result that the only parts which reinforce one another will be those which have the wave-length appropriate to the velocity c with which the disturbing influence advances over the surface, and which are (moreover) travelling in the direction of this advance. And the investigations of Arts 234, 238 shew that the groups of waves, of this particular length, which are produced, are continually being left behind.

These results have a bearing on such questions as the 'wave-resistance' of ships. It appears from Art 243, in the two-dimensional form of the problem, that a local disturbance of pressure advancing with velocity c [$< (gh)^{\frac{1}{2}}$] over still water of depth h is followed by a simple-harmonic train of waves of the length $(2\pi/\kappa)$ appropriate to the velocity c , and determined therefore by Art 228 (4), whilst the water in front of the disturbance is sensibly at rest. If we imagine a fixed vertical plane to be drawn in the rear of the disturbance, the space in front of this plane gains, per unit time, the additional wave-energy $\frac{1}{2}g\rho a^2c$, where a is the amplitude of the waves generated. The energy transmitted across the plane is given by Art 235 (14). The difference represents the work done by the disturbing force. Hence if R denote the horizontal resistance experienced by the disturbing body, we have

$$R = \frac{1}{2}g\rho a^2 \left(1 - \frac{2\kappa h}{\sinh 2\kappa h}\right) \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

As c increases from zero to $(gh)^{\frac{1}{2}}$, κh diminishes from ∞ to 0, and therefore R diminishes from $\frac{1}{2}g\rho a^2$ to 0*.

When $c > (gh)^{\frac{1}{2}}$, the water is unaffected beyond a certain small distance on either side, and the wave-resistance R is then zero†.

An interesting variation of the question is presented when we have a layer of fluid on the top of another fluid of somewhat greater density. If

* It must be remarked, however, that the amplitude a due to a disturbance of given character will also vary with c . This is exemplified in Art 242 (41), in the case of infinite depth. It appears that, if P be given, $a \propto \kappa e^{-\kappa b}$, where $\kappa = g/c^2$.

† Cf Sir W Thomson "On Ship Waves," *Proc. Inst. Mech. Eng.*, Aug 3, 1887 [*Popular Lectures and Addresses*, London, 1889-94, t. iii p 450]. A formula equivalent to (1) was given in a paper by the same author, *Phil. Mag.* (5), t. xxii p 451.

ρ, ρ' be the densities of the lower and upper fluids, respectively, and if the depth of the upper layer be h' , whilst that of the lower fluid is practically infinite, the results of Stokes quoted in Art 231 shew that two wave-systems may be generated, whose lengths ($2\pi/\kappa$) are related to the velocity c of the disturbance by the formulae

$$c^2 = \frac{g}{\kappa}, \quad c^2 = \frac{\rho - \rho'}{\rho \coth \kappa h' + \rho'} \frac{g}{\kappa}. \quad \dots \dots \dots (2)$$

It is easily proved that the value of κ determined by the second equation is real only so long as

$$c^2 < \frac{\rho - \rho'}{\rho} gh' \quad \dots \dots \dots (3)$$

If c exceeds the critical value thus indicated, only one type of waves will be generated, and if the difference of densities be slight the wave-resistance will be practically the same as in the case of a single fluid, the circumstances being similar to those of Art 241. But if c fall below the critical value, a second type of waves may be produced, in which the amplitude at the common boundary greatly exceeds that at the upper surface, and it is to these waves that the 'dead-water resistance' referred to in Art 231 is attributed*

Waves of Finite Amplitude.

246. The restriction to 'infinitely small' motions, in the investigations of Arts 226, . implies that the ratio (a/λ) of the maximum elevation to the wave-length must be small. The determination of the wave-forms which satisfy the conditions of uniform propagation without change of type, when this restriction is abandoned, forms the subject of a classical research by Stokes†

The problem is most conveniently treated as one of steady motion. If we neglect small quantities of the order α^3/λ^3 , the solution of the problem in the case of infinite depth is contained in the formulae‡

$$\frac{\phi}{c} = -x + \beta e^{ky} \sin kx, \quad \frac{\psi}{c} = -y + \beta e^{ky} \cos kx \quad \dots \quad (1)$$

* Ekman, *l.c. ante* p 354

† "On the theory of Oscillatory Waves," *Camb Trans*, t viii (1847) [reprinted, with a "Supplement," *Math and Phys Papers*, t i pp 197, 314]

The outlines of a more general investigation, including the case of permanent waves on the common surface of two horizontal currents, have been given by von Helmholtz, "Zur Theorie von Wind und Wellen," *Berl Monatsber*, July 25, 1889 [*Ges Abh*, t iii p 309] See also Wien, *Hydrodynamik*, p 169

‡ Lord Rayleigh, *l.c. ante* p. 246

The equation of the wave-profile $\psi = 0$ is found by successive approximations to be

$$y = \beta e^{ky} \cos kx = \beta \left(1 + ky + \frac{1}{2}k^2 y^2 + \dots \right) \cos kx \\ = \frac{1}{2}k\beta^2 + \beta \left(1 + \frac{3}{8}k^2\beta^2 \right) \cos kx + \frac{1}{2}k\beta^2 \cos 2kx + \frac{3}{8}k^2\beta^3 \cos 3kx + \dots, \quad (2)$$

or, if we put $\beta(1 + k^2\beta^2) = a$,

$$y - \frac{1}{2}ka^2 = a \cos kx + \frac{1}{2}ka^2 \cos 2kx + \frac{3}{8}k^2a^3 \cos 3kx + \dots \quad (3)$$

So far as we have developed it, this coincides with the equation of a trochoid, in which the circumference of the rolling circle is $2\pi/k$, or λ , and the length of the arm of the tracing point is a

We have still to shew that the condition of uniform pressure along this stream-line can be satisfied by a suitably chosen value of c . We have, from (1), without approximation

$$\frac{p}{\rho} = \text{const.} - gy - \frac{1}{2}c^2 \{ 1 - 2k\beta e^{ky} \cos kx + k^2\beta^2 e^{2ky} \}, \quad \dots (4)$$

and therefore, at points of the line $y = \beta e^{ky} \cos kx$,

$$\frac{p}{\rho} = \text{const.} + (kc^2 - g)y - \frac{1}{2}k^2c^2\beta^2 e^{2ky} \\ = \text{const.} + (kc^2 - g - k^3c^2\beta^2)y + \dots \quad \dots (5)$$


Hence the condition for a free surface is satisfied, to the present order of approximation, provided

$$c^2 = \frac{g}{k} + k^2c^2\beta^2 = \frac{g}{k} (1 + k^2a^2). \quad \dots (6)$$

This determines the velocity of progressive waves of permanent type, and shews that it increases somewhat with the amplitude a

For methods of proceeding to a higher approximation, and for the treatment of the case of finite depth, we must refer to the original investigations of Stokes

The figure shews the wave-profile, as given by (3), in the case of $ka = \frac{1}{2}$, or $a/\lambda = 0.796$



The approximately trochoidal form gives an outline which is sharper near the crests, and flatter in the troughs, than in the case of the simple-harmonic waves of infinitely small amplitude investigated in Art 228, and these features become accentuated as the amplitude is increased. If the trochoidal form were exact, instead of merely approximate, the limiting form would

have cusps at the crests, as in the case of Gerstner's waves to be considered presently

In the actual problem, which is one of irrotational motion, the extreme form has been shewn by Stokes*, in a very simple manner, to have sharp angles of 120° . The question being still treated as one of steady motion, the motion near the angle will be given by the formulae of Art 63, viz if we introduce polar coordinates r, θ with the crest as origin, and the initial line of θ drawn vertically downwards, we have

$$\psi = Cr^m \cos m\theta, \dots \dots \dots (7)$$

with the condition that $\psi = 0$ when $\theta = \pm \alpha$ (say), so that $m\alpha = \frac{1}{2}\pi$ This formula leads to

$$q = mCr^{m-1}, \dots \dots \dots (8)$$

where q is the resultant fluid velocity But since the velocity vanishes at the crest, its value at a neighbouring point of the free surface will be given by

$$q^2 = 2gr \cos \alpha, \dots \dots \dots (9)$$

as in Art. 24 (2). Comparing (8) and (9), we see that we must have $m = \frac{3}{2}$, and therefore $\alpha = \frac{1}{3}\pi$ †.

In the case of progressive waves advancing over still water, the particles at the crests, when these have their extreme forms, are moving forwards with exactly the velocity of the wave.

Another point of interest in connection with these waves of permanent type is that they possess, relatively to the undisturbed water, a certain momentum in the direction of wave-propagation The momentum, per wavelength, of the fluid contained between the free surface and a depth h (beneath the level of the origin) which we will suppose to be great compared with λ , is

$$-\rho \iint \frac{\partial \psi}{\partial y} dx dy = \rho ch\lambda, \dots \dots \dots (10)$$

since $\psi = 0$, by hypothesis, at the surface, and $= ch$, by (1), at the great depth h In the absence of waves, the equation to the upper surface would be $y = \frac{1}{2}ka^2$, by (3), and the corresponding value of the momentum would therefore be

$$\rho c (h + \frac{1}{2}ka^2) \lambda. \dots \dots \dots (11)$$

The difference of these results is equal to

$$\pi \rho a^2 c, \dots \dots \dots (12)$$

* *Math and Phys. Papers*, t 1. p 227.

† The wave-profile has been investigated and traced by Michell, "The Highest Waves in Water," *Phil. Mag* (5), t xxxvi p 480 (1893). He finds that the extreme height is 142λ , and that the wave-velocity is greater than in the case of infinitely small height in the ratio of 1.2 to 1.

which gives therefore the momentum, per wave-length, of a system of progressive waves of permanent type, moving over water which is at rest at a great depth.

To find the vertical distribution of this momentum, we remark that the equation of a stream-line $\psi = ch'$ is found from (2) by writing $y + h'$ for y , and $\beta e^{-kh'}$ for β . The mean-level of this stream-line is therefore given by

$$y = -h' + \frac{1}{2}k\beta^2e^{-2kh'} \dots\dots\dots (13)$$

Hence the momentum, in the case of undisturbed flow, of the stratum of fluid included between the surface and the stream-line in question would be, per wave-length,

$$\rho c\lambda \{h' + \frac{1}{2}k\beta^2(1 - e^{-2kh'})\} \dots\dots\dots (14)$$

The actual momentum being $\rho ch'\lambda$, we have, for the momentum of the same stratum in the case of waves advancing over still water,

$$\pi\rho a^2c(1 - e^{-2kh'}). \dots\dots\dots (15)$$

It appears therefore that the motion of the individual particles, in these progressive waves of permanent type, is not purely oscillatory, and that there is, on the whole, a slow but continued advance in the direction of wave-propagation* The rate of this flow at a depth h' is found approximately by differentiating (15) with respect to h' , and dividing by $\rho\lambda$, viz. it is

$$k^2a^2ce^{-2kh'} \dots\dots\dots (16)$$

This diminishes rapidly from the surface downwards

247 A system of *exact* equations, expressing a possible form of wave-motion when the depth of the fluid is infinite, was given so long ago as 1802 by Gerstner†, and at a later period independently by Rankine‡ The circumstance, however, that the motion in these waves is not irrotational detracts somewhat from the physical interest of the results

If the axis of x be horizontal, and that of y be drawn vertically upwards, the formulae in question may be written

$$x = a + \frac{1}{k}e^{kb}\sin k(a+ct), \qquad y = b - \frac{1}{k}e^{kb}\cos k(a+ct), \dots\dots (1)$$

where the specification is on the Lagrangian plan (Art. 16), viz, a, b are two parameters serving to identify a particle, and x, y are the coordinates of this particle at time t The constant k determines the wave-length, and c is the velocity of the waves, which are travelling in the direction of x -negative

* Stokes, *l c ante* p 392 Another very simple proof of this statement has been given by Lord Rayleigh, *l c ante* p 246
† Professor of Mathematics at Prague, 1789-1823 His paper, "Theorie der Wellen," was published in the *Abh d k bohm Ges. d Wiss*, 1802 [Gilbert's *Annalen d Physik*, t xxxii (1809)].
‡ "On the Exact Form of Waves near the Surface of Deep Water," *Phil Trans*, 1863 [*Sc Papers*, p 481]

To verify this solution, and to determine the value of c , we remark, in the first place, that

$$\frac{\partial (x, y)}{\partial (a, b)} = 1 - e^{2kb}, \quad \dots \quad (2)$$

so that the Lagrangian equation of continuity (Art 16 (2)) is satisfied. Again, substituting from (1) in the equations of motion (Art 13), we find

$$\left. \begin{aligned} \frac{\partial}{\partial a} \left(\frac{p}{\rho} + gy \right) &= kc^2 e^{kb} \sin k(a + ct), \\ \frac{\partial}{\partial b} \left(\frac{p}{\rho} + gy \right) &= -kc^2 e^{kb} \cos k(a + ct) + kc^2 e^{2kb}, \end{aligned} \right\} \dots \dots (3)$$

whence

$$\frac{p}{\rho} = \text{const.} - g \left\{ b - \frac{1}{k} e^{kb} \cos k(a + ct) \right\} - c^2 e^{kb} \cos k(a + ct) + \frac{1}{2} c^2 e^{2kb} \dots (4)$$


For a particle on the free surface the pressure must be constant, this requires

$$c^2 = \frac{g}{k}, \quad \dots \dots (5)$$

as in Art. 228 This makes

$$\frac{p}{\rho} = \text{const} - gb + \frac{1}{2} c^2 e^{2kb} \dots \dots (6)$$

It is obvious from (1) that the path of any particle (a, b) is a circle of radius $k^{-1} e^{kb}$



The figure shews the forms of the lines of equal pressure $b = \text{const.}$, for

a series of equidistant values of b^* . These curves are trochoids, obtained by rolling circles of radii k^{-1} on the under sides of the lines $y = b + k^{-1}$, the distances of the tracing points from the respective centres being $k^{-1}e^{kb}$. Any one of these lines may be taken as representing the free surface, the extreme-admissible form being that of the cycloid. The dotted lines represent the successive forms taken by a line of particles which is vertical when it passes through a crest or a trough.

It has already been stated that the motion of the fluid in these waves is rotational. To prove this, we remark that

$$\begin{aligned} u\delta x + v\delta y &= \left(\dot{x} \frac{\partial x}{\partial a} + y \frac{\partial y}{\partial a} \right) \delta a + \left(\dot{x} \frac{\partial x}{\partial b} + y \frac{\partial y}{\partial b} \right) \delta b \\ &= \frac{c}{k} \delta \{ e^{kb} \sin k(a + ct) \} + ce^{2kb} \delta a, \quad \dots \quad (7) \end{aligned}$$

which is not an exact differential.

The circulation in the boundary of the parallelogram whose vertices coincide with the particles

$$(a, b), (a + \delta a, b), (a + \delta a, b + \delta b), (a, b + \delta b)$$

$$\text{is, by (7),} \quad - \frac{\partial}{\partial b} (ce^{2kb} \delta a) \delta b,$$

and the area of the circuit is

$$\frac{\partial(x, y)}{\partial(a, b)} \delta a \delta b = (1 - e^{2kb}) \delta a \delta b$$

Hence the angular velocity (ω) of the element (a, b) is

$$\omega = - \frac{kce^{2kb}}{1 - e^{2kb}} \quad \dots \quad (8)$$

This is greatest at the surface, and diminishes rapidly with increasing depth. Its *sense* is opposite to that of the revolution of the particles in their circular orbits.

A system of waves of the present type cannot therefore be originated from rest, or destroyed, by the action of forces of the kind contemplated in the general theorem of Arts 17, 33. We may however suppose that by properly adjusted pressures applied to the surface of the waves the liquid is gradually reduced to a state of flow in horizontal lines, in which the velocity (u') is a function of the ordinate (y') only†. In this state we shall have $\partial x' / \partial a = 1$, while y' is a function of b determined by the condition

$$\frac{\partial(x', y')}{\partial(a, b)} = \frac{\partial(x, y)}{\partial(a, b)}, \quad \dots \quad (9)$$

* The diagram is very similar to the one given originally by Gerstner, and copied more or less closely by subsequent writers. A version of Gerstner's investigation, including in one respect a correction, was given in the preceding edition of this work, Art 233.

† For a fuller statement of the argument see Stokes, *Math. and Phys. Papers*, t. i. p. 222.

or
$$\frac{\partial y'}{\partial b} = 1 - e^{2kb} \dots\dots\dots (10)$$

This makes
$$\frac{\partial u'}{\partial b} = \frac{\partial u'}{\partial y'} \frac{\partial y'}{\partial b} = -2\omega \frac{\partial y'}{\partial b} = 2kce^{2kb}, \dots\dots\dots (11)$$

and therefore
$$u' = ce^{2kb} \dots\dots\dots (12)$$

Hence, for the genesis of the waves by ordinary forces, we require as a foundation an initial horizontal motion, in the direction *opposite* to that of propagation of the waves ultimately set up, which diminishes rapidly from the surface downwards, according to the law (12), where b is a function of y' determined by

$$y' = b - \frac{1}{2}k^{-1}e^{2kb} \dots\dots\dots (13)$$

It is to be noted that these rotational waves, when established, have zero momentum.

248 Scott Russell, in his interesting experimental investigations*, was led to pay great attention to a particular type which he calls the 'solitary wave.' This is a wave consisting of a single elevation, of height not necessarily small compared with the depth of the fluid, which, if properly started, may travel for a considerable distance along a uniform canal, with little or no change of type. Waves of depression, of similar relative amplitude, were found not to possess the same character of permanence, but to break up into series of shorter waves.

The solitary type may be regarded as an extreme case of Stokes' oscillatory waves of permanent type, the wave-length being great compared with the depth of the canal, so that the widely separated elevations are practically independent of one another. The methods of approximation employed by Stokes become, however, unsuitable when the wave-length much exceeds the depth; and subsequent investigations of the solitary wave have proceeded on different lines

The first of these was given independently by Boussinesq† and Lord Rayleigh‡. The latter writer, treating the problem as one of steady motion, starts virtually from the formula

$$\phi + i\psi = F(x + iy) = e^{iy \frac{d}{dx}} F(x), \dots\dots\dots (1)$$

where $F(x)$ is real. This is especially appropriate to cases, such as the

* "Report on Waves," *Brit Ass Rep*, 1844

† *Comptes Rendus*, June 19, 1871.

‡ *Lc ante* p. 246

present, where one of the family of stream-lines is straight. We derive from (1)

$$\phi = F - \frac{y^2}{2!} F'' + \frac{y^4}{4!} F^{iv} - \dots, \quad \psi = y F' - \frac{y^3}{3!} F''' + \frac{y^5}{5!} F^{v} - \dots, \quad (2)$$

where the accents denote differentiations with respect to x . The stream-line $\psi = 0$ here forms the bed of the canal, whilst at the free surface we have $\psi = -ch$, where c is the uniform velocity, and h the depth, in the parts of the fluid at a distance from the wave, whether in front or behind

The condition of uniform pressure along the free surface gives

$$u^2 + v^2 = c^2 - 2g(y - h), \quad \dots \dots \dots (3)$$

or, substituting from (2),

$$F'^2 - y^2 F' F''' + y^2 F''^2 + \dots = c^2 - 2g(y - h). \quad \dots \dots (4)$$

But, from (2) we have, along the same surface,

$$y F' - \frac{y^3}{3!} F''' + \dots = -ch. \quad \dots \dots \dots (5)$$

It remains to eliminate F between (4) and (5); the result will be a differential equation to determine the ordinate y of the free surface. If (as we will suppose) the function $F'(x)$ and its differential coefficients vary so slowly with x that they change only by a small fraction of their values when x increases by an amount comparable with the depth h , the terms in (4) and (5) will be of gradually diminishing magnitude, and the elimination in question can be carried out by a process of successive approximation

Thus, from (5)

$$F' = -\frac{ch}{y} + \frac{1}{6} y^2 F''' + \dots = -ch \left\{ \frac{1}{y} + \frac{1}{6} y^2 \left(\frac{1}{y} \right)'' + \dots \right\}, \quad \dots (6)$$

and if we retain only terms up to the order last written, the equation (4) becomes

$$\frac{1}{y^2} - \frac{2}{3} y \left(\frac{1}{y} \right)'' + y^2 \left(\frac{1}{y} \right)' = \frac{1}{h^2} - \frac{2g(y - h)}{c^2 h^2},$$

or, on reduction,

$$\frac{1}{y^2} + \frac{2}{3} \frac{y''}{y} - \frac{1}{3} \frac{y'^2}{y^3} = \frac{1}{h^2} - \frac{2g(y - h)}{c^2 h^2} \quad \dots \dots \dots (7)$$

If we multiply by y' , and integrate, determining the arbitrary constant so as to make $y' = 0$ for $y = h$, we obtain

$$-\frac{1}{y} + \frac{1}{3} \frac{y'^2}{y} = -\frac{1}{h} + \frac{y - h}{h^2} - \frac{g(y - h)^2}{c^2 h^2},$$

or

$$y'^2 = 3 \frac{(y - h)^2}{h^2} \left(1 - \frac{gy}{c^2} \right) \quad \dots \dots \dots (8)$$

Hence y' vanishes only for $y = h$ and $y = c^2/g$, and since the last factor must be positive, it appears that c^2/g is a *maximum* value of y . Hence the wave is necessarily one of elevation only, and, denoting by a the maximum height above the undisturbed level, we have

$$c^2 = g(h + a), \dots\dots\dots (9)$$

which is exactly the empirical formula for the wave-velocity adopted by Russell

The extreme form of the wave must, as in Art 246, have a sharp crest of 120° , and since the fluid is there at rest we shall have $c^2 = 2ga$. If the formula (9) were applicable to such an extreme case, it would follow that $a = h$.

If we put, for shortness,

$$y - h = \eta, \quad \frac{h^2(h + a)}{3a} = b^2, \quad \dots\dots\dots (10)$$

we find, from (8)


$$\eta' = \pm \frac{\eta}{b} \left(1 - \frac{\eta}{a}\right)^{\frac{1}{2}}, \quad \dots\dots\dots (11)$$

the integral of which is

$$\eta = a \operatorname{sech}^2 \frac{1}{2} \frac{x}{b}, \quad \dots\dots\dots (12)$$

if the origin of x be taken beneath the summit

There is no definite 'length' of the wave, but we may note, as a rough indication of its extent, that the elevation has one-tenth of its maximum value when $x/b = 3.636$



The annexed drawing of the curve

$$y = 1 + \frac{1}{2} \operatorname{sech}^2 \frac{1}{2} x$$

represents the wave-profile in the case $a = \frac{1}{2}h$. For lower waves the scale of y must be contracted, and that of x enlarged, as indicated by the annexed table giving the ratio b/h , which determines the horizontal scale, for various values of a/h .

It will be found, on reviewing the above investigation, that the approximations consist in neglecting the fourth power of the ratio $(h + a)/2b$

If we impress on the fluid a velocity $-c$ parallel to x we get the case of a progressive wave on still water. It is not difficult to shew that, when the ratio a/h is small, the path of each particle is then an arc of a parabola having its axis vertical and apex upwards*

a/h	b/h
1	1.915
2	1.414
3	1.202
4	1.080
5	1.000
6	.943
7	.900
8	.866
9	.839
10	.816

It might appear, at first sight, that the above theory is inconsistent with the results of Art 185, where it was argued that a wave of finite height whose length is great compared with the depth must inevitably suffer a continual change of form as it advances, the changes being the more rapid the greater the elevation above the undisturbed level. The investigation referred to postulates, however, a length so great that the vertical acceleration may be neglected, with the result that the horizontal velocity is sensibly uniform from top to bottom (Art 171). The numerical table above given shews, on the other hand, that the longer the 'solitary wave' is, the lower it is. In other words, the more nearly it approaches to the character of a 'long' wave, in the sense of Art 171, the more easily is the change of type averted by a slight adjustment of the particle-velocities†.

The motion at the outskirts of the solitary wave can be represented by a very simple formula. Considering a progressive wave travelling in the direction of x -positive, and taking the origin in the bottom of the canal, at a point in the front part of the wave, we assume

$$\phi = Ae^{-m(x-ct)} \cos my \quad . \quad . \quad . \quad (13)$$

This satisfies $\nabla^2\phi=0$, and the surface-condition

$$\frac{\partial^2\phi}{\partial t^2} + g \frac{\partial\phi}{\partial y} = 0 \quad . \quad . \quad . \quad . \quad . \quad . \quad (14)$$

will also be satisfied for $y=h$, provided

$$c^2 = gh \frac{\tan mh}{mh} \quad . \quad . \quad . \quad . \quad . \quad . \quad (15)$$

This will be found to agree approximately with Lord Rayleigh's investigation if we put $m=b^{-1}$.

The above remark, which was kindly communicated to the author by the late Sir George Stokes ‡, was suggested by an investigation by McCowan§, who shewed that the formula

$$\frac{\phi + \psi}{c} = -(x + \psi) + a \tanh \frac{1}{2} m (x + \psi), \quad . \quad . \quad . \quad . \quad . \quad . \quad (16)$$

* Boussinesq, l.c

† Stokes, "On the Highest Wave of Uniform Propagation," *Proc Camb Phil Soc*, t. iv. p 361 (1883) [*Math and Phys Papers*, t v p 140]

‡ Cf. his *Math and Phys. Papers*, t v p 162

§ "On the Solitary Wave," *Phil. Mag* (5), t. xxxii p 45 (1891).

satisfies the conditions very approximately, provided

$$c^2 = \frac{g}{m} \tan m h, \quad \dots \quad (17)$$

and

$$m a = \frac{2}{3} \sin^2 m (h + \frac{2}{3} a), \quad \alpha = a \tan \frac{1}{2} m (h + a), \quad \dots \quad (18)$$

where α denotes the maximum elevation above the mean level, and a is a subsidiary constant. In a subsequent paper* the extreme form of the wave when the crest has a sharp angle of 120° was examined. The limiting value of the ratio a/h was found to be 78, in which case the wave-velocity is given by $c^2 = 1.56gh$.

249 By a slight modification the investigation of Rayleigh and Boussinesq can be made to give the theory of a system of oscillatory waves of finite height in a canal of limited depth†. In the steady-motion form of the problem the momentum per wave-length (λ) is represented by

$$\iint \rho u dx dy = -\rho \int \frac{\partial \psi}{\partial x} dx dy = -\rho \psi_1 \lambda, \quad \dots \quad (19)$$

where ψ_1 corresponds to the free surface. If h be the mean depth, this momentum may be equated to $\rho c h \lambda$, where c denotes (in a sense) the mean velocity of the stream. On this understanding we have, at the surface, $\psi_1 = -ch$, as before. The arbitrary constant in (3), on the other hand, must be left for the moment undetermined, so that we write

$$u^2 + v^2 = C - 2gy. \quad \dots \quad (20)$$

We then find, in place of (8),

$$y'^2 = \frac{3g}{c^2 h^2} (y - l)(h_1 - y)(y - h_2), \quad \dots \quad (21)$$

where h_1, h_2 are the upper and lower limits of y , and

$$l = \frac{c^2 h^2}{gh_1 h_2} \dots \quad (22)$$

It is implied that l cannot be greater than h_2 .

$$\text{If we now write} \quad y = h_1 \cos^2 \chi + h_2 \sin^2 \chi, \quad \dots \quad (23)$$

$$\text{we find} \quad \beta \frac{d\chi}{dx} = \sqrt{\{1 - k^2 \sin^2 \chi\}}, \quad \dots \quad (24)$$

$$\text{where} \quad \beta = \sqrt{\left\{ \frac{4h_1 h_2 l}{3(h_1 - l)} \right\}}, \quad k^2 = \frac{h_1 - h_2}{h_1 - l} \dots \quad (25)$$

* "On the Highest Wave of Permanent Type," *Phil Mag* (5), t. xxxviii p 351 (1894)

† Korteweg and De Vries, "On the Change of Form of Long Waves advancing in a Rectangular Canal, and on a New Type of Long Stationary Waves," *Phil Mag* (5), t. xxxix p 422 (1895). The method adopted by these writers is somewhat different. Moreover, as the title indicates, the paper includes an examination of the manner in which the wave-profile is changing at any instant, if the conditions for permanency of type are not satisfied.

For other modifications of Lord Rayleigh's method reference may be made to Gwyther, *Phil Mag* (5), t. i pp 213, 308, 349 (1900).

Hence, if the origin of x be taken at a crest, we have

$$x = \beta \int_0^{\chi} \sqrt{1 - k^2 \sin^2 \chi} \, d\chi = \beta F(\chi, k), \dots \dots \dots (26)$$

and $y = h_2 + (h_1 - h_2) \operatorname{cn}^2 \frac{x}{\beta} \pmod{k} \dots \dots \dots (27)^*$

The wave-length is given by

$$\lambda = 2\beta \int_0^{1/2\pi} \frac{d\chi}{\sqrt{1 - k^2 \sin^2 \chi}} = 2\beta E_1(k). \dots \dots \dots (28)$$

Again, from (23) and (24),

$$\int_0^{\lambda} y dx = 2\beta \int_0^{1/2\pi} \frac{h_1 \cos^2 \chi + h_2 \sin^2 \chi}{\sqrt{1 - k^2 \sin^2 \chi}} d\chi = 2\beta \{l E_1(k) + (h_1 - l) E_1(k)\} \dots \dots \dots (29)$$

Since this must be equal to $h\lambda$, we have

$$(h - l) E_1(k) = (h_1 - l) E_1(k). \dots \dots \dots (30)$$

In equations (25), (28), (30) we have four relations connecting the six quantities h_1 , h_2 , l , k , λ , β , so that if two of these be assigned the rest are analytically determinate. The wave-velocity c is then given by (22)†. For example, the form of the waves, and their velocity, are determined by the length λ , and the height h_1 of the crests above the bottom.

The solitary wave of Art. 248 is included as a particular case. If we put $l = h_2$, we have $k = 1$, and the formulæ (28) and (30) then shew that $\lambda = \pi\beta$, $h_2 = h$.

250. The theory of waves of permanent type has been brought into relation with general dynamical principles by von Helmholtz‡.

If in the equations of motion of a 'gyrostatic' system, Art. 141 (24), we put

$$Q_1 = \frac{\partial V}{\partial q_1}, \quad Q_2 = \frac{\partial V}{\partial q_2}, \quad \dots, \quad Q_n = \frac{\partial V}{\partial q_n}, \quad \dots \dots (1)$$

where V is the potential energy, it appears that the conditions for steady motion, with q_1, q_2, \dots, q_n constant, are

$$\frac{\partial}{\partial q_1} (V + K) = 0, \quad \frac{\partial}{\partial q_2} (V + K) = 0, \quad \dots, \quad \frac{\partial}{\partial q_n} (V + K) = 0, \dots (2)$$

* The waves represented by (27) are called 'cnoidal waves' by the authors cited. For the method of proceeding to a higher approximation we must refer to the original paper.

† When the depth is finite, a question arises as to what is meant exactly by the 'velocity of propagation.' The velocity adopted in the text is that of the wave-profile relative to the centre of inertia of the mass of fluid included between two vertical planes at a distance apart equal to the wave-length. Cf. Stokes, *Math. and Phys. Papers*, t. i. p. 202.

‡ "Die Energie der Wogen und des Windes," *Berl. Monatsber.* July 17, 1890 [*Ges. Abh.*, t. iii. p. 333].

where K is the energy of the motion corresponding to any given values of the coordinates $q_1, q_2, \dots q_n$ when these are prevented from varying by the application of suitable extraneous forces.

This energy is here supposed expressed in terms of the constant momenta corresponding to the ignored coordinates χ, χ', \dots , and of the palpable coordinates $q_1, q_2, \dots q_n$. It may however also be expressed in terms of the velocities χ, χ', \dots and the coordinates $q_1, q_2, \dots q_n$, in this form we denote it by T_0 . It may be shewn, exactly as in Art 142, that $\partial T_0 / \partial q_r = -\partial K / \partial q_r$, so that the conditions (2) are equivalent to

$$\frac{\partial}{\partial q_1} (V - T_0) = 0, \quad \frac{\partial}{\partial q_2} (V - T_0) = 0, \quad \dots, \quad \frac{\partial}{\partial q_n} (V - T_0) = 0. \quad (3)$$

Hence the condition for free steady motion with any assigned constant values of $q_1, q_2, \dots q_n$ is that the corresponding value of $V + K$, or of $V - T_0$, should be stationary. Cf Art. 202 (11)

Further, if in the equations of Art 141 we write $-\partial V / \partial q_r + Q_r$ for Q_r , so that Q_r now denotes a component of extraneous force, we find, on multiplying by $q_1, q_2, \dots q_n$ in order, and adding,

$$\frac{d}{dt} (\mathcal{T} + V + K) = Q_1 \dot{q}_1 + Q_2 \dot{q}_2 + \dots + Q_n \dot{q}_n, \quad \dots \dots \dots (4)$$

where \mathcal{T} is the part of the energy which involves the velocities $\dot{q}_1, \dot{q}_2, \dots \dot{q}_n$. It follows, by the same argument as in Art. 204, that the condition for 'secular' stability, when there are dissipative forces affecting the coordinates $q_1, q_2, \dots q_n$, but not the ignored coordinates χ, χ', \dots , is that $V + K$ should be a minimum.

In the application to the problem of stationary waves, it will tend to clearness if we eliminate all infinities from the question by imagining that the fluid circulates in a ring-shaped canal of uniform rectangular section (the sides being horizontal and vertical), of very large radius. The generalized velocity $\dot{\chi}$ corresponding to the ignored coordinate may be taken to be the flux per unit breadth of the channel, and the constant momentum of the circulation may be replaced by the cyclic constant κ . The coordinates $q_1, q_2, \dots q_n$ of the general theory are now represented by the value of the surface-elevation (η) considered as a function of the longitudinal space-coordinate x . The corresponding components of extraneous force are represented by arbitrary pressures applied to the surface

If l denote the whole length of the circuit, then considering unit breadth of the canal we have

$$V = \frac{1}{2} g \rho \int_0^l \eta^2 dx, \quad \dots \dots \dots (5)$$

where η is subject to the condition

$$\int_0^l \eta dx = 0 \quad \dots \quad \dots \quad \dots \quad (6)$$

If we could with the same ease obtain a general expression for the kinetic energy of the steady motion corresponding to any prescribed form of the surface, the minimum condition in either of the forms above given would, by the usual processes of the Calculus of Variations, lead to a determination of the possible forms, if any, of stationary waves*

Practically, this is not feasible, except by methods of successive approximation, but we may illustrate the question by reproducing, on the basis of the present theory, the results already obtained for 'long' waves of infinitely small amplitude

If h be the depth of the canal, the velocity in any section when the surface is maintained at rest, with arbitrary elevation η , is $\chi/(h+\eta)$, where χ is the flux. Hence, for the cyclic constant,

$$\kappa = \chi \int_0^l (h+\eta)^{-1} dx = \frac{l\chi}{h} \left(1 + \frac{1}{h^2 l} \int_0^l \eta^2 dx \right), \quad (7)$$

approximately, where the term of the first order in η has been omitted, in virtue of (6)

The kinetic energy, $\frac{1}{2}\rho\kappa\chi$, may be expressed in terms of either χ or κ . We thus obtain the forms

$$T_0 = \frac{1}{2} \frac{\rho l \chi^2}{h} \left(1 + \frac{1}{h^2 l} \int_0^l \eta^2 dx \right), \quad \dots \quad (8)$$

$$K = \frac{1}{2} \frac{\rho h \kappa^2}{l} \left(1 - \frac{1}{h^2 l} \int_0^l \eta^2 dx \right). \quad \dots \quad \dots \quad (9)$$

The variable part of $V - T_0$ is

$$\frac{1}{2} \rho \left(g - \frac{\dot{\chi}^2}{h^3} \right) \int_0^l \eta^2 dx, \quad \dots \quad \dots \quad (10)$$

and that of $V + K$ is

$$\frac{1}{2} \rho \left(g - \frac{\kappa^2}{h l^2} \right) \int_0^l \eta^2 dx \quad \dots \quad \dots \quad (11)$$

It is obvious that these are both stationary for $\eta=0$; and that they will be stationary for any infinitely small values of η , provided $\dot{\chi}^2 = gh^3$, or $\kappa^2 = gh l^2$. If we put $\chi = ch$, or $\kappa = cl$, this condition gives

$$c^2 = gh, \quad \dots \quad \dots \quad (12)$$

in agreement with Art 174

It appears, moreover, that $\eta=0$ makes $V+K$ a maximum or a minimum according as c^2 is greater or less than gh . In other words, the plane form of the surface is secularly

* For some general considerations bearing on the problem of stationary waves on the common surface of two currents reference may be made to von Helmholtz' paper. This also contains, at the end, some speculations, based on calculations of energy and momentum, as to the length of the waves which would be excited in the first instance by a wind of given velocity. These appear to involve the assumption that the waves will necessarily be of permanent type, since it is only on some such hypothesis that we get a determinate value for the momentum of a train of waves of small amplitude.

stable if, and only if, $c < \sqrt{g\hbar}$. It is to be remarked, however, that the dissipative forces here contemplated are of a special character, viz. they affect the *vertical* motion of the surface, but not (directly) the flow of the liquid. It is otherwise evident from Art. 174 that if pressures be applied to maintain any given constant form of the surface, then if $c^2 > g\hbar$ these pressures must be greatest over the elevations and least over the depressions. Hence if the pressures be removed, the inequalities of the surface will tend to increase.

Wave-Propagation in Two Dimensions

251 We may next consider some cases of wave-propagation in two horizontal dimensions x, y . The axis of z being drawn vertically upwards, we have, on the hypothesis of infinitely small motions,

$$\frac{p}{\rho} = \frac{\partial \phi}{\partial t} - gz + F(t), \quad \dots \dots \dots (1)$$

where ϕ satisfies

$$\nabla^2 \phi = 0. \quad \dots \dots \dots (2)$$

The arbitrary function $F(t)$ may be supposed merged in the value of $\partial \phi / \partial t$.

If the origin be taken in the undisturbed surface, and if ζ denote the elevation at time t above this level, the pressure-condition to be satisfied at the surface is

$$\zeta = \frac{1}{g} \left[\frac{\partial \phi}{\partial t} \right]_{z=0}, \quad \dots \dots \dots (3)$$

and the kinematical surface-condition is

$$\frac{\partial \zeta}{\partial t} = - \left[\frac{\partial \phi}{\partial z} \right]_{z=0}, \quad \dots \dots \dots (4)$$

cf. Art. 226. Hence, for $z = 0$, we must have

$$\frac{\partial^2 \phi}{\partial t^2} + g \frac{\partial \phi}{\partial z} = 0, \quad \dots \dots \dots (5)$$

or, in the case of simple-harmonic motion,

$$\sigma^2 \phi = g \frac{\partial \phi}{\partial z}, \quad \dots \dots \dots (6)$$

if the time-factor be $e^{i(\sigma t + \epsilon)}$.

The fluid being supposed to extend to infinity, horizontally and downwards, we may briefly examine, in the first place, the effect of a local initial disturbance of the surface, in the case of symmetry about the origin.

The typical solution for the case of initial *rest* is easily seen, on reference to Art. 100, to be

$$\left. \begin{aligned} \phi &= g \frac{\sin \sigma t}{\sigma} e^{kz} J_0(k\varpi), \\ \zeta &= \cos \sigma t J_0(k\varpi), \end{aligned} \right\} \quad \dots \dots \dots (7)$$

provided $\sigma^2 = gk$, (8)

as in Art 227.

To generalize this, subject to the condition of symmetry, we have recourse to the theorem

$$f(\varpi) = \int_0^\infty J_0(k\varpi) k dk \int_0^\infty f(\alpha) J_0(k\alpha) \alpha d\alpha \quad \dots \quad (9)$$

of Art 100 (12). Thus, corresponding to the initial conditions,

$$\zeta = f(\varpi), \quad \phi_0 = 0, \quad \dots \quad (10)$$

we have
$$\left. \begin{aligned} \phi &= g \int_0^\infty \frac{\sin \sigma t}{\sigma} e^{kz} J_0(k\varpi) k dk \int_0^\infty f(\alpha) J_0(k\alpha) \alpha d\alpha, \\ \zeta &= \int_0^\infty \cos \sigma t J_0(k\varpi) k dk \int_0^\infty f(\alpha) J_0(k\alpha) \alpha d\alpha. \end{aligned} \right\} \quad (11)$$

If the initial elevation be concentrated in the immediate neighbourhood of the origin, then, assuming

$$\int_0^\infty f(\alpha) 2\pi \alpha d\alpha = 1, \quad \dots \quad (12)$$

we have
$$\phi = \frac{g}{2\pi} \int_0^\infty \frac{\sin \sigma t}{\sigma} e^{kz} J_0(k\varpi) k dk \quad \dots \quad (13)$$

Expanding, and making use of (8), we get

$$\phi = \frac{gt}{2\pi} \int_0^\infty \left\{ k - \frac{gt^2}{3!} k^3 + \frac{(gt^2)^2}{5!} k^5 - \dots \right\} e^{kz} J_0(k\varpi) dk \quad \dots \quad (14)$$

If we put $z = -r \cos \theta, \quad \varpi = r \sin \theta, \quad \dots \quad (15)$

we have
$$\int_0^\infty e^{kz} J_0(k\varpi) dk = \frac{1}{r}, \quad \dots \quad (16)$$

by Art 102 (9), and thence*

$$\int_0^\infty e^{kz} J_0(k\varpi) k^n dk = \left(\frac{\partial}{\partial z} \right)^n \frac{1}{r} = n! \frac{P_n(\mu)}{r^{n+1}}, \quad \dots \quad (17)$$

where $\mu = \cos \theta$ (cf Art. 85). Hence

$$\phi = \frac{gt}{2\pi} \left\{ \frac{P_1(\mu)}{r^2} - \frac{gt^2}{3!} \frac{P_2(\mu)}{r^3} + \frac{(gt^2)^2}{5!} \frac{P_3(\mu)}{r^4} - \dots \right\} \quad \dots \quad (18)$$

From this the value of ζ is to be obtained by (3) It appears from Arts 84, 85 that

$$P_{2n+1}(0) = 0, \quad P_{2n}(0) = (-)^n \frac{1 \cdot 3 \dots (2n-1)}{2 \cdot 4 \dots 2n}, \quad \dots \quad (19)$$

* Hobson, *Proc Lond Math Soc.*, t xxv. pp 72, 73 This formula may, however, be dispensed with, see the foot-note on p. 365 *ante*

whence

$$\zeta = \frac{1}{2\pi\omega^2} \left\{ \frac{1^2}{2^1} \frac{gt^2}{\omega} - \frac{1^2 \cdot 3^2}{6^1} \left(\frac{gt^2}{\omega} \right)^3 + \frac{1^2 \cdot 3^2 \cdot 5^2}{10^1} \left(\frac{gt^2}{\omega} \right)^5 - \dots \right\} \quad (20)^*$$

It follows that any particular phase of the motion is associated with a particular value of gt^2/ω , and thence that the various phases travel radially outwards from the origin, each with a constant acceleration

No exact equivalent for (20), analogous to the formula (20) of Art 236 which was obtained in the two-dimensional form of the problem, and accordingly suitable for discussion in the case where gt^2/ω is large, has as yet been discovered. Cauchy and Poisson have, however, given processes of approximation. The method of the latter writer is substantially as follows. Since, by Art 100 (7),

$$J_0(k\omega) = \frac{2}{\pi} \int_0^{\frac{1}{2}\pi} \cos(k\omega \cos \beta) d\beta, \quad (21)$$

the second of the equations (11) may be written, under the present circumstances,

$$\zeta = \lim_{z=0} \left[-\frac{1}{\pi^2 g} \frac{\partial^2}{\partial t^2} \int_0^\infty \cos \sigma t e^{kz} dk \int_0^{\frac{1}{2}\pi} \cos(k\omega \cos \beta) d\beta \right], \quad (22)$$

where z is supposed to be negative before the limit. It may be shewn, exactly as in Art 236, that when $gt^2/2\omega$, and therefore, *a fortiori*, $gt^2/(2\omega \cos \beta)$ is large,

$$\lim_{z=0} \int_0^\infty \cos \sigma t \cos(k\omega \cos \beta) e^{kz} dk = \frac{\sqrt{(\pi\omega')}}{2\omega \cos \beta} \left(\cos \frac{1}{2}\omega' + \sin \frac{1}{2}\omega' \right), \quad (23)$$

where $\omega' = gt^2/(2\omega \cos \beta)$. Hence

$$\zeta = -\frac{1}{(2\pi\omega)^{\frac{3}{2}} g^{\frac{1}{2}}} \frac{\partial^2}{\partial t^2} t \int_0^{\frac{1}{2}\pi} \left\{ \cos \left(\frac{1}{2}\omega \sec \beta \right) + \sin \left(\frac{1}{2}\omega \sec \beta \right) \right\} \frac{d\beta}{\cos^{\frac{3}{2}} \beta}, \dots (24)$$

where

$$\omega = \frac{gt^2}{2\omega} \dots \dots \dots (25)$$

The definite integral in (24) is equivalent to

$$\int_0^\infty \left\{ \cos \left(\frac{1}{2}\omega \cosh u \right) + \sin \left(\frac{1}{2}\omega \cosh u \right) \right\} \sqrt{(\cosh u)} du, \dots (26)$$

or

$$\int_0^\infty \left\{ \cos \left(\frac{1}{2}\omega + \omega \sinh^2 \frac{1}{2}u \right) + \sin \left(\frac{1}{2}\omega + \omega \sinh^2 \frac{1}{2}u \right) \right\} \times \left\{ 2d(\sinh \frac{1}{2}u) + \frac{2 \tanh \frac{1}{2}u d(\sinh^2 \frac{1}{2}u)}{\sqrt{(\cosh u) + \cosh \frac{1}{2}u}} \right\} \dots (27)$$

Since

$$\int_0^\infty \cos(\omega \sinh^2 \frac{1}{2}u) d(\sinh \frac{1}{2}u) = \int_0^\infty \sin(\omega \sinh^2 \frac{1}{2}u) d(\sinh \frac{1}{2}u) = \frac{1}{2} \sqrt{\frac{\pi}{2\omega}}, \dots (28)$$

the first part of the integral (27) reduces to

$$\sqrt{\frac{2\pi}{\omega}} \cos \frac{1}{2}\omega \dots (29)$$

The coefficient of $d(\sinh^2 \frac{1}{2}u)$, in the second part, vanishes for $u=0$ and $u=\infty$, and Poisson

* This result was given by Cauchy and Poisson

proceeds to shew by a series of partial integrations that, when ω is large, this second part may be neglected. Hence, substituting the form (29) in (24), we find

$$\zeta = -\frac{1}{2^{\frac{1}{2}}\pi\omega g} \frac{\partial^2}{\partial t^2} \cos \frac{gt^2}{4\omega}, \quad \dots \dots \quad (30)$$

or keeping, for consistency, only the most important term,

$$\zeta = \frac{gt^2}{2^{\frac{1}{2}}\pi\omega^3} \cos \frac{gt^2}{4\omega}, \quad \dots \dots \quad (31)$$

a result given by Cauchy and Poisson

It is not necessary to dwell on the interpretation, which will be readily understood from what has been said in Art 238 with respect to the two-dimensional case. The consequences were worked out in some detail by Poisson on the hypothesis of an initial paraboloidal depression.

When the initial data are of *impulse*, the typical solution is

$$\left. \begin{aligned} \phi &= \cos \sigma t e^{kz} J_0(k\omega), \\ \zeta &= -\frac{1}{g} \sigma \sin \sigma t J_0(k\omega), \end{aligned} \right\} \dots \dots \dots (32)$$

which, being generalized, gives, for the initial conditions

$$\rho\phi_0 = F(\omega), \quad \zeta = 0, \quad \dots \dots \dots (33)$$

the solution

$$\left. \begin{aligned} \phi &= \frac{1}{\rho} \int_0^\infty \cos \sigma t e^{kz} J_0(k\omega) k dk \int_0^\infty F(\alpha) J_0(k\alpha) \alpha d\alpha, \\ \zeta &= -\frac{1}{g\rho} \int_0^\infty \sigma \sin \sigma t J_0(k\omega) k dk \int_0^\infty F(\alpha) J_0(k\alpha) \alpha d\alpha. \end{aligned} \right\} \dots \dots (34)$$

In particular, for a concentrated impulse at the origin, such that

$$\int_0^\infty F(\alpha) 2\pi\alpha d\alpha = 1, \quad \dots \dots \dots (35)$$

we find

$$\phi = \frac{1}{2\pi\rho} \int_0^\infty \cos \sigma t e^{kz} J_0(k\omega) k dk \quad \dots \dots \dots (36)$$

Since this may be written

$$\phi = \frac{1}{2\pi\rho} \frac{\partial}{\partial t} \int_0^\infty \frac{\sin \sigma t}{\sigma} e^{kz} J_0(k\omega) k dk, \quad \dots \dots \dots (37)$$

we find, performing $1/g\rho \cdot \partial/\partial t$ on the results contained in (18) and (20),

$$\left. \begin{aligned} \phi &= \frac{1}{2\pi\rho} \left\{ \frac{P_1(\mu)}{r^2} - \frac{gt^2}{2!} \frac{P_2(\mu)}{r^3} + \frac{(gt^2)^2}{4!} \frac{P_3(\mu)}{r^4} - \dots \right\}, \\ \zeta &= \frac{t}{2\pi\rho\omega^3} \left\{ 1 - \frac{1^2}{5!} \frac{3^2}{\omega^2} \left(\frac{gt^2}{\omega} \right)^2 + \frac{1^2}{9!} \frac{3^2}{\omega^2} \frac{5^2}{\omega^2} \left(\frac{gt^2}{\omega} \right)^4 - \dots \right\} \end{aligned} \right\} \quad (38)$$

Again, when $gt^2/2\omega$ is large, we have, in place of (31),

$$\zeta = -\frac{gt^3}{2^{\frac{1}{2}}\pi\rho\omega^4} \sin \frac{gt^2}{4\omega} \quad \dots \dots \dots (39)$$

252 We may next investigate the effect of a local periodic pressure applied to the surface, following the method of Art 239.

In the three-dimensional form of the problem, we have, in place of Art 239 (4),

$$p = \rho \left(\frac{\partial \phi}{\partial t} - gz + \mu \phi \right) \quad \dots \dots \dots (1)$$

This gives
$$\zeta = \frac{1}{g} \frac{\partial \phi_0}{\partial t} + \frac{\mu}{g} \phi_0 - \frac{p_0}{g\rho}, \quad \dots \dots (2)$$

subject to the kinematical condition (4) of Art 251

In the case of symmetry about the axis of z , assuming

$$p_0 = J_0(k\varpi) e^{i\sigma t}, \quad \phi = C e^{i\sigma t + kz} J_0(k\varpi), \quad \dots \dots (3)$$

we find
$$(gk^2 - \sigma^2 + i\mu\sigma) C = \frac{i\sigma}{\rho}, \quad \dots \dots (4)$$

and thence
$$g\rho\zeta = -\frac{k}{k - (\kappa - i\mu_1)} J_0(k\varpi) e^{i\sigma t}, \quad \dots \dots (5)$$

where
$$\kappa = \frac{\sigma^2}{g}, \quad \mu_1 = \frac{\mu\sigma}{g}, \quad \dots \dots (6)$$

as in Art 239

Hence, corresponding to a symmetrical surface-pressure

$$p_0 = f(\varpi) e^{i\sigma t}, \quad \dots \dots \dots (7)$$

we find (see Art. 251 (9))

$$g\rho\zeta = -e^{i\sigma t} \int_0^\infty \frac{J_0(k\varpi) k^2 dk}{k - (\kappa - i\mu_1)} \int_0^\infty f(\alpha) J_0(k\alpha) \alpha d\alpha \quad \dots \dots (8)$$

Thus, for an integral pressure $P e^{i\sigma t}$ distributed uniformly over a circle of radius a , we have

$$\int_0^\infty f(\alpha) J_0(k\alpha) \alpha d\alpha = \frac{P}{\pi a^2} \int_0^a J_0(k\alpha) \alpha d\alpha = \frac{P}{\pi k a} J_1(ka), \quad \dots \dots (9)$$

and thence
$$g\rho\zeta = -\frac{P}{\pi a} e^{i\sigma t} \int_0^\infty \frac{J_0(k\varpi) J_1(ka)}{k - (\kappa - i\mu_1)} k dk \quad \dots \dots (10)$$

Returning to the general case, since

$$k^2 J_0(k\varpi) = -\frac{1}{\varpi} \frac{\partial}{\partial \varpi} \varpi \frac{\partial}{\partial \varpi} J_0(k\varpi), \quad \dots \dots (11)$$

by the differential equation of J_0 , we have

$$g\rho\zeta = e^{i\sigma t} \frac{1}{\varpi} \frac{\partial}{\partial \varpi} \varpi \frac{\partial}{\partial \varpi} \int_0^\infty \frac{J_0(k\varpi) dk}{k - (\kappa - i\mu_1)} \int_0^\infty f(\alpha) J_0(k\alpha) \alpha d\alpha \quad \dots \dots (12)$$

For a concentrated pressure $Pe^{i\sigma t}$ at the origin, this becomes

$$g\rho\zeta = \frac{Pe^{i\sigma t}}{2\pi} \frac{1}{\varpi} \frac{\partial}{\partial \varpi} \varpi \frac{\partial}{\partial \varpi} \int_0^\infty \frac{J_0(k\varpi) dk}{k - (\kappa - i\mu_1)}. \quad \dots (13)$$

Now, since $J_0(k\varpi) = \frac{2}{\pi} \int_0^\infty \sin(k\varpi \cosh u) du, \quad \dots (14)$

by Art 192 (7), we have

$$\begin{aligned} \int_0^\infty \frac{J_0(k\varpi) dk}{k - (\kappa - i\mu_1)} &= -\frac{i}{\pi} \int_0^\infty du \int_0^\infty \frac{e^{ik\varpi \cosh u} - e^{-ik\varpi \cosh u}}{k - (\kappa - i\mu_1)} dk \\ &= -\frac{i}{\pi} \int_0^\infty \left\{ 2\pi i e^{-i(\kappa - i\mu_1)\varpi \cosh u} - 2(\mu_1 + i\kappa) \int_0^\infty \frac{e^{-m\varpi \cosh u} dm}{m^2 - (\mu_1 + i\kappa)^2} \right\} du, \end{aligned} \quad (15)$$

where the definite integral with respect to k has been transformed by the method of Art 241

We may now put $\mu_1 = 0$ without inconvenience; thus

$$\lim_{\mu_1=0} \int_0^\infty \frac{J_0(k\varpi) dk}{k - (\kappa - i\mu_1)} = \pi D_0(\kappa\varpi) - \frac{2\kappa}{\pi} \int_0^\infty du \int_0^\infty \frac{e^{-m\varpi \cosh u} dm}{m^2 + \kappa^2}, \quad (16)$$

where D_0 is the function defined in Art 192. Hence (13) becomes*

$$\begin{aligned} g\rho\zeta &= -\frac{1}{2}\kappa^2 Pe^{i\sigma t} D_0(\kappa\varpi) - \frac{\kappa P}{\pi^2} e^{i\sigma t} \int_0^\infty du \int_0^\infty \frac{e^{-m\varpi \cosh u} m^2 dm}{m^2 + \kappa^2} \\ &= -\frac{1}{2}\kappa^2 Pe^{i\sigma t} D_0(\kappa\varpi) - \frac{\kappa^2 P}{2\pi} e^{i\sigma t} \left\{ \frac{1^2}{\kappa^3 \varpi^3} - \frac{1^2 \cdot 3^2}{\kappa^5 \varpi^5} + \frac{1^2 \cdot 3^2 \cdot 5^2}{\kappa^7 \varpi^7} - \dots \right\}, \end{aligned} \quad (17)$$

where the series in $\{ \}$ is of the semi-convergent kind. At distances ϖ which are great compared with $2\pi/\kappa$, the first term only is sensible, and we have

$$g\rho\zeta = -\frac{1}{2}\kappa^2 Pe^{i\sigma t} D_0(\kappa\varpi) = -\frac{\kappa^2 P}{\sqrt{(2\pi\kappa\varpi)}} e^{i(\sigma t - \kappa\varpi - \frac{1}{2}\pi)}, \quad \dots (18)$$

approximately This gives a system of annular waves whose amplitude varies inversely as the square root of the distance from the origin

Taking the real part of our expressions, we find, from (17),

$$-\frac{\partial \zeta}{\partial t} = \frac{\kappa^2 \sigma P}{2g\rho} J_0(\kappa\varpi) \cos \sigma t + \text{terms in } \sin \sigma t. \quad \dots (19)$$

Hence the mean rate at which the concentrated pressure $P \cos \sigma t$ does work in generating waves is

$$\frac{\kappa^2 \sigma P^2}{4g\rho} \quad \text{or} \quad \frac{\sigma^5 P^2}{4g^3 \rho}, \quad \dots (20)$$

* Use is here made of the identity

$$\frac{1}{\varpi} \frac{\partial}{\partial \varpi} \varpi \frac{\partial}{\partial \varpi} e^{-m\varpi \cosh u} = m^2 e^{-m\varpi \cosh u} - \frac{m}{\varpi} \frac{\partial}{\partial u} (e^{-m\varpi \cosh u} \sinh u)$$

varying as the *fifth* power of the frequency. The contrast with the case of a periodic force acting at a point in an infinite elastic solid, and other similar problems, where the rate of work varies as the *square* of the frequency, is interesting from the point of view of the dynamics of dispersive media*.

253 We proceed to consider the effect of a local disturbance of pressure advancing with constant velocity over the surface. This will give us, at all events as to the main features, an explanation of the peculiar system of waves which is seen to accompany a ship moving through sufficiently deep water.


A *complete* investigation, after the manner of Arts 240, 241, would appear to be somewhat difficult; but the general characteristics can readily be made out with the help of preceding results.

Let us suppose that we have a pressure-point moving with velocity c along the axis of x , in the negative direction, and that at the instant under consideration it has reached a point O . The elevation ζ at any point P may be regarded as due to a series of infinitely small impulses applied at equal infinitely short intervals at points of the axis of x to the right of O . Of the annular wave-systems thus successively generated, those only will combine to produce a sensible effect at P which had their origin in the neighbourhood of a certain point Q , determined by the consideration that the phase at P is 'stationary' for variations in the position of Q . Now if t is the time which the source of disturbance has taken to travel from Q to O , the phase of the waves at P , originated at Q , is

$$\frac{gt^2}{4\varpi} + \frac{1}{2}\pi, \quad \dots \dots \dots (1)$$

where $\varpi = QP$ (Art 251 (39)). Hence the condition for stationary phase is

$$\varpi = \frac{2\varpi}{t} \quad \dots \dots \dots (2)$$



Since, in this differentiation, O and P are regarded as fixed, we have $\varpi = c \cos \theta$, where $\theta = OQP$, hence

$$OQ = ct = 2\varpi \sec \theta. \quad \dots \dots \dots (3)$$

* Arts 251, 252 are taken from a paper cited on p 378 *ante*

It is further evident that the points in the immediate neighbourhood of P , for which the resultant phase is the same as at P , will lie in a line perpendicular to QP . A glance at the figure on the opposite page then shews that the curve of the wave-ridges is characterized by the property that the tangent bisects the interval between the origin and the foot of the normal. If p denote the perpendicular from the origin to the tangent, and θ the angle which p makes with the axis of x , we have, by a known formula,


$$PZ = - \frac{dp}{d\theta},$$

whence

$$2p = - \frac{dp}{d\theta} \cot \theta, \quad \dots \dots \dots (4)$$

$$p = a \cos^2 \theta \quad \dots \dots \dots (5)$$

For consecutive wave-ridges the values of the arbitrary constant a differ by $2\pi c^2/g$. This is easily seen by considering the parts of the curves for which θ is small



The forms of the curves are shewn in the annexed figure*, traced from the equations


$$\left. \begin{aligned} x &= p \cos \theta - \frac{dp}{d\theta} \sin \theta = \frac{1}{4}a (5 \cos \theta - \cos 3\theta), \\ y &= p \sin \theta + \frac{dp}{d\theta} \cos \theta = -\frac{1}{4}a (\sin \theta + \sin 3\theta). \end{aligned} \right\} \dots \dots \dots (6)$$

* Cf Sir W Thomson, "On Ship Waves," *Proc Inst Mech. Eng*, Aug. 3, 1887 [*Popular Lectures*, t in p 482] where a similar drawing is given. The investigation there referred to,

The values of x and y are stationary when $\sin^2 \theta = \frac{1}{3}$, this gives a series of cusps lying on the straight lines

$$\frac{y}{x} = \pm \frac{1}{2\sqrt{2}} = \pm \tan 19^\circ 28' \dots \dots \dots (7)$$

Although the mode of disturbance is different, the action of the bows of a ship may be roughly compared to that of a pressure-point of the kind we have been considering. The preceding figure accounts clearly for the two systems of transverse and lateral waves which are in fact observed, and for the specially conspicuous 'echelon' waves at the cusps, where these two systems coalesce. These are well shewn in the annexed drawing* by Mr R. E. Froude of the waves produced by a model



A similar system of waves is generated at the stern of the ship, which may roughly be regarded as a negative pressure-point. With varying speeds of the ship the stern-waves may tend partially to annul, or to reinforce, the effect of the bow-waves, and consequently the wave-resistance to the

based apparently on the theory of 'group-velocity,' has unfortunately not been published. See also R. E. Froude, "On Ship Resistance," *Papers of the Greenock Phil. Soc.*, Jan 19, 1894.

In the preceding edition of this work it was assumed that the effect of a pressure concentrated at a point might be inferred by superposing *lines* of pressure (through O) uniformly in all azimuths, and using the results of Art 241. It is easily seen, however, that such a distribution of lines of pressure is equivalent to a pressure-intensity varying inversely as the distance from O . This is not an adequate representation of a localized pressure, since it makes the total pressure on a circular area having its centre at O increase indefinitely with the radius of the circle (*Phil Trans*, A, t ccm. p 33). The assumption in question leads to the same configuration of the wave-ridges as in the text, but would give a different distribution of the elevation ζ in the system.

* Copied, by permission of Mr Froude and the Council of the Institute of Naval Architects, from a paper by the late W. Froude, "On the Effect on the Wave-Making Resistance of Ships of Length of Parallel Middle Body," *Trans. Inst. Nav. Arch.*, t xvii (1877).

ship as a whole for a given speed may fluctuate up and down as the length of the ship is increased*. Cf Art 242.

To obtain an approximate estimate of the actual height of the waves, in our special form of the problem, in the different parts of the system, we have recourse to the formula (39) of Art 251. If P_0 denote the total disturbing pressure, the elevation at P due to the annular wave-system started at a point Q' to the right of O may be written

$$\delta\zeta = -\frac{gt'^3}{8\sqrt{2\pi\rho\omega'^4}} \sin \frac{gt'^2}{4\omega'} P_0 \delta t', \quad \dots \dots \dots (8)$$

where

$$\omega' = PQ', \quad t' = \frac{OQ'}{c}$$

This is to be integrated with respect to t' , but (as already explained) the only parts of the integral which contribute appreciably to the final result will be those for which t' has very nearly the value (t) corresponding to the special point Q above determined

As regards the phase, we have, writing $t' = t + \tau$,

$$\frac{gt'^2}{4\omega'} = \frac{gt^2}{4\omega} + \tau \frac{d}{dt} \left(\frac{gt^2}{4\omega} \right) + \frac{\tau^2}{1 \cdot 2} \cdot \frac{d^2}{dt^2} \left(\frac{gt^2}{4\omega} \right) + \dots \dots \dots (9)$$

The second term vanishes by hypothesis, since the phase at P for waves started near Q is 'stationary' Again, we find

$$\frac{d^2}{dt^2} \left(\frac{gt^2}{4\omega} \right) = \frac{g}{2\omega} - \frac{gt}{\omega^2} \omega + \frac{gt^2}{4} \left(\frac{2\omega^2}{\omega^3} - \frac{\omega}{\omega^2} \right).$$

$$\text{Since} \quad \omega = c \cos \theta, \quad \omega = \frac{c^2 \sin^2 \theta}{\omega}, \quad \dots \dots \dots (10)$$

this reduces, with the help of (2), to

$$\frac{d^2}{dt^2} \left(\frac{gt^2}{4\omega} \right) = \frac{g}{\omega} \left(\frac{1}{2} - \tan^2 \theta \right) \quad \dots \dots \dots (11)$$

Owing to the fluctuations of the trigonometrical term no great error will be committed if we neglect the variation of the first factor in (8), or if, further, we take the limits of integration with respect to τ to be $\pm \infty$. Hence at a point P on a wave-ridge, where

$$\frac{gt^2}{4\omega} = 2s\pi - \frac{1}{2}\pi,$$

* See W. Froude, *l c*, and R E Froude, "On the Leading Phenomena of the Wave-Making Resistance of Ships," *Trans Inst Nav Arch*, t xxii (1881), where drawings of actual wave-patterns under varied conditions of speed are given, which are, as to their main features, in striking agreement with the results of the above theory. Some of these drawings are reproduced in Lord Kelvin's paper in the *Proc Inst Mech. Eng*, above cited.

For a discussion of the wave-resistance encountered by an ideal form of ship see Michell, *Phil Mag* (5), t xlv p 106 (1898).

s being integral, we have

$$\zeta = \frac{gt^2 P_0}{8\sqrt{2\pi\rho\omega^4}} \int_{-\infty}^{\infty} \cos m^2 \tau^2 d\tau, \quad \dots \dots \dots (12)$$

approximately, provided

$$m^2 = \frac{g}{2\omega} \left| \frac{1}{2} - \tan^2 \theta \right| \quad \dots \dots \dots (13)$$

The definite integral in (12) is equal to $\sqrt{(\frac{1}{2}\pi)} m^{-1}$, the positive value of m being understood. Hence, the elevation along the wave-ridge whose parameter is α is found to be

$$\zeta = \frac{g^{\frac{1}{2}} P_0}{\pi^{\frac{1}{2}} \rho c^2 a^{\frac{1}{2}}} \cdot \frac{\sec^3 \theta}{\sqrt{1 - 3 \sin^2 \theta}} \cdot \dots \dots \dots (14)^*$$

The formula makes ζ infinite at a cusp, where $\sin^2 \theta = \frac{1}{3}$, but this is merely an indication of the failure of our approximation. That the elevation at a point P in the neighbourhood of a cusp would be relatively great might have been foreseen, since, as appears from (9) and (11), the range of points on the axis of x which have sent waves to P in sensibly the same phase is then abnormally extended.

The infinity which occurs when $\theta = \frac{1}{2}\pi$ is of a somewhat different character, being due to the artificial nature of the assumption we have made, of a pressure concentrated at a *point*. With a diffused pressure this difficulty would disappear.

It is to be noticed, moreover, that the whole of this investigation applies only to points for which $gt^2/4\omega$ is large, cf Arts 238, 251. It will be found on examination, that this restriction is equivalent to an assumption that the parameter a is large compared with $2\pi c^2/g$. The argument therefore does not apply without reserve to the parts of the wave-pattern near the origin.

To examine the modification produced in the wave-pattern when the depth of the water has to be taken into account, the preceding argument must be put in a more general form. If, as before, t is the time the pressure-point has taken to travel from Q to O , it may be shewn that the phase of the disturbance at P , due to the impulse delivered at Q , will differ only by a constant from

$$k(Vt - \omega), \quad \dots \dots \dots (15)$$

if $2\pi/k$ be the predominant wave-length in the neighbourhood of P , and V the corresponding wave-velocity†. This predominant wave-length is

* The reader may test the above method by applying it to find the amplitude of the waves in the two-dimensional problem of Art 241, assuming the formula (35) of Art 237 for the effect of a single impulse.

† The symbol c , which was previously employed in this sense, now denotes the velocity of the pressure-point over the water.

determined by the condition that the phase is stationary for variations of the wave-length only, i.e.

$$\frac{\partial}{\partial k} k(Vt - \varpi) = 0, \text{ or } \varpi = Ut, \quad \dots \dots \quad (16)$$

where $U = d(kV)/dk$, is the group-velocity (Art 234)*.

For the effective part of the disturbance at P , the phase (15) must further be stationary as regards variations in the position of Q , hence, differentiating partially with respect to t , we have

$$\varpi = V, \text{ or } V = c \cos \theta, \quad \dots \dots \quad (17)$$

since $\varpi = c \cos \theta$. Now, referring to the figure on p. 412, we have

$$p = ct \cos \theta - \varpi = Vt - \varpi \quad \dots \dots \quad (18)$$

Hence for a given wave-ridge p will bear a constant ratio to the wave-length λ , and in passing from one wave-ridge to the next this ratio will increase (or decrease) by unity. Since λ is determined as a function of θ by (17), this gives the relation between p and θ

Thus in the case of infinite depth, the formula (17) gives

$$c^2 \cos^2 \theta = V^2 = \frac{g\lambda}{2\pi}, \quad \dots \dots \dots \quad (19)$$

and the required relation is of the form

$$p = a \cos^2 \theta, \quad \dots \dots \dots \quad (20)$$

as above.

When the depth (h) is finite, we have

$$c^2 \cos^2 \theta = V^2 = \frac{g\lambda}{2\pi} \tanh \frac{2\pi h}{\lambda}, \quad \dots \dots \quad (21)$$

and the relation is

$$\frac{p}{a} \tanh \frac{a}{p} = \frac{c^2}{gh} \cos^2 \theta, \quad \dots \dots \dots \quad (22)$$

where the values of a for successive wave-ridges are in arithmetic progression. The forms of the curves in various cases have been sketched by Ekman†. Since the expression on the left-hand side cannot exceed unity, it appears that if $c^2 > gh$ there will be an inferior limit to the value of θ , determined by

$$\cos^2 \theta = \frac{gh}{c^2}. \quad \dots \dots \dots (23)$$

It follows that when the speed of the disturbing influence exceeds $\sqrt{(gh)}$

* Cf Sir W. Thomson, "On the Waves produced by a Single Impulse in Water of any Depth, or in a Dispersive Medium," *Proc R S*, t xlii p 80 (1887), where the argument (which is easily extended) is given for the two-dimensional case.

† *l c ante* p 354

the transverse waves disappear, and we have only the lateral waves. This tends to diminish the wave-making resistance (cf Art 245)*

Standing Waves in Limited Masses of Water.

254 The problem of free oscillations in two horizontal dimensions (x, y), in the case where the depth is uniform and the fluid is bounded laterally by vertical walls, can be reduced to the same analytical form as in Art 187.

If the origin be taken in the undisturbed surface, and if ζ denote the elevation at time t above this level, the conditions to be satisfied at the free surface are as in Art 251 (3), (4).

The equation of continuity, $\nabla^2\phi = 0$, and the condition of zero vertical motion at the depth $z = -h$, are both satisfied by

$$\phi = \phi_1 \cosh k(z + h), \quad \dots \dots \dots (1)$$

where ϕ_1 is a function of x, y , such that

$$\frac{\partial^2 \phi_1}{\partial x^2} + \frac{\partial^2 \phi_1}{\partial y^2} + k^2 \phi_1 = 0 \quad \dots \dots (2)$$

The form of ϕ_1 and the admissible values of k are determined by this equation, and by the condition that

$$\frac{\partial \phi_1}{\partial n} = 0, \quad \dots \dots \dots (3)$$

at the vertical walls. The corresponding values of the 'speed' (σ) of the oscillations are then given by the surface-condition (6), of Art. 251, viz we have

$$\sigma^2 = gk \tanh kh. \quad \dots \dots \dots (4)$$

This makes

$$\zeta = \frac{ik}{\sigma} \sinh kh \quad \phi_1 \quad \dots \dots (5)$$

The conditions (2) and (3) are of the same form as in the case of small depth, and we could therefore at once write down the results for a rectangular or a circular† tank. The values of k , and the forms of the free surface, in the various fundamental modes, are the same as in Arts 188, 189‡, but the

* It is found that the power required to propel a torpedo-boat in relatively shallow water increases with the speed up to a certain critical velocity, dependent on the depth, then decreases, and finally increases again. See papers by Yarrow and Marniner, *Trans. Inst. Nav. Arch.* t. xlvii. pp. 339, 344 (1905).

† For references to the original investigations by Poisson and Lord Rayleigh of waves in a circular tank see p. 272. The problem was also treated by Merian, *Ueber die Bewegung tropfbarer Flüssigkeiten in Gefässen*, Basel, 1828 [see VonderMuhll, *Math. Ann.* t. xxvii. p. 575] and by Ostrogradsky, "Mémoire sur la propagation des ondes dans un bassin cylindrique," *Mém. des Sav. Étrangers*, t. iii (1832).

‡ It may be remarked that either of the two modes figured on pp. 271, 272, may be easily excited by properly-timed horizontal agitation of a tumbler containing water.

amplitude of the oscillation now diminishes with increasing depth below the surface, according to the law (1), whilst the speed of any particular mode is given by (4)

When kh is small, we have $\sigma^2 = k^2 gh$, as in the Arts referred to.

255 The number of cases of motion with a *variable* depth, of which the solution has been obtained, is very small

1° We may notice, first, the two-dimensional oscillations of water across a channel whose section consists of two straight lines inclined at 45° to the vertical*

The axes of y , z being respectively horizontal and vertical, in the plane of a cross-section, we assume

$$\phi + v\psi = A \{ \cosh k(y+iz) + \cos k(y+iz) \}, \quad (1)$$

the time-factor $\cos(\sigma t + \epsilon)$ being understood This gives

$$\phi = A (\cosh ky \cos kz + \cos ky \cosh kz), \quad \psi = A (\sinh ky \sin kz - \sin ky \sinh kz). \quad (2)$$

The latter formula shews at once that the lines $y = \pm z$ constitute the stream-line $\psi = 0$, and may therefore be taken as fixed boundaries

The condition to be satisfied at the free surface is, as in Art. 226,

$$\sigma^2 \phi = g \frac{\partial \phi}{\partial z} \quad \dots \dots \dots (3)$$

Substituting from (2) we find, if h denote the height of the surface above the origin,

$$\sigma^2 (\cosh ky \cos kh + \cos ky \cosh kh) = gk (-\cosh ky \sin kh + \cos ky \sinh kh)$$

This will be satisfied for all values of y , provided

$$\sigma^2 \cos kh = -gk \sin kh, \quad \sigma^2 \cosh kh = gk \sinh kh, \quad \dots \dots (4)$$

whence

$$\tanh kh = -\tan kh \quad \dots \dots (5)$$

This determines the admissible values of k , the corresponding values of σ are then given by either of the equations (4)

Since (2) makes ϕ an *even* function of y , the oscillations which it represents are symmetrical with respect to the medial plane $y = 0$

The asymmetrical oscillations are given by

$$\phi + v\psi = vA \{ \cosh k(y+iz) - \cos k(y+iz) \}, \quad \dots \dots (6)$$

$$\text{or } \phi = -A (\sinh ky \sin kz + \sin ky \sinh kz), \quad \psi = A (\cosh ky \cos kz - \cos ky \cosh kz) \quad (7)$$

The stream-line $\psi = 0$ consists, as before, of the lines $y = \pm z$, and the surface-condition (3) gives

$$\sigma^2 (\sinh ky \sin kh + \sin ky \sinh kh) = gk (\sinh ky \cos kh + \sin ky \cosh kh)$$

This requires

$$\sigma^2 \sin kh = gk \cos kh, \quad \sigma^2 \sinh kh = gk \cosh kh, \quad \dots \dots (8)$$

whence

$$\tanh kh = \tan kh \quad \dots \dots (9)$$

* Kirchhoff, "Ueber stehende Schwingungen einer schweren Flüssigkeit," *Berl Monatsber.*, May 15, 1879 [*Ges. Abh.*, p 428]; Greenhill, *l c. ante* p 356.

The equations (5) and (9) present themselves in the theory of the lateral vibrations of a bar free at both ends, viz they are both included in the equation

$$\cos m \cosh m = 1, \quad \dots \dots \dots (10)^*$$

where $m = 2kh$

The root $kh=0$, of (9), which is extraneous in the theory referred to, is now important, it corresponds in fact to the slowest mode of oscillation in the present problem. Putting $Ak^2 = B$, and making k infinitesimal, the formulae (7) become, on restoring the time-factor, and taking the real parts,


$$\phi = -2Byz \cos(\sigma t + \epsilon), \quad \psi = B(y^2 - z^2) \cos(\sigma t + \epsilon), \quad \dots \dots (11)$$

whilst from (8)
$$\sigma^2 = \frac{g}{h} \quad \dots \dots \dots (12)$$

The corresponding form of the free surface is

$$\zeta = \frac{1}{g} \left[\frac{d\phi}{dt} \right]_{z=h} = 2\sigma Bhy \sin(\sigma t + \epsilon) \quad \dots \dots (13)$$

The surface in this mode is therefore always plane. The annexed figure shews the lines of motion ($\psi = \text{const}$) for a series of equidistant values of ψ



The next gravest mode is symmetrical, and is given by the lowest finite root of (5), which is $kh = 2.3650$, whence $\sigma = 1.5244(g/h)^{\frac{1}{2}}$. The profile of the surface has now two nodes, whose positions are determined by putting $\phi = 0$, $z = h$, in (2), whence it is found that

$$\frac{y}{h} = \pm 0.516^{\dagger}$$

The next mode corresponds to the lowest finite root of (9), and so on \ddagger

2° Greenhill, in the paper already cited, has investigated the *symmetrical* oscillations

* Cf Lord Rayleigh, *Theory of Sound*, t. i, Art 170, where the numerical solution of the equation is fully discussed

\dagger Lord Rayleigh, *Theory of Sound*, Art 178

\ddagger An experimental verification of the frequencies, and of the positions of the loops (places of maximum vertical amplitude), in various fundamental modes, was made by Kirchhoff and Hansemann, "Ueber stehende Schwingungen des Wassers," *Wied Ann.*, t x. (1880) [Kirchhoff, *Ges. Abh.*, p 442]

of the water across a channel whose section consists of two straight lines inclined at 60° to the vertical. In the (analytically) simplest mode of this kind we have, omitting the time-factor,

$$\phi + \psi = \lambda A (y + iz)^3 + B, \quad . \quad . \quad . \quad (14)$$

$$\text{or} \quad \phi = Az(z^2 - 3y^2) + B, \quad \psi = Ay(y^2 - 3z^2), \quad . \quad . \quad . \quad (15)$$

the latter formula making $\psi = 0$ along the boundary $y = \pm \sqrt{3} z$. The surface-condition (3) is satisfied for $z = h$, provided

$$\sigma^2 = g/h, \quad B = 2A h^3 \quad . \quad . \quad . \quad . \quad . \quad (16)$$

The corresponding form of the free surface is

$$\zeta = \frac{1}{g} \left[\frac{\partial \phi}{\partial t} \right]_{z=h} = - \frac{3A}{\sigma} (h^2 - y^2) \sin(\sigma t + \epsilon), \quad . \quad . \quad . \quad (17)$$

a parabolic cylinder, with two nodes at distances of 5774 of the half-breadth from the centre. The slowest mode, which must evidently be of asymmetrical type, has not yet been determined.

3° If in any of the above cases we transfer the origin to either edge of the canal, and then make the breadth infinite, we get a system of standing waves on a sea bounded by a sloping bank. This may be regarded as made up of an incident and a reflected system. The reflection is complete, but there is in general a change of phase.

When the inclination of the bank is 45° the solution is

$$\phi = H \{ e^{kx} (\cos ky - \sin ky) + e^{-ky} (\cos kz + \sin kz) \} \cos(\sigma t + \epsilon) \quad . \quad (18)$$

For an inclination of 30° to the horizontal we have

$$\begin{aligned} \phi = H \{ e^{kx} \sin ky + e^{-\frac{1}{2}k(\sqrt{3}y+z)} \sin \frac{1}{2}k(y - \sqrt{3}z) \\ - \sqrt{3}e^{-\frac{1}{2}k(\sqrt{3}y-z)} \cos \frac{1}{2}k(y + \sqrt{3}z) \} \cos(\sigma t + \epsilon) \quad . \quad . \quad (19) \end{aligned}$$

In each case $\sigma^2 = gk$, as in the case of waves on an unlimited sheet of deep water.

These results, which may easily be verified *ab initio*, were given by Kirchhoff (*l.c.*)

256. An interesting problem which presents itself in this connection is that of the transversal oscillations of water contained in a canal of *circular* section. This has not yet been solved, but it may be worth while to point out that an approximate determination of the frequency of the slowest mode, in the case where the free surface is at the level of the axis, can be effected by Lord Rayleigh's method, explained in Art. 167.

If we assume as an 'approximate type' that in which the free surface remains always plane, making a small angle θ (say) with the horizontal, it appears, from Art. 72, 3°, that the kinetic energy T is given by

$$2T = \left(\frac{4}{\pi} - \frac{\pi}{4} \right) \rho a^4 \theta^2, \quad . \quad . \quad . \quad . \quad . \quad (1)$$

where a is the radius, whilst for the potential energy V we have

$$2V = \frac{2}{3} g \rho a^3 \theta^2. \quad . \quad . \quad . \quad . \quad . \quad (2)$$

If we assume that $\theta \propto \cos(\sigma t + \epsilon)$, this gives

$$\sigma^2 = \frac{8\pi}{48 - 3\pi^2} \frac{g}{a}, \quad \dots \dots \dots (3)$$

whence $\sigma = 1.169 (g/a)^{\frac{1}{2}}$ *

In the case of a rectangular section of breadth $2a$, and depth a , the speed is given by Art. 254 (4), where we must put $k = \pi/2a$ from Art. 188, and $h = a$. This gives

$$\sigma^2 = \frac{1}{2}\pi \tanh \frac{1}{2}\pi \frac{g}{a}, \quad \dots \dots \dots (4)$$

or $\sigma = 1.200 (g/a)^{\frac{1}{2}}$. The frequency in the actual problem is less, since the kinetic energy due to a given motion of the surface is greater, whilst the potential energy for a given deformation is the same. Cf Art 45.

257 We may next consider the free oscillations of the water included between two transverse partitions in a uniform horizontal canal. Before proceeding to particular cases, we may examine for a moment the nature of the analytical problem.

If the axis of x be parallel to the length, and the origin be taken in one of the ends, the velocity potential in any one of the fundamental modes referred to may, by Fourier's theorem, be supposed expressed in the form

$$\phi = (P_0 + P_1 \cos kx + P_2 \cos 2kx + \dots + P_s \cos skx + \dots) \cos(\sigma t + \epsilon), \quad (1)$$

where $k = \pi/l$, if l denote the length of the compartment. The coefficients P_s are here functions of y, z . If the axis of z be drawn vertically upwards, and that of y be therefore horizontal and transverse to the canal, the forms of these functions, and the admissible values of σ , are to be determined from the equation of continuity

$$\nabla^2 \phi = 0, \quad \dots \dots \dots (2)$$

$$\text{with the conditions that} \quad \frac{\partial \phi}{\partial n} = 0 \quad \dots \dots \dots (3)$$

$$\text{at the sides, and that} \quad \sigma^2 \phi = g \frac{\partial \phi}{\partial z} \quad \dots \dots \dots (4)$$

at the free surface. Since $\partial \phi / \partial x$ must vanish for $x = 0$ and $x = l$, it follows from known principles† that each term in (1) must satisfy the conditions (2), (3), (4) independently, viz we must have

$$\frac{\partial^2 P_s}{\partial y^2} + \frac{\partial^2 P_s}{\partial z^2} - s^2 k^2 P_s = 0, \quad \dots \dots \dots (5)$$

* Lord Rayleigh finds, as a closer approximation, $\sigma = 1.1644 (g/a)^{\frac{1}{2}}$, see *Phil Mag* (5), t. XLVII. p. 566 (1899) [*Sc. Papers*, t. IV p. 407].

† See Stokes, "On the Critical Values of the Sums of Periodic Series," *Camb. Trans*, t. VIII. (1847) [*Math and Phys Papers*, t. I p. 236].

with
$$\frac{\partial P_s}{\partial n} = 0 \quad \dots \dots \dots (6)$$

at the lateral boundary, and

$$\sigma^2 P_s = g \frac{\partial P_s}{\partial z} \quad \dots \dots \dots (7)$$

at the free surface

The term P_0 gives purely transverse oscillations such as have been discussed in Art 255. Any other term $P_s \cos skx$ gives a series of fundamental modes with s nodal lines transverse to the canal, and 0, 1, 2, 3, ... nodal lines parallel to the length.

It will be sufficient for our purpose to consider the term $P_1 \cos kx$. It is evident that the assumption

$$\phi = P_1 \cos kx \cdot \cos(\sigma t + \epsilon), \quad \dots \dots \dots (8)$$

with a proper form of P_1 and the corresponding value of σ determined as above, gives the velocity-potential of a possible system of standing waves, of arbitrary wave-length $2\pi/k$, in an unlimited canal of the given form of section. Now, as explained in Art. 228, by superposition of two properly adjusted systems of standing waves of this type we can build up a system of progressive waves

$$\phi = P_1 \cos(kx \mp \sigma t). \quad \dots \dots \dots (9)$$

We infer that progressive waves of simple-harmonic profile, of any assigned wave-length, are possible in an infinitely long canal of any uniform section.

We might go further, and assert the possibility of an infinite number of types, of any given wave-length, with wave-velocities ranging from a certain lowest value to infinity. The types, however, in which there are longitudinal nodes at a distance from the sides are from the present point of view of subordinate interest.

Two extreme cases call for special notice, viz where the wave-length is very great or very small compared with the dimensions of the transverse section.

The most interesting types of the former class have no longitudinal nodes, and are covered by the general theory of 'long' waves given in Arts 168, 169. The only additional information we can look for is as to the shapes of the wave-ridges in the direction transverse to the canal.

In the case of relatively short waves, the most important type is one in which the ridges extend across the canal with gradually varying height, and the wave-velocity is that of free waves on deep water as given by Art. 228 (6).

There is another type of short waves which may present itself when the banks are inclined, and which we may distinguish by the name of 'edge-

waves,' since the amplitude diminishes exponentially as the distance from the bank increases. In fact, if the amplitude at the edges be within the limits imposed by our approximations, it will become altogether insensible at a distance whose projection on the slope exceeds a wave-length. The wave-velocity is *less* than that of waves of the same length on deep water. It does not appear that the type of motion here referred to is very important.

A general formula for these edge-waves has been given by Stokes*. Taking the origin in one edge, the axis of z vertically upwards, and that of y transverse to the canal, and treating the breadth as relatively infinite, the formula in question is

$$\phi = H e^{-k(y \cos \beta - z \sin \beta)} \cos k(x - ct), \dots \dots \dots (10)$$

where β is the slope of the bank to the horizontal, and

$$c = \left(\frac{g}{k} \sin \beta \right)^{\frac{1}{2}}. \dots \dots \dots (11)$$

The reader will have no difficulty in verifying this result.

258. We proceed to the consideration of some special cases. We shall treat the question as one of standing waves in an infinitely long canal, or in a compartment bounded by two transverse partitions whose distance apart is a multiple of half the arbitrary wave-length ($2\pi/k$), but the investigations can easily be modified as above so as to apply to progressive waves, and we shall occasionally state results in terms of the wave-velocity.

1° The solution for the case of a rectangular section, with horizontal bed and vertical sides, could be written down at once from the results of Arts 188, 254. The nodal lines are transverse and longitudinal, except in the case of a coincidence in period between two distinct modes, when more complex forms are possible. This will happen, for instance, in the case of a square tank.

2° In the case of a canal whose section consists of two straight lines inclined at 45° to the vertical we have, first, a type discovered by Kelland† viz if the axis of x coincide with the bottom line of the canal,

$$\phi = A \cosh \frac{ky}{\sqrt{2}} \cosh \frac{kz}{\sqrt{2}} \cos kx \cos(\sigma t + \epsilon) \dots \dots (1)$$

This evidently satisfies $\nabla^2 \phi = 0$, and makes

$$\frac{\partial \phi}{\partial y} = \pm \frac{\partial \phi}{\partial z}, \dots \dots \dots (2)$$

for $y = \pm z$, respectively. The surface-condition (Art 257 (4)) then gives

$$\sigma^2 = \frac{gk}{\sqrt{2}} \tanh \frac{kh}{\sqrt{2}}, \dots \dots \dots (3)$$

* "Report on Recent Researches in Hydromechanics," *Brit Ass Rep*, 1846 [*Math. and Phys Papers*, t. i. p. 167].

† "On Waves," *Trans R S Edin.*, t. xiv (1839)

where h is the height of the free surface above the bottom line. If we put $\sigma = kc$, the wave-velocity c is given by

$$c^2 = \frac{g}{\sqrt{2}k} \tanh \frac{kh}{\sqrt{2}}, \quad \dots \dots \dots (4)$$

where $k = 2\pi/\lambda$, if λ be the wave-length

When h/λ is small, this reduces to

$$c = \left(\frac{1}{2} gh\right)^{\frac{1}{2}}, \quad \dots \dots \dots (5)$$

in agreement with Art 169 (13), since the mean depth is now denoted by $\frac{1}{2}h$.

When, on the other hand, h/λ is moderately large, we have

$$c^2 = \frac{g}{k\sqrt{2}} \quad \dots \dots \dots (6)$$

The formula (1) indicates now a rapid increase of amplitude towards the sides. We have here, in fact, an instance of 'edge-waves,' and the wave-velocity agrees with that obtained by putting $\beta = 45^\circ$ in Stokes' formula

The remaining types of oscillation which are symmetrical with respect to the medial plane $y=0$ are given by the formula

$$\phi = C (\cosh \alpha y \cos \beta z + \cos \beta y \cosh \alpha z) \cos kx \cos (\sigma t + \epsilon), \quad \dots \dots (7)$$

provided α, β, σ are properly determined. This evidently satisfies (2), and the equation of continuity gives

$$\alpha^2 - \beta^2 = k^2 \quad \dots \dots \dots (8)$$

The surface-condition, Art 257 (4), to be satisfied for $z=h$, requires

$$\sigma^2 \cosh \alpha h = g\alpha \sinh \alpha h, \quad \sigma^2 \cos \beta h = -g\beta \sin \beta h \quad (9)$$

$$\text{Hence} \quad \alpha h \tanh \alpha h + \beta h \tan \beta h = 0 \quad \dots \dots (10)$$

The values of α, β are determined by (8) and (10), and the corresponding values of σ are then given by either of the equations (9). If, for a moment, we write

$$x = \alpha h, \quad y = \beta h, \quad \dots \dots \dots (11)$$

the roots are given by the intersections of the curve

$$x \tanh x + y \tan y = 0, \quad \dots \dots \dots (12)$$

whose general form can be easily traced, with the hyperbola

$$x^2 - y^2 = k^2 h^2 \quad \dots \dots \dots (13)$$

There are an infinite number of real solutions, with values of βh lying in the second, fourth, sixth, ... quadrants. These give respectively 2, 4, 6, ... longitudinal nodes of the free surface. When h/λ is moderately large, we have $\tanh \alpha h = 1$, nearly, and βh is (in the simplest mode of this class) a little greater than $\frac{1}{2}\pi$. The two longitudinal nodes in this case approach very closely to the edges as λ is diminished, whilst the wave-velocity becomes practically equal to that of waves of length λ on deep water. As a numerical example, assuming $\beta h = 1.1 \times \frac{1}{2}\pi$, we find

$$\alpha h = 10.910, \quad kh = 10.772, \quad c = 1.0064 \left(\frac{g}{k}\right)^{\frac{1}{2}}.$$

The distance of either nodal line from the nearest edge is then $12h$.

We may next consider the asymmetrical modes. The solution of this type which is analogous to Kelland's was noticed by Greenhill (*l.c.*). It is

$$\phi = A \sinh \frac{ky}{\sqrt{2}} \sinh \frac{kz}{\sqrt{2}} \cos kx \cos (\sigma t + \epsilon), \quad \dots \dots (14)$$

The equations (20) and (26) were arrived at by Macdonald, by a different process. The surface value of P is

$$P = H \left\{ 1 + 2 \coth \frac{3}{2} \sqrt[3]{3} \left(\cosh \frac{3kh}{2} - \frac{\sigma^2}{gh} \sinh \frac{3kh}{2} \right) \right\} \dots \dots \dots (27)$$

The equation (20) is a quadratic in σ^2/gh . In the case of a wave whose length ($2\pi/k$) is great compared with h , we have

$$\coth \frac{3kh}{2} = \frac{2}{3kh},$$

nearly, and the roots of (20) are then

$$\frac{\sigma^2}{gh} = 1/kh, \text{ and } \frac{\sigma^2}{gh} = 1/kh, \dots \dots \dots (28)$$

approximately. If we put $\sigma = kh$, the former result gives $c^2 = gh$, in accordance with the usual theory of 'long' waves (Art. 168, 169). The formula (27) now makes $P = 3H$, approximately; thus independent of g , so that the wave ridges are nearly straight. The second of the roots (28) makes $c^2 = g/h$, giving a much greater wave velocity; but the considerations adduced above shew that there is nothing paradoxical in this. It will be found on examination that the cross sections of the waves are parabolic in form, and that there are two nodal lines parallel to the length of the canal. The period is, in fact, almost exactly that of the symmetrical transverse oscillation discussed in Art. 255.

When, on the other hand, the wave length is short compared with the transverse dimensions of the canal, kh is large, and $\coth \frac{3}{2} kh = 1$, nearly. The roots of (25) are then

$$\frac{\sigma^2}{gh} = 1 \text{ and } \frac{\sigma^2}{gh} = \frac{1}{2}, \dots \dots \dots (29)$$

approximately. The former result makes $P = H$, nearly, so that the wave ridges are straight, experiencing only a slight change of altitude towards the sides. The speed, $\sigma = gh^{\frac{1}{2}}$, is exactly what we should expect from the general theory of waves on relatively deep water.

If in this case we transfer the origin to one edge of the water surface, writing $z+h$ for z , and $y = \sqrt[3]{3}h$ for y , and then make h infinite, we get the case of a system of waves travelling parallel to a shore which slopes downwards at an angle of 30° to the horizon. The result is

$$\phi = H \left\{ e^{\frac{1}{2}kx} + e^{-\frac{1}{2}kx} \sqrt[3]{3} y^{-\frac{1}{2}} \cos \frac{1}{2} kx \right\} \cos kx \cos (\sigma t + \epsilon), \dots \dots \dots (30)$$

where $c = \frac{1}{2} gh^{\frac{1}{2}}$. This admits of immediate verification. At a distance of a wave length or so from the shore, the value of ϕ , near the surface, reduces to

$$\phi = H e^{\frac{1}{2}kx} \cos kx \cos (\sigma t + \epsilon), \dots \dots \dots (31)$$

practically, as in Art. 227. Near the edge the elevation changes sign, there being a longitudinal node for which

$$\sqrt[3]{3} ky = \log_e 2, \dots \dots \dots (32)$$

or $y/k = 1.27$.

The second of the two roots (29) gives a system of edge-waves, the results being equivalent to those obtained by making $\beta = 30^\circ$ in Stokes' formula.

This shews that $\zeta_n \propto \cos(\sigma_n t + \epsilon)$, where


$$\sigma_n^2 = \frac{2n(n-1)}{2n+1} \frac{g}{a}. \quad \dots\dots\dots (10)$$

For the same density of liquid, $g \propto a$, and the frequency is therefore independent of the dimensions of the globe.

The formula makes $\sigma_1 = 0$, as we should expect, since in the deformation expressed by a surface-harmonic of the first order the surface remains spherical, and the period is therefore infinitely long

"For the case $n=2$, or an ellipsoidal deformation, the length of the isochronous simple pendulum becomes $\frac{5}{4}a$, or one and a quarter times the earth's radius, for a homogeneous liquid globe of the same mass and diameter as the earth, and therefore for this case, or for any homogeneous liquid globe of about $5\frac{1}{2}$ times the density of water, the half-period is 47 m 12 s"

"A steel globe of the same dimensions, without mutual gravitation of its parts, could scarcely oscillate so rapidly, since the velocity of plane waves of distortion in steel is only about 10,140 feet per second, at which rate a space equal to the earth's diameter would not be travelled in less than 1 h. 8 m. 40 s.*"



* Sir W Thomson, *l c* The exact theory of the vibrations of an elastic sphere gives, for the slowest oscillation of a steel globe of the dimensions of the earth, a period of 1 h 18 m. See a paper "On the Vibrations of an Elastic Sphere," *Proc Lond. Math Soc*, t. xii. p. 212 (1882) The vibrations of a sphere of incompressible substance, under the joint influence of gravity and elasticity, have been discussed by Bromwich, *Proc Lond Math Soc*, t. xxx. p 98 (1898).

When the surface oscillates in the form of a *zonal* harmonic spheroid of the second order, the equation of the lines of motion is $x\varpi^2 = \text{const}$, where ϖ denotes the distance of any point from the axis of symmetry, which is taken as axis of x (see Art 95 (11)). The forms of these lines, for a series of equidistant values of the constant, are shewn in the figure.

260 This problem may also be treated very compactly by the method of 'normal coordinates' (Art 167)

The kinetic energy is given by the formula

$$T = \frac{1}{2}\rho \iint \phi \frac{\partial \phi}{\partial r} dS, \quad \dots \dots \dots (11)$$

where δS is an element of the surface $r = a$. Hence, when the surface oscillates in the form $r = a + \zeta_n$, we find, on substitution from (2) and (4),

$$T = \frac{1}{2} \frac{\rho a}{n} \iint \dot{\zeta}_n^2 dS \quad \dots \dots \dots (12)$$

To find the potential energy, we may suppose that the external surface is constrained to assume in succession the forms $r = a + \theta \zeta_n$, where θ varies from 0 to 1. At any stage of this process, the gravitation potential at the surface is, by (6),

$$\Omega = \text{const} + \frac{2(n-1)}{2n+1} g\theta \zeta_n \quad \dots \dots (13)$$

Hence the work required to add a film of thickness $\zeta_n \delta \theta$ is

$$\theta \delta \theta \frac{2(n-1)}{2n+1} g\rho \iint \zeta_n^2 dS \quad \dots \dots (14)$$

Integrating this from $\theta = 0$ to $\theta = 1$, we find

$$V = \frac{n-1}{2n+1} g\rho \iint \zeta_n^2 dS \quad \dots \dots (15)$$

The results corresponding to the general deformation (1) are obtained by prefixing the sign Σ of summation with respect to n , in (12) and (15), since the terms involving products of surface-harmonics of different orders vanish, by Art 87

The fact that the general expressions for T and V thus reduce to sums of squares shews that any spherical-harmonic deformation is of a 'normal type.' Also, assuming that $\zeta_n \propto \cos(\sigma_n t + \epsilon)$, the consideration that the total energy $T + V$ must be constant leads us again to the result (10)

In the case of the forced oscillations due to a disturbing potential $\Omega' \cos(\sigma t + \epsilon)$ which satisfies the equation $\nabla^2 \Omega' = 0$ at all points of the fluid, we must suppose Ω' to be expanded in a series of solid harmonics. If $\bar{\zeta}_n$ be

the equilibrium-elevation corresponding to the term of order n , we have, by Art. 167 (13), for the forced oscillation,

$$\zeta_n = \frac{1}{1 - \sigma^2/\sigma_n^2} \bar{\zeta}_n, \quad \dots \dots \dots (16)$$

where σ is the imposed speed, and σ_n that of the free oscillations of the same type, as given by (10)

The numerical results given above for the case $n=2$ shew that, in a non-rotating liquid globe of the same dimensions and mean density as the earth, forced oscillations having the characters and periods of the actual lunar and solar tides, would practically have the amplitudes assigned by the equilibrium-theory

261. The investigation is easily extended to the case of an ocean of any uniform depth, covering a symmetrical spherical nucleus.

Let b be the radius of the nucleus, a that of the external surface. The surface-form being

$$r = a + \sum_1^{\infty} \zeta_n, \quad \dots \dots \dots (1)$$

we assume, for the velocity-potential,

$$\phi = \left\{ (n+1) \frac{r^n}{b^n} + n \frac{b^{n+1}}{r^{n+1}} \right\} S_n, \quad \dots \dots \dots (2)$$

where the coefficients have been adjusted so as to make $\partial\phi/\partial r = 0$ for $r=b$

$$\text{The condition that} \quad \frac{\partial\zeta}{\partial t} = -\frac{\partial\phi}{\partial r}, \quad \dots \dots \dots (3)$$

$$\text{for } r=a, \text{ gives} \quad \frac{\partial\zeta_n}{\partial t} = -n(n+1) \left\{ \left(\frac{a}{b}\right)^n - \left(\frac{b}{a}\right)^{n+1} \right\} \frac{S_n}{a} \quad \dots \dots \dots (4)$$

For the gravitation-potential at the free surface (1) we have

$$\Omega = -\frac{4\pi\gamma\rho_0 a^3}{3r} - \sum_1^{\infty} \frac{4\pi\gamma\rho a}{2n+1} \zeta_n, \quad \dots \dots \dots (5)$$

where ρ_0 is the mean density of the whole mass. Hence, putting $g = \frac{4}{3}\pi\gamma\rho_0 a$, we find

$$\Omega = \text{const} + g \sum_1^{\infty} \left(1 - \frac{3}{2n+1} \frac{\rho}{\rho_0} \right) \zeta_n \quad \dots \dots \dots (6)$$

The pressure-condition at the free surface then gives

$$\left\{ (n+1) \left(\frac{a}{b}\right)^n + n \left(\frac{b}{a}\right)^{n+1} \right\} \frac{\partial S_n}{\partial t} = \left(1 - \frac{3}{2n+1} \frac{\rho}{\rho_0} \right) g \zeta_n \quad \dots \dots \dots (7)$$

The elimination of S_n between (4) and (7) leads to

$$\frac{\partial^2 \zeta_n}{\partial t^2} + \sigma_n^2 \zeta_n = 0, \quad \dots \dots \dots (8)$$

$$\text{where} \quad \sigma_n^2 = \frac{n(n+1) \left\{ \left(\frac{a}{b}\right)^n - \left(\frac{b}{a}\right)^{n+1} \right\}}{(n+1) \left(\frac{a}{b}\right)^n + n \left(\frac{b}{a}\right)^{n+1}} \left(1 - \frac{3}{2n+1} \frac{\rho}{\rho_0} \right) \frac{g}{a} \quad \dots \dots \dots (9)$$

If $\rho = \rho_0$, we have $\sigma_1 = 0$ as we should expect. When $\rho > \rho_0$ the value of σ_1 is imaginary, the equilibrium configuration in which the external surface of the fluid is concentric with the nucleus is then unstable (Cf Art 198)

If in (9) we put $b = 0$, we reproduce the result of the preceding Art. If, on the other hand, the depth of the ocean be small compared with the radius, we find, putting $b = a - h$, and neglecting the square of h/a ,

$$\sigma_n^2 = n(n+1) \left(1 - \frac{3}{2n+1} \frac{\rho}{\rho_0} \right) \frac{gh}{a^2}, \quad \dots \dots (10)$$

provided n be small compared with a/h . This agrees with Laplace's result, obtained in a more direct manner in Art 198

But if n be comparable with a/h , we have, putting $n = ka$,

$$\left(\frac{a}{b} \right)^n = \left(1 - \frac{h}{a} \right)^{-ka} = e^{kh},$$

so that (9) reduces to

$$\sigma^2 = gk \tanh kh, \quad (11)$$

as in Art 227. Moreover, the expression (2) for the velocity-potential becomes, if we write $r = a + z$,

$$\phi = \phi_1 \cosh k(z+h), \quad (12)$$

where ϕ_1 is a function of the coordinates in the surface, which may now be treated as plane. Cf Art 254

The formulae for the kinetic and potential energies, in the general case, are easily found by the same method as in the preceding Art to be

$$T = \frac{1}{2} \rho a \sum_{n=1}^{\infty} \frac{(n+1) \left(\frac{a}{b} \right)^n + n \left(\frac{b}{a} \right)^{n+1}}{n(n+1) \left\{ \left(\frac{a}{b} \right)^n - \left(\frac{b}{a} \right)^{n+1} \right\}} \iint \zeta_n^2 dS, \quad \dots \dots (13)$$

and

$$V = \frac{1}{2} g \rho \sum_{n=1}^{\infty} \left(1 - \frac{3}{2n+1} \frac{\rho}{\rho_0} \right) \iint \zeta_n^2 dS \quad \dots \dots (14)$$

The latter result shews, again, that the equilibrium configuration is one of minimum potential energy, and therefore thoroughly stable, provided $\rho < \rho_0$

In the case where the depth is relatively small, whilst n is finite, we obtain, putting $b = a - h$,

$$T = \frac{1}{2} \frac{\rho a^2}{h} \sum_{n=1}^{\infty} \frac{1}{n(n+1)} \iint \zeta_n^2 dS, \quad \dots \dots (15)$$

whilst the expression for V is of course unaltered

If the amplitudes of the harmonics ζ_n be regarded as generalized coordinates, the formula (15) shews that for relatively small depths the 'inertia-coefficients' vary inversely as the depth. We have had frequent illustrations of this principle in our discussions of tidal waves

Capillarity

262. The part played by Cohesion in certain cases of fluid motion has long been recognized in a general way, but it is only within comparatively recent years that the question has been subjected to exact mathematical treatment. We proceed to give some account of the remarkable investigations of Lord Kelvin and Lord Rayleigh in this field.

It is beyond our province to discuss the physical theory of the matter*. It is sufficient, for our purpose, to know that the free surface of a liquid, or, more generally, the common surface of two fluids which do not mix, behaves as if it were in a state of uniform *tension*, the stress between two adjacent portions of the surface, estimated at per unit length of the common boundary-line, depending only on the nature of the two fluids and on the temperature. We shall denote this 'surface-tension,' as it is called, by the symbol T_1 . Its value in C.G.S. units (dynes per linear centimetre) appears to be about 74 for a water-air surface at 20° C.†, it diminishes somewhat with rise of temperature. The corresponding value for a mercury-air surface is about 540.

An equivalent statement is that the potential energy of any system, of which the surface in question forms part, contains a term proportional to the area of the surface, the amount of this 'superficial energy' per unit area being equal to T_1 ‡. Since the condition of stable equilibrium is that the energy should be a minimum, the surface tends to contract as much as is consistent with the other conditions of the problem.

The chief modification which the consideration of surface-tension will introduce into our previous methods is contained in the theorem that the fluid pressure is now discontinuous at a surface of separation, viz. we have

$$p - p' = T_1 \left(\frac{1}{R_1} + \frac{1}{R_2} \right),$$

where p, p' are the pressures close to the surface on the two sides, and R_1, R_2 are the principal radii of curvature of the surface, to be reckoned negative when the corresponding centres of curvature lie on the side to which the accent refers. This formula is readily obtained by resolving along the normal the forces acting on a rectangular element of a superficial film, bounded by lines of curvature, but it seems unnecessary to give here the proof, which may be found in most modern treatises on Hydrostatics.

* For this, see Maxwell, *Encyc. Britann.*, Art "Capillary Action" [*Sc. Papers*, Cambridge, 1890, t. II, p. 541], where references to the older writers are given. Also, Lord Rayleigh, "On the Theory of Surface Forces," *Phil. Mag.* (5), t. xxx, pp. 285, 456 (1890) [*Sc. Papers*, t. III, p. 397].

† Lord Rayleigh, "On the Tension of Water-Surfaces, Clean and Contaminated, investigated by the method of Ripples," *Phil. Mag.* (5), t. xxx, p. 386 (1890) [*Sc. Papers*, t. III, p. 394].

‡ See Maxwell, *Theory of Heat*, London, 1871, c. xx.

263 The simplest problem we can take, to begin with, is that of waves on a plane surface forming the common boundary of two fluids at rest.

If the origin be taken in this plane, and the axis of y normal to it, the velocity-potentials corresponding to a simple-harmonic deformation of the common surface may be assumed to be

$$\left. \begin{aligned} \phi &= Ce^{ky} \cos kx \cos(\sigma t + \epsilon), \\ \phi' &= C'e^{-ky} \cos kx \cos(\sigma t + \epsilon), \end{aligned} \right\} \dots \dots (1)$$

where the former equation relates to the side on which y is negative, and the latter to that on which y is positive. For these values satisfy $\nabla^2 \phi = 0$, $\nabla^2 \phi' = 0$, and make the velocity zero for $y = \mp \infty$, respectively.

The corresponding displacement of the surface in the direction of y will be of the type

$$\eta = a \cos kx \sin(\sigma t + \epsilon); \dots \dots \dots (2)$$

and the conditions that

$$\frac{\partial \eta}{\partial t} = -\frac{\partial \phi}{\partial y} = -\frac{\partial \phi'}{\partial y},$$

for $y = 0$, give

$$\sigma a = -kC = kC'. \dots \dots \dots (3)$$

If, for the moment, we ignore gravity, the variable part of the pressure is given by

$$\left. \begin{aligned} \frac{p}{\rho} &= \frac{\partial \phi}{\partial t} = \frac{\sigma^2 a}{k} e^{ky} \cos kx \sin(\sigma t + \epsilon), \\ \frac{p'}{\rho} &= \frac{\partial \phi'}{\partial t} = -\frac{\sigma^2 a}{k} e^{-ky} \cos kx \sin(\sigma t + \epsilon) \end{aligned} \right\} \dots \dots \dots (4)$$

To find the pressure-condition at the common surface, we may calculate the forces which act in the direction of y on a strip of breadth δx . The fluid pressures on the two sides have a resultant $(p' - p)\delta x$, and the difference of the tensions parallel to y on the two edges gives $\delta(T_1 \partial \eta / \partial x)$. We thus get the equation

$$p - p' + T_1 \frac{\partial^2 \eta}{\partial x^2} = 0, \dots \dots \dots (5)$$

to be satisfied when $y = 0$ approximately. This might have been written down at once as a particular case of the general surface condition (Art. 262). Substituting in (5) from (2) and (4), we find

$$\sigma^2 = \frac{T_1 k^3}{\rho + \rho'}, \dots \dots \dots (6)$$

which determines the speed of the oscillations of wave-length $2\pi/k$.

The energy of motion, per wave-length, of the fluid included between two planes parallel to xy , at unit distance apart, is

$$T = \frac{1}{2} \rho \int_0^\lambda \left[\phi \frac{\partial \phi}{\partial y} \right]_{y=0} dx - \frac{1}{2} \rho' \int_0^\lambda \left[\phi' \frac{\partial \phi'}{\partial y} \right]_{y=0} dx \quad \dots (7)$$

If we assume

$$\eta = a \cos kx, \quad \dots \dots \dots (8)$$

where a depends on t only, and therefore, having regard to the kinematical conditions,

$$\phi = -k^{-1} a e^{ky} \cos kx, \quad \phi' = k^{-1} a e^{-ky} \cos kx, \quad \dots (9)$$

we find

$$T = \frac{1}{4} (\rho + \rho') k^{-1} a^2 \lambda \quad \dots \dots \dots (10)$$

Again, the energy of extension of the surface of separation is

$$V = T_1 \int_0^\lambda \left\{ 1 + \left(\frac{\partial \eta}{\partial x} \right)^2 \right\}^{\frac{1}{2}} dx - T_1 \lambda = \frac{1}{2} T_1 \int_0^\lambda \left(\frac{\partial \eta}{\partial x} \right)^2 dx \quad \dots (11)$$

Substituting from (8), this gives

$$V = \frac{1}{4} T_1 k^2 a^2 \cdot \lambda. \quad \dots \dots \dots (12)$$

To find the mean energy, of either kind, per unit length of the axis of x , we must omit the factor λ

If we assume that $a \propto \cos(\sigma t + \epsilon)$, where σ is determined by (6), we verify that the total energy $T + V$ is constant

Conversely, if we assume that

$$\eta = \Sigma (a \cos kx + \beta \sin kx), \quad \dots \dots \dots (13)$$

it is easily seen that the expressions for T and V will reduce to sums of squares of a , β and α , β , respectively, with constant coefficients, so that the quantities a , β are 'normal coordinates' The general theory of Art 167 then leads independently to the formula (6) for the speed

By compounding two systems of standing waves, as in Art 228, we obtain a progressive wave-system

$$\eta = a \cos (kx \mp \sigma t), \quad \dots \dots \dots (14)$$

travelling with the velocity

$$c = \frac{\sigma}{k} = \left(\frac{T_1 k}{\rho + \rho'} \right)^{\frac{1}{2}}, \quad \dots \dots \dots (15)$$

or, in terms of the wave-length,

$$c = \left(\frac{2\pi T_1}{\rho + \rho'} \right)^{\frac{1}{2}} \lambda^{-\frac{1}{2}} \quad \dots \dots \dots (16)$$

The contrast with Art 228 is noteworthy, as the wave-length is diminished, the period diminishes in a more rapid ratio, so that the wave-velocity *increases*

Since c varies as $\lambda^{-\frac{1}{2}}$, the group-velocity is, by Art 234 (3),

$$U = c - \lambda \frac{dc}{d\lambda} = \frac{3}{2} c. \quad \dots \dots \dots (17)$$

The fact that the group-velocity for capillary waves exceeds the wave-velocity helps to explain some interesting phenomena to be referred to later (Arts. 266, 268)

For numerical illustration we may take the case of a free water-surface, thus, putting $\rho = 1$, $\rho' = 0$, $T_1 = 74$, we have the following results, the units being the centimetre and second*.

Wave-length	Wave-velocity	Frequency
50	30	61
10	68	680
05	96	1930

264 When gravity is to be taken into account, the common surface, in equilibrium, will of course be horizontal. Taking the positive direction of y upwards, the pressure at the disturbed surface will be given by

$$\left. \begin{aligned} \frac{p}{\rho} = \frac{\partial \phi}{\partial t} - gy &= \left(\frac{\sigma^2}{k} - g \right) a \cos kx \sin (\sigma t + \epsilon), \\ \frac{p'}{\rho'} = \frac{\partial \phi'}{\partial t} - gy &= - \left(\frac{\sigma^2}{k} + g \right) a \cos kx \sin (\sigma t + \epsilon), \end{aligned} \right\} \dots\dots(1)$$

approximately. Substituting in Art. 263 (5), we find

$$\sigma^2 = \frac{\rho - \rho'}{\rho + \rho'} gk + \frac{T_1 k^3}{\rho + \rho'}. \quad \dots \dots \dots (2)$$

Putting $\sigma = kc$, we find, for the velocity of a train of progressive waves,

$$c^2 = \frac{\rho - \rho'}{\rho + \rho'} \frac{g}{k} + \frac{T_1}{\rho + \rho'} k, \quad k = \frac{1-s}{1+s} \left(\frac{g}{k} + T'k \right), \quad \dots \dots (3)$$

where we have written

$$\frac{\rho'}{\rho} = s, \quad \frac{T_1}{\rho - \rho'} = T' \quad \dots \dots \dots (4)$$

In the particular cases of $T_1 = 0$ and $g = 0$, respectively, we fall back on the results of Arts 231, 1°, and 263

There are several points to be noticed with respect to the formula (3) In the first place, although, as the wave-length ($2\pi/k$) diminishes from ∞ to 0, the speed (σ) continually increases, the wave-velocity, after falling to

* Cf Sir W Thomson, *Math and Phys Papers*, t iii p 520
The above theory gives the explanation of the ‘crispations’ observed on the surface of water contained in a finger-bowl set into vibration by stroking the rim with a wetted finger. It is to be observed, however, that the frequency of the capillary waves in this experiment is *double* that of the vibrations of the bowl, see Lord Rayleigh, “On Maintained Vibrations,” *Phil. Mag* (5), t xv p. 229 (1883) [*Sc. Papers*, t ii p. 188, *Theory of Sound*, 2nd ed, c xx]

a certain minimum, begins to increase again This minimum value (c_m , say) is given by

$$c_m^2 = \frac{1-s}{1+s} \cdot 2 (gT')^{\frac{1}{2}}, \quad \dots \dots \dots (5)$$

and corresponds to a wave-length

$$\lambda_m = \frac{2\pi}{k_m} = 2\pi \sqrt{\left(\frac{T'}{g}\right)} \dots \dots \dots (6)^*$$

In terms of λ_m and c_m the formula (3) may be written

$$\frac{c^2}{c_m^2} = \frac{1}{2} \left(\frac{\lambda}{\lambda_m} + \frac{\lambda_m}{\lambda} \right), \quad \dots \dots \dots (7)$$

shewing that for any prescribed value of c , greater than c_m , there are two admissible values (reciprocals) of λ/λ_m For example, corresponding to

$\frac{c}{c_m} =$	1.2	1.4	1.6	1.8	2.0
-------------------	-----	-----	-----	-----	-----

we have

$\frac{\lambda}{\lambda_m} =$	2.476	3.646	4.917	6.322	7.873
	4.04	2.74	2.03	1.58	1.27,

to which we add, for future reference,

$\sin^{-1} \frac{c_m}{c} =$	56° 26'	45° 35'	38° 41'	33° 45'	30°
-----------------------------	---------	---------	---------	---------	-----

For sufficiently large values of λ the first term in the formula (3) for c^2 is large compared with the second, the force governing the motion of the waves being mainly that of gravity On the other hand, when λ is very small, the second term preponderates, and the motion is mainly governed by cohesion, as in Art 263 As an indication of the actual magnitudes here in question, we may note that if $\lambda/\lambda_m > 10$, the influence of cohesion on the wave-velocity amounts only to about 5 per cent., whilst gravity becomes relatively ineffective to a like degree if $\lambda/\lambda_m < \frac{1}{10}$.

It has been proposed by Lord Kelvin to distinguish by the name of 'ripples' waves whose length is less than λ_m .

The relative importance of gravity and cohesion, as depending on the value of λ , may be traced to the form of the expression for the potential energy of a deformation of the type


$$\eta = a \cos kx \quad \dots \dots \dots (8)$$

The part of this energy due to the extension of the bounding surface is, per unit area,

$$\frac{\pi^2 T_1 a^2}{\lambda^2}, \quad \dots \dots \dots (9)$$

* The theory of the minimum wave-velocity, together with most of the substance of Arts 263, 264, was given by Sir W. Thomson, "Hydrokinetic Solutions and Observations," *Phil. Mag.* (4), t. xlv p. 374 (1871) [*Baltimore Lectures*, p. 598], see also *Nature*, t. v p. 1 (1871).

i.e. provided λ be less than the wave-length λ_m of minimum velocity when the denser fluid is below. Hence in the case of water above and air below the maximum wave-length consistent with stability is 1.73 cm. If the fluids be included between two parallel vertical



walls, this imposes a superior limit to the admissible wave-length, and we learn that there is stability (in the two-dimensional problem) provided the interval between the walls does not exceed 86 cm. We have here an explanation, in principle, of a familiar experiment in which water is retained by atmospheric pressure in an inverted tumbler, or other vessel, whose mouth is covered by a gauze with sufficiently fine meshes*.

265. We next consider the case of waves on a horizontal surface forming the common boundary of two parallel currents U , U' †

If we apply the method of Art. 232, we find without difficulty that the condition for stationary waves is now

$$\rho U^3 + \rho' U'^3 = \frac{g}{k}(\rho - \rho') + kT_1, \quad \dots \quad (1)$$

* The case where the fluids are contained in a cylindrical tube was solved by Maxwell, *Encyc. Britann.*, Art. "Capillary Action," t. v. p. 69 [*Sci. Papers*, t. ii. p. 585], and compared with some experiments of Duprez. The agreement is better than might have been expected when we consider that the special condition to be satisfied at the line of contact of the surface with the wall of the tube has been left out of account.

† Cf. Sir W. Thomson, *Phil. Mag.* (4), t. xlii. p. 368 (1871) [*Baltimore Lectures*, p. 590].

the last term being due to the altered form of the pressure-condition which has to be satisfied at the surface

This may be written

$$\left(\frac{\rho U + \rho' U'}{\rho + \rho'}\right)^2 = \frac{g}{k} \frac{\rho - \rho'}{\rho + \rho'} + \frac{k T_1}{\rho + \rho'} - \frac{\rho \rho'}{(\rho + \rho')^2} (U - U')^2. \quad \dots \dots (2)$$

The relative velocity of the waves, which is superposed on the mean velocity of the currents (Art. 232), is $\pm c$, provided

$$c^2 = c_0^2 - \frac{\rho \rho'}{(\rho + \rho')^2} (U - U')^2, \quad \dots \dots (3)$$

where c_0 denotes the wave-velocity in the absence of currents.

The various inferences to be drawn from (3) are much as in the Art. cited, with the important qualification that, since c_0 has now a minimum value, viz the c_m of Art. 264 (5), the equilibrium of the surface when plane is stable for disturbances of all wave-lengths so long as

$$|U - U'| < \frac{1+s}{s^{\frac{1}{2}}} c_m, \quad \dots \dots (4)$$

where $s = \rho'/\rho$

When the relative velocity of the two currents exceeds this value, c becomes imaginary for wave-lengths lying between certain limits. It is evident that in the alternative method of Art 233 the time-factor $e^{i\sigma t}$ will now take the form $e^{\pm \alpha t + i\beta t}$, where

$$\alpha = \left\{ \frac{s}{(1+s)^2} (U - U')^2 - c_0^2 \right\}^{\frac{1}{2}} k, \quad \beta = \frac{s}{1+s} k |U - U'| \quad \dots (5)$$

The real part of the exponential indicates the possibility of a disturbance of continually increasing amplitude

For the case of air over water we have $s = 0.0129$, $c_m = 23.2$ (c s), whence the maximum value of $|U - U'|$ consistent with stability is about 646 centimetres per second, or (roughly) 12.5 sea-miles per hour*. For slightly greater values the instability will manifest itself by the formation, in the first instance, of wavelets of about two-thirds of an inch in length, which will continually increase in amplitude until they transcend the limits implied in our approximation

266 We resume the investigation of the effect of a steady pressure-disturbance on the surface of a running stream, by the methods of Arts. 240, 241, including now the effect of capillary forces. This will give, in addition to the former results, the explanation (in principle) of the fringe of ripples

* The wind-velocity at which the surface of water actually begins to be ruffled by the formation of capillary waves, so as to lose the power of distinct reflection, is much less than this, and is determined by other causes. We shall revert to this point later (Chap. XI).

which is seen in advance of a solid moving at a moderate speed through still water, or on the up-stream side of any disturbance in a uniform current

Beginning with a simple-harmonic distribution of pressure, we assume

$$\frac{\phi}{c} = -x + \beta e^{ky} \sin kx, \quad \frac{\psi}{c} = -y + \beta e^{ky} \cos kx, \quad \dots \quad (1)$$

the upper surface coinciding with the stream-line $\psi = 0$, whose equation is

$$y = \beta \cos kx, \quad \dots \quad (2)$$

approximately. At a point just beneath this surface we find, as in Art 240 (5), for the variable part of the pressure,

$$p_0 = \beta \rho \{ (kc^2 - g) \cos kx + \mu c \sin kx \}, \quad \dots \quad (3)$$

where μ is the frictional coefficient. At an adjacent point just above the surface we must have

$$p_0' = p_0 + T_1 \frac{d^2 y}{dx^2} = \beta \rho \{ (kc^2 - g - k^2 T') \cos kx + \mu c \sin kx \}, \quad \dots \quad (4)$$

where T' is now written for T_1/ρ . This is equal to the real part of

$$\beta \rho (kc^2 - g - k^2 T' - i\mu c) e^{ikx}$$

We infer that to the imposed pressure

$$p_0 = C \cos kx \quad \dots \quad (5)$$

will correspond the surface-form

$$\rho y = C \frac{(kc^2 - g - k^2 T') \cos kx - \mu c \sin kx}{(kc^2 - g - k^2 T')^2 + \mu^2 c^2} \quad \dots \quad (6)$$

Let us first suppose that the velocity c of the stream exceeds the minimum wave-velocity (c_m) investigated in Art 264. We may then write

$$kc^2 - g - k^2 T' = T' (k - \kappa_1)(\kappa_2 - k), \quad \dots \quad (7)$$

where κ_1, κ_2 are the two values of k corresponding to the wave-velocity c on still water, in other words, $2\pi/\kappa_1, 2\pi/\kappa_2$ are the lengths of the two systems of free waves which could maintain a stationary position in space, on the surface of the flowing stream. We will suppose that $\kappa_2 > \kappa_1$.

In terms of these quantities, the formula (6) may be written

$$\rho y = \frac{C}{T'} \frac{(k - \kappa_1)(\kappa_2 - k) \cos kx - \mu' \sin kx}{(k - \kappa_1)^2 (\kappa_2 - k)^2 + \mu'^2}, \quad \dots \quad (8)$$

where $\mu' = \mu c/T'$. This shews that if μ' be small the pressure is least over the crests, and greatest over the troughs of the waves when k is greater than κ_2 or less than κ_1 , whilst the reverse is the case when k is intermediate to κ_1, κ_2 . In the case of a progressive disturbance advancing over still water, these results are seen to be in accordance with Art. 167 (13).

267 From (8) we can infer as in Art 241 the effect of a pressure of integral amount P concentrated on a line of the surface at the origin, viz. we find

$$y = \frac{P}{\pi T_1} \int_0^\infty \frac{(k - \kappa_1)(\kappa_2 - k) \cos kx - \mu' \sin kx}{(k - \kappa_1)^2 (\kappa_2 - k)^2 + \mu'^2} dk. \quad \dots \quad (9)$$

The definite integral is the real part of

$$\int_0^\infty \frac{e^{ikx} dk}{(k - \kappa_1)(\kappa_2 - k) - i\mu'} \quad \dots \quad (10)$$

The dissipation-coefficient μ' has been introduced solely for the purpose of making the problem determinate, we may therefore avail ourselves of the slight gain in simplicity obtained by supposing μ' to be infinitesimal. In this case the two roots of the denominator in (10) are

$$k = \kappa_1 + i\nu, \quad k = \kappa_2 - i\nu,$$

where

$$\nu = \frac{\mu'}{\kappa_2 - \kappa_1}.$$

The integral (10) is therefore equivalent to

$$\frac{1}{\kappa_2 - \kappa_1 - 2i\nu} \left\{ \int_0^\infty \frac{e^{ikx} dk}{k - (\kappa_1 + i\nu)} - \int_0^\infty \frac{e^{ikx} dk}{k - (\kappa_2 - i\nu)} \right\}. \quad \dots \quad (11)$$

These integrals are of the forms discussed in Art. 241. Since $\kappa_2 > \kappa_1$, ν is positive, and it appears that when x is positive the former integral is equal to

$$2\pi i e^{i\kappa_1 x} + \int_0^\infty \frac{e^{-ikx}}{k + \kappa_1} dk, \quad \dots \quad (12)$$

and the latter to

$$\int_0^\infty \frac{e^{-ikx}}{k + \kappa_2} dk \quad \dots \quad (13)$$

On the other hand, when x is negative, the former reduces to

$$\int_0^\infty \frac{e^{-ikx}}{k + \kappa_1} dk, \quad \dots \quad (14)$$

and the latter to

$$-2\pi i e^{i\kappa_2 x} + \int_0^\infty \frac{e^{-ikx}}{k + \kappa_2} dk. \quad \dots \quad (15)$$

We have here simplified the formulae by putting $\nu = 0$ after the transformations

If we now discard the imaginary parts of our expressions, we obtain the results which immediately follow

When μ' is infinitesimal, the equation (9) gives, for x positive,

$$\frac{\pi T_1}{P} \cdot y = - \frac{2\pi}{\kappa_2 - \kappa_1} \sin \kappa_1 x + F(x), \quad \dots \quad (16)$$

and, for x negative,

$$\frac{\pi T_1}{P} \cdot y = - \frac{2\pi}{\kappa_2 - \kappa_1} \sin \kappa_2 x + F(x), \quad \dots \quad (17)$$

where

$$F(x) = \frac{1}{\kappa_2 - \kappa_1} \left\{ \int_0^\infty \frac{\cos kx}{k + \kappa_1} dk - \int_0^\infty \frac{\cos kx}{k + \kappa_2} dk \right\}. \quad \dots \quad (18)$$

This function $F(x)$ can be expressed in terms of the known functions $C_1 \kappa_1 x$, $S_1 \kappa_1 x$, $C_1 \kappa_2 x$, $S_1 \kappa_2 x$, by Art 241 (28) The disturbance of level represented by it is very small for values of x , whether positive or negative, which exceed, say, half the greater wave-length ($2\pi/\kappa_1$)

Hence, beyond some such distance, the surface is covered on the down-stream side by a regular train of simple-harmonic waves of length $2\pi/\kappa_1$, and on the up-stream side by a train of the shorter wave-length $2\pi/\kappa_2$ It appears from the numerical results of Art 264 that when the velocity c of the stream much exceeds the minimum wave-velocity (c_m) the former system of waves is governed mainly by gravity, and the latter by cohesion

It is worth notice that, in contrast with the case of Art. 241, the elevation is now finite when $x=0$, viz. we have


$$\frac{\pi T_1}{Q} \ y = \frac{1}{\kappa_2 - \kappa_1} \log \frac{\kappa_2}{\kappa_1} \quad (19)$$

This follows easily from (16) and (18)

The figure shews the transition between the two sets of waves, in the case of $\kappa_2 = 5\kappa_1$

The general explanation of the effects of an isolated pressure-disturbance advancing over still water, indicated near the end of Art. 241, is now modified by the fact that there are *two* wave-lengths corresponding to the given velocity c For one of these (the shorter) the group-velocity is greater, whilst for the other it is less, than c We can thus understand why the waves of shorter wave-length should be found ahead, and those of longer wave-length in the rear, of the disturbing pressure

It will be noticed that the formulae (16), (17) make the height of the up-stream capillary waves the same as that of the down-stream gravity-waves, but this result will be greatly modified when the pressure is diffused over a band of sensible breadth, instead of being concentrated on a mathematical line If, for example, the breadth of the band do not exceed one-fourth of the wave-length on the



down-stream side, whilst it considerably exceeds the wave-length of the up-stream ripples, as may happen with a very moderate velocity, the different parts of the breadth will on the whole reinforce one another as regards their action on the down-stream side, whilst on the up-stream side we shall have 'interference,' with a comparatively small residual amplitude

This point may be illustrated by assuming that the integral surface-pressure P has the distribution

$$p' = \frac{P}{\pi} \frac{b}{b^2 + x^2}, \quad . \quad .. \quad . \quad (20)$$

which is more diffused, the greater the value of b

The method of calculation will be understood from Art 242 The result is that on the down-stream side

$$y = -\frac{2P}{\rho T'(\kappa_2 - \kappa_1)} e^{-\kappa_1 b} \sin \kappa_1 x + \dots, \quad (21)$$

and on the up-stream side

$$y = -\frac{2P}{\rho T'(\kappa_2 - \kappa_1)} e^{-\kappa_2 b} \sin \kappa_2 x + \dots, \quad (22)$$

where the terms which are insensible at a distance of half a wave-length or so from the origin are omitted. The exponential factors shew the attenuation due to diffusion, this is greater on the side of the capillary waves, since $\kappa_2 > \kappa_1$

When the velocity c of the stream is less than the minimum wave-velocity, the factors of

$$kc^2 - g - k^2 T'$$

are imaginary There is now no indeterminateness caused by putting $\mu = 0$ *ab initio* The surface-form is given by

$$y = -\frac{P}{\pi \rho} \int_0^\infty \frac{\cos kx}{k^2 T' - kc^2 + g} dk \quad \dots \quad (23)$$

The integral might be transformed by the previous method, but it is evident *à priori* that its value tends rapidly, with increasing x , to zero, on account of the more and more rapid fluctuations in sign of $\cos kx$ The disturbance of level is now confined to the neighbourhood of the origin For $x=0$ we find

$$y = -\frac{P}{(c_m^4 - c^4)^{\frac{1}{2}} \rho} \left(1 + \frac{2}{\pi} \sin^{-1} \frac{c^2}{c_m^2} \right). \quad \dots \quad (24)$$

Finally we have the critical case where c is exactly equal to the minimum wave-velocity, and therefore $\kappa_2 = \kappa_1$ The first term in (16) or (17) is now infinite, whilst the remainder of the expression, when evaluated, is finite. To get an intelligible result in this case it is necessary to retain the frictional coefficient μ' .

If we put $\mu' = 2\omega^2$, we have

$$(k - \kappa)^2 + i\mu' = \{k - (\kappa + \omega - i\omega)\} \{k - (\kappa - \omega + i\omega)\}, \quad . \quad . \quad . \quad (25)$$

so that the integral (10) may now be equated to

$$\frac{1+i}{4\omega} \left\{ \int_0^\infty \frac{e^{ikx}}{k - (\kappa + \omega - i\omega)} dk - \int_0^\infty \frac{e^{ikx}}{k - (\kappa - \omega + i\omega)} dk \right\} \quad . \quad . \quad (26)$$

The formulae of Art 241 shew that when ω is small the most important part of this expression, for points at a distance from the origin on either side, is

$$\frac{1+i}{4\omega} \cdot 2\pi i e^{i\kappa x} \quad . \quad . \quad . \quad (27)$$

It appears that the surface-elevation is now given by

$$\frac{\pi T_1}{P} \cdot y = - \frac{\pi}{\mu^{\frac{1}{2}}} \cos(\kappa x - \frac{1}{4}\pi) \quad . \quad . \quad . \quad (28)$$

The examination of the effect of inequalities in the bed of a stream, by the method of Art 244, must be left to the reader

268. The investigation by Lord Rayleigh*, from which the foregoing differs principally in the manner of treating the definite integrals, was undertaken with a view to explaining more fully some phenomena described by Scott Russell† and Lord Kelvin‡

“When a small obstacle, such as a fishing line, is moved forward slowly through still water, or (which of course comes to the same thing) is held stationary in moving water, the surface is covered with a beautiful wave-pattern, fixed relatively to the obstacle. On the up-stream side the wave-length is short, and, as Thomson has shewn, the force governing the vibrations is principally cohesion. On the down-stream side the waves are longer, and are governed principally by gravity. Both sets of waves move with the same velocity relatively to the water, namely, that required in order that they may maintain a fixed position relatively to the obstacle. The same condition governs the velocity, and therefore the wave-length, of those parts of the pattern where the fronts are oblique to the direction of motion. If the angle between this direction and the normal to the wave-front be called θ , the velocity of propagation of the waves must be equal to $v_0 \cos \theta$, where v_0 represents the velocity of the water relatively to the fixed obstacle.

“Thomson has shewn that, whatever the wave-length may be, the velocity of propagation of waves on the surface of water cannot be less than about 23 centimetres per second. The water must run somewhat faster than

* *l c ante* p 378

† “On Waves,” *Brit Ass Rep*, 1844

‡ *l c ante* p 437

this in order that the wave-pattern may be formed. Even then the angle θ is subject to a limit defined by $v_0 \cos \theta = 23$, and the curved wave-front has a corresponding asymptote

“The immersed portion of the obstacle disturbs the flow of the liquid independently of the deformation of the surface, and renders the problem in its original form one of great difficulty. We may however, without altering the essence of the matter, suppose that the disturbance is produced by the application to one point of the surface of a slightly abnormal pressure, such as might be produced by electrical attraction, or by the impact of a small jet of air. Indeed, either of these methods—the latter especially—gives very beautiful wave-patterns*”

The character of the wave-pattern can be made out by the method explained near the end of Art. 253

If we take account of capillarity alone, the formula (17) of the Art. cited gives

$$c^2 \cos^2 \theta = V^2 = \frac{2\pi T'}{\lambda}, \dots \dots \dots (1)$$

by Art. 263, and the form of the wave-ridges is accordingly determined by the equation

$$p = a \sec^2 \theta \dots \dots \dots (2) +$$

This leads to

$$x = a \sec \theta (1 - 2 \tan^2 \theta), \quad y = 3a \sec \theta \tan \theta. \dots \dots (3)$$

When gravity and capillarity are both regarded, we have, by Art. 264,

$$c^2 \cos^2 \theta = V^2 = \frac{g\lambda}{2\pi} + \frac{2\pi T'}{\lambda} \dots \dots \dots (4)$$

Hence, if we put

$$c_m = (4gT')^{\frac{1}{2}}, \quad b = 2\pi \left(\frac{T'}{g}\right)^{\frac{1}{2}}, \dots \dots \dots (5)$$

we have

$$\frac{\cos^2 \theta}{\cos^2 \alpha} = \frac{1}{2} \left(\frac{\lambda}{b} + \frac{b}{\lambda} \right), \quad \dots \dots \dots (6)$$

where

$$\cos \alpha = \frac{c_m}{c} \dots \dots \dots (7)$$

The relation between p and θ is therefore of the form

$$\frac{\cos^2 \theta}{\cos^2 \alpha} = \frac{1}{2} \left(\frac{p}{a \cos^2 \alpha} + \frac{a \cos^2 \alpha}{p} \right), \dots \dots \dots (8)$$

or

$$\frac{p}{a} = \cos^2 \theta \pm \sqrt{(\cos^4 \theta - \cos^4 \alpha)} \dots \dots \dots (9)$$

The four straight lines for which $\theta = \pm \alpha$ are asymptotes of the curve thus determined. The values of $\frac{1}{2}\pi - \alpha$ for several values of the ratio c/c_m have been given in Art. 263.

* Lord Rayleigh, *l.c.*

+ Since U is now $> V$, it appears from Art. 253 (18) that the constant a must be negative



When the ratio c/c_m is at all considerable, α is nearly equal to $\frac{1}{2}\pi$, and the asymptotes make very acute angles with the axis of x . The upper figure on the preceding page gives the part of the curve which is relevant to the physical problem in the case of $c = 10c_m$ *. The ratio of the wave-lengths of the 'waves' and the 'ripples' in the line of symmetry is then, of course, very great. The curve should be compared with that which forms the basis of the figure on p 413.

As the ratio c/c_m is diminished, the asymptotes open out, whilst the two cusps on either side of the axis approach one another, coincide, and finally disappear†. The wave-system has then a configuration of the kind shewn in the lower diagram, which is drawn for the case where the ratio of the wave-lengths in the line of symmetry is 4 : 1. This corresponds to $\alpha = 26^\circ 34'$, or $c = 1.12c_m$ ‡.

When $c < c_m$, the wave-pattern disappears.

269 Another problem of great interest is the determination of the nature of the equilibrium of a cylindrical column of liquid, of circular section. This contains the theory of the well-known experiments of Bidone, Savart, and others, on the behaviour of a jet issuing under pressure from a small orifice in the wall of a containing vessel. It is obvious that the uniform velocity in the direction of the axis of the jet does not affect the dynamics of the question, and may be disregarded in the analytical treatment.

We will take first the two-dimensional vibrations of the column, the motion being supposed to be the same in each section. Using polar coordinates r, θ in the plane of a section, with the origin in the axis, we may write, in accordance with Art. 63,

$$\phi = A \frac{r^s}{a^s} \cos s\theta \cdot \cos(\sigma t + \epsilon), \quad \dots \dots \dots (1)$$

where a is the mean radius. The equation of the boundary at any instant will then be

$$r = a + \zeta, \quad \dots \dots \dots (2)$$

where
$$\zeta = -\frac{sA}{\sigma a} \cos s\theta \cdot \sin(\sigma t + \epsilon), \quad \dots \dots \dots (3)$$

the relation between the coefficients being determined by

$$\frac{\partial \zeta}{\partial t} = -\frac{\partial \phi}{\partial r}, \quad \dots \dots \dots (4)$$

* The necessary calculations were made by Mr H J Woodall. The scale of the figure does not admit of the asymptotes being shewn distinct from the curve.

† A tentative diagram shewed that they were nearly coincident for $c = 2c_m$ ($\alpha = 60^\circ$).

‡ The figure may be compared with the drawing, from observation, given by Scott Russell, *l c*.

for $r = a$ For the variable part of the pressure inside the column, close to the surface, we have

$$\frac{p}{\rho} = \frac{\partial \phi}{\partial t} = -\sigma A \cos s\theta \sin(\sigma t + \epsilon) \quad \dots \dots \dots (5)$$

The curvature of a curve which differs infinitely little from a circle having its centre at the origin is found by elementary methods to be

$$\frac{1}{R} = \frac{1}{r} - \frac{1}{r^2} \frac{d^2 r}{d\theta^2},$$

or, in the notation of (2),

$$\frac{1}{R} = \frac{1}{a} - \frac{1}{a^2} \left(\zeta + \frac{\partial^2 \zeta}{\partial \theta^2} \right) \quad \dots \quad \dots \quad \dots \dots (6)$$

Hence the surface condition

$$p = \frac{T_1}{R} + \text{const}, \quad \dots \quad \dots \quad \dots \dots (7)$$

gives, on substitution from (5),

$$\sigma^2 = s(s^2 - 1) \frac{T_1}{\rho a^3}, \quad \dots \quad \dots \quad \dots \dots (8)^*$$

For $s = 1$, we have $\sigma = 0$; to our order of approximation the section remains circular, being merely displaced, so that the equilibrium is neutral. For all other integral values of s , σ^2 is positive, so that the equilibrium is thoroughly stable for two-dimensional deformations. This is evident *a priori*, since the circle is the form of least perimeter, and therefore least potential energy, for given sectional area.

In the case of a jet issuing from an orifice in the shape of an ellipse, an equilateral triangle, or a square, prominence is given to the disturbance of the type $s = 2, 3$, or 4 , respectively. The motion being steady, the jet exhibits a system of stationary waves, whose length is equal to the velocity of the jet multiplied by the period $(2\pi/\sigma)$ †.

270. Abandoning now the restriction to two dimensions, we assume that

$$\phi = \phi_1 \cos kz \cos(\sigma t + \epsilon), \quad \dots \quad \dots \quad \dots \dots (9)$$

where the axis of z coincides with that of the cylinder, and ϕ_1 is a function of the remaining coordinates x, y . Substituting in the equation of continuity, $\nabla^2 \phi = 0$, we get

$$(\nabla_1^2 - k^2) \phi_1 = 0, \quad \dots \quad \dots \quad \dots \dots (10)$$

* For the original investigation, by the method of energy, see Lord Rayleigh, "On the Instability of Jets," *Proc Lond Math Soc*, t x p 4 (1878), and "On the Capillary Phenomena of Jets," *Proc Roy Soc*, t xxix p 71 (1879) [*Sc Papers*, t i. pp 361, 377, *Theory of Sound*, 2nd ed c xx]. The latter paper contains a comparison of the theory with experiment.

† It is assumed that this wave-length is large compared with the circumference of the jet. Otherwise, the formula (18) must be employed, with $\sigma = kc$, where c is the velocity of the jet.

where $\nabla_1^2 = \partial^2/\partial x^2 + \partial^2/\partial y^2$. If we put $x = r \cos \theta$, $y = r \sin \theta$, this may be written

$$\frac{\partial^2 \phi_1}{\partial r^2} + \frac{1}{r} \frac{\partial \phi_1}{\partial r} + \frac{1}{r^2} \frac{\partial^2 \phi_1}{\partial \theta^2} - k^2 \phi_1 = 0 \quad \dots \quad (11)$$

This equation is of the form considered in Arts 101, 189, except for the sign of k^2 , the solutions which are finite for $r = 0$ are therefore of the type

$$\phi_1 = BI_s(kr) \left. \begin{matrix} \cos \\ \sin \end{matrix} \right\} s\theta, \quad \dots \quad (12)$$

where, as in Art 209 (11),

$$I_s(z) = \frac{z^s}{2^s s!} \left(1 + \frac{z^2}{2(2s+2)} + \frac{z^4}{2 \cdot 4(2s+2)(2s+4)} + \dots \right). \quad (13)$$

Hence, writing

$$\phi = BI_s(kr) \cos s\theta \cos kz \cos(\sigma t + \epsilon), \quad \dots \quad (14)$$

we have, by (4),

$$\zeta = -B \frac{ka I_s'(ka)}{\sigma a} \cos s\theta \cos kz \sin(\sigma t + \epsilon) \quad \dots \quad (15)$$

To find the sum of the principal curvatures, we remark that, as an obvious consequence of Euler's and Meunier's theorems on curvature of surfaces, the curvature of any section differing infinitely little from a principal normal section is, to the first order of small quantities, the same as that of the principal section itself. It is sufficient therefore in the present problem to calculate the curvatures of a transverse section of the cylinder, and of a section through the axis. These are the principal sections in the undisturbed state, and the principal sections of the deformed surface will make infinitely small angles with them. For the transverse section the formula (6) applies, whilst for the axial section the curvature is $-\partial^2 \zeta / \partial z^2$, so that the required sum of the principal curvatures is

$$\begin{aligned} \frac{1}{R_1} + \frac{1}{R_2} &= \frac{1}{a} - \frac{1}{a^2} \left(\zeta + \frac{\partial^2 \zeta}{\partial \theta^2} \right) - \frac{\partial^2 \zeta}{\partial z^2} \\ &= \frac{1}{a} - B \frac{ka I_s'(ka)}{\sigma a^3} (k^2 a^2 + s^2 - 1) \cos s\theta \cos kz \sin(\sigma t + \epsilon) \quad \dots (16) \end{aligned}$$

Also, at the surface,

$$\frac{\rho}{\rho} = \frac{\partial \phi}{\partial t} = -\sigma BI_s(ka) \cos s\theta \cos kz \sin(\sigma t + \epsilon) \quad \dots \quad (17)$$

The surface-condition of Art 262 then gives

$$\sigma^2 = \frac{ka I_s'(ka)}{I_s(ka)} (k^2 a^2 + s^2 - 1) \frac{T_1}{\rho a^3} \quad \dots \quad (18)$$

For $s > 0$, σ^2 is positive, but in the case ($s = 0$) of symmetry about the axis σ^2 will be negative if $ka < 1$, that is, the equilibrium is unstable for

disturbances whose wave-length ($2\pi/k$) exceeds the circumference of the jet. To ascertain the type of disturbance for which the instability is greatest, we require to know the value of ka which makes

$$\frac{kaI_0'(ka)}{I_0(ka)}(k^2a^2 - 1)$$

a maximum. For this Lord Rayleigh finds $k^2a^2 = .4858$, whence, for the wave-length of maximum instability,

$$\frac{2\pi}{k} = 4.508 \times 2a$$

There is a tendency therefore to the production of bead-like swellings and contractions, of this wave-length, with continually increasing amplitude, until finally the jet breaks up into detached drops*

271 This leads naturally to the discussion of the small oscillations of a drop of liquid about the spherical form†. We will slightly generalize the question by supposing that we have a sphere of liquid, of density ρ , surrounded by an infinite mass of other liquid of density ρ'

Taking the origin at the centre, let the shape of the common surface at any instant be given by

$$r = a + \zeta = a + S_n \cdot \sin(\sigma t + \epsilon), \quad \dots \quad (1)$$

where a is the mean radius, and S_n is a surface-harmonic of order n . The corresponding values of the velocity-potential will be, at internal points,

$$\phi = -\frac{\sigma a}{n} \frac{r^n}{a^n} S_n \cos(\sigma t + \epsilon), \quad \dots \dots \dots (2)$$

and, at external points,

$$\phi' = \frac{\sigma a}{n+1} \frac{a^{n+1}}{r^{n+1}} S_n \cdot \cos(\sigma t + \epsilon), \quad \dots \dots \dots (3)$$

since these make

$$\frac{\partial \zeta}{\partial t} = -\frac{\partial \phi}{\partial r} = -\frac{\partial \phi'}{\partial r},$$

* The argument here is that if we have a series of possible types of disturbance, with time-factors $e^{a_1 t}$, $e^{a_2 t}$, $e^{a_3 t}$, ..., where $a_1 > a_2 > a_3 > \dots$, and if these be excited simultaneously, the amplitude of the first will increase relatively to those of the other components in the ratios $e^{(a_1 - a_2)t}$, $e^{(a_1 - a_3)t}$, ... The component with the greatest a will therefore ultimately predominate.

The instability of a cylindrical jet surrounded by other fluid has been discussed by Lord Rayleigh, "On the Instability of Cylindrical Fluid Surfaces," *Phil Mag* (5), t xxxiv p 177 (1892) [*Sc Papers*, t iii. p 594]. For a jet of air in water the wave-length of maximum instability is found to be $6.48 \times 2a$.

† Lord Rayleigh, *l c ante* p 449, Webb, *Mess of Math.*, t ix. p. 177 (1880)

for $r = a$ The variable parts of the internal and external pressures at the surface are then given by

$$p = \dots + \frac{\rho \sigma^2 a}{n} S_n \cdot \sin(\sigma t + \epsilon), \quad p' = \dots - \frac{\rho' \sigma^2 a}{n+1} S_n \cdot \sin(\sigma t + \epsilon) \quad . \quad (4)$$

To find the sum of the curvatures we make use of the theorem of Solid Geometry, that if λ, μ, ν be the direction-cosines of the normal at (x, y, z) to that surface of the family

$$F(x, y, z) = \text{const.}$$

which passes through the point, viz

$$\lambda, \mu, \nu = \frac{F_x, F_y, F_z}{\sqrt{(F_x^2 + F_y^2 + F_z^2)}},$$

$$\text{then} \quad \frac{1}{R_1} + \frac{1}{R_2} = \frac{\partial \lambda}{\partial x} + \frac{\partial \mu}{\partial y} + \frac{\partial \nu}{\partial z} \quad . \quad . \quad . \quad (5)$$

Since the square of ζ is to be neglected, the equation (1) of the harmonic spheroid may also be written

$$r = a + \zeta_n, \quad . \quad . \quad . \quad . \quad . \quad . \quad (6)$$

$$\text{where} \quad \zeta_n = \frac{r^n}{a^n} S_n \cdot \sin(\sigma t + \epsilon), \quad . \quad . \quad . \quad . \quad . \quad (7)$$

i.e. ζ_n is a *solid* harmonic of degree n We thus find

$$\left. \begin{aligned} \lambda &= \frac{x}{r} - \frac{\partial \zeta_n}{\partial x} + n \frac{x}{r^2} \zeta_n, \\ \mu &= \frac{y}{r} - \frac{\partial \zeta_n}{\partial y} + n \frac{y}{r^2} \zeta_n, \\ \nu &= \frac{z}{r} - \frac{\partial \zeta_n}{\partial z} + n \frac{z}{r^2} \zeta_n, \end{aligned} \right\} \quad . \quad . \quad . \quad . \quad . \quad (8)$$

whence

$$\frac{1}{R_1} + \frac{1}{R_2} = \frac{2}{r} + \frac{n(n+1)}{r^2} \zeta_n = \frac{2}{a} + \frac{(n-1)(n+2)}{a^2} S_n \cdot \sin(\sigma t + \epsilon) \quad . \quad (9)$$

Substituting from (4) and (9) in the general surface-condition of Art 262, we find

$$\sigma^2 = n(n+1)(n-1)(n+2) \frac{T_1}{\{(n+1)\rho + n\rho'\} a^3} \quad . \quad . \quad . \quad (10)$$

If we put $\rho' = 0$, this gives

$$\sigma^2 = n(n-1)(n+2) \frac{T_1}{\rho a^3} \quad . \quad . \quad . \quad . \quad (11)$$

The most important mode of vibration is that for which $n = 2$, we then have

$$\sigma^2 = \frac{8T_1}{\rho a^3}$$

Hence for a drop of water, putting $T_1 = 74$, $\rho = 1$, we find, for the frequency,

$$\frac{\sigma}{2\pi} = 3.87 a^{-3} \text{ vibrations per second,}$$

if a be the radius in centimetres. The radius of the sphere which would vibrate seconds is $a = 2.47$ cm or a little less than an inch.

The case of a spherical bubble of air, surrounded by liquid, is obtained by putting $\rho = 0$ in (10), viz. we have

$$\sigma^2 = (n+1)(n-1)(n+2) \frac{T_1}{\rho' a^3}. \quad \dots \dots (12)$$

For the same density of the liquid, the frequency of any given mode is greater than in the case represented by (11), on account of the diminished inertia of Art. 91 (7), (8).

CHAPTER X.

WAVES OF EXPANSION

272 A TREATISE on Hydrodynamics would hardly be complete without some reference to this subject, if merely for the reason that all actual fluids are more or less compressible, and that it is only when we recognize this compressibility that we escape such apparently paradoxical results as that of Art 20, where a change of pressure was found to be propagated *instantaneously* through a liquid mass

We shall accordingly investigate in this Chapter the general laws of propagation of small disturbances, passing over, however, for the most part, such details as belong more properly to the Theory of Sound.

In most cases which we shall consider, the changes of pressure are small, and may be taken to be proportional to the changes in density, thus

$$\Delta p = \kappa \frac{\Delta \rho}{\rho},$$

where $\kappa (= \rho dp/d\rho)$ is a certain coefficient, called the 'elasticity of volume' For a given liquid the value of κ varies with the temperature, and (very slightly) with the pressure For water at 15° C., $\kappa = 2.22 \times 10^{10}$ dynes per square centimetre, for mercury at the same temperature $\kappa = 5.42 \times 10^{11}$. The case of gases will be considered presently

Plane Waves

273. We take first the case of plane waves in a uniform medium.

The motion being in one dimension (x), the dynamical equation is, in the absence of extraneous forces,

$$\frac{\partial u}{\partial t} + u \frac{\partial u}{\partial x} = - \frac{1}{\rho} \frac{\partial p}{\partial x} = - \frac{1}{\rho} \frac{dp}{d\rho} \frac{\partial \rho}{\partial x}, \dots \dots \dots (1)$$

whilst the equation of continuity, Art. 8 (4), reduces to

$$\frac{\partial \rho}{\partial t} + \frac{\partial}{\partial x} (\rho u) = 0. \dots \dots \dots (2)$$

If we put $\rho = \rho_0(1 + s)$, (3)

where ρ_0 is the density in the undisturbed state, s may be called the 'condensation' in the plane x . Substituting in (1) and (2), we find, on the supposition that the motion is infinitely small,

$$\frac{\partial u}{\partial t} = -\frac{\kappa}{\rho_0} \frac{\partial s}{\partial x}, \quad \dots \dots \dots (4)$$

and
$$\frac{\partial s}{\partial t} = -\frac{\partial u}{\partial x}, \quad \dots \dots \dots (5)$$

if
$$\kappa = \left[\rho \frac{dp}{d\rho} \right]_{\rho=\rho_0}, \quad \dots \dots \dots (6)$$

as above Eliminating s we have

$$\frac{\partial^2 u}{\partial t^2} = c^2 \frac{\partial^2 u}{\partial x^2}, \quad \dots \dots \dots (7)$$

where
$$c^2 = \frac{\kappa}{\rho_0} = \left[\frac{dp}{d\rho} \right]_{\rho=\rho_0} \dots \dots \dots (8)$$

The equation (7) is of the form treated in Art 169, and the complete solution is

$$u = f(ct - x) + F(ct + x), \quad \dots \dots \dots (9)$$

representing two systems of waves travelling with the constant velocity c , one in the positive and the other in the negative direction of x . It appears from (5) that the corresponding value of s is given by

$$cs = f(ct - x) - F(ct + x) \dots \dots \dots (10)$$

For a single wave we have $u = \pm cs$, (11)

since one or other of the functions f , F is zero. The upper or the lower sign is to be taken according as the wave is travelling in the positive or the negative direction. It is easily shewn in this case that the approximations involved in (4) and (5) are valid provided u is everywhere small compared with c .

There is an exact correspondence between the above approximate theory and that of 'long' gravity-waves on water. If we write η/h for s , and gh for κ/ρ_0 , the equations (4) and (5), above, become identical with Art 168 (3), (5)

274. With the value of κ given in Art 272, we find for water at 15° C.

$$c = 1490 \text{ metres per second}$$

The number obtained directly by Colladon and Sturm* in their experiments on the lake of Geneva was 1437, at a temperature of 8° C

* *Ann de Chim et de Phys.*, t xxxvi (1827) It may be mentioned that the velocity of sound in water contained in a tube is liable to be appreciably diminished by the yielding of the wall. See Helmholtz, *Fortschritte d Physik*, t. iv. p 119 (1848) [*Ges Abh*, t 1 p 242], Korteweg, *Wied Ann.*, t. v. p 526 (1878), Lamb, *Manch Mem*, t xli No 1 (1898).

In the case of a gas, if we assume that the temperature is constant the value of κ is determined by Boyle's Law

$$\frac{p}{p_0} = \frac{\rho}{\rho_0}, \quad \dots \quad (1)$$

$$\text{viz} \quad \kappa = p_0, \quad \dots \quad (2)$$

$$\text{so that} \quad c = \sqrt{\left(\frac{p_0}{\rho_0}\right)} \quad \dots \quad (3)$$

This is known as the 'Newtonian' velocity of sound*. If we denote by H the height of a 'homogeneous atmosphere' of the gas, we have $p_0 = g\rho_0 H$, and therefore

$$c = (gH)^{\frac{1}{2}}, \quad \dots \quad (4)$$

which may be compared with the formula (13) of Art 169 for the velocity of 'long' gravity-waves in liquids. For air at 0°C we have as corresponding values

$$p_0 = 76 \times 13.60 \times 981, \quad \rho_0 = 0.0129,$$

in absolute C.G.S. units, whence

$$c = 280 \text{ metres per second}$$

This is considerably below the value found by direct observation.

The reconciliation of theory and fact is due to Laplace†. When a gas is suddenly compressed, its temperature rises, so that the pressure is increased more than in proportion to the diminution of volume, and a similar statement applies of course to the case of a sudden expansion. The formula (1) is appropriate only to the case where the expansions and rarefactions are so gradual that there is ample time for equalization of temperature by thermal conduction and radiation. In most cases of interest, the alternations of density are exceedingly rapid, the flow of heat from one element to another has hardly set in before its direction is reversed, so that practically each element behaves as if it neither gained nor lost heat.

On this view we have, in place of (1), the 'adiabatic' law

$$\frac{p}{p_0} = \left(\frac{\rho}{\rho_0}\right)^\gamma, \quad \dots \quad (5)$$

where, as explained in books on Thermodynamics, γ is the ratio of the two specific heats of the gas. This makes

$$\kappa = \gamma p_0, \quad \dots \quad (6)$$

* *Principia*, Lib. II, Sect. VIII, Prop. 48

† The usual reference is to a paper "Sur la vitesse du son dans l'air et dans l'eau," *Ann. de Chim. et de Phys.*, t. III, p. 238 (1816) [*Mécanique Céleste*, Livre 12^{me}, c. III (1823)]. But Poisson in a memoir of date 1807 (see p. 463) refers to this explanation as having been already given by Laplace.

and therefore
$$c = \sqrt{\left(\frac{\gamma p_0}{\rho_0}\right)} \quad \dots \quad (7)$$

If we put $\gamma = 1.410^*$, the former result is to be multiplied by 1.187, whence

$$c = 332 \text{ metres per second,}$$

which agrees very closely with the best direct determinations

The confidence felt by physicists in the soundness of Laplace's view is so complete that it is now usual to apply the formula (7) in the inverse manner, and to infer the values of γ for various gases and vapours from observation of wave-velocities in them

In strictness, a similar distinction should be made between the 'adiabatic' and 'isothermal' coefficients of elasticity of a liquid or a solid, but practically the difference is unimportant. Thus in the case of water the ratio of the two volume-elasticities is calculated to be 1.0012†

The effects of thermal radiation and conduction on air-waves have been studied theoretically by Stokes‡ and Lord Rayleigh§. When the oscillations are too rapid for equalization of temperature, but not so rapid as to exclude communication of heat between adjacent elements, the waves diminish in amplitude as they advance, owing to the dissipation of energy which takes place in the thermal processes. The effect of conduction will be noticed, along with that of viscosity, in the next Chapter.

According to the law of Charles and Dalton

$$\frac{p_0}{\rho_0} \propto 1 + 0.00366\theta,$$

where θ is the temperature centigrade. Hence the velocity of sound will vary as the square root of the absolute temperature. For several of the more permanent gases, which have sensibly the same value of γ , the formula (7) shews that the velocity varies inversely as the square root of the density, provided the relative densities be determined under the same conditions of pressure and temperature.

275. The theory of plane waves can also be treated very simply by the Lagrangian method (Arts 13, 14).

If ξ denote the displacement at time t of the particles whose undisturbed abscissa is x , the stratum of matter originally included between the planes x and $x + \delta x$ is at the time $t + \delta t$ bounded by the planes

$$x + \xi \quad \text{and} \quad x + \xi + \left(1 + \frac{\partial \xi}{\partial x}\right) \delta x,$$

* The value found by direct experiment

† Everett, *Units and Physical Constants*

‡ "An Examination of the possible effect of the Radiation of Heat on the Propagation of Sound," *Phil. Mag.* (4), t. i. p. 305 (1851) [*Math. and Phys. Papers*, t. iii. p. 142]

§ *Theory of Sound*, Art. 247. In a recent paper "On the Cooling of Air by Radiation and Conduction, and on the Propagation of Sound," *Phil. Mag.* (5), t. xlvii. p. 308 (1899) [*Sc. Papers*, t. iv. p. 376], Lord Rayleigh concludes on experimental grounds that conduction is much more effective in this respect than radiation.

so that the equation of continuity is

$$\rho \left(1 + \frac{\partial \xi}{\partial x} \right) = \rho_0, \quad \dots \dots \dots (1)$$

where ρ_0 is the density in the undisturbed state. Hence if s denote the 'condensation' ($\rho = \rho_0(1 + s)$), we have

$$s = - \frac{\partial \xi}{\partial x} \quad \dots \dots \dots (2)$$

The dynamical equation, obtained by considering the forces acting on unit area of the above stratum, is

$$\rho_0 \frac{\partial^2 \xi}{\partial t^2} = - \frac{\partial p}{\partial x} \quad \dots \dots \dots (3)$$

These equations are exact, but in the case of *small* motions we may write

$$p = p_0 + \kappa s, \quad \dots \dots \dots (4)$$

and

$$s = - \frac{\partial \xi}{\partial x} \quad \dots \dots \dots (5)$$

Substituting in (3) we find

$$\frac{\partial^2 \xi}{\partial t^2} = c^2 \frac{\partial^2 \xi}{\partial x^2}, \quad \dots \dots \dots (6)$$

where $c^2 = \kappa/\rho_0$. The solution of (6) is the same as in Arts. 169, 273.

276. The *kinetic energy* of a system of plane waves is given by

$$T = \frac{1}{2} \rho_0 \iiint u^2 dx dy dz, \quad \dots \dots \dots (1)$$

where u is the velocity at the point (x, y, z) at time t .

The calculation of the *intrinsic energy* requires a little care. If v be the volume of unit mass, the work which this gives out in expanding from its actual volume to the normal volume v_0 is

$$\int_v^{v_0} p dv, \quad \dots \dots \dots (2)$$

Putting $v = v_0/(1 + s)$, $p = p_0 + \kappa s$, we find, for the intrinsic* energy E of unit mass

$$E = \frac{1}{2} p_0 s + \left(\frac{1}{2} \kappa - p_0 \right) s^2, \quad \dots \dots \dots (3)$$

if we neglect terms of higher order. Hence, for the intrinsic energy of the fluid which in the disturbed condition occupies any given region, we have the expression

$$W = \iiint E \rho dx dy dz = \rho_0 \iiint E (1 + s) dx dy dz = \rho_0 \iiint \left(p_0 s + \frac{1}{2} \kappa s^2 \right) dx dy dz, \quad \dots \dots \dots (4)$$

* According to strict thermodynamic usage this name is not appropriate unless the expansions and contractions are *adiabatic*. In the case of the *isothermal* relation the expression (4) gives the increment of what is known as the 'free energy.'

this becomes

$$\frac{\partial^2 \xi}{\partial t^2} = \frac{p_0}{\rho_0} \cdot \frac{\frac{\partial^2 \xi}{\partial x^2}}{\left(1 + \frac{\partial \xi}{\partial x}\right)^2} \quad \dots \quad (3)$$

In the same way, the 'adiabatic' relation

$$\frac{p}{p_0} = \left(\frac{\rho}{\rho_0}\right)^\gamma, \quad \dots \quad (4)$$

leads to

$$\frac{\partial^2 \xi}{\partial t^2} = \frac{\gamma p_0}{\rho_0} \frac{\frac{\partial^2 \xi}{\partial x^2}}{\left(1 + \frac{\partial \xi}{\partial x}\right)^{\gamma+1}} \quad \dots \quad (5)$$

These exact equations (3) and (5) may be compared with the similar equation for 'long' waves in a uniform canal, Art 172 (3)

It appears from (1) that the equation (6) of Art 275 could be regarded as exact if the relation between p and ρ were such that

$$\rho^2 \frac{dp}{d\rho} = \rho_0^2 c^2 \quad \dots \quad (6)$$

Hence plane waves of finite amplitude can be propagated without change of type if, and only if,

$$p - p_0 = \rho_0 c^2 \left(1 - \frac{\rho_0}{\rho}\right) \quad \dots \quad (7)$$

A relation of this form does not hold for any known substance, whether at constant temperature or when free from gain or loss of heat by conduction and radiation*. Hence sound-waves of finite amplitude must inevitably undergo a change of type as they proceed

278. The laws of propagation of waves of finite amplitude have been investigated, independently and by different methods, by Earnshaw and Riemann. It is proposed to give here a brief account of these investigations, referring for further details to the original papers, and to the very full discussion of the matter by Lord Rayleigh†

Riemann's method‡ has already been applied in this treatise to the discussion of the corresponding question in the theory of 'long' gravity-waves on liquids (Art 185) He starts from the Eulerian equations of Art 273, which may be written

$$\frac{\partial u}{\partial t} + u \frac{\partial u}{\partial x} = -\frac{1}{\rho} \frac{dp}{d\rho} \frac{\partial \rho}{\partial x}, \quad \dots \quad (1)$$

$$\frac{\partial \rho}{\partial t} + u \frac{\partial \rho}{\partial x} = -\rho \frac{\partial u}{\partial x} \quad \dots \quad (2)$$

* The relation would make p negative when ρ falls below a certain value

† *Theory of Sound*, c xi

‡ "Ueber die Fortpflanzung ebener Luftwellen von endlicher Schwingungswerte," *Gott. Abh.*, t viii p 43 (1858-9) [*Werke*, 2^{te} Aufl., Leipzig, 1892, p 157] See also H. Weber, *Part. Diff.-Gl d math Phys*, t ii. p 469

If we put $P = f(\rho) + u$, $Q = f(\rho) - u$, (3)

where $f(\rho)$ is as yet undetermined, we find, multiplying (2) by $f'(\rho)$, and adding to (1),

$$\frac{\partial P}{\partial t} + u \frac{\partial P}{\partial x} = -\frac{1}{\rho} \frac{dp}{d\rho} \frac{\partial \rho}{\partial x} - \rho f'(\rho) \frac{\partial u}{\partial x}$$

If we now determine $f(\rho)$ so that

$$\{f'(\rho)\}^2 = \frac{1}{\rho^2} \frac{dp}{d\rho}, \quad (4)$$

this may be written

$$\frac{\partial P}{\partial t} + u \frac{\partial P}{\partial x} = -\rho f'(\rho) \frac{\partial P}{\partial x} \quad (5)$$

In the same way we obtain

$$\frac{\partial Q}{\partial t} + u \frac{\partial Q}{\partial x} = \rho f'(\rho) \frac{\partial Q}{\partial x} \quad (6)$$

The condition (4) is satisfied by

$$f(\rho) = \int_{\rho_0}^{\rho} \left(\frac{dp}{d\rho} \right)^{\frac{1}{2}} \frac{d\rho}{\rho} \quad (7)$$

Substituting in (5) and (6), we find

$$\left. \begin{aligned} dP &= \left[dx - \left\{ \left(\frac{dp}{d\rho} \right)^{\frac{1}{2}} + u \right\} dt \right] \frac{\partial P}{\partial x}, \\ dQ &= \left[dx + \left\{ \left(\frac{dp}{d\rho} \right)^{\frac{1}{2}} - u \right\} dt \right] \frac{\partial Q}{\partial x} \end{aligned} \right\} \quad (8)$$

Hence $dP = 0$, or P is constant, for a geometrical point moving with the velocity

$$\frac{dx}{dt} = \left(\frac{dp}{d\rho} \right)^{\frac{1}{2}} + u, \quad (9)$$

whilst Q is constant for a point whose velocity is

$$\frac{dx}{dt} = -\left(\frac{dp}{d\rho} \right)^{\frac{1}{2}} + u \quad (10)$$

Hence, any given value of P moves forward, and any value of Q moves backward, with the velocity given by (9) or (10), as the case may be

These results enable us to understand, in a general way, the nature of the motion in any given case. Thus if the initial disturbance be confined to the space between the two planes $x = a$, $x = b$, we may suppose that P and Q both vanish for $x > a$ and for $x < b$. The region within which P is variable will advance, and that within which Q is variable will recede, until after a time these regions separate and leave between them a space for which $P = 0$, $Q = 0$, and in which the fluid is therefore at rest. The original

disturbance has thus been split up into two progressive waves travelling in opposite directions. In the advancing wave we have $Q=0$, and therefore

$$u=f(\rho), \quad \dots \dots \dots (11)$$

so that both the density and the particle-velocity are propagated forwards at the rate given by (9). Whether we adopt the isothermal or the adiabatic law of expansion, this velocity of propagation will be found to be greater, the greater the value of ρ . The law of progress of the wave may be illustrated by drawing a curve with x as abscissa and ρ as ordinate, and making each point of this curve move forward with the appropriate velocity, as given by (9) and (11). Since those parts move faster which have the greater ordinates, the curve will eventually become at some point perpendicular to x . The quantities $\partial u/\partial x$, $\partial \rho/\partial x$ are then infinite; and the preceding method fails to yield any information as to the subsequent course of the motion. Cf Art. 185.

279 Similar results can be deduced from Earnshaw's investigation* which is, however, somewhat less general in that it applies only to a progressive wave supposed already established.

For simplicity we will suppose p and ρ to be connected by Boyle's Law

$$p=c^2\rho. \quad \dots \dots \dots (1)$$

If we write $y=x+\xi$, so that y denotes the absolute coordinate at time t of the particle whose undisturbed abscissa is x , the equation (3) of Art. 277 becomes

$$\frac{\partial^2 y}{\partial t^2}=c^2 \frac{\partial^2 y}{\partial x^2} / \left(\frac{\partial y}{\partial x} \right)^2 \quad \dots \dots \dots (2)$$

$$\text{This is satisfied by} \quad \frac{\partial y}{\partial t}=f\left(\frac{\partial y}{\partial x}\right), \quad \dots \dots \dots (3)$$

$$\text{provided} \quad \left\{ f' \left(\frac{\partial y}{\partial x} \right) \right\}^2 = c^2 / \left(\frac{\partial y}{\partial x} \right)^2 \quad \dots \dots \dots (4)$$

$$\text{Hence a first integral of (2) is} \quad \frac{\partial y}{\partial t}=C \pm c \log \frac{\partial y}{\partial x} \quad \dots \dots \dots (5)$$

To obtain the 'general integral' of (5) we must eliminate a between the equations

$$\left. \begin{aligned} y &= ax + (C \pm c \log a) t + \phi(a), \\ 0 &= ax \pm ct + a\phi'(a), \end{aligned} \right\} \quad \dots \dots \dots (6) +$$

$$\text{where } \phi \text{ is arbitrary. Now} \quad \frac{\partial y}{\partial x} = \frac{\rho_0}{\rho},$$

so that, if u be the velocity of the particle x , we have

$$u = \frac{\partial y}{\partial t} = C \pm c \log \frac{\rho_0}{\rho} \quad \dots \dots \dots (7)$$

On the outskirts of the wave we shall have $u=0$, $\rho=\rho_0$. It follows that $C=0$, and therefore

$$\rho = \rho_0 e^{\mp u/c} \quad \dots \dots \dots (8)$$

* "On the Mathematical Theory of Sound," *Phil. Trans.*, vol. p. 133 (1858)

+ See Forsyth, *Differential Equations*, c. ix.

Hence in a progressive wave ρ and u must be connected by this relation. If this be satisfied initially, the function ϕ which occurs in (6) is to be determined from the conditions at time $t=0$ by the equation

$$\phi'(\rho_0/\rho) = -x \quad . \quad (9)$$

To obtain results independent of the particular form of the wave, consider two particles (which we will distinguish by suffixes) so related that the value of ρ which obtains for the first particle at time t_1 is found at the second particle at time t_2

The value of $a (= \rho_0/\rho)$ is the same for both, and therefore by (6), with $C=0$,

$$\left. \begin{aligned} y_2 - y_1 &= a(x_2 - x_1) \pm c(t_2 - t_1) \log a, \\ 0 &= a(x_2 - x_1) \pm c(t_2 - t_1) \end{aligned} \right\} \quad . \quad (10)$$

$$\text{The latter equation may be written} \quad \frac{\Delta y}{\Delta t} = \mp c \frac{\rho}{\rho_0}, \quad (11)$$

showing that the value of ρ is propagated *from particle to particle* at the rate ρ/ρ_0 . The rate of propagation *in space* is given by

$$\frac{\Delta y}{\Delta t} = \mp c \pm c \log a = \mp c + u \quad . \quad (12)$$

This is in agreement with Riemann's results, since on the present 'isothermal' hypothesis $(dp/d\rho)^{\frac{1}{2}} = c$

For a wave travelling in the positive direction we must take the lower signs. If it be one of condensation ($\rho > \rho_0$), u is positive, by (8). It follows that the denser parts of the wave are continually gaining on the rarer, and at length overtake them, the subsequent motion is then beyond the scope of our analysis.

Eliminating x between the equations (6), and writing for $c \log a$ its value $-u$, we find for a wave travelling in the positive direction,

$$y = (c+u)t + F(a), \quad . \quad . \quad . \quad . \quad . \quad (13)$$

where F is an arbitrary function. In virtue of (8) this is equivalent to

$$u = f\{y - (c+u)t\} \quad . \quad . \quad . \quad . \quad . \quad (14)$$

This formula is due to Poisson*. Its interpretation, leading to the same results as above, for the mode of alteration of the wave as it proceeds, forms the subject of a paper by Stokes†

280 The conditions for a wave of permanent type have been investigated in a very simple manner by Rankine‡.

Let A, B be two points of an ideal tube of unit section drawn in the direction of propagation, which is (say) that of x -positive, and let the values of the pressure, the density, and the particle-velocity at A and B be denoted by p_1, ρ_1, u_1 and p_2, ρ_2, u_2 , respectively

* "Mémoire sur la Théorie du Son," *Journ. de l'École Polytechn.*, t. vii. p. 367 (1807)

† "On a Difficulty in the Theory of Sound," *Phil. Mag.* (3), t. xxiii. p. 349 (1848) [*Math. and Phys. Papers*, t. ii. p. 51]

‡ "On the Thermodynamic Theory of Waves of Finite Longitudinal Disturbance," *Phil. Trans.*, t. clx. p. 277 (1870) [*Misc. Sc. Papers*, p. 530]

If, as in Art. 174, we impress on everything a velocity c equal and opposite to that of the wave, we reduce the problem to one of steady motion. Since the same amount of matter now crosses in unit time each section of the tube, we have

$$\rho_1(c - u_1) = \rho_2(c - u_2) = m, \quad \dots \dots \dots (1)$$

say, where m denotes the mass swept past in unit time by a plane moving with the wave, in the original form of the problem. This quantity m is called by Rankine the 'mass-velocity' of the wave.

Again, the total force acting on the mass included between A and B is $p_2 - p_1$, in the direction BA , and the rate at which this mass is gaining momentum in the same direction is

$$m(c - u_1) - m(c - u_2).$$

Hence

$$p_2 - p_1 = m(u_2 - u_1) \quad \dots \dots \dots (2)$$

Combined with (1) this gives

$$p_1 + \frac{m^2}{\rho_1} = p_2 + \frac{m^2}{\rho_2} \quad \dots \dots \dots (3)$$

Hence a wave of finite amplitude could not be propagated unchanged except in a medium such that

$$p + \frac{m^2}{\rho} = \text{const.} \quad \dots \dots \dots (4)$$

This conclusion has already been arrived at, in a different manner, in Art. 277. It may be noticed that, if we write $v = 1/\rho$, the relation (4) is represented on 'Watt's Diagram' by a *straight line*

If the variation of density be slight, the relation (4) may, however, be regarded as holding approximately for actual fluids, provided m have the proper value. Putting

$$\rho = \rho_0(1 + s), \quad p = p_0 + \kappa s, \quad m = \rho_0 c, \quad \dots \dots \dots (5)$$

we find

$$c^2 = \frac{\kappa}{\rho_0}, \quad \dots \dots \dots (6)$$

as in Art. 273

The fact that in actual fluids a progressive wave of finite amplitude continually alters its type, so that the variations of density towards the front become more and more abrupt, has led various writers to speculate on the possibility of a wave of discontinuity, analogous to a 'bore' in water-waves.

It has been shewn, first by Stokes*, and afterwards by several other writers, that the conditions of constancy of mass and of constancy of momentum can both be satisfied for such a wave. The simplest case is when there is no variation in the values of ρ and u except at the plane of

* l c. ante p. 463

discontinuity If, in the preceding argument, the sections A, B be taken, one behind, and the other in front of this plane, we have, by (3),

$$m = \left(\frac{p_1 - p_2}{\rho_1 - \rho_2} \rho_1 \rho_2 \right)^{\frac{1}{2}}, \dots \dots \dots (7)$$

$$c - u_2 = \frac{m}{\rho_2} = \left(\frac{p_1 - p_2}{\rho_1 - \rho_2} \frac{\rho_1}{\rho_2} \right)^{\frac{1}{2}}, \dots \dots \dots (8)$$

and

$$u_1 - u_2 = \frac{m}{\rho_2} - \frac{m}{\rho_1} = \pm \left(\frac{(p_1 - p_2)(\rho_1 - \rho_2)}{\rho_1 \rho_2} \right)^{\frac{1}{2}} \dots \dots \dots (9)$$

The upper or the lower sign is to be taken according as ρ_1 is greater or less than ρ_2 , i.e. according as the wave is one of condensation or of rarefaction. The results involve *differences* of velocity, as we should expect, since any uniform velocity of the whole medium may be superposed.

We may assume, for instance, that the quantities p_2, ρ_2, u_2 , which define the condition of the medium ahead of the wave, are given arbitrarily, also that the density ρ_1 of the air in the advancing wave is prescribed. Further, some definite relation between p_1, ρ_1 and p_2, ρ_2 , based on physical considerations, is presupposed. The remaining quantities m, c, u_1 are then determined by (7), (8), (9).

These results have, however, lost some of their interest since it has been pointed out by Lord Rayleigh* that in actual fluids the equation of energy cannot be satisfied consistently with (1) and (2). Calculating the excess of the work done per unit time on the fluid entering the space AB at B over that done by the fluid leaving at A , and subtracting the gain of kinetic energy, we obtain

$$p_2(c - u_2) - p_1(c - u_1) - \frac{1}{2}m\{(c - u_1)^2 - (c - u_2)^2\},$$

or

$$p_1 u_1 - p_2 u_2 - \frac{1}{2}m(u_1^2 - u_2^2),$$

or

$$\frac{1}{2}(p_1 + p_2)(u_1 - u_2), \dots \dots \dots (10)$$

these forms being equivalent in virtue of the dynamical equation (2). The corresponding result *per unit mass* is obtained by dividing by m . If we substitute for $u_1 - u_2$ from (1) or (9), we obtain

$$\frac{1}{2}(p_1 + p_2)(v_2 - v_1), \dots \dots \dots (11)$$

where v is written for $1/\rho$

If the two states of the medium be represented by two points A, B on Watt's diagram, the expression (11) is equal to the area included between the straight line AB , the axis of v , and the ordinates of A, B . If the transition from B to A be effected without gain or loss of heat, the points in question will lie on the same 'adiabatic curve,' and the gain of intrinsic

* *Theory of Sound*, Art 253.

energy will be represented by the area included between this curve, the axis of v , and the extreme ordinates. For an actual gas, the adiabatic is concave upwards, and the latter area is accordingly less (in absolute value) than the former. If we have regard to the signs to be attributed to the areas, we find that for a wave of condensation ($v_1 < v_2$) the work done on the medium is more than is accounted for by the increase of the kinetic and intrinsic energies, whilst in a wave of rarefaction ($v_1 > v_2$) the work given out is more than the equivalent of the apparent loss of energy.

It appears that the equation of energy cannot be satisfied for discontinuous waves, except in the case of a hypothetical medium whose adiabatic lines are straight. This is identical with the condition already obtained for permanency of type in continuous waves.

In the above investigation no account has been taken of dissipative forces, such as viscosity and thermal conduction and radiation. Practically, a wave of discontinuity would imply a finite difference of temperature between the portions of the fluid on the two sides of the plane of discontinuity, so that, to say nothing of viscosity, there would necessarily be a dissipation of energy due to thermal action at the junction. Whether, when this is allowed for, the relation between the two states can be reconciled with the equation of energy is a physical question into which we do not enter*. It would appear that the possibility of a discontinuous wave of rarefaction is in any case excluded, since (as may easily be shewn graphically) this would involve a loss of 'entropy' in an irreversible process.

Spherical Waves.

281. Let us next suppose that the disturbance is symmetrical with respect to a fixed point, which we take as origin. The motion is necessarily

* It is discussed to some extent by Rankine, who points out that the *integral* amount of heat absorbed by any portion of the medium, in its passage from one state to the other, must be zero.

In some investigations by Hugoniot, which are expounded by Hadamard in his *Leçons sur la propagation des ondes et les équations de l'hydrodynamique*, Paris, 1903, the argument given in the text is inverted. The possibility of a wave of discontinuity being *assumed*, it is pointed out that the equation of energy will be satisfied if we equate the expression (10) to the increment of the intrinsic energy (for which see Art 11 (8)). On this ground the formula

$$\frac{1}{2} (p_1 + p_2) (v_2 - v_1) = \frac{1}{\gamma - 1} (p_1 v_1 - p_2 v_2)$$

is propounded, as governing the transition from one state to the other. "Telle est la relation qu'Hugoniot a substituée à $[pv^\gamma = \text{const}]$ pour exprimer que la condensation ou dilatation brusque se fait sans absorption ni dégagement de chaleur. On lui donne actuellement le nom de *loi adiabatique dynamique*, la relation $[pv^\gamma = \text{const}]$, qui convient aux changements lents, étant désignée sous le nom de *loi adiabatique statique*" (Hadamard, p. 192). But no physical evidence is adduced in support of the proposed law.

For another discussion of the matter, reference may be made to H. Weber, *Part Diff.-Gl.*, t. II c. xxii.

irrotational, so that a velocity-potential ϕ exists, which is here a function of r , the distance from the origin, and t , only. If as before we neglect the squares of small quantities, we have by Art 20 (3)

$$\int \frac{dp}{\rho} = \frac{\partial \phi}{\partial t}.$$

In the notation of Arts 272, 273 we may write

$$\int \frac{dp}{\rho} = \int \frac{\kappa ds}{\rho_0} = c^2 s,$$

whence
$$c^2 s = \frac{\partial \phi}{\partial t} \quad \dots \dots \dots (1)$$

To form the equation of continuity we remark that, owing to the difference of flux across the inner and outer surfaces, the space included between the spheres r and $r + \delta r$ is gaining mass at the rate

$$\frac{\partial}{\partial r} \left(4\pi r^2 \rho \frac{\partial \phi}{\partial r} \right) \delta r$$

Since the same rate is also expressed by $\partial \rho / \partial t \cdot 4\pi r^2 \delta r$ we have

$$r^2 \frac{\partial \rho}{\partial t} = \frac{\partial}{\partial r} \left(\rho r^2 \frac{\partial \phi}{\partial r} \right) \quad \dots \dots \dots (2)$$

This might also have been arrived at by direct transformation of the general equation of continuity, Art 8 (4) In the case of infinitely small motions, it becomes

$$\frac{\partial s}{\partial t} = \frac{1}{r^2} \frac{\partial}{\partial r} \left(r^2 \frac{\partial \phi}{\partial r} \right), \quad \dots \dots \dots (3)$$

whence, substituting from (1),

$$\frac{\partial^2 \phi}{\partial t^2} = \frac{c^2}{r^2} \frac{\partial}{\partial r} \left(r^2 \frac{\partial \phi}{\partial r} \right). \quad \dots \dots \dots (4)$$

This may be put into the more convenient form

$$\frac{\partial^2}{\partial t^2} r \phi = c^2 \frac{\partial^2}{\partial r^2} r \phi, \quad \dots \dots \dots (5)$$

so that the solution is

$$r \phi = f(r - ct) + F(r + ct) \quad \dots \dots \dots (6)$$

Hence the motion is made up of two systems of spherical waves, travelling, one outwards, the other inwards, with velocity c . Considering for a moment the first system alone, we have

$$cs = - \frac{1}{r} f' (r - ct),$$

which shews that a condensation is propagated outwards with velocity c , but diminishes as it proceeds, its amount varying inversely as the distance from the origin. The velocity due to the same train of waves is

$$-\frac{\partial \phi}{\partial r} = -\frac{1}{r} f'(r-ct) + \frac{1}{r^2} f(r-ct)$$

As r increases the second term becomes less and less important compared with the first, so that ultimately the velocity is propagated according to the same law as the condensation.

We notice that whenever diverging or converging waves are alone present we have

$$\frac{1}{r} \frac{\partial}{\partial r} (r\phi) = \mp cs, \quad \dots \dots \dots (7)$$

this corresponds to Art 273 (11)

For some purposes the formula for a system of divergent waves is more conveniently written

$$4\pi r\phi = f\left(t - \frac{r}{c}\right). \quad \dots \dots \dots (8)$$

Since this makes

$$\lim_{r=0} \left[-4\pi r^2 \frac{\partial \phi}{\partial r} \right] = f(t), \quad \dots \dots \dots (9)$$

the system in question may be regarded as due to a source of strength $f(t)$ at the origin, cf Art 194.

It follows from (1) that

$$\int s dt = 0, \quad \dots \dots \dots (10)$$

provided the initial and final values of ϕ both vanish. This will be the case whenever the source $f(t)$ is in action only for a finite time. The fact that a diverging spherical wave must necessarily contain both condensed and rarefied portions was first remarked by Stokes*. Cf. Art 195

As in the case of plane progressive waves (Art. 276), the energy of a system of divergent spherical waves is half kinetic and half potential. This follows from the general argument of Art 173, and may be verified independently as follows. We have, identically,

$$r^2 \left(\frac{\partial \phi}{\partial r} \right)^2 = \left\{ \frac{\partial (r\phi)}{\partial r} \right\}^2 - \frac{\partial}{\partial r} (r\phi^2)$$

If we write

$$q = -\frac{\partial \phi}{\partial r}, \quad c^2 s = \frac{\partial \phi}{\partial t}, \quad \dots \dots \dots (11)$$

* "On Some Points in the Received Theory of Sound," *Phil Mag* (3), t xxxiv p 52 (1849) [*Math and Phys Papers*, t ii p 82] See also Lord Rayleigh, *Theory of Sound*, Art 279

this gives, by (7), in the case of a divergent wave-system,

$$r^2 Q^2 = c^2 r^2 s^2 - \frac{\partial}{\partial r} (r \phi^2)$$

Hence
$$\int_0^\infty \frac{1}{2} \rho Q^2 \cdot 4\pi r^2 dr = \int_0^\infty \frac{1}{2} \rho c^2 s^2 \cdot 4\pi r^2 dr, \quad \dots \quad (12)$$

if $r\phi^2$ vanishes at the inner and outer boundaries of the system*.

282 The determination of the functions f and F in (6), in terms of the initial conditions, for an unlimited space, can be effected as follows.

Let us suppose that the distributions of velocity and condensation at time $t=0$ are determined by the formulae

$$\phi = \psi(r), \quad \frac{\partial \phi}{\partial t} = \chi(r), \quad \dots \dots \dots (13)$$

where ψ, χ are arbitrary functions. Comparing with (6), we have

$$f(z) + F(z) = z\psi(z), \quad \dots \dots \dots (14)$$

$$-f'(z) + F'(z) = \frac{z}{c} \chi(z),$$

the latter of which gives on integration

$$-f(z) + F(z) = \frac{1}{c} \int_0^z z \chi(z) dz + C \quad \dots \dots \dots (15)$$

Again, the condition that there is no creation or annihilation of fluid at the origin gives

$$f(-z) + F(z) = 0 \quad \dots \dots \dots (16)$$

The formulae (14) and (15) determine the functions f and F for positive values of z , and (16) then determines f for negative values of z †.

The final result may be written

$$r\phi = \frac{1}{2}(r-ct)\psi(r-ct) + \frac{1}{2}(r+ct)\psi(r+ct) + \frac{1}{2c} \int_{r-ct}^{r+ct} z\chi(z) dz, \quad \dots (17)$$

or

$$r\phi = -\frac{1}{2}(ct-r)\psi(ct-r) + \frac{1}{2}(ct+r)\psi(ct+r) + \frac{1}{2c} \int_{ct-r}^{ct+r} z\chi(z) dz, \quad \dots (18)$$

according as r is greater or less than ct

As a very simple example we may suppose that the air is initially at rest, and that the initial disturbance consists of a uniform condensation s_0 extending through a sphere of radius a . We have then $\psi(z)=0$, whilst $\chi(z)=c^2 s_0$ or 0 according as $z \leq a$. At a distance

* *Proc Lond. Math. Soc*, t xxxv. p 160 (1902).

† Lord Rayleigh, *Theory of Sound*, Art. 279.

$r(>a)$ from the origin, the motion will not begin until $t=(r-a)/c$, and will cease when $t=(r+a)/c$. For intermediate instants we shall have

$$r\phi = \frac{1}{4}cs_0\{a^2 - (r-ct)\}^2, \quad \quad (19)$$

and thence

$$\frac{s}{s_0} = \frac{r-ct}{2r}. \quad . \quad (20)$$

The disturbance is now confined to a spherical shell of thickness $2a$, and the condensation s is positive through the outer half, and negative through the inner half, of the thickness

We shall require, shortly, an expression for the value of ϕ at the origin, for all values of t , in terms of the initial circumstances. We have, by (6) and (16),

$$\begin{aligned} [\phi]_{r=0} &= \lim_{r=0} \frac{f(r-ct) + F(r+ct)}{r} \\ &= \lim_{r=0} \frac{F(ct+r) - F(ct-r)}{r} = 2F'(ct), \end{aligned}$$

or, by (14) and the consecutive equation,

$$[\phi]_{r=0} = \frac{d}{dt} t\psi(ct) + t\chi(ct). \quad \dots \dots \dots (21)$$

General Equation of Sound-Waves

283 We proceed to the general case of propagation of expansion-waves. We neglect, as before, small quantities of the second order, so that the dynamical equation is as in Art. 281,

$$c^2s = \frac{\partial\phi}{\partial t}. \quad \dots \dots \dots (1)$$

Also, writing $\rho = \rho_0(1+s)$ in the general equation of continuity, Art. 8 (4), we have, with the same approximation,

$$\frac{\partial s}{\partial t} = \frac{\partial^2\phi}{\partial x^2} + \frac{\partial^2\phi}{\partial y^2} + \frac{\partial^2\phi}{\partial z^2}. \quad \dots \dots \dots (2)$$

The elimination of s between (1) and (2) gives

$$\frac{\partial^2\phi}{\partial t^2} = c^2 \left(\frac{\partial^2\phi}{\partial x^2} + \frac{\partial^2\phi}{\partial y^2} + \frac{\partial^2\phi}{\partial z^2} \right), \quad \dots \dots \dots (3)$$

or, in our former notation,

$$\frac{\partial^2\phi}{\partial t^2} = c^2\nabla^2\phi \quad \dots \dots \dots (4)$$

Since this equation is linear, it will be satisfied by the arithmetic mean of any number of separate solutions $\phi_1, \phi_2, \phi_3, \dots$. As in Art. 38, let us imagine an infinite number of systems of rectangular axes to be arranged uniformly about any point P as origin, and let $\phi_1, \phi_2, \phi_3, \dots$ be the velocity-potentials

of motions which are the same with respect to these systems as the original motion ϕ is with respect to the system x, y, z . In this case the arithmetic mean ($\bar{\phi}$, say), of the functions $\phi_1, \phi_2, \phi_3, \dots$ will be the velocity-potential of a motion symmetrical with respect to the point P , and will therefore come under the investigation of Art 282, provided r denote the distance of any point from P . In other words, if $\bar{\phi}$ be a function of r and t , defined by the equation

$$\bar{\phi} = \frac{1}{4\pi} \iint \phi d\omega, \quad \dots \dots \dots (5)$$

where ϕ is any solution of (4), and $\delta\omega$ is the solid angle subtended at P by an element of the surface of a sphere of radius r having this point as centre, then

$$\frac{\partial^2}{\partial t^2} \frac{r\bar{\phi}}{r^2} = c^2 \frac{\partial^2}{\partial r^2} \frac{r\bar{\phi}}{r^2} \quad \dots \dots \dots (6)^*$$

Hence
$$r\bar{\phi} = f(r - ct) + F(r + ct) \quad \dots \dots \dots (7)$$

The mean value of ϕ over a sphere having any point P of the medium as centre is therefore subject to the same laws as the velocity-potential of a symmetrical spherical disturbance. We see at once that the value of ϕ at P at the time t depends on the means of the values which ϕ and $\partial\phi/\partial t$ originally had at points of a sphere of radius ct described about P as centre, so that the disturbance is propagated in all directions with uniform velocity c . Thus if the original disturbance extend only through a finite portion Σ of space, the disturbance at any point P external to Σ will begin after a time r_1/c , will last for a time $(r_2 - r_1)/c$, and will then cease altogether; r_1, r_2 denoting the radii of two spheres described with P as centre, the one just excluding, the other just including Σ .

To express the solution of (4), already virtually obtained, in an analytical form, let the values of ϕ and $\partial\phi/\partial t$, when $t = 0$, be

$$\phi = \psi(x, y, z), \quad \frac{\partial\phi}{\partial t} = \chi(x, y, z). \quad \dots \dots \dots (8)$$

The mean values of these functions over a sphere of radius r described about (x, y, z) as centre are

$$\begin{aligned} \bar{\phi} &= \frac{1}{4\pi} \iint \psi(x + lr, y + mr, z + nr) d\omega, \\ \frac{\partial\bar{\phi}}{\partial t} &= \frac{1}{4\pi} \iint \chi(x + lr, y + mr, z + nr) d\omega, \end{aligned}$$

* This result was obtained, in a different manner, by Poisson, "Mémoire sur la théorie du son," *Journ. de l'École Polytechn.*, t vii pp 334-338 (1807). The remark that it leads at once to the complete solution of (4) is due to Liouville, *Journ. de Math.*, t i. p. 1 (1856).

where l, m, n denote the direction-cosines of any radius of this sphere, and $\delta\omega$ the corresponding elementary solid angle. If we put

$$l = \sin \theta \cos \omega, \quad m = \sin \theta \sin \omega, \quad n = \cos \theta,$$

we shall have $\delta\omega = \sin \theta \delta\theta \delta\omega$

Hence, comparing with Art. 282 (21), we see that the value of ϕ at the point (x, y, z) , at any subsequent time t , is

$$\begin{aligned} \phi = & \frac{1}{4\pi} \frac{\partial}{\partial t} t \iint \psi(x + ct \sin \theta \cos \omega, y + ct \sin \theta \sin \omega, z + ct \cos \theta) \sin \theta d\theta d\omega \\ & + \frac{t}{4\pi} \iint \chi(x + ct \sin \theta \cos \omega, y + ct \sin \theta \sin \omega, z + ct \cos \theta) \sin \theta d\theta d\omega, \dots (9) \end{aligned}$$

which is the form given by Poisson*

284 The expression for the kinetic energy of the fluid contained in any given region is

$$T = \frac{1}{2} \rho_0 \iiint \left\{ \left(\frac{\partial \phi}{\partial x} \right)^2 + \left(\frac{\partial \phi}{\partial y} \right)^2 + \left(\frac{\partial \phi}{\partial z} \right)^2 \right\} dx dy dz \quad \dots \quad (1)$$

Hence
$$\frac{dT}{dt} = \rho_0 \iiint \left(\frac{\partial \phi}{\partial x} \frac{\partial \dot{\phi}}{\partial x} + \frac{\partial \phi}{\partial y} \frac{\partial \dot{\phi}}{\partial y} + \frac{\partial \phi}{\partial z} \frac{\partial \dot{\phi}}{\partial z} \right) dx dy dz,$$

where $\dot{\phi}$ stands for $\partial \phi / \partial t$. By Green's Theorem (Art. 43), this may be put in the form

$$\begin{aligned} \frac{dT}{dt} &= -\rho_0 \iint \phi \frac{\partial \phi}{\partial n} dS - \rho_0 \iiint \phi \nabla^2 \phi dx dy dz \\ &= -\rho_0 \iint \dot{\phi} \frac{\partial \phi}{\partial n} dS - \frac{\rho_0}{c^2} \iiint \dot{\phi} \dot{\phi} dx dy dz \end{aligned}$$

Hence if
$$W = \frac{1}{2} \kappa \iiint s^2 dx dy dz = \frac{1}{2} \frac{\rho_0}{c^2} \iiint \dot{\phi}^2 dx dy dz, \quad \dots \quad (2)$$

we have
$$\frac{d}{dt} (T + W) = -\rho_0 \iint \phi \frac{\partial \phi}{\partial n} dS \quad \dots \quad (3)$$

We have seen (Art. 276) that, subject to a certain condition, W represents the intrinsic energy†

The complete interpretation of (3) may be left to the reader. In various important cases, e.g. when the boundary is fixed ($\partial \phi / \partial n = 0$), or free ($\phi = 0$), the surface-integral vanishes, and we have

$$T + W = \text{const} \quad \dots \quad (4)$$

* "Mémoire sur l'intégration de quelques équations linéaires aux différences partielles, et particulièrement de l'équation générale du mouvement des fluides élastiques," *Mém. de l'Acad. des Sciences*, t. III. p. 121 (1819)

For other proofs see Kirchhoff, *Mechanik*, c. xxiii, and Rayleigh, *Theory of Sound*, Art. 273.

† See, however, the footnote on p. 453

This leads to a proof of the determinateness of the motion consequent on a given initial distribution of velocity and condensation. For if ϕ_1, ϕ_2 were two distinct forms of the velocity potential satisfying the prescribed initial conditions, then, in the motion for which $\phi = \phi_1 - \phi_2$, $T + W$ would be constantly null, since it vanishes initially. Since every element of T and W is essentially positive, this requires that the derivatives of ϕ with respect to x, y, z, t should all vanish, i.e. ϕ_1 and ϕ_2 can only differ by an absolute constant*. The argument applies, of course, to all cases where we can predicate the vanishing of the surface integral in (3).

Simple Harmonic Vibrations

285. In the case of simple harmonic motion, the time-factor being $e^{i\omega t}$, the equation (4) of Art. 283 takes the form

$$(\nabla^2 + k^2)\phi = 0, \quad \dots\dots\dots(1)$$

provided
$$k = \frac{\omega}{c}, \quad \dots\dots\dots(2)$$

It appears on comparison with Art. 276 that $2\pi/k$ is the wave-length of plane waves of the assumed period ($2\pi/\omega$).

In the case of symmetry with respect to the origin, we have by Art. 281 (5), or by transformation of (1),

$$c^2 \cdot r \frac{d\phi}{dr} + k^2 \cdot r \phi = 0, \quad \dots\dots\dots(3)$$

The solution of this may be written†

$$\phi = A \frac{\sin kr}{kr} + B \frac{\cos kr}{kr}. \quad \dots\dots\dots(4)$$

If the motion is finite at the origin we must have $B = 0$, and (4) reduces to

$$\phi = A \frac{\sin kr}{kr}. \quad \dots\dots\dots(5)$$

It may be noticed that this solution may be obtained by superposition of systems of plane waves, the directions of propagation being distributed uniformly. Thus, for a system of plane waves whose direction of propagation makes an angle θ with the axis of x , we have

$$\phi = e^{ikr \cos \theta}, \quad \dots\dots\dots(6)$$

and the mean value of this for all directions through the origin is

$$\phi = \frac{1}{4\pi} \int_0^\pi e^{ikr \cos \theta} \cdot 2\pi \sin \theta \, d\theta = \frac{\sin kr}{kr}. \quad \dots\dots\dots(7)$$

* Kirchhoff, *Mechanik*, c. xiii.

† The time factor is omitted here and elsewhere for shortness.

We can draw from (5) a conclusion applicable to the general case, to which the equation (1) refers. We have seen (Art. 283) that the mean value of ϕ over a sphere of radius r , described with any point O as centre, satisfies an equation of the form (3). Hence in the notation of the Art quoted, we have

$$\bar{\phi} = \frac{\sin kr}{kr} \phi_0, \quad \dots \dots \dots (8)$$

where ϕ_0 denotes the value of ϕ at O . This assumes that ϕ has no singularities within the sphere to which r refers*. Cf Art 38

Returning to the case of symmetry, we note that the solution (4) may also be written

$$\phi = C \frac{e^{-ikr}}{r} + D \frac{e^{ikr}}{r}. \quad \dots \dots \dots (9)$$

It is evident on reference to Art 281 (8) that the formula

$$\phi = \frac{e^{-ikr}}{4\pi r} \quad \dots \dots \dots (10)$$

represents the system of diverging waves due to a unit source at the origin

286. The general theory of functions satisfying the equation

$$(\nabla^2 + k^2) \phi = 0 \quad \dots \dots \dots (1)$$

has been developed by Helmholtz†, Lord Rayleigh‡, and others§. It has many points of analogy with that of Laplace's equation $\nabla^2 \phi = 0$, which is, indeed, a particular case, obtained by making either $c = \infty$, or $\sigma = 0$.

The typical solution of (1) from which all others can be derived, is that which corresponds to a unit source, viz

$$\phi = \frac{e^{-ikr}}{4\pi r}, \quad \dots \dots \dots (2)$$

where r denotes distance from the source

It appears from Green's Theorem (Art 43) that if ϕ , ϕ' be any two functions which, together with their first and second derivatives, are finite and single-valued throughout any finite region, we have

$$\iiint \left(\phi \frac{\partial \phi'}{\partial n} - \phi' \frac{\partial \phi}{\partial n} \right) dS = \iiint (\phi' \nabla^2 \phi - \phi \nabla^2 \phi') dx dy dz \dots \dots (3)$$

* The theorem was given by H. Weber, *Crelle*, t. lxxix (1868)

† "Theorie der Luftschwingungen in Röhren mit offenen Enden," *Crelle*, t. lvi p. 1 (1859) [*Wiss. Abh.*, t. ii p. 303]

‡ *Theory of Sound*, t. ii

§ For an account of the more recent mathematical theory, see Poockels, "Ueber die partielle Differentialgleichung $\Delta u + k^2 u = 0$," Leipzig, 1891, and Sommerfeld, *l.c. ante* p. 59

If, in addition, ϕ and ϕ' both satisfy (1), the right-hand member vanishes, and we have

$$\iint \phi \frac{\partial \phi'}{\partial n} dS = \iint \phi' \frac{\partial \phi}{\partial n} dS \quad \dots \dots \dots (4)$$

From this we deduce, by exactly the same process* as in Art. 57, the formula

$$\phi_P = -\frac{1}{4\pi} \iint \frac{e^{-ikr}}{r} \frac{\partial \phi}{\partial n} dS + \frac{1}{4\pi} \iint \phi \frac{\partial}{\partial n} \left(\frac{e^{-ikr}}{r} \right) dS, \quad \dots \dots (5)$$

giving the value of ϕ at any point P of a region in terms of the values of ϕ and $\partial\phi/\partial n$ at the boundary. The symbol r here denotes the distances of the respective surface-elements from P , and we see that the value of ϕ may be regarded as due to a certain distribution of simple and double sources over the boundary†

Again, if r' denote distance from a point P' external to the region, we have

$$0 = -\frac{1}{4\pi} \iint \frac{e^{-ikr'}}{r'} \frac{\partial \phi}{\partial n} dS + \frac{1}{4\pi} \iint \phi \frac{\partial}{\partial n} \left(\frac{e^{-ikr'}}{r'} \right) dS \quad \dots \dots (6)$$

It is to be noticed that, as in Art 58, the particular distribution of sources over the boundary which is exhibited in (5) is only one out of an infinite number which would give exactly the same value of ϕ at points *within* the region. For instance, by addition of (5) and (6) we get another such distribution, which may, moreover, be varied indefinitely by varying the position of P' ‡.

The theorems (5) and (6) will apply to the case of an infinite region bounded internally by one or more closed surfaces, provided that at an infinite distance R from the origin ϕ tends to the form

$$\phi = C \frac{e^{-ikR}}{R} \quad \dots \dots \dots (7)$$

We may express this by saying that there are no sources of sound at infinity.

We can carry the analogy with the theory of the ordinary potential one step further, and express the value of ϕ at any point of a *finite* region in terms of simple sources only, or double sources only, distributed over the boundary, thus

$$\phi_P = -\frac{1}{4\pi} \iint \frac{e^{-ikr}}{r} \left(\frac{\partial \phi}{\partial n} + \frac{\partial \phi'}{\partial n'} \right) dS, \quad \dots \dots \dots (8)$$

$$\text{or} \quad \phi_P = \frac{1}{4\pi} \iint (\phi - \phi') \frac{\partial}{\partial n} \left(\frac{e^{-ikr}}{r} \right) dS, \quad \dots \dots \dots (9)$$

* Viz we put $\phi' = e^{-ikr}/r$, where r denotes distance from a fixed point, and isolate this point (when it falls within the region considered), by drawing a small spherical surface about it

† Helmholtz, *l c*

‡ Larmor, *l c ante* p 59

where the auxiliary function ϕ' is subject to the conditions that it must satisfy

$$(\nabla^2 + k^2) \phi' = 0, \quad . \quad . \quad . \quad . \quad (10)$$

throughout the rest of infinite space, and must tend to the form (7) at infinity, whilst at the boundary

$$\phi' = \phi, \quad \text{or} \quad \frac{\partial \phi'}{\partial n} = \frac{\partial \phi}{\partial n}, \quad . \quad (11)$$

as the case may be. The proof is as in Art 58

It would be wrong, however, to assume that, as in the case of the ordinary potential, a function ϕ necessarily exists which satisfies (1) throughout a given region, and also fulfils the condition that ϕ or $\partial\phi/\partial n$ shall assume arbitrarily prescribed values over the boundary. The supposed existence-theorem holds, it is true, *as a rule*, but it fails for a series of definite values of k , which correspond to the normal modes of vibration of the mass of air occupying the region, when the boundary-condition is $\phi = 0$, or $\partial\phi/\partial n = 0$, respectively.

For the same reason, the formulae (8) and (9) cannot be applied without reservation to the case of an infinite region, since the determination of the auxiliary function ϕ' may be impossible

To illustrate these points, let us suppose that throughout a sphere of radius a , having its centre at the origin O , we have

$$\phi = \frac{\sin kR}{R}, \quad . \quad . \quad . \quad . \quad (12)$$

where R now denotes distance from O . If we put

$$\phi' = \sin ka \cdot \frac{e^{-\nu k(R-a)}}{R}, \quad . \quad . \quad . \quad (13)$$

in the external space, the conditions of validity of the formula (8) are satisfied, and we find

$$\phi = \frac{ke^{\nu ka}}{4\pi a} \iint \frac{e^{-\nu kr}}{r} dS \quad .(14)$$

It is not difficult to verify, *a posteriori*, that this is equivalent to (12) for $R < a$ and to (13) for $R > a$

Again, let us seek a surface-distribution of simple sources which will make

$$\phi = \frac{e^{-\nu kR}}{R}, \quad . \quad (15)$$

in the space external to the sphere. The value of ϕ' for the internal space, which coincides with this at the boundary, is

$$\phi' = \frac{e^{-\nu ka}}{\sin ka} \frac{\sin kR}{R}, \quad . \quad . \quad . \quad (16)$$

and we get

$$\phi = \frac{k}{4\pi a \sin ka} \iint \frac{e^{-\nu kr}}{r} dS \quad . \quad . \quad . \quad (17)$$

But the determination of ϕ' fails whenever k is a root of $\sin ka = 0$. It appears in fact that when this condition is satisfied a uniform distribution of simple sources over a sphere of radius a produces *no* effect at external points.

If all the dimensions of the region referred to are small compared with the wave-length, we may put $e^{-ikr} = 1$, approximately, in (5), and the formula assumes the shape

$$\phi_P = -\frac{1}{4\pi} \iint \frac{1}{r} \frac{\partial \phi}{\partial n} dS + \frac{1}{4\pi} \iint \phi \frac{\partial}{\partial n} \left(\frac{1}{r} \right) dS, \quad (18)$$

as in Art 57. Hence, within distances small compared with the wave-length, the variations of ϕ may be calculated as if it satisfied the equation $\nabla^2 \phi = 0$. This principle is of great service in the approximate treatment of various acoustical questions (cf Arts 293, 294)

Finally, we may remark that, if we restore the time-factor, the formula (8) may be written

$$\phi_P = -\frac{1}{4\pi} \iint \frac{e^{i\sigma(t-\frac{r}{c})}}{r} \frac{\partial \phi}{\partial n} dS + \frac{1}{4\pi} \iint \phi \frac{\partial}{\partial n} \left(\frac{e^{i\sigma(t-\frac{r}{c})}}{r} \right) dS \quad \dots (19)$$

This may be generalized by Fourier's double-integral theorem, which may be written in the form

$$\phi(t) = \frac{1}{2\pi} \int_{-\infty}^{\infty} d\sigma \int_{-\infty}^{\infty} \phi(\tau) e^{i\sigma(t-\tau)} d\tau. \dots\dots\dots (20)$$

If we denote by $\phi(t)$ the value which ϕ has at the point (x, y, z) at the instant t , whether this point be within the region or on its boundary, and by $f(t)$ the value which $\partial\phi/\partial n$ has at a point of the boundary, we obtain

$$\phi_P(t) = -\frac{1}{4\pi} \iint \frac{f\left(t - \frac{r}{c}\right)}{r} dS + \frac{1}{4\pi} \iint \frac{\partial}{\partial n} \phi \left(t - \frac{r}{c} \right) dS, \quad \dots\dots (21)$$

provided that in the last term the space-differentiation applies only to r as it appears explicitly. This remarkable formula, which gives the value of ϕ at any instant, at a point P , in terms of antecedent values of ϕ and $\partial\phi/\partial n$ at points of a closed surface surrounding P , was first obtained by Kirchhoff*, in a different manner, from the general equation (4) of Art. 283. It has been supposed by various writers to contain *the* precise mathematical formulation of 'Huygens' principle' in Acoustics, but as has been already pointed out, in connection with the special case (5), the representation of ϕ in this manner is largely arbitrary and indeterminate.

* "Zur Theorie der Lichtstrahlen," *Beil. Ber.*, 1882, p. 641 [*Ges. Abh.*, t. II p. 22]. Various other proofs have been given, cf Larmor, *loc. ante* p. 59, and Love, *Proc. Lond. Math. Soc.* (2), t. I p. 37 (1903).

Applications of Spherical Harmonics

287. The solution of the equation

$$(\nabla^2 + k^2)\phi = 0, \quad \phi = 0 \quad \text{on } r = a, \quad (1)$$

when the boundary condition (have reference to *spherical* surfaces) may be conducted as follows.

We may suppose the value of ϕ over any sphere of radius r having its centre at the origin, to be expanded in a series of spherical surface harmonics whose coefficients are functions of r . We therefore write

$$\phi = \sum R_n \phi_n, \quad r > 0, \quad (2)$$

where ϕ_n is a solid harmonic of degree n , and R_n is a function of r only. Now

$$\begin{aligned} \nabla^2 (R_n \phi_n) &= \nabla^2 R_n \cdot \phi_n + 2 \frac{r}{r^3} R_n \frac{d\phi_n}{dr} + \frac{r}{r^3} \frac{d^2 R_n}{dr^2} \phi_n + \frac{r}{r^3} R_n \frac{d^2 \phi_n}{dr^2} + R_n \nabla^2 \phi_n \\ &= \nabla^2 R_n \cdot \phi_n + \frac{2}{r} \frac{dR_n}{dr} \left(\frac{r}{r} \frac{d\phi_n}{dr} + \frac{r}{r} \frac{d\phi_n}{dr} + \frac{r}{r} \frac{d^2 \phi_n}{dr^2} \right) + R_n \nabla^2 \phi_n. \end{aligned} \quad (3)$$

And, by the definition of a solid harmonic, we have

$$\nabla^2 \phi_n = 0,$$

and

$$\frac{r}{r} \frac{d\phi_n}{dr} + \frac{r}{r} \frac{d\phi_n}{dr} + \frac{r}{r} \frac{d^2 \phi_n}{dr^2} = n\phi_n.$$

Hence

$$\nabla^2 (R_n \phi_n) = \left\{ \nabla^2 R_n + \frac{2n}{r} \frac{dR_n}{dr} + \frac{d^2 R_n}{dr^2} + \frac{2(n+1)}{r} \frac{dR_n}{dr} \right\} \phi_n. \quad (4)$$

If we substitute in (1), the terms in ϕ_n must satisfy the equation independently, whence

$$\frac{d^2 R_n}{dr^2} + \frac{2(n+1)}{r} \frac{dR_n}{dr} + R_n = 0. \quad (5)$$

This can be integrated by setting $R_n = A e^{\lambda r}$. Thus assuming that

$$R_n = \sum A_n e^{\lambda_n r}$$

the relation between consecutive coefficients is found to be

$$m(2n+1+\lambda_n)(\lambda_{n+1}-\lambda_n) = 0.$$

This gives two arithmetical series beginning with $m = 0$ and $m = 1$ and with $m = 2n+1$, then

$$\begin{aligned} R_n &= A \left(1 - \frac{k^2 r^2}{2(2n+3)} + \frac{k^4 r^4}{2 \cdot 4(2n+3)(2n+5)} - \dots \right) \\ &\quad + B r^{-(n+1)} \left(1 - \frac{k^2 r^2}{2(1-2n)} + \frac{k^4 r^4}{2 \cdot 4(1-2n)(3-2n)} - \dots \right). \end{aligned}$$

where A, B are arbitrary constants. Hence if we put $\phi_n = r^n S_n$, so that S_n is a surface-harmonic of order n , the general solution of (1) may be written

$$\phi = \sum \{A\psi_n(kr) + B\Psi_n(kr)\} r^n S_n, \quad \dots \dots \dots (6)$$

where

$$\begin{aligned} \psi_n(\zeta) &= \frac{1}{1 \cdot 3 \cdot (2n+1)} \left(1 - \frac{\zeta^2}{2(2n+3)} + \frac{\zeta^4}{2 \cdot 4(2n+3)(2n+5)} - \dots \right), \\ \Psi_n(\zeta) &= \frac{1 \cdot 3 \cdot (2n-1)}{\zeta^{2n+1}} \left(1 - \frac{\zeta^2}{2(1-2n)} + \frac{\zeta^4}{2 \cdot 4(1-2n)(3-2n)} - \dots \right) \end{aligned} \quad (7)^*$$

The first term of (6) is alone to be retained when the motion is finite at the origin

The functions $\psi_n(\zeta)$, $\Psi_n(\zeta)$ can also be expressed in finite terms, as follows

$$\psi_n(\zeta) = \left(-\frac{d}{\zeta d\zeta}\right)^n \frac{\sin \zeta}{\zeta}, \quad \Psi_n(\zeta) = \left(-\frac{d}{\zeta d\zeta}\right)^n \frac{\cos \zeta}{\zeta} \quad (8)$$

These are readily identified with (7) by expanding $\sin \zeta$, $\cos \zeta$, and performing the differentiations. As particular cases we have

$$\begin{aligned} \psi_0(\zeta) &= \frac{\sin \zeta}{\zeta}, \quad \psi_1(\zeta) = \frac{\sin \zeta}{\zeta} - \frac{\cos \zeta}{\zeta^2}, \\ \psi_2(\zeta) &= \left(\frac{3}{\zeta^3} - \frac{1}{\zeta}\right) \sin \zeta - \frac{3 \cos \zeta}{\zeta^4} \end{aligned} \quad (9)$$

The formulae (6) and (8) shew that the general solution of the equation

$$\frac{d^2 R_n}{d\zeta^2} + \frac{2(n+1)}{\zeta} \frac{dR_n}{d\zeta} + R_n = 0, \quad \dots \dots \dots (10)$$

which is obtained by writing ζ for kr in (5), is

$$R_n = \left(\frac{d}{\zeta d\zeta}\right)^n \frac{Ae^{i\zeta} + Be^{-i\zeta}}{\zeta} \quad \dots \dots \dots (11)$$

This is easily verified; for if R_n be any solution of (10) we find that the corresponding equation for R_{n+1} is satisfied by

$$R_{n+1} = \frac{dR_n}{\zeta d\zeta},$$

and by repeated applications of this result it appears that (10) is satisfied by

$$R_n = \left(\frac{d}{\zeta d\zeta}\right)^n R_0, \quad \dots \dots \dots (12)$$

* There is a slight deviation here from the notation adopted by Heine, *Kugelfunktionen*, t. 1. p. 82. It may be noted that the formula (6) gives an immediate proof of the theorem (8) of Art. 285.

where R_0 is the solution of

$$\frac{d}{d\xi} \xi R_0' + \xi R_0 = 0,$$

that is

$$R_0 = \frac{1}{\xi} \quad \text{or} \quad R_0 = \frac{1}{\xi^2}. \quad (13^*)$$

It will be convenient to have a special notation for that combination of the functions $\Psi_n(\xi)$, $\Psi_n(\xi)$ which is appropriate to the expression of *diverging waves*. We write

$$f_n(\xi) = \left(-\frac{d}{d\xi} \right)^n e^{-\xi^2} \Psi_n(\xi) = \psi_n(\xi). \quad (14)$$

A particular case

$$f_0(\xi) = e^{-\xi^2}, \quad f_1(\xi) = \left(\frac{1}{\xi} + \frac{1}{\xi^3} \right) e^{-\xi^2}, \quad f_2(\xi) = \left(\frac{1}{\xi^2} + \frac{3}{\xi^4} + \frac{3}{\xi^6} \right) e^{-\xi^2}. \quad (15)$$

The general formula is

$$f_n(\xi) = \frac{(-1)^n}{\xi^{n+1}} \left(1 + \frac{n(n+1)}{2\xi^2} + \frac{(n-1)n(n+1)(n+2)}{2 \cdot 4 \cdot (\xi^2)} + \dots + \frac{1 \cdot 2 \cdot 3 \dots 2n-1}{2^n (n!) \xi^{2n}} \right) e^{-\xi^2}. \quad (16)$$

This may be proved by 'mathematical induction,' or by means of the differential equation satisfied by $f_n(\xi)$ ¹. If we equate separately real and imaginary parts, expressions for $\Psi_n(\xi)$, $\Psi_n(\xi)$, in terms of $\cos \xi^2$, $\sin \xi^2$ and finite algebraical series, can be deduced by (14).

The functions $\Psi_n(\xi)$, $\Psi_n(\xi)$, $f_n(\xi)$ all satisfy recurrence formulae of the types

$$\Psi_n'(\xi) = \xi \Psi_{n+1}(\xi) - \xi \Psi_{n-1}(\xi), \quad (17)$$

$$\xi \Psi_n'(\xi) + (2n+1) \Psi_n(\xi) = \Psi_{n+1}(\xi), \quad (18)$$

these are frequently useful in reduction.

288 A simple application of the foregoing analysis to the vibration of air contained in a spherical envelope.

1. Let us first consider the free vibrations when the envelope is *free*; then, when the motion is finite at the origin, we have

$$\psi = 1/\psi_0 + e^{-k^2 r} S_n e^{i\omega t}, \quad (19)$$

with the boundary condition $-k\psi_n + k^2 r + n\psi_n(kr) = 0$,

a being the radius. This determines the admissible values of k and ω in a set of roots.

* The above analysis, which has a wide application to radiations of physical functions, is given, in one form or another, by various authors, from Lagrange, "Sur la distribution de la chaleur par un réflecteurment de la terre," *Annales des L'ec. polyt.* An. 1805, p. 245 (1806) [1822, *Extrait*, Livre II, p. 117], to Poincaré. For references to the history of the matter, see also, as a problem in Differential Equations, see Goursat, "On Bessel's Equation and its Transformations," *Phil. Trans.*, 1901.

¹ Stokes, *loc. cit.* p. 464. The solution is different.

It is evident from Art. 281² that the equation reduces always to the form

$$\tan k = P/k, \quad \text{..... (3)}$$

where P is a rational algebraic function. The roots can then be calculated without difficulty, either by means of a table, or by a method devised by Fourier³.

In the case of the present investigation ($\mu = 0$), we have

$$\tan k = 1 - \frac{3k^2}{k_0^2} e^{-k^2}, \quad \text{..... (4)}$$

where $k_0^2 = 4\pi^2 \lambda^2 / d^2$, λ being the wave-length.

$$\tan k = 0, \quad k = 0, \quad \text{..... (5)}$$

which defines the first root $k = 0$ of the normal mode. The roots of this equation, which presents a transcendental problem, can be calculated most readily by means of a table⁴. The following values are observed for the first few roots are

$$k = 1.4303, \quad 2.4599, \quad 3.4509, \quad 4.4774, \quad 5.4818, \quad 6.4844, \quad \text{..... (6)}$$

expressed in the form $k = \pi n$, where n is integral. The n numbers give the ratio of the diameter of the sphere to the wave-length. Taking the reciprocals we find

$$\frac{\lambda}{d} = 0.6987, \quad 0.4067, \quad 0.2896, \quad 0.2233, \quad 0.1824, \quad 0.1542, \quad \text{..... (7)}$$

The values of the second and higher roots of (4) the roots of lower order give the positions of the spherical nodes ($\mu = 0$). Thus in the second mode there is a spherical node at a radial distance

$$\frac{r}{d} = \frac{1.4303}{2.4599} = 0.5817,$$

for the case $\mu = 1$, it coincides with that of the harmonic S_1 , and for the case $\mu = 0$, we have

$$\tan k = 1 \left\{ \frac{\sin k}{k} - \frac{\cos k}{k_0} \right\} e^{-k^2}, \quad \text{..... (8)}$$

$$\text{which is equivalent to } \tan k = \frac{2k}{k_0} e^{-k^2}, \quad \text{..... (9)}$$

the next root is $k = 0$. The next root gives, for the ratio of the diameter to the wave-length,

$$\frac{\lambda}{d} = 0.6157,$$

and the value of k^2 is then approximate to the square of integer, 2, 3, 4, In the case of the case $\mu = 0$, the equation is,

$$\frac{\lambda}{d} = 1.000$$

In this, the presence of the normal mode, the air wags to and fro much in the same manner as is already shown page. In the case of any one of the higher roots, the roots of

¹ *Leçons de Géométrie de la Châlonais*, Paris, 1822, Art. 286.
² Euler, *Introductio in Analysin Infinitorum*, Lausanne, 1748, t. II, p. 319; Rayleigh, *Theory of Sound*, Art. 266.
³ Fourier, *Leçons d'Analyse Physique*, Paris, 1869-70, t. I, p. 266.

lower order give the positions of the spherical nodes ($\partial\phi/\partial r=0$). For the further discussion of the problem we must refer to the investigation by Lord Rayleigh*

2° To find the motion of the enclosed air due to a prescribed normal vibration of the boundary, say

$$\frac{\partial\phi}{\partial r}=S_n e^{i\sigma t}, \quad . \quad . \quad (10)$$

we have

$$\phi=A\psi_n(kr)^n S_n e^{i\sigma t}, \quad (11)$$

with the condition

$$A\{ka\psi_n'(ka)+n\psi_n(ka)\}\alpha^{n-1}=1,$$

and therefore

$$\phi=\frac{\psi_n(kr)}{ka\psi_n'(ka)+n\psi_n(ka)}\alpha\left(\frac{r}{a}\right)^n S_n e^{i\sigma t} \quad (12)$$

This expression becomes infinite, as we should expect, whenever ka is a root of (2), i.e. whenever the period of the imposed vibration coincides with that of one of the natural periods, of the same spherical-harmonic type.

By putting $ka=0$ we pass to the case of an incompressible fluid. The formula (12) then reduces to

$$\phi=\frac{a}{n}\left(\frac{r}{a}\right)^n S_n e^{i\sigma t}, \quad . \quad .. \quad . \quad (13)$$

as in Art 91. It is important to notice that the same result holds approximately, even in the case of a gas, whenever ka is small, i.e. whenever the wave-length ($2\pi/k$) corresponding to the actual period is large compared with the circumference of the sphere. We have here an illustration of a general principle stated in Art 286, of which considerable use will be made presently (Arts 293, 294).

3° To determine the motion of a gas within a space bounded by two concentric spheres, we require the complete formula (6) of Art 287. The only interesting case, however, is where the two radii are nearly equal, and this can be solved more easily by an independent process†

In terms of polar coordinates r, θ, ω , the equation $(\nabla^2+k^2)\phi=0$ becomes

$$\frac{\partial^2\phi}{\partial r^2}+\frac{2}{r}\frac{\partial\phi}{\partial r}+\frac{1}{r^2}\left[\frac{\partial}{\partial\mu}\left\{(1-\mu^2)\frac{\partial\phi}{\partial\mu}\right\}+\frac{1}{1-\mu^2}\frac{\partial^2\phi}{\partial\omega^2}\right]+k^2\phi=0, \quad . \quad . \quad (14)$$

where $\mu=\cos\theta$. If, now, $\partial\phi/\partial r=0$ for $r=a$ and $r=b$, where a and b are nearly equal, we may neglect the radial motion altogether, so that the equation reduces to

$$\frac{\partial}{\partial\mu}\left\{(1-\mu^2)\frac{\partial\phi}{\partial\mu}\right\}+\frac{1}{1-\mu^2}\frac{\partial^2\phi}{\partial\omega^2}+k^2a^2\phi=0 \quad . \quad . \quad (15)$$

It appears, exactly as in Art 198, that the only solutions which are finite over the whole spherical surface are of the type

$$\phi\propto S_n, \quad \text{.....} \quad . \quad . \quad . \quad (16)$$

where S_n is a surface-harmonic of integral order n , and that the corresponding values of k are given by

$$k^2a^2=n(n+1) \quad (17)$$

* "On the Vibrations of a Gas contained within a Rigid Spherical Envelope," *Proc Lond Math Soc*, t iv p 93 (1872), *Theory of Sound*, Art 331

† Lord Rayleigh, *Theory of Sound*, Art 333. The direct solution is given by Chree, *Mess of Math*, t xv p 20 (1886)

In the gravest mode ($n=1$) the gas sways to and fro across the equator of the harmonic S_1 , being, in the extreme phases of the oscillation, condensed at one pole and rarefied at the other. Since $ka=\sqrt{2}$ in this case, we have for the equivalent wave-length $\lambda/2a=2.221$.

In the next mode ($n=2$) the type of the vibration depends on that of the harmonic S_2 . If this be zonal, the equator is a node. The frequency is determined by $ka=\sqrt{6}$, or $\lambda/2a=1.283$.

289 We may next consider the propagation of waves *outwards* from a spherical surface in an unlimited medium *

If at the surface ($r=a$) we have a prescribed normal velocity

$$\dot{r} = S_n e^{i\sigma t}, \quad \dots \quad (1)$$

the appropriate solution of $(\nabla^2 + k^2)\phi = 0$ is, in the notation of Art. 287,

$$\phi = C_n f_n(kr) r^n S_n e^{i\sigma t} \quad (2)$$

The condition $-\frac{\partial\phi}{\partial r} = S_n e^{i\sigma t}, \quad \dots \quad (3)$

which is to be satisfied at the surface of the sphere ($r=a$), gives

$$C_n = -\frac{1}{\{k a f_n'(ka) + n f_n(ka)\} a^{n-1}} \quad \dots \quad (4)$$

At distances r which are large compared with the wave-length ($2\pi/k$), we have

$$f_n(kr) = \frac{e^{ikr}}{(kr)^{n+1}}, \quad \dots \quad (5)$$

approximately, so that (2) becomes

$$\phi = \frac{C_n}{k^{n+1}} \frac{e^{ikr}}{r} S_n, \quad \dots \quad (6)$$

or, in real form $\phi = \frac{|C_n|}{k^{n+1}} \cos k(ct - r + \epsilon) S_n \quad \dots \quad (7)$

The rate of propagation of energy outwards is

$$- \iint p \frac{\partial\phi}{\partial r} r^2 d\omega, \quad \dots \quad (8)$$

where $\delta\omega$ is an elementary solid angle, and r may conveniently be taken to be very great. Since

$$p = p_0 + \rho_0 \frac{\partial\phi}{\partial t}, \quad \dots \quad (9)$$

we find, for the mean value of (8)

$$\frac{1}{2} \frac{\rho_0 c}{k^{2n}} |C_n|^2 \iint S_n^2 d\omega. \quad \dots \quad (10)$$

This might have been written down at once from the results of Art. 276, since the waves propagated in any assigned direction tend to become ultimately plane.

* This problem was solved, in a somewhat different manner, by Stokes, "On the Communication of Vibrations from a Vibrating Body to a surrounding Gas," *Phil. Trans.*, 1868 [*Math. and Phys. Papers*, t. iv. p. 299]

When $n > 0$, the normal velocity is in opposite phases over any two regions of the spherical surface $r=a$ which are separated by a nodal line $S_n=0$. The lateral motion of the air near the sphere, from places which are moving outwards to others which are moving inwards will consequently, if the wave-length be not too small, have the effect of diminishing the intensity of the disturbance propagated to a distance, as compared with what it would have been if the normal velocity had been everywhere in the same phase, and this effect will be more marked the higher the order n of the harmonic involved, owing to the greater number of compartments into which the surface of the sphere is divided by the nodal lines. Moreover, for the same harmonic S_n , and for an assigned frequency $(\sigma/2\pi)$, the influence of the lateral motion will increase with great rapidity as the wave-velocity c , and (consequently) the wave-length $2\pi/k$, is increased. This accounts for the feeble character of the sound emitted by a bell in an atmosphere of hydrogen, as compared with what is observed in the case of air*.

To verify these statements, we note that if the lateral motion of the air had been prevented by a multitude of conical partitions extending indefinitely outwards in the directions of the radii of the sphere, the expression (10) would have been replaced by

$$\frac{1}{2} \rho_0 c |C_0|^2 \iint S_n^2 d\omega \quad (11)$$

The ratio (I_n , say) which this bears to (10) is equal to the 'absolute value' of the expression

$$\frac{(ka)^{2n} \{ka f_n'(ka) + n f_n(ka)\}^2}{\{ka f_0'(ka)\}^2}. \quad (12)$$

From the values of f_0, f_1, f_2 given in Art. 287 (15), we easily obtain

$$I_0=1, \quad I_1=\frac{4+k^4a^4}{k^2a^2(1+k^2a^2)}, \quad I_2=\frac{81+9k^2a^2-2k^4a^4+k^6a^6}{k^4a^4(1+k^2a^2)}. \quad (13)$$

The following numerical examples are given (with others) by Stokes

ka	I_0	I_1	I_2
4	1	0.95588	0.87523
2	1	1	1.8625
1	1	2.5	44.5
0.5	1	13	1064.2
0.25	1	60.294	19650

Again, to compare the rates of communication of energy under similar circumstances to two different gases, we have, for the ratio of these rates, the absolute value of the expression

$$\frac{(k'a)^{2n-1} \{k'a f_n'(ka) + n f_n(k'a)\}^2}{(ka)^{2n-1} \{ka f_n'(ka) + n f_n(ka)\}^2}, \quad (14)$$

where the accent attached to k refers to the second gas. This is easily deduced from (10) and (4), with the help of the relations

$$\frac{\rho_0 c}{\rho_0' c'} = \frac{c'}{c} = \frac{k}{k'},$$

* Stokes, *l.c.*

the frequency being taken to be the same in the two cases * For $n=2$, the ratio comes out equal to

$$\frac{(ka)^7 (81 + 9k'^2 a^2 - 2k'^4 a^4 + k'^6 a^6)}{(k'a)^7 (81 + 9k^2 a^2 - 2k^4 a^4 + k^6 a^6)} \quad (15)$$

Thus, supposing the two gases to be oxygen and hydrogen, and taking $ka = 5$, $k'a = 125$, we find that the rates of propagation of energy outwards are as 16000 : 1, nearly

290 The case $n=1$ of the preceding Art is specially interesting from the point of view of the theory of the pendulum, since it corresponds to an oscillation of the sphere, as rigid, to and fro in a straight line. It should be noticed, however, that the neglect of the terms of the second order in the dynamical equations involves the assumption that the amplitude of vibration of the sphere is small compared with the radius,

$$\text{Putting} \quad S_1 = a \cos \theta, \quad (16)$$

where θ is the angle which r makes with the line in which the centre oscillates, the formula (2) reduces to

$$\phi = C \frac{1 + \nu k r}{k^3 r^2} e^{\nu(\sigma t - kr)} a \cos \theta \quad (17)$$

The value of C , as determined by the surface-condition, is

$$C = \frac{k^3 a^3 (2 - k^2 a^2 - 2\nu k a)}{4 + k^4 a^4} e^{\nu k a} \quad (18)$$

The resultant pressure on the sphere is

$$X = - \int_0^\pi \Delta p \cos \theta \cdot 2\pi a^2 \sin \theta d\theta, \quad (19)$$

$$\text{where} \quad \Delta p = c^2 \rho_0 s = \rho_0 \frac{\partial \phi}{\partial t} = \nu \sigma \rho_0 \phi \quad (20)$$

Substituting from (17) and (18), and performing the integration, we find

$$X = - \frac{4}{3} \pi \rho_0 a^3 \cdot \frac{2 + k^2 a^2 - \nu k^3 a^3}{4 + k^4 a^4} \nu \sigma a e^{\nu \sigma t} \quad (21)$$

This may be written in the form

$$X = - \frac{4}{3} \pi \rho_0 a^3 \frac{2 + k^2 a^2}{4 + k^4 a^4} \frac{dU}{dt} - \frac{4}{3} \pi \rho_0 a^3 \frac{k^3 a^3}{4 + k^4 a^4} \sigma U, \quad (22)$$

where $U (= a e^{\nu \sigma t})$ denotes the velocity of the sphere†. If we reverse the sign of X , we get the extraneous force which must be applied to the sphere in order to maintain the assumed simple-harmonic vibration.

The first term of the expression in (22) is the same as if the inertia of the sphere were increased by the amount

$$\frac{2 + k^2 a^2}{4 + k^4 a^4} \times \frac{4}{3} \pi \rho_0 a^3, \quad (23)$$

* It is assumed that the ratio γ of the specific heats is the same for the two gases.

† This formula is given by Lord Rayleigh, *Theory of Sound*, Art. 325. For another treatment of the problem of the vibrating sphere, see Poisson, "Sur les mouvements simultanés d'un pendule et de l'air environnant," *Mém. de l'Acad. des Sciences*, t. xi p. 521 (1832), and Kirchhoff, *Mechanik*, c. xxiii.

whilst the second is the same as if the sphere were subject to a frictional force varying as the velocity, the coefficient being

$$\frac{k^3 \alpha^3}{4 + k^4 \alpha^4} \times \frac{4}{3} \pi \rho_0 \alpha^3 \sigma \quad (24)$$

In the case of an incompressible fluid, and, more generally, whenever the wave-length $2\pi/k$ is large compared with the circumference of the sphere, we may put $k\alpha = 0$. The addition to the inertia is then half that of the fluid displaced, whilst the frictional coefficient vanishes*. Cf Art 92

The frictional coefficient is in any case of high order in $k\alpha$, so that the vibrations of a sphere whose circumference is moderately small compared with the wave-length are only slightly affected in this way. To find the energy expended per unit time in generating waves in the surrounding medium, we must multiply the frictional term in (22), now regarded as an equation in real quantities, by U , and take the mean value, this is found to be

$$\frac{2}{3} \pi \rho_0 \alpha^3 \frac{k^3 \alpha^3}{4 + k^4 \alpha^4} \sigma \alpha^2 \quad (25)$$

In other words, if ρ_1 be the mean density of the sphere, the fraction of its energy which is expended in one period is

$$2\pi \frac{\rho_0}{\rho_1} \frac{k^3 \alpha^3}{4 + k^4 \alpha^4} \quad (26)$$

291. The same analysis can be applied to calculate the scattering of waves by a spherical obstacle. In particular we shall consider the case of an incident system of plane waves, travelling in the direction of x -negative, and represented, apart from the time-factor, by

$$\phi = e^{ikx} \quad \dots \quad (1)$$

Since this satisfies $(\nabla^2 + k^2)\phi = 0$, and has no singularities in the neighbourhood of the origin, and is (further) symmetrical about the axis of x , it must admit of being expanded in a series of terms of the type

$$\psi_n(kr) r^n \cdot P_n(\cos \theta), \quad \dots \quad (2)$$

provided $x = r \cos \theta = r\mu$, say

The requisite formula is, in fact,

$$e^{i\zeta\mu} = \sum (2n+1) (i\zeta)^n \psi_n(\zeta) P_n(\mu) \quad \dots \quad (3)$$

This can be established in various ways. One method is to expand $e^{i\zeta\mu}$ in powers of μ , and to substitute for these powers their equivalents in terms of zonal harmonics, by means of the formula

$$\begin{aligned} \mu^n = \frac{n!}{1.3.5 \dots (2n+1)} & \left\{ (2n+1) P_n + (2n-3) \frac{2n+1}{2} P_{n-2} \right. \\ & \left. + (2n-7) \frac{(2n+1)(2n-1)}{2.4} P_{n-4} + \dots \right\} \dots (4) \end{aligned}$$

* Poisson, *l c*

In the case of the plane wave-system (1), we have by (3)

$$B_n = (2n+1) i^n k^n, \quad (13)$$

and the most important part of the scattered waves, at a distance r which is large compared with the wave-length, is accordingly represented by

$$\phi = B_0 f_0(kr) + B_1 f_1(kr) \cos \theta = - (ka)^3 \left(\frac{1}{3} + \frac{1}{2} \cos \theta \right) \frac{e^{-ikr}}{kr} \quad (14)$$

The physical origin of the two terms is explained near the end of Art 294

As in Art. 289, the rate at which energy is propagated outwards in the scattered waves is

$$\frac{1}{2} \frac{\rho_0 c}{k^{2n}} |B_n|^2 \iint S_n^2 d\omega \quad (15)$$

The proper standard of comparison here is the energy-flux across unit area of a wave-front in the incident system (1). On the present scale, this is $\frac{1}{2} \rho_0 k^2 c$, by Art 276, and the ratio of (15) to this is, in the present case,

$$\frac{4\pi}{(2n+1) k^{2n+2}} |B_n|^2 \quad (16)$$

The terms of lowest order, when ka is small, are those for which $n=0, n=1$. The sum of these gives

$$\frac{7}{15} (ka)^4 \pi a^2 \quad (17)$$

The rate at which energy is scattered varies therefore inversely as the fourth power of the wave-length*

As a numerical example, a spherule $\frac{1}{1000}$ of an inch in diameter scatters only 1.43×10^{-17} of the incident energy, if the wave-length be four feet. There is therefore no difficulty in understanding how a fog which is quite opaque optically may transmit ordinary sounds with great freedom

292 We will next take the case where the sphere is moveable, but is urged towards a fixed position by a force varying as the displacement

Its equation of motion, parallel to x , will then be of the form

$$M \left(\frac{d^2 \xi}{dt^2} + \sigma_0^2 \xi \right) = - \iint p \cos \theta a^2 d\omega \quad (18)$$

If the time-factor be e^{ikt} , we have

$$p = p_0 + \rho_0 \frac{\partial}{\partial t} (\phi + \phi') = p_0 + ikc\rho_0 (\phi + \phi') \quad (19)$$

Hence, substituting in (18),

$$(\sigma_0^2 - k^2 c^2) M \xi = -ikc \{B_1 \psi_1(ka) + B_1' f_1(ka)\} \frac{4}{3} \pi \rho_0 a^3, \quad (20)$$

since the products of harmonics of different orders vanish when integrated over the sphere.

Again, the kinematic-surface condition

$$-\frac{\partial}{\partial t} (\phi + \phi') = \frac{d\xi}{dt} \cos \theta = ikc\xi \cos \theta, \quad (21)$$

* The above problem was investigated, by a somewhat different analysis, by Lord Rayleigh, "Investigation of the Disturbance produced by a Spherical Obstacle on the Waves of Sound," *Proc Lond Math Soc*, t. iv p 253 (1872), see also his *Theory of Sound*, Arts 296, 334, 335. The formula (17) is given by him in a paper "On the Transmission of Light through an Atmosphere containing Small Particles in Suspension," *Phil Mag.* (5), t. xlvii p 375 (1899) [*Sc Papers*, t. iv p 397].

where

$$\left. \begin{aligned} g_1(ka) &= \{ka\psi_1'(ka) + \psi_1(ka)\} \left(\frac{\sigma_0^2 a^2}{c^2} - k^2 a^2 \right) + 2\beta k^2 a^2 \psi_1(ka), \\ G_1(ka) &= \{ka\Psi_1'(ka) + \Psi_1(ka)\} \left(\frac{\sigma_0^2 a^2}{c^2} - k^2 a^2 \right) + 2\beta k^2 a^2 \Psi_1(ka) \end{aligned} \right\} \quad (33)$$

The modulus of the right-hand member of (32) is never greater than unity, but it attains the value unity, and the amplitude of the scattered waves is therefore a maximum, when

$$G_1(ka) = 0, \quad (34)$$

in which case

$$B_1 = -iB_1 \quad (35)$$

If we substitute for $\Psi_1(ka)$ from Art 287 (7), the equation (34) takes the form

$$-(2 + \frac{1}{2}k^4 a^4 + \dots) \left(\frac{\sigma_0^2 a^2}{c^2} - k^2 a^2 \right) + 2\beta k^2 a^2 (1 + \frac{1}{2}k^2 a^2 + \dots) = 0, \quad (36)$$

and it is easily ascertained that when $\sigma_0 a/c$ is small this is satisfied by a real value of ka which is a very little less than that corresponding to the free vibrations, viz

$$ka = \frac{\sigma_0 a}{(1 + \beta)^{\frac{1}{2}} c} \quad (37)$$

In the case of the plane system of waves represented by Art 291 (1) we have

$$B_1 = 3k, \quad (38)$$

by (13) and (35), and the velocity-potential of the scattered waves is, in real form,

$$\phi = -3 \frac{\sin k(ct - r)}{kr} \cos \theta, \quad (39)$$

corresponding to the incident waves

$$\phi = \cos k(ct + x) \quad (40)$$

Again, on reference to (21), or directly from (22) and (40), we find

$$\xi = \frac{6}{k^3 a^3 c} \sin kct \quad (41)$$

The amplitude of vibration of the air-particles in the original wave is $1/c$ on the present scale. The amplitude of the sphere exceeds this in the ratio $6/k^3 a^3$. Moreover it appears from (15) that the dissipation of energy in the scattered waves, when a maximum, is $6\pi\rho_0 c$, or, in terms of the energy-flux in the primary waves,

$$\frac{3}{\pi} \lambda^2 \quad (42)$$

The ratio of this to the dissipation (17) produced by a fixed sphere is $\frac{16}{3} (ka)^{-6}$

On the other hand, it is to be noticed that the wave-length of maximum dissipation is very sharply defined. It may be shewn without much difficulty that the dissipation sinks to one-half the maximum when the wave-length of the incident vibration deviates from the critical value by the fraction

$$\frac{\beta k^2 a^3}{4(1 + \beta)}$$

of itself. In any acoustical application this will be an exceedingly minute fraction. In practice, massive bodies are not usually set into vigorous sympathetic vibration by the direct impact of air-waves, but rather through the intermediary of resonance-boxes and sounding boards.

The occurrence of the factor 3 in (42) calls for some remark. The result is independent of the direction of the incident waves, owing to the three degrees of freedom which the

where $p = \sin \alpha$. If the plane waves are treated as vibration in a definite straight line, the mean of the vibration is independent of the direction of incidence, and the mean for all directions is the same. *

293 The diffraction of plane waves of sound by a lamina, or by an aperture into space, may also be treated by approximate methods provided the linear dimensions of the aperture be small compared with the wave-length. The result is not of course the exact opposite of that which usually prevails in Optics, and the results are accordingly quite different in character. In particular we meet with nothing of the nature of second maxima on the axis under the present condition.

Let us first take the case where a train of waves, travelling in the direction of the positive z -axis, on a flat disk in the plane $x = 0$. If the disk were absent the motion would be represented by

$$\phi = e^{ikz}, \quad \text{.....(1)}$$

everywhere. This gives a normal velocity $= ik$ at the surface of the disk; and the complete solution is therefore

$$\phi = e^{ikz} + \chi, \quad \text{.....(2)}$$

where χ represents the motion which would be produced in the surrounding air by the vibration of the disk normal to its plane with the velocity ik . The formulae of Art. 286 when applied to the region bounded internally by the two surfaces of the disk give

$$\chi = -\frac{1}{2\pi} \int \left(\chi_{en} + \frac{r^{ik}}{r} \right) dS, \quad \text{.....(3)}$$

provided the integration extends over the positive side only of the disk. In the reduction advantage has been taken of the fact that the values of χ and of χ_n at adjacent points on opposite sides of the disk, are evidently equal and opposite. If x, y be the coordinates of P relative to an origin on the disk, we may write $ren = e^{ikr}$, and if the distance of P from any point of the disk is large compared with the linear dimensions of the latter, we have further

$$\chi = -\frac{1}{2\pi} \int \chi dS - \frac{e^{ikr}}{r}, \quad \text{.....(4)}$$

where r may now be taken to denote distance from the origin. The scattered waves are therefore such as would be produced by a double source of variable strength.

The incident wave of this Art. is taken from a paper entitled "A Problem in Resonance, and some of the Effects of Electric Apertures of Light," *Proc. Lond. Math. Soc.*, I. xxii. p. 41 (1898). The result is remarkable in that it is due to Lord Rayleigh, "Some General Theorems concerning Electric Resonance," *Phil. Mag.* (6), I. p. 97 (1902).

* See also H. Bragg, "On the Passage of Waves through Apertures in Plane Screens, and Allied Problems," *Math. Phys. Eng. Sci. p. 279* (1904) (*Sci. Progress*, I. 49, p. 283).

Under the fundamental condition above stated, the variation of χ in the immediate neighbourhood of the disk is very approximately the same as if the fluid were incompressible (Art 286) In the latter case, if the density of the fluid, and the velocity of the disk normal to its plane, were each taken equal to unity, the expression $2\iint\chi dS$ would be equal to the 'inertia-coefficient' of the disk (Art 121 (3)) Denoting this coefficient, which is determined solely by the size and shape of the disk, by M , we have, in the present case,

$$\iint\chi dS = \frac{1}{2}ikM, \quad \dots \dots (5)$$

and therefore

$$\chi_P = -\frac{ikM}{4\pi} \frac{\partial}{\partial x} \left(\frac{e^{-ikr}}{r} \right) = -\frac{k^2 M}{4\pi} \frac{e^{-ikr}}{r} \cos \theta, \quad \dots \dots (6)$$

approximately, where θ is the angle which OP makes with Ox

For a *circular* disk of radius a , we have, by Arts 102, 108,

$$M = \frac{8}{3}a^3, \quad (7)$$

and therefore

$$\chi_P = -\frac{8}{3} \frac{\pi a^3}{\lambda^2} \frac{e^{-ikr}}{r} \cos \theta \quad (8)$$

2° When plane waves are incident directly upon a screen occupying the plane $x=0$, we should have, if the screen were complete,

$$\phi = e^{ikx} + e^{-ikx}, \quad \text{or } = 0, \quad \dots \dots (9)$$

according as $x \geq 0$, the term e^{-ikx} representing the reflected waves When there is an aperture, we assume

$$\phi = e^{ikx} + e^{-ikx} + \chi, \quad \text{and} \quad \phi = \chi', \quad \dots \dots (10)$$

for the two sides, respectively. The continuity of pressure and velocity requires

$$2 + \chi = \chi', \quad \frac{\partial \chi}{\partial x} = \frac{\partial \chi'}{\partial x}, \quad \dots \dots (11)$$

over the aperture, whilst

$$\frac{\partial \chi}{\partial x} = 0, \quad \frac{\partial \chi'}{\partial x} = 0, \quad \dots \dots (12)$$

over the rest of the plane $x=0$

These conditions are all fulfilled if we take χ and χ' to be the potentials of the distributions of simple sources over the area of the aperture which will make

$$\chi = -1, \quad \chi' = +1, \quad \dots \dots (13)$$

respectively, over this area.

Now if we apply the formulae (5) and (6) of Art 286 to the region which lies to the right of the plane $x=0$, and further take P' to be the image of P with respect to this plane, we obtain by addition

$$\chi_P = -\frac{1}{2\pi} \iint \frac{e^{-ikr}}{r} \frac{\partial \chi}{\partial n} dS, \quad \dots \dots (14)$$

since $r' = r$ for $x = 0$. In the present case the integration may be confined to the area of the aperture, in virtue of (12). At distances r which are great compared with the dimensions of the latter, this reduces to

$$\chi_P = -\frac{1}{2\pi} \iint \frac{\partial \chi}{\partial n} dS \frac{e^{-ikr}}{r} \quad \dots \quad (15)$$

If k were $= 0$, the determination of χ in accordance with (13) would be identical with the electrostatic problem of finding the field due to a charged and insulated metal disk having the shape of the aperture, and for points in the immediate neighbourhood the field will in the actual problem have sensibly the same configuration. Hence we may write

$$\iint \frac{\partial \chi}{\partial n} dS = 2\pi C, \quad \dots \quad (16)$$

where C is the 'electrostatic capacity' of the metal disk*. Thus (15) becomes

$$\chi_P = -C \frac{e^{-ikr}}{r}, \quad \dots \quad (17)$$

approximately. From this the value of χ' follows by the obvious relation

$$\chi'(-x, y, z) = -\chi(x, y, z) \quad \dots \quad (18)$$

It appears that the transmitted waves are such as would be produced by a *simple* source of suitable strength.

In the case of a circular aperture

$$C = \frac{2}{\pi} a, \quad (19)$$

and

$$\chi_P = -\frac{2a}{\pi} \frac{e^{-ikr}}{r} \quad \dots \quad (20)$$

Comparison with (8) shows that, under the assumed condition, the amplitude of the waves scattered by a disk is, at like distances, much less than that of the waves transmitted by an aperture of the same size and shape. It is readily seen that the total energy transmitted per second through the circular aperture bears to the energy-flux in the primary waves the ratio

$$\frac{8}{\pi} a^2 \quad \text{or} \quad 816\pi a^2 \quad \dots \quad (21)$$

The ratio of the amplitude of the scattered waves, at any distant point, to that of the primary waves, is independent of the wave-length, so long as this is large compared with the greatest breadth of the aperture.

294 A similar calculation can be applied to the scattering of sound-waves by an obstacle of any form, under the same fundamental condition that the dimensions of the obstacle are all small compared with the wave-length†

* For small values of k , the two functions χ, χ' together express the flow of an incompressible fluid through the aperture. Cf Arts 102, 3°, 108, 1°; and 113.

† Lord Rayleigh, "On the Incidence of Aerial and Electric Waves upon Small Obstacles in the Form of Ellipsoids or Elliptic Cylinders," *Phil Mag.* (5), t. xlv. p. 28 (1897) [*Sc Papers*, t. iv p. 305].

The origin being taken in or near the obstacle, we assume

$$\phi = e^{ikx} + \chi, \quad \dots \dots \dots (1)$$

where the first term represents the incident, and the second the scattered waves. At the surface of the obstacle, supposed rigid and fixed, we must have

$$\frac{\partial \chi}{\partial n} = -\frac{\partial}{\partial n} e^{ikx} = -ikl e^{ikx}, \quad \dots \dots (2)$$

provided l, m, n be the direction-cosines of the normal, drawn outwards

The formula (5) of Art. 286 gives

$$\chi_P = -\frac{1}{4\pi} \iint \frac{e^{-ikr}}{r} \frac{\partial \chi}{\partial n} dS + \frac{1}{4\pi} \iint \chi \frac{\partial}{\partial n} \left(\frac{e^{-ikr}}{r} \right) dS, \quad \dots (3)$$

where the integrations extend over the surface of the obstacle. We proceed to obtain an approximate value of the expression on the right-hand when the distances r are large compared with the dimensions of the obstacle. The coordinates of any point on the surface will be denoted by x, y, z , whilst those of the point P are distinguished as x_1, y_1, z_1 .

Taking the first term, we write

$$\frac{e^{-ikr}}{r} = \left(\frac{e^{-ikr}}{r} \right)_0 + x \left(\frac{\partial}{\partial x} \frac{e^{-ikr}}{r} \right)_0 + y \left(\frac{\partial}{\partial y} \frac{e^{-ikr}}{r} \right)_0 + z \left(\frac{\partial}{\partial z} \frac{e^{-ikr}}{r} \right)_0 + \dots,$$

where the zero-suffix implies that x, y, z are to be put $= 0$ in the expressions to which it is attached. This may also be written

$$\frac{e^{-ikr}}{r} = \left(1 - x \frac{\partial}{\partial x_1} - y \frac{\partial}{\partial y_1} - z \frac{\partial}{\partial z_1} + \dots \right) \frac{e^{-ikr_0}}{r_0}, \quad (4)$$

where r_0 denotes the distance of P from the origin. Again, from (2),

$$\frac{\partial \chi}{\partial n} = -ikl + k^2 xl + \dots \dots \dots (5)$$

Taking the product of (4) and (5), and integrating over the surface, we obtain

$$\iint \frac{e^{-ikr}}{r} \frac{\partial \chi}{\partial n} dS = k^2 Q \frac{e^{-ikr_0}}{r_0} + ikQ \frac{\partial}{\partial x_1} \frac{e^{-ikr_0}}{r_0}, \quad (6)$$

approximately, where Q is the volume of the obstacle. We have here made use of the obvious relations

$$\iint l dS = 0, \quad \iint x l dS = Q, \quad \iint y l dS = 0, \quad \iint z l dS = 0 \quad \dots (7)$$

The terms retained on the right-hand of (6) are of the same order of magnitude, whilst those which are omitted are small in comparison.

As regards the second term in (3), we have

$$\frac{\partial}{\partial n} \frac{e^{-ikr}}{r} = \left(l \frac{\partial}{\partial x} + m \frac{\partial}{\partial y} + n \frac{\partial}{\partial z} \right) \frac{e^{-ikr}}{r} = - \left(l \frac{\partial}{\partial x_1} + m \frac{\partial}{\partial y_1} + n \frac{\partial}{\partial z_1} \right) \frac{e^{-ikr}}{r}. \quad (8)$$

We may, consistently with our former approximation, write r_0 for r , and remove the space-derivatives of e^{-ikr_0}/r_0 outside the signs of integration. The result then involves the surface-integrals

$$\iint l\chi dS, \quad \iint m\chi dS, \quad \iint n\chi dS \quad \dots \quad (9)$$

It appears from (2) or (5), and from a general principle stated in Art 286, that the function χ is, in the immediate neighbourhood of the obstacle, sensibly identical with the velocity-potential of the motion of a liquid produced by a translation of the obstacle through it with the velocity ik parallel to x . Hence the integrals (9) are recognized as components of 'impulse' under the imagined circumstances, and we may write, in conformity with Arts 121, 123,

$$\iint l\chi dS = ik\mathbf{A}, \quad \iint m\chi dS = ik\mathbf{C}', \quad \iint n\chi dS = ik\mathbf{B}', \quad \dots \quad (10)$$

provided the density of the hypothetical liquid be taken to be unity. Hence

$$\iint \chi \frac{\partial}{\partial n} \left(\frac{e^{-ikr}}{r} \right) dS = -ik \left(\mathbf{A} \frac{\partial}{\partial x_1} + \mathbf{C}' \frac{\partial}{\partial y_1} + \mathbf{B}' \frac{\partial}{\partial z_1} \right) \frac{e^{-ikr_0}}{r_0} \quad \dots \quad (11)$$

The final approximate formula is therefore

$$\chi_P = -\frac{k^2 Q}{4\pi} \frac{e^{-ikr}}{r} - \frac{ik}{4\pi} \left\{ (\mathbf{A} + Q) \frac{\partial}{\partial x_1} + \mathbf{C}' \frac{\partial}{\partial y_1} + \mathbf{B}' \frac{\partial}{\partial z_1} \right\} \frac{e^{-ikr}}{r}, \quad \dots \quad (12)$$

where the zero-suffix attached to r has been omitted, as no longer necessary. When kr is large, this may be written

$$\chi_P = -\frac{k^2 Q}{4\pi} \frac{e^{-ikr}}{r} - \frac{k^2}{4\pi} \{ (\mathbf{A} + Q)\lambda_1 + \mathbf{C}'\mu_1 + \mathbf{B}'\nu_1 \} \frac{e^{-ikr}}{r}, \quad \dots \quad (13)$$

where λ_1, μ_1, ν_1 are the direction-cosines of r .

The scattered waves may be regarded as due to the combination of a simple and a double source. The axis of the latter is not in general coincident with the direction of the incident waves.

A more symmetrical formula is obtained if we suppose the primary waves to come from any arbitrary direction (λ, μ, ν) , so that (1) is replaced by

$$\phi = e^{ik(\lambda x + \mu y + \nu z)} + \chi \quad \dots \quad (14)$$

On reviewing the steps of the preceding investigation, we find without difficulty

$$\begin{aligned} \chi_P = & -\frac{k^2 Q}{4\pi} \frac{e^{-ikr}}{r} - \frac{k^2 Q}{4\pi} (\lambda\lambda_1 + \mu\mu_1 + \nu\nu_1) \frac{e^{-ikr}}{r} \\ & - \frac{k^2}{4\pi} \{ \mathbf{A}\lambda\lambda_1 + \mathbf{B}\mu\mu_1 + \mathbf{C}\nu\nu_1 \\ & + \mathbf{A}'(\mu\nu_1 + \mu_1\nu) + \mathbf{B}'(\nu\lambda_1 + \nu_1\lambda) + \mathbf{C}'(\lambda\mu_1 + \lambda_1\mu) \} \frac{e^{-ikr}}{r}, \quad \dots \quad (15) \end{aligned}$$

in place of (13) As in Art 124, the directions of the coordinate axes can be chosen so that \mathbf{A}' , \mathbf{B}' , $\mathbf{C}' = 0$, and the formula then reduces to

$$\chi_P = -\frac{k^2 Q}{4\pi} \frac{e^{-ikr}}{r} - \frac{k^2}{4\pi} \{(\mathbf{A} + Q) \lambda \lambda_1 + (\mathbf{B} + Q) \mu \mu_1 + (\mathbf{C} + Q) \nu \nu_1\} \frac{e^{-ikr}}{r} \quad (16)$$

In the case of an ellipsoid of semi-axes a , b , c , we have by Art 121 (4),

$$\mathbf{A} + Q = \frac{2}{2 - \alpha_0} Q, \quad \mathbf{B} + Q = \frac{2}{2 - \beta_0} Q, \quad \mathbf{C} + Q = \frac{2}{2 - \gamma_0} Q, \quad \dots \quad (17)$$

where α_0 , β_0 , γ_0 are defined by Art 114 (6) In the case of the sphere $\alpha_0 = \beta_0 = \gamma_0 = \frac{2}{3}$, and if we substitute in (13) we reproduce the result (14) of Art 291 In the case of the circular disk ($\alpha = b$, $c = 0$), we have $Q = 0$, $\mathbf{A} = \frac{2}{3} \alpha^3$, $\mathbf{B} = 0$, $\mathbf{C} = 0$, and (16) reduces to

$$\chi_P = -\frac{2}{3} \frac{k^2 \alpha^3}{\pi} \lambda \lambda_1 \frac{e^{-ikr}}{r} \quad (18)$$

The effect of obliquity of the disk to the incident waves is to diminish the amplitude of the scattered waves in the ratio of the cosine (λ) of the obliquity

The explanation of the two types of disturbance in (13) or (16) may be easily given in general terms In the first place, if the obstacle were absent, the space which it occupies would be the seat of alternate condensations and rarefactions By its resistance to these, the obstacle exerts a certain reaction on the medium, the waves at a great distance, thus produced, are in fact such as would be caused in an otherwise quiescent medium by a periodic variation in the volume of the obstacle, just sufficient to compensate the variations of density referred to The result is equivalent to a 'simple source' of sound Superposed on this disturbance, we have a second wave-system due to the *immobility* of the obstacle If the latter were freely moveable, and had (moreover) the same inertia as the air which it displaces, it would sway backwards and forwards in the sound vibrations, and this second wave-system would be absent This system is, in fact, that which would be produced if the obstacle were to vibrate to and fro in a straight line, with a motion equal and opposite to that of the air-particles in the undisturbed waves This is equivalent to a 'double source' of sound

The problem of Diffraction, when the wave-length is *small* (instead of large) compared with the dimensions of the obstacle, presents difficulties which have not yet been altogether overcome even in the case of the sphere. Lord Rayleigh has, however, in a recent paper* investigated the incipient formation of a sound-shadow in the particular case where the wave-length is one-tenth of the circumference

295. If, no longer restricting ourselves to simple-harmonic vibrations, we seek to integrate the equation

$$\frac{\partial^2 \phi}{\partial t^2} = c^2 \nabla^2 \phi \quad \dots \dots \dots (1)$$

* "On the Acoustic Shadow of a Sphere," *Phil Trans*, A, t cccii p 87 (1904)

$$\text{whence} \quad (\lambda^2 c^2 + \sigma_0^2) B = \frac{2\beta c}{a^3} (\lambda a + 1) \lambda A, \quad \lambda c B = -\frac{1}{a^3} (\lambda^2 a^2 + 2\lambda a + 2) A \quad (13)$$

Eliminating the ratio A/B , we obtain the biquadratic* in λ

$$(\lambda^2 c^2 + \sigma_0^2) (\lambda^2 a^2 + 2\lambda a + 2) + 2\beta c^2 \lambda^2 (\lambda a + 1) = 0 \quad (14)$$

Distinguishing the several roots by suffixes, we have

$$\xi = \sum_1^4 \frac{\lambda_s^2 a^2 + 2\lambda_s a + 2}{c a^3 \lambda_s} A_s e^{\lambda_s c t}, \quad \dots \quad (15)$$

$$\phi = -\sum_1^4 (\lambda_s r + 1) \frac{A_s}{r^2} e^{\lambda_s (c t - r + a)} \cos \theta \quad (16)$$

If we start with arbitrary values of ξ and $d\xi/dt$, the medium being previously at rest, this solution presupposes that $t > 0$ and $r < ct + a$. The initial circumstances supply two conditions to be satisfied by the four constants A_s . Thus, assuming that for $t=0$

$$\xi = 0, \quad \frac{d\xi}{dt} = U_0, \quad \dots \quad (17)$$

$$\text{we have} \quad \sum_1^4 \left(\lambda_s a + 2 + \frac{2}{\lambda_s a} \right) A_s = 0, \quad \sum_1^4 (\lambda_s^2 a^2 + 2\lambda_s a + 2) A_s = U_0 a^3 \quad (18)$$

The remaining conditions result from a consideration of the discontinuity at the spherical boundary of the advancing wave. Let δS be an element of this boundary, and through the contour of δS draw normals outwards to meet a parallel surface at a distance $c\delta t$, we thus mark out an element of volume $\delta S \cdot c\delta t$. In time δt the fluid contained in this element has its normal velocity changed from 0 to $-\partial\phi/\partial r$, the normal velocity just within the boundary, by the action of the excess of pressure $c^2\rho_0 s$ on the inner face. Hence

$$-\frac{\partial\phi}{\partial r} \rho_0 \delta S \cdot c\delta t = c^2 \rho_0 s \cdot \delta S \cdot \delta t, \quad (19)$$

or, since $c^2 s = \partial\phi/\partial t$,

$$\frac{\partial\phi}{\partial t} = -c \frac{\partial\phi}{\partial r},$$

which is to be satisfied for $r = ct + a$. Substituting from (16) we find

$$\sum (\lambda_s r + 2) A_s = 0$$

This equation cannot hold generally unless

$$\sum \lambda_s A_s = 0, \quad \sum A_s = 0, \quad \dots \quad (20)$$

which (it will be noticed) at the same time secure the continuity of ϕ , and thence of the velocity-components tangential to the wave-front

The four conditions (18), (20) may now be written

$$\sum \lambda_s^2 A_s = U_0 a, \quad \sum \lambda_s A_s = 0, \quad \sum A_s = 0, \quad \sum \frac{A_s}{\lambda_s} = 0, \quad \dots \quad (21)$$

whence

$$A_1 = \frac{\lambda_1}{(\lambda_1 - \lambda_2)(\lambda_1 - \lambda_3)(\lambda_1 - \lambda_4)} U_0 a, \quad \dots \quad (22)$$

The motion of the air is accordingly given by

$$\left. \begin{aligned} \phi &= \frac{\partial}{\partial r} \sum_1^4 \frac{A_s}{r} e^{\lambda_s (c t - r + a)} \cos \theta & [r < ct + a], \\ \phi &= 0 & [r > ct + a] \end{aligned} \right\} \quad (23)$$

* If we put $\lambda = i k$, $\lambda c = i \sigma$, this becomes identical with the biquadratic referred to in Art. 292.

† The theory of discontinuities at wave-fronts has been treated systematically by Christoffel, "Untersuchungen über die mit dem Fortbestehen linearer partieller Differential-Gleichungen verträglichen Unstetigkeiten," *Ann. di. Matemat.*, t. viii p. 81 (1876); and by Love, "Wave-Motions with Discontinuities at Wave-Fronts," *Proc. Lond. Math. Soc.* (2), t. i p. 37 (1903).

In practice β is a very minute fraction, and the roots of (14) are, to a first approximation,

$$\lambda_1 = \frac{i\sigma_0}{c}, \quad \lambda_2 = -\frac{i\sigma_0}{c}, \quad \lambda_3 = \frac{-1+i}{\alpha}, \quad \lambda_4 = \frac{-1-i}{\alpha}. \quad (24)$$

If the distance travelled by a sound-wave in the period of vibration be a considerable multiple of the circumference of the sphere, λ_1, λ_4 will be large compared with λ_2, λ_3 . Hence, substituting in (22) and (23), we find, for $r < ct + \alpha$,

$$\phi = \frac{\partial}{\partial r} \left\{ \frac{U_0 \alpha^3}{2r} \cos \sigma_0 \left(t - \frac{r-\alpha}{c} \right) - \frac{\sqrt{2} U_0 \alpha^3}{4r} e^{-(ct+\alpha-r)/\alpha} \cos \left(\frac{ct+\alpha-r}{\alpha} - \frac{1}{4}\pi \right) \right\} \cos \theta. \quad (25)$$

The first part of this expression is the same as if the sphere had been executing simple-harmonic vibrations of period $2\pi/\sigma_0$ and amplitude U_0/σ_0 for an indefinite time. The second part is insensible at a distance of several diameters of the sphere from the inner side of the boundary of the advancing wave, but near this boundary it becomes comparable with the first part. To trace the decay of the oscillations, it would be necessary to proceed to a second approximation, but this part of the question has been already dealt with in Arts 290, 292. It will be sufficient to remark that the most important part of the disturbance, well within the advancing wave, will be given by an expression of the form

$$\phi = \frac{C}{r} e^{-m(ct-r)} \cos \sigma_0 \left(t - \frac{r}{c} + \epsilon \right) \cos \theta. \quad (26)$$

The factor e^{-mct} exhibits the decay of the vibration at any place as the original energy of the pendulum is gradually spent in the generation of waves. To account for the factor e^{mr} , we note that within the region occupied by the waves the amplitude at any point Q will (except for spherical divergence) be greater than that at a point P , nearer to the centre on the same radius-vector, in the ratio $e^{m \cdot PQ}$, for the reason that it represents a disturbance which started earlier by an interval PQ/c , during which the vibration of the pendulum has been decaying according to the law e^{-mct} .

Sound-Waves in Two Dimensions

296. When ϕ is independent of z , we have

$$\frac{\partial^2 \phi}{\partial t^2} = c^2 \nabla_1^2 \phi, \quad \dots \dots \dots (1)$$

$$\text{where} \quad \nabla_1^2 = \frac{\partial^2}{\partial x^2} + \frac{\partial^2}{\partial y^2} \quad \dots \dots \dots (2)$$

In the case of symmetry about the origin this becomes

$$\frac{\partial^2 \phi}{\partial t^2} = c^2 \left(\frac{\partial^2 \phi}{\partial r^2} + \frac{1}{r} \frac{\partial \phi}{\partial r} \right), \quad \dots \dots \dots (3)$$

where $r = \sqrt{(x^2 + y^2)}$. The general solution has been obtained in Art 194, in the form

$$2\pi\phi = \int_0^\infty f\left(t - \frac{r}{c} \cosh u\right) du + \int_0^\infty F\left(t + \frac{r}{c} \cosh u\right) du; \quad \dots \dots (4)$$

* Cf a paper "On a Peculiarity of the Wave-System due to the Free Vibrations of a Nucleus in an Extended Medium," *Proc. Lond. Math. Soc.*, t xxxi p. 208 (1900)

and it was further shown that the solution

$$2\pi\phi = \int_0^t f\left(t - \frac{r}{c} \cosh u\right) du \quad \dots\dots\dots (5)$$

represents the system of diverging waves produced by a source $f(t)$ at the origin.

We are now able to give another derivation of these results. It appears from Art. 281 (8) that if a point source $f(t)$ be situate at the point $(0, 0, z)$ its effect at a point in the plane xy at a distance r from the origin is represented by

$$\frac{1}{4\pi\sqrt{(r^2 + z^2)}} f\left(t - \frac{\sqrt{(r^2 + z^2)}}{c}\right) \delta z.$$

If we integrate this with respect to z between the limits $\pm \infty$, we get the effect of a system of point-sources distributed over the axis of z with uniform line-density $f(t)$; thus

$$\phi = \frac{1}{4\pi} \int_{-\infty}^{\infty} f\left(t - \frac{\sqrt{(r^2 + z^2)}}{c}\right) \frac{dz}{\sqrt{(r^2 + z^2)}} = \frac{1}{2\pi} \int_0^t f\left(t - \frac{r}{c} \cosh u\right) du \quad (6)$$

The same method can of course be applied to obtain the second term on (4).

The equations of sound-motion in one, two, or three dimensions, subject to the condition of symmetry, are all included in the form

$$\frac{1}{r^m} \frac{d^2 \phi}{dt^2} = c^2 \left(\frac{1}{r^{m-1}} \frac{d}{dr} \left(r^{m-1} \frac{d\phi}{dr} \right) \right), \quad \dots\dots\dots (7)$$

The complicated and somewhat intractable form in which the solution for the case $m = 2$ has been obtained is in striking contrast to the analytical simplicity and constant formal resemblance of the solutions for the cases $m = 1, m = 3$; but the circumstances must not be allowed to mislead us as to the true physical relations. For the sake of a definite comparison between the three cases, we may examine the effect of a pulse $f(t) = \delta(t - B)$ of a line source, and (C) of a point source, where δ denotes a unit impulse.

$$f(t) = \frac{\delta}{2\pi\sqrt{1 - e^{-2t}}} \quad \dots\dots\dots (8)$$

This gives a convenient representation of a source of a more or less constant strength, since the time during which it is sensible can be made as short as we please by increasing δ , whilst the time integral is unaffected.

The results may be conveniently expressed in terms of the condensation s :

(A) In the case $m = 1$, we find, for $t > 0$,

$$s = \frac{\delta}{2c} \frac{1}{\left(\frac{r - ct}{c}\right)^2 + \tau^2}, \quad \dots\dots\dots (9)$$

(B) When $m = 2$, the analytical work is similar to that of Art. 190, ⁽¹⁾ The result for the most important part of the wave,

$$s = \frac{1}{4\sqrt{2\pi}r^2} \sqrt{\left(\frac{cr}{r}\right)^2 \sin^2 \frac{1}{2}\pi - (\eta/\cos^2 \eta)}, \quad \dots\dots\dots (10)$$


where η is determined by

$$t = \frac{r}{c} + \tau \tan \eta.$$

A

B

C



(C) In three dimensions we have

$$s = \frac{r}{2\pi c^2} \frac{c}{r \left\{ \left(\frac{r}{c} - t \right)^2 + 1 \right\}^{1/2}}. \quad (13)$$

The three cases are represented, with r as ordinate and t as abscissa, in Figs. 195, 196, 197. The scale of t is the same in each case, but there is, of course, no relation between the scales of r . In (A) we have a wave of pure condensation, in (B) the pure wave is followed by a rarefaction of less amount, but lasting for a longer time. Since the condensation and rarefaction are anti-symmetrical, in (B) and (C) the waves must have, at any point,

$$\int_{-\infty}^{+\infty} s dt = 0, \quad (14)$$

cf. Arts. 195, 281. If the source had been strictly limited in duration, the wave, in the case of three dimensions, would have remained absolutely at rest after the passage of the wave, as in the case of one dimension, although for a different reason. In the case of two dimensions, the wave has an indefinitely extended tail, and there is an asymptotic approach to rest.

It appears that from a physical stand point the case $n = 1$, $n = 2$, $n = 3$ forms a sequence with a regular gradation of properties due to the increasing mobility of the medium.

When we abandon the restriction to symmetry, the general solution of (13) is, in polar coordinates,

$$\phi = \Sigma (Q_s r^s \cos s\theta + R_s r^s \sin s\theta), \quad (15)$$

where Q_s , R_s are functions of r and t satisfying

$$\frac{\partial^2 Q_s}{\partial t^2} + c^2 \left\{ \frac{\partial^2 Q_s}{\partial r^2} + \frac{2s+1}{r} \frac{\partial Q_s}{\partial r} \right\} = 0, \quad (16)$$

and the corresponding equation in R_s . The solution of (16) is

$$Q_s = \left(\frac{r}{c} \right)^s \left\{ Q_0 + \dots + \dots \right\}, \quad (17)$$

where

$$Q_0 = \int_0^m f \left(t - \frac{r}{c} \cosh u \right) du + \int_0^t F \left(t + \frac{r}{c} \cosh u \right) du, \quad (18)$$

The proof is similar to that of Art. 295 (5)*.

297. In the case of simple-harmonic motion ($c = 1$), we have, in polar coordinates,

$$\frac{\partial^2 \phi}{\partial r^2} + \frac{1}{r} \frac{\partial \phi}{\partial r} + \frac{1}{r^2} \frac{\partial^2 \phi}{\partial \theta^2} + k^2 \phi = 0, \quad (19)$$

where $k = \sigma/c$. The solution of this equation, subject to the condition of finiteness at the origin is, as in Art. 189,

$$\phi = \Sigma (A_s \cos s\theta + B_s \sin s\theta) J_s(kr), \quad (20)$$

where s may have all integral values from 0 to ∞ .

* This Art. is taken, with slight alterations, from a paper cited on p. 261 *ante*.

From this we derive at once the theorem that the mean value $(\bar{\phi})$ of ϕ , over a circle of radius r described with the origin as centre, is

$$\bar{\phi} = J_0(kr) \phi_0, \quad \dots \dots \dots (3)$$

where ϕ_0 is the value at the origin*. This theorem (which is subject, of course, to the condition above stated), is analogous to that of Art 285 (8), and might have been proved in a similar manner.

In the transverse oscillations of the air contained in a cylindrical vessel of radius a , the normal modes are given by the several terms of (2), where the admissible values of k , and thence of σ , are determined by

$$J_s'(ka) = 0, \quad (4)$$

a being the radius. The interpretation of the results will be understood from Art 189, where the mathematical problem is identical. The figures on pp 271, 272 shew the forms of the lines of equal pressure, to which the motions of the particles are orthogonal, in two of the more important modes†

The Bessel's Functions $J_s(\zeta)$ are subject to the recurrence-formula

$$\frac{d}{d\zeta} \frac{J_s(\zeta)}{\zeta^s} = - \frac{J_{s+1}(\zeta)}{\zeta^s}, \quad \dots \dots \dots (5)$$

which corresponds to Art 287 (17). This easily follows from the series-expression for $J_s(\zeta)$, given in Art 101. From (4), and from the differential equation of $J_s(\zeta)$, viz

$$f''(\zeta) + \frac{1}{\zeta} f'(\zeta) + \left(1 - \frac{s^2}{\zeta^2}\right) f(\zeta) = 0, \quad \dots \dots \dots (6)$$

various other recurrence-formulae may be derived, e.g

$$\zeta J_s'(\zeta) + s J_s(\zeta) = \zeta J_{s-1}(\zeta), \quad \dots \dots \dots (7)$$

corresponding to Art. 287 (18)

By successive applications of (5) we obtain

$$J_s(\zeta) = \zeta^s \left(- \frac{d}{\zeta d\zeta} \right)^s J_0(\zeta). \quad \dots \dots \dots (8)$$

It is easily verified, by the method of 'mathematical induction,' that the expression on the right-hand of (8) is in fact a solution of the differential equation (6) provided $J_0(\zeta)$ is a solution of the same equation with s put = 0. This suggests a convenient choice, for our purposes, of the Bessel's Functions 'of the second kind.' We write

$$D_s(\zeta) = \zeta^s \left(- \frac{d}{\zeta d\zeta} \right)^s D_0(\zeta), \quad \dots \dots \dots (9)$$

where $D_0(\zeta)$ is the function introduced in Art. 192†, viz.

$$D_0(\zeta) = \frac{2}{\pi} \int_0^\infty e^{-i\zeta \cosh u} du \quad \dots \dots \dots (10)$$

* H Weber, *Math Ann.*, t 1 (1868)

† The problem is fully discussed by Lord Rayleigh, *Theory of Sound*, Art. 339

‡ It may be shewn, by the method of Art. 296, that $D_0(kr)$ is the potential of a uniform

It is evident without further proof that $D_s(\xi)$ will satisfy the differential equation (6), and have the same system of recurrence formulae as $J_s(\xi)$. As an important special case of (9), we have

$$D_1(\xi) = D_1'(\xi), \quad \dots \dots \dots (11)$$

The following approximations are useful. When ξ is small we have, by Arts. 100, 192,

$$J_0(\xi) = 1 - \frac{\xi^2}{4} + \dots, \quad D_0(\xi) = \frac{2}{\pi} (\log \frac{1}{2}\xi + \gamma + \frac{1}{2}i\pi + \dots), \quad (12)$$

and thence, by (8) and (9), for $s > 0$,

$$J_s(\xi) = \frac{\xi^s}{2^s s!} + \dots, \quad D_s(\xi) = \frac{2^{s+1}(-1)^s}{\pi \xi^s} + \dots \quad (13)$$

Again, for large values of ξ ,

$$J_s(\xi) = \left(\frac{2}{\pi\xi}\right)^{\frac{1}{2}} \sin\left(\xi - \frac{1}{4}\pi - \frac{1}{2}s\pi\right) + \dots, \quad D_s(\xi) = \left(\frac{2}{\pi\xi}\right)^{\frac{1}{2}} i^s e^{i(\xi - \frac{1}{4}\pi - \frac{1}{2}s\pi)}, \quad (14)$$

The formulae may be used to investigate the communication of vibrations to an oscillating cylinder (e.g. a piano string) to the surrounding air. The radial velocity at the surface of the cylinder being

$$U = a e^{i\omega t}, \quad \dots \dots \dots (15)$$

the radial velocity at the surface $r = a$ will be

$$= \frac{i\phi}{r^2} e^{i\omega t} \cos \theta, \quad \dots \dots \dots (16)$$

The corresponding value of ϕ is

$$\phi = iAD_1(ka) \cos \theta e^{i\omega t}, \quad \dots \dots \dots (17)$$

with the condition

$$-kD_1'(ka)A = a, \quad \dots \dots \dots (18)$$

If, as we will suppose, the circumference of the cylinder is very small compared with the wave-length of the sound, ka will be a small fraction, and we find from (18)

$$A = \frac{1}{2}\pi ka^2 a.$$

Hence at distances r which are large compared with k^{-1} , we have, by (17),

$$\phi = \sqrt{\left(\frac{1}{2}\pi\right)} \cdot \frac{ik^{\frac{1}{2}}a^2}{r^{\frac{1}{2}}} a \cos \theta e^{i\omega t - \frac{1}{2}kr} e^{i\pi/4}, \quad \dots \dots \dots (19)$$

If the velocity at the boundary $r = a$ had been everywhere equal, with the amplitude a , the value of ϕ at a distance would have been

$$\phi = \sqrt{\left(\frac{1}{2}\pi\right)} \cdot \frac{a}{k^{\frac{1}{2}}r^{\frac{1}{2}}} e^{i\omega t - \frac{1}{2}kr} e^{i\pi/4}, \quad \dots \dots \dots (20)$$

In the actual case the intensity, as measured by the square of the amplitude, is less in the ratio k^2a^2 , which is by hypothesis very small. This illustrates the effect of lateral diffusion near the surface of the cylinder, in reducing the amplitude of the waves propagated to a distance; cf. Art. 289. For example, by far the greater part of the sound due to a piano string comes, not directly from the wire, but from the sounding board, which is set into forced vibration by the alternating pressures at the supports.

distribution of simple harmonic point-sources along the axis of . . . See Lord Rayleigh, "On Point-, Line-, and Plane-Sources of Sound," *Proc. Lond. Math. Soc.*, t. xix, p. 504 (1890), [*Sc. Papers*, t. iii, p. 44; *Theory of Sound*, Art. 342].

The reaction of the air on the vibrating cylinder is

$$\int_0^{2\pi} e^{i\cos\theta} d\theta = 2\pi \quad \rho_0 c \int_0^{2\pi} \frac{\partial \phi}{\partial t} \cos \theta = -\pi \rho_0 c \cdot i \sigma A D_1(ka) e^{i\sigma t} \\ \pi \rho_0 c^2 \cdot \frac{D_1(ka)}{ka D_1'(ka)} \frac{dU}{dt}, \quad \dots \dots \dots (21)$$

297 298 — When J is small, this reduces to

$$\pi \rho_0 c^2 \cdot \frac{dU}{dt}, \quad \dots \dots \dots (22)$$

approximately. The most important part of the effect is that the inertia of the cylinder is increased by an amount equal to that of the air displaced; cf. Art. 68*.

298. We may also investigate the scattering of a system of plane waves by a fixed cylindrical obstacle whose axis is parallel to the wave-fronts.

Assuming, for the potential of the incident waves,

$$\phi = e^{ikr}, \quad \dots \dots \dots (1)$$

as in Art. 291, we require in the first place to expand this in a series of the type (2) of Art. 297. The requisite formula is

$$e^{ikr} = J_0(kr) + 2iJ_1(kr) \cos \theta + \dots + 2i^n J_n(kr) \cos n\theta + \dots \quad \dots (2)$$

This may be proved directly†, by expanding $e^{ikr \cos \theta}$, making use of the formula

$$\cos^n \theta = \frac{1}{2^n} \left\{ \cos n\theta + \frac{n}{1} \cos(n-2)\theta + \frac{n(n-1)}{1 \cdot 2} \cos(n-4)\theta + \dots \right\}, \\ \dots \dots \dots (3)$$

and picking out the coefficient of $\cos s\theta$ in the result.

The expansion (2) involves the equality

$$\frac{1}{\pi} \int_0^{2\pi} e^{ikr \cos \theta} \cos s\theta d\theta = i^n J_n(kr), \quad \dots \dots \dots (4)$$

which is a known formula in Bessel's Functions‡. Conversely, if we assume this, as otherwise established, we have another proof of (2).

The scattered waves being represented by

$$q' = B_n D_n(kr) \cos s\theta, \quad \dots \dots \dots (5)$$

$$\text{the surface condition} \quad \frac{\partial}{\partial r} (\phi + q') = 0 \quad [r = a] \quad \dots \dots \dots (6)$$

* A fuller investigation is given by Stokes, *loc. ante* p. 483.

† Heine, *Kugelfunctionen*, t. i. p. 82.

‡ Gray and Mathews, p. 18; Whittaker, *Modern Analysis*, Art. 153. The case $s=0$ has already been met with in Art. 100; it may be interpreted as shewing how the potential $J_0(kr)$ can be obtained by superposition of systems of plane waves travelling in directions uniformly distributed about the origin in the plane xy ; cf. Art. 285 (7).

gives
$$B_s = -\frac{2\nu^s J_s'(ka)}{D_s'(ka)}, \quad . \quad . \quad . \quad (7)$$

except in the case $s=0$, when the factor 2 is to be omitted

If ka be small, we have, approximately,

$$J_0'(ka) = -\frac{1}{2}ka, \quad D_0'(ka) = -\frac{2}{\pi ka}, \quad . \quad . \quad . \quad (8)$$

and, for $s > 0$,
$$J_s'(ka) = \frac{(ka)^{s-1}}{2^s(s-1)!}, \quad D_s'(ka) = -\frac{2^s s!}{\pi (ka)^{s+1}} \quad (9)$$

Hence
$$B_0 = -\frac{1}{4}\pi k^2 a^2, \quad B_s = \frac{\pi \nu^s (ka)^{2s}}{2^{2s-1} s! (s-1)!} \quad [s > 0] \quad . \quad . \quad . \quad (10)$$

The most important terms correspond to $s=0$, $s=1$. Neglecting the rest, we have, for the scattered waves,

$$\phi = -\frac{1}{4}\pi k^2 a^2 \{D_0(kr) - 2\nu D_1(kr) \cos \theta\} \quad . \quad . \quad . \quad (11)$$

For large values of kr this becomes, on restoring the time-factor,

$$\phi = -\frac{1}{2}\sqrt{\frac{1}{2}\pi} \frac{k^{\frac{3}{2}} a^2}{r^{\frac{1}{2}}} (1 + 2 \cos \theta) e^{i(\sigma t - kr - \frac{1}{4}\pi)} \quad . \quad . \quad . \quad (12)^*$$

The rate (per unit length of the cylinder) at which energy is carried outwards by the scattered waves is

$$-\int_0^\pi p \frac{\partial \phi}{\partial r} \nu d\theta = -\rho_0 r \int_0^{2\pi} \frac{\partial \phi}{\partial t} \frac{\partial \phi}{\partial r} d\theta,$$

where r may conveniently be taken very great. If we substitute the real part of ϕ from (12), the mean value is found to be

$$\frac{3}{8}\pi^2 \rho_0 \sigma (ka)^4 \quad . \quad . \quad . \quad . \quad . \quad (13)$$

The energy-flux in the primary waves is, as in Art. 291, $\frac{1}{2}\rho_0 k^2 c$. The ratio of (13) to this is (since $\sigma = kc$)

$$\frac{3}{8}\pi^2 (ka)^3 \quad 2a \quad . \quad . \quad . \quad . \quad . \quad (14)$$

Thus a wire $\frac{1}{16}$ of an inch in diameter scatters only 6.63×10^{-5} of the incident energy, when the wave-length is four feet.

299. The approximate methods of Arts. 293, 294 can be applied to the corresponding problems in two dimensions†. The formula (5) of Art. 286 is now replaced by

$$\phi_P = -\frac{1}{4} \int D_0(kr) \frac{\partial \phi}{\partial n} ds + \frac{1}{4} \int \phi \frac{\partial}{\partial n} D_0(kr) ds, \quad . \quad . \quad . \quad (1)$$

which is established in a manner analogous to that indicated on p. 475. In the case of a region extending to infinity the line-integrals can be restricted to the internal boundary, provided that at a great distance R from the origin ϕ is comparable with $e^{-\nu k R}/R$.

In the same way we have

$$0 = -\frac{1}{4} \int D_0(kr') \frac{\partial \phi}{\partial n} ds + \frac{1}{4} \int \phi \frac{\partial}{\partial n} D_0(kr') ds, \quad . \quad . \quad . \quad (2)$$

where r' denotes distance from a point P' external to the region considered

* Cf. Lord Rayleigh, *Theory of Sound*, Art. 343.

† Lord Rayleigh, *ll. cc. ante* pp. 491, 493.

Within a region whose dimensions in the plane xy are small compared with the wave-length kr will be small, and the formula (1) reduces to

$$\phi_P = \frac{1}{2\pi} \int \log r \frac{\partial \phi}{\partial n} ds - \frac{1}{2\pi} \int \phi \frac{\partial}{\partial n} \log r ds, \dots \dots \dots (3)$$

where a constant term has been omitted. This satisfies the equation

$$\nabla_1^2 \phi = 0 \quad \dots \dots \dots (4)$$

appropriate to the case of an incompressible fluid

1° Taking first the direct impact of waves on a plane lamina, we write

$$\phi = e^{ikx} + \chi, \quad \dots \dots \dots (5)$$

where χ is the potential of the scattered waves. If the lamina be supposed to occupy that portion of the plane $x=0$ which lies between the lines $y = \pm b$, the condition to be satisfied by χ is

$$\frac{\partial \chi}{\partial x} = -ik, \quad [x=0, \quad b > y > -b] \quad \dots \dots \dots (6)$$

The formula (1) gives
$$\chi_P = \frac{1}{2} \int_{-b}^b \chi \frac{\partial}{\partial n} D_0(kr) dy, \quad \dots \dots \dots (7)$$

where the values of χ and $\partial D_0 / \partial n$ on the positive face of the lamina are to be understood. If x, y refer to the position of P we may write $\partial / \partial n = -\partial / \partial x$, and at a distance r from the origin, large compared with $2b$, we have

$$\chi_P = -\frac{1}{2} \int_{-b}^b \chi dy \cdot \frac{\partial}{\partial x} D_0(kr). \quad \dots \dots \dots (8)$$

The definite integral is one-half the 'impulse' of the lamina (per unit length) when moving broadside-on with velocity ik in an incompressible fluid of unit density, hence by Art. 71 (11)

$$\int_{-b}^b \chi dy = \frac{1}{2} ik \pi b^2, \quad \dots \dots \dots (9)$$

and therefore
$$\chi_P = -\frac{1}{4} i \pi k b^2 \frac{\partial}{\partial x} D_0(kr) = \frac{1}{4} i \pi k^2 b^2 D_1(kr) \cos \theta. \quad \dots \dots \dots (10)$$

When kr is large this reduces to

$$\chi_P = -\frac{1}{2} \frac{\pi^{\frac{1}{2}} k^{\frac{1}{2}} b^2}{\sqrt{2}} e^{-i(kr + \frac{1}{4}\pi)} \cos \theta, \quad \dots \dots \dots (11)$$

by Art. 297 (14)

The ratio of the energy scattered per second to the energy-flux in the primary waves is easily found to be

$$\frac{1}{16} \pi^2 (kb)^3 \cdot 2b, \quad \dots \dots \dots (12)$$

which is exactly one-sixth of the corresponding ratio in the case of a circular cylinder of radius b (Art. 298 (14))

2°. In the case of an aperture bounded by parallel straight edges ($y = \pm b$) in a plane screen ($x=0$), we assume as in Art. 293, 2°

$$\phi = e^{ikx} + e^{-ikx} + \chi, \quad \text{and} \quad \phi = \chi', \quad \dots \dots \dots (13)$$

for the two sides respectively, and seek to determine χ, χ' so that

$$\chi = -1, \quad \chi' = +1 \quad \dots \dots \dots (14)$$

over the aperture, whilst $\frac{\partial \chi}{\partial x} = 0$, $\frac{\partial \chi'}{\partial x} = 0$ (15)

over the screen. Now if we apply (1) and (2) to the part of the plane lying to the right of the axis of y , and if we further take P' at the image of P , we have by addition

$$\chi_P = -\frac{1}{2} \int_{-b}^b D_0(kr) \frac{\partial \chi}{\partial n} dy, \text{ (16)}$$

where δn is drawn from the positive face. At distances r from the origin which are large compared with $2b$, this becomes

$$\chi_P = -\frac{1}{2} \int_{-b}^b \frac{\partial \chi}{\partial n} dy \cdot D_0(kr). \text{ (17)}$$

In the immediate neighbourhood of the aperture the motion represented by the functions χ , χ' must resemble the flow of a liquid through the same aperture, and an approximate value of the definite integral in (17) is accordingly obtained by comparison with the results of Art 66, 1°. It appears that corresponding to a flux unity through the aperture the increment of χ in passing from the aperture itself to a distance r which is large compared with $2b$ is

$$\frac{1}{\pi} \log \frac{2r}{b}.$$

We may still suppose r to be small compared with the wave-length, and the formulæ (14) and (17) then shew that the corresponding increment of χ in the actual problem is

$$1 + \frac{1}{\pi} \int_{-b}^b \frac{\partial \chi}{\partial n} dy (\log \frac{1}{2} kr + \gamma + \frac{1}{2} i\pi), \text{ (18)}$$

by Art 297 (12). Equating this to

$$\frac{1}{\pi} \int_{-b}^b \frac{\partial \chi}{\partial n} dy \cdot \log \frac{2r}{b}, \text{ (19)}$$

we find

$$\int_{-b}^b \frac{\partial \chi}{\partial n} dy = -\frac{\pi}{\log \frac{1}{4} kb + \gamma + \frac{1}{2} i\pi}. \text{ (20)}$$

Hence when kr is large, we have from (17)

$$\chi_P = \log \frac{1}{4} kb + \gamma + \frac{1}{2} i\pi \cdot D_0(kr) = \log \frac{1}{4} kb + \gamma + \frac{1}{2} i\pi \left(\frac{\pi}{2kr} \right)^{\frac{1}{2}} e^{-i(kr + \frac{1}{2}\pi)}. \text{ (21)}$$

The value of χ' at any point P on the negative side of the plane $x=0$ is equal and opposite to the value of χ at the image of P with respect to the plane.

The ratio of the energy transmitted through the aperture to the energy-flux in the primary waves is found to be

$$kb \{ (\log \frac{1}{4} kb + \gamma)^2 + \frac{1}{4} \pi^2 \} \cdot 2b. \text{ (22)}$$

If the wave-length be 10, or 100, or 1000 times the breadth of the aperture, the factor of $2b$ comes out equal to 1.240, or 3.795, or 17.20, respectively.

3°. The two-dimensional problem of the diffraction of plane waves by a cylindrical obstacle of any form of cross-section can be treated by the method of Art. 294*, the formula (1) above taking the place of Art 286 (5). As no new point arises, it will be

* Cf. Lord Rayleigh, *l.c. ante* p. 493.

sufficient to state the chief result. The waves are supposed to be incident from the direction $(\lambda, \mu, 0)$, and we write, accordingly,

$$\phi = e^{ik(\lambda x + \mu y)} + \chi, \quad (23)$$

where χ is to represent the scattered waves. We assume also that the axes of x, y have special directions in the plane of the cross-section, such that the kinetic energy (per unit length parallel to z) of an incompressible fluid of unit density, when the cylinder moves through it with velocity $(u, v, 0)$, would be given by an expression of the form

$$\frac{1}{2} (\mathbf{A}u^2 + \mathbf{B}v^2), \quad (24)$$

the term in uv being absent. The dimensions of the section being supposed small compared with the wave-length, the waves scattered in the direction $(\lambda_1, \mu_1, 0)$ are given by

$$\chi_P = -\frac{k^2 S}{(8\pi k r)^{\frac{1}{2}}} e^{-i(kr + \frac{1}{2}\pi)} - \frac{\lambda^2}{(8\pi k r)^{\frac{1}{2}}} \{(\mathbf{A} + S)\lambda\lambda_1 + (\mathbf{B} + S)\mu\mu_1\} e^{-i(kr + \frac{1}{2}\pi)}, \quad (25)$$

where S is the area of the cross-section.

For an elliptic section whose semi-axes in the directions of x, y are a, b , we have (see Art. 71 (11))

$$S = \pi ab, \quad \mathbf{A} = \pi b^2, \quad \mathbf{B} = \pi a^2. \quad (26)$$

In the cases of a circular cylinder ($a=b$), and of a flat lamina ($a=0$), we reproduce results already obtained.

300 We may also investigate the disturbance produced in a train of plane waves by a thin screen which is interrupted by a series of parallel, equal, and equidistant slits. As before, the treatment is approximate, and involves the assumption that the wave-length is large compared with the distance between the centres of successive apertures.

As a subsidiary question, we require to determine the flow of an incompressible fluid through a fixed rigid grating of the above kind. This can be solved by Schwarz' method (Art. 73), but for the present purpose it will be sufficient to state, and verify, the result. The axis of x being taken normal to the plane of the grating, and that of y in this plane, at right angles to the lengths of the apertures, we write

$$\cosh w = \mu \cosh z, \quad \dots \quad (1)$$


where, for the moment,

$$w = \phi + i\psi, \quad z = x + iy, \quad \dots \quad (2)$$

and the constant μ is supposed greater than unity. This makes w a cyclic function, but we avoid all indeterminateness if in the first instance we confine ourselves to that half of the plane xy for which $x > 0$, and if further we fix the value of w at any one point. We will assume that at the origin $\psi = 0$, whilst ϕ is equal to the real positive value of $\cosh^{-1} \mu$.

The formula (1) gives

$$\cosh \phi \cos \psi = \mu \cosh x \cos y, \quad \sinh \phi \sin \psi = \mu \sinh x \sin y. \quad (3)$$



The locus $\phi = 0$ consists of those portions of the axis of y for which

$$1 > \mu \cos y > -1,$$

these represent the apertures, so that on the scale of our formulae the half-breadth of an aperture is $\sin^{-1}(1/\mu)$. For other portions of the region $x > 0$, ϕ will be positive. Again, the lines $\psi = 0$, $\psi = \pm \pi$, $\psi = \pm 2\pi$, .. will consist partly of the lines $y = 0$, $y = \pm \pi$, $y = \pm 2\pi$, .., respectively, and partly of those portions of the axis of y for which

$$|\mu \cos y| > 1,$$

these correspond to the parts of the screen between the apertures

The curves $\phi = \text{const.}$, $\psi = \text{const.}$ are traced, for a particular case, on the opposite page, the value of μ adopted for convenience of calculation being

$$\mu = \cosh \frac{1}{6}\pi = 1.2040,$$

whence $\sin^{-1} \frac{1}{\mu} = .312\pi$, $\cos^{-1} \frac{1}{\mu} = 188\pi$

The latter numbers give the relative breadths of the apertures and of the intervening portions of the screen

The formulae (3), and the diagram*, admit of a variety of interpretations in Electrostatics and other mathematically cognate subjects. In the present application we must suppose that, at two points symmetrically situated on opposite sides of the axis of y , the values of ψ are identical, whilst those of ϕ are equal in magnitude but of opposite signs

It appears from (3), or by inspection of the figure, that the function ϕ in (3) is a periodic even function of y , the period being π . It can therefore be expanded by Fourier's Theorem in a series of cosines of multiples of $2y$, the coefficients being functions of x whose general form is to be determined by substitution in the equation

$$\nabla^2 \phi = 0. \quad \dots \quad (4)$$

Thus, for x positive we find, having regard to the condition to be satisfied for large values of x ,

$$\phi = \log \mu + x + \sum_1^{\infty} C'_s e^{-2sx} \cos 2sy \quad \dots \quad (5)^\dagger$$

* Taken from a paper cited on p. 516 below. A formula equivalent to (1) was given by Lamour in the *Mathematique Tripos*, Part II, 1895.

† The precise values of the coefficients C'_s are not required for our purpose. It may be shewn that

$$C'_s = \left(\frac{1}{s} \right)^{s-1} F\left(s, -s, 1, \frac{1}{\mu^2}\right) = \frac{(-1)^{s-1}}{s} \left(1 - \frac{1}{\mu^2}\right) F\left(1+s, 1-s, 1, \frac{1}{\mu^2}\right),$$

in the hypergeometric notation. See the paper cited

If we introduce a more general linear unit, and denote the breadth of each aperture by a , and that of each intervening strip by b , we may write

$$\cosh \phi \cos \psi = \mu \cosh \frac{\pi x}{a+b} \cos \frac{\pi y}{a+b}, \quad \sinh \phi \sin \psi = \mu \sinh \frac{\pi x}{a+b} \sin \frac{\pi y}{a+b}, \quad \dots \quad (6)$$

where
$$\mu = \sec \frac{\pi b}{2(a+b)} = \operatorname{cosec} \frac{\pi a}{2(a+b)}. \quad \dots \quad (7)$$

The expansion (5) is now replaced by

$$\phi = \log \mu + \frac{\pi x}{a+b} + \sum_i C_s e^{-\kappa_s x} \cos \frac{2s\pi y}{a+b}, \quad \dots \quad (8)$$

where
$$\kappa_s = \frac{2s\pi}{a+b}. \quad \dots \quad (9)$$

We turn now to the acoustical problem. Corresponding to a train of incident waves whose potential is e^{ikx} , we assume*

$$\Phi = e^{ikx} + e^{-ikx} + \chi, \quad \text{or} \quad \Phi = \chi', \quad \dots \quad (10)$$

according as $x \gtrless 0$. As in Arts 293, 2°, and 299, 2°, we must have

$$\chi = -1, \quad \chi' = +1, \quad \dots \quad (11)$$

over the apertures, and
$$\frac{\partial \chi}{\partial x} = 0, \quad \frac{\partial \chi'}{\partial x} = 0, \quad \dots \quad (12)$$

over the rest of the plane $x = 0$. Since χ must satisfy

$$(\nabla^2 + k^2) \chi = 0, \quad \dots \quad (13)$$

and must further be periodic with respect to y , with the period $a+b$, it must admit of being expanded in a Fourier's series of the form

$$\chi = B_0 e^{-ikx} + \sum_1^\infty B_s e^{-\lambda_s x} \cos \frac{2s\pi y}{a+b}, \quad (14)$$

provided

$$\lambda_s^2 = \frac{4s^2\pi^2}{(a+b)^2} - k^2 \quad (15)$$

Since, by hypothesis, $a+b$ is small compared with the wave-length $2\pi/k$, the right-hand side of (15) is positive. Hence the quantities λ_s are real, and, moreover, differ respectively very little from κ_s . Terms involving $e^{\lambda_s x}$ are excluded by the condition of finiteness for $x = \infty$, so that the waves represented by χ are ultimately plane. The fact that they must travel outwards from the grating justifies the omission of the term in e^{ikx} .

If k were zero, the conditions determining χ would be the same as if the fluid were incompressible, and we should have

$$\chi = -1 + C\phi, \quad \dots \quad (16)$$

* The symbol Φ is here used for the acoustic velocity-potential, as ϕ at present bears a special meaning.

where ϕ is the function determined (in the manner above explained) by (6), and C is some constant, and we may anticipate that the same expression will hold approximately in the actual case for the immediate neighbourhood of the grating. Again, for small values of kx , the expansion (14) takes the form

$$\chi = B_0(1 - ikx) + \sum_1^{\infty} B_s e^{-\kappa_s x} \cos \frac{2s\pi y}{a+b}, \quad \dots \dots (17)$$

where the substitution of κ_s for λ_s in the exponential involves an error of the order $k^2(a+b)^2/4\pi^2$. Hence, substituting from (8) in (16), we find that (16) and (17) are in fact identical, provided

$$B_0 = -1 + C \log \mu, -ikB_0 = \frac{\pi C}{a+b}, \quad (18)$$

$$\text{and, for } s > 0, \quad B_s = CC_s \quad \dots \dots (19)$$

$$\text{Hence} \quad B_0 = -\frac{1}{1 + ikl}, \quad \dots \dots (20)$$

$$\text{where} \quad l = \frac{a+b}{\pi} \log \sec \frac{\pi b}{2(a+b)}. \quad \dots \dots (21)$$

As regards χ' , all the conditions are satisfied if we suppose that its value at any point P' on the negative side of the grating is equal in absolute magnitude, but opposite in sign, to that of χ at the image P of P' on the positive side. Hence

$$\chi' = -B_0 e^{ikx} - \sum_1^{\infty} B_s e^{\lambda_s x} \cos \frac{2s\pi y}{a+b} \quad \dots \dots (22)$$

At a distance of several wave-lengths from the grating the last terms in (14) and (22) may be neglected, and the waves are sensibly plane. On reference to (10) we see that the coefficients of the reflected and transmitted waves are $1 + B_0$ and $-B_0$, or

$$\frac{ikl}{1 + ikl} \quad \text{and} \quad \frac{1}{1 + ikl}, \quad (23)$$

respectively, that of the primary waves being taken as unit. Hence the intensities I, I' of these waves are given by

$$I = \frac{k^2 l^2}{1 + k^2 l^2}, \quad I' = \frac{1}{1 + k^2 l^2} \quad \dots \dots (24)$$

For sufficiently great wave-lengths there is very little reflection, even when the apertures occupy only a small fraction of the area of the screen. As corresponding numerical values we have

$$\frac{a}{a+b} = 0, \quad .1, \quad .2, \quad .3, \quad .4, \quad .5, \quad .6, \quad .7, \quad .8, \quad .9, \quad 1.0,$$

$$\frac{l}{a+b} = \infty, \quad .590, \quad .374, \quad .251, \quad .169, \quad .110, \quad .067, \quad .037, \quad .016, \quad .004, \quad 0.$$

Let us suppose, for example, that the wave-length is ten times the interval $a + b$, and that the apertures occupy one-tenth of the area of the grating. It will be found that the reflected and transmitted intensities are

$$I = \cdot 121, \quad I' = \cdot 879,$$

respectively. Notwithstanding the comparative narrowness of the openings, 88 per cent of the sound gets through.

301. A similar method applies to the case of a grating composed of parallel equidistant wires.

We note in the first place that the potential and stream functions of an incompressible fluid, due to a system of equal and equidistant line sources cutting the plane xy perpendicularly at the points $(0, 0)$, $(0, \pm a)$, $(0, \pm 2a)$, ..., are given (Art. 61) by the formula

$$w \propto \log z + \log(z - ia) + \log(z + ia) + \log(z - 2ia) + \log(z + 2ia) + \dots, \quad (1)$$

where

$$w = \phi + i\psi, \quad z = x + iy, \quad (2)$$

or, say,

$$w = \log \sinh \frac{\pi z}{a}. \quad (3)$$

This makes

$$\phi = \frac{1}{2} \log \frac{1}{2} \left(\cosh \frac{2\pi x}{a} - \cos \frac{2\pi y}{a} \right), \quad \psi = \tan^{-1} \left\{ \frac{\tanh \frac{\pi y}{a}}{\tanh \frac{\pi x}{a}} \right\}, \quad (4)$$

in agreement with a result given by Maxwell*.

The case of a row of *double* sources having their axes parallel to x is obtained by differentiating (3) with respect to z ; we thus find

$$w = \frac{\pi}{a} \coth \frac{\pi z}{a}, \quad (5)$$

whence

$$\phi = \frac{\pi}{a} \frac{\sinh \frac{2\pi x}{a}}{\cosh \frac{2\pi x}{a} - \cos \frac{2\pi y}{a}}, \quad \psi = \frac{\pi}{a} \frac{\sin \frac{2\pi y}{a}}{\cosh \frac{2\pi x}{a} - \cos \frac{2\pi y}{a}}, \quad (6)$$

These results enable us to solve very simply a number of problems in Hydrodynamics, Magnetic Induction, and so on. In particular, the potential and stream functions for a liquid flowing through a grating of parallel cylindrical bars of radius b are given by

$$w = z + \frac{\pi b^2}{a} \coth \frac{\pi z}{a}, \quad (7)$$

or

$$\phi = x + \frac{\pi b^2}{a} \frac{\sinh \frac{2\pi x}{a}}{\cosh \frac{2\pi x}{a} - \cos \frac{2\pi y}{a}}, \quad \psi = y - \frac{\pi b^2}{a} \frac{\sin \frac{2\pi y}{a}}{\cosh \frac{2\pi x}{a} - \cos \frac{2\pi y}{a}}, \quad (8)$$

* *Electricity and Magnetism*, Art. 203.

if the velocity at infinity is unity, in the direction of x negative. This follows from the periodicity with respect to y , and from the fact that for small values of x, y we have

$$\psi = y \left(1 - \frac{b^2}{x^2 + y^2} \right), \quad . \quad . \quad . \quad . \quad (9)$$

approximately. It is assumed that the radius b of a bar is small compared with the distance a between the axes of consecutive bars.

If the real part of z be positive, we have from (7)

$$w = z + \frac{\pi b^2}{a} \left(1 + 2 \sum_1^\infty e^{-\frac{2s\pi z}{a}} \right), \quad . \quad . \quad . \quad . \quad (10)$$

whence

$$\phi = x + \frac{\pi b^2}{a} \left(1 + 2 \sum_1^\infty e^{-\frac{2s\pi x}{a}} \cos \frac{2s\pi y}{a} \right) \quad (11)$$

Similarly if x be negative, we find

$$\phi = x - \frac{\pi b^2}{a} \left(1 + 2 \sum_1^\infty e^{\frac{2s\pi x}{a}} \cos \frac{2s\pi y}{a} \right). \quad . \quad . \quad . \quad (12)$$

In the acoustical problem the velocity-potential will be of the form

$$\Phi = e^{ikx} + A e^{-ikx} + \sum_1^\infty C_s e^{-\lambda_s x} \cos \frac{2s\pi y}{a}, \quad . \quad . \quad (13)$$

or

$$\Phi = B e^{ikx} - \sum_1^\infty C_s e^{-\lambda_s x} \cos \frac{2s\pi y}{a}, \quad . \quad . \quad . \quad (14)$$

according as $x \gtrless 0$, where λ_s is the positive quantity defined by

$$\lambda_s^2 = \frac{4s^2\pi^2}{a^2} - k^2 \quad . \quad . \quad . \quad . \quad (15)$$

For values of x which are small compared with the wave-length we may ignore the difference between λ_s and $2s\pi/a$, provided the wave-length be large compared with a . Under these circumstances the formulae (13), (14) reduce to

$$\Phi = 1 + A + ik(1-A)x + \sum_1^\infty C_s e^{-\frac{2s\pi x}{a}} \cos \frac{2s\pi y}{a}, \quad . \quad . \quad (16)$$

and

$$\Phi = B + ikBx - \sum_1^\infty C_s e^{\frac{2s\pi x}{a}} \cos \frac{2s\pi y}{a}, \quad . \quad . \quad . \quad (17)$$

respectively. The function Φ accordingly assumes the form

$$\Phi = \alpha\phi + \beta, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (18)$$

where ϕ is determined by (11) and (12), and α, β are constants, provided

$$1 + A = \alpha \frac{\pi b^2}{a} + \beta, \quad B = -\alpha \frac{\pi b^2}{a} + \beta, \quad ik(1-A) = \alpha, \quad ikB = \alpha, \quad C_s = 2\alpha \frac{\pi b^2}{a}. \quad (19)$$

These make

$$A = \frac{ikl}{1+ikl}, \quad B = \frac{1}{1+ikl}, \quad . \quad . \quad . \quad . \quad (20)$$

where

$$l = \frac{\pi b^2}{a} \quad . \quad . \quad . \quad . \quad (21)$$

The intensities of the reflected and transmitted waves are therefore

$$I = \frac{k^2 l^2}{1+k^2 l^2}, \quad I' = \frac{1}{1+k^2 l^2} \quad . \quad . \quad . \quad . \quad (22)$$

If the half-wave-length be large compared with b^2/a , we have free transmission, with hardly any reflection. This further illustrates the "extreme smallness of the obstruction offered by fine wires or fibres to the passage of sound*."

The diffraction of plane waves of sound by the straight edge of a 'semi-infinite' plane screen, and the formation of a sound-shadow, have been investigated by Sommerfeld†, and (with some extensions) by Carslaw‡. The data here involve no special linear magnitude except the wave-length, and the general character of the results is accordingly independent of the latter

Atmospheric Waves.

302 The theory of such questions as the large-scale oscillations of the earth's atmosphere, where the equilibrium-density cannot be taken to be uniform, is still very imperfect. One special difficulty is that of taking into account the physical conditions which are imposed in the upper regions of the atmosphere. It will be seen that the formulae indicate in certain cases an indefinite increase of amplitude with height. This not only tends to violate the restriction to 'infinitely small' motions, it also indicates that in neglecting viscosity, whose retarding effect varies inversely as the density, and therefore increases continually upwards, we are ignoring an important factor in the phenomena.

Let us suppose that we have a gas in equilibrium under certain constant forces having a potential Ω , and let us denote by ρ_0 and p_0 the values of ρ and p in this state, these quantities being in general functions of the co-ordinates x, y, z . We have, then,

$$dp_0 = -\rho_0 d\Omega \quad \dots \quad (1)$$

The equations of small motion, under the influence (it may be) of disturbing forces having a potential Ω' , may therefore be written

$$\left. \begin{aligned} \rho_0 \frac{\partial u}{\partial t} &= -\frac{\partial p}{\partial x} + \frac{\rho}{\rho_0} \frac{\partial p_0}{\partial x} - \rho_0 \frac{\partial \Omega'}{\partial x}, \\ \rho_0 \frac{\partial v}{\partial t} &= -\frac{\partial p}{\partial y} + \frac{\rho}{\rho_0} \frac{\partial p_0}{\partial y} - \rho_0 \frac{\partial \Omega'}{\partial y}, \\ \rho_0 \frac{\partial w}{\partial t} &= -\frac{\partial p}{\partial z} + \frac{\rho}{\rho_0} \frac{\partial p_0}{\partial z} - \rho_0 \frac{\partial \Omega'}{\partial z}. \end{aligned} \right\} \quad \dots \quad (2)$$

* Lord Rayleigh, *Theory of Sound*, t. II Art. 343.

The investigations of Arts. 300, 301 are adapted from a paper "On the Reflection and Transmission of Electric Waves by a Metallic Grating," *Proc. Lond. Math. Soc.*, t. XXIX p. 523 (1898).

† "Mathematische Theorie der Diffraction," *Math. Ann.*, t. XLVII p. 317 (1895). A verification of Sommerfeld's result is given by Drude, *Lehrbuch der Optik*, Leipzig, 1900, p. 188.

‡ "Some Multiform Solutions of the Partial Differential Equation of Physics and their Applications," *Proc. Lond. Math. Soc.*, t. XXX p. 121 (1899), "Oblique Incidence of a train of Plane Waves on a Semi-Infinite Plane," *Proc. Edin. Math. Soc.*, t. XIX (1901).

The general equation of continuity, Art. 8 (4), gives, with the same approximation,

$$\rho_0 \frac{\partial s}{\partial t} = -\frac{\partial}{\partial x}(\rho_0 u) - \frac{\partial}{\partial y}(\rho_0 v) - \frac{\partial}{\partial z}(\rho_0 w) \quad \dots (3)$$

The case that lends itself most readily to mathematical treatment is where the equilibrium-temperature is uniform*, and the expansions and contractions are assumed to follow the 'isothermal' law, so that

$$p = c^2 \rho, \quad \dots \dots \dots (4)$$

c denoting the Newtonian velocity of sound. If we write

$$\rho = \rho_0(1+s), \quad p = p_0(1+s),$$

the equations (2) reduce to the forms

$$\left. \begin{aligned} \frac{\partial u}{\partial t} &= -c^2 \frac{\partial}{\partial x}(s - \bar{s}), \\ \frac{\partial v}{\partial t} &= -c^2 \frac{\partial}{\partial y}(s - \bar{s}), \\ \frac{\partial w}{\partial t} &= -c^2 \frac{\partial}{\partial z}(s - \bar{s}), \end{aligned} \right\} \quad \dots \dots \dots (5)$$

where

$$\bar{s} = -\frac{\Omega'}{c^2}, \quad \dots \dots \dots (6)$$

that is, \bar{s} denotes the 'equilibrium-value' of the condensation due to the disturbing-potential Ω' .

We find, by elimination of u, v, w between (3) and (5),

$$\frac{\partial^2 s}{\partial t^2} = c^2 \nabla^2 (s - \bar{s}) + \frac{c^2}{\rho^2} \left(\frac{\partial \rho_0}{\partial x} \frac{\partial}{\partial x} + \frac{\partial \rho_0}{\partial y} \frac{\partial}{\partial y} + \frac{\partial \rho_0}{\partial z} \frac{\partial}{\partial z} \right) (s - \bar{s}). \quad \dots (7)$$

303 If we neglect the curvature of the earth, and suppose the axis of z to be drawn vertically upwards, ρ_0 will be a function of z only, determined by

$$\frac{\partial p_0}{\partial z} = -g\rho_0. \quad \dots \dots \dots (1)$$

On the present hypothesis of uniform temperature, we have, by Boyle's Law,

$$p_0 = g\rho_0 H, \quad \dots \dots \dots (2)$$

where H denotes as in Art. 274 the height of a 'homogeneous atmosphere' at the given temperature. Hence

$$\rho_0 \propto e^{-z/H}. \quad \dots \dots \dots (3)$$

* The motion is in this case irrotational, and might have been investigated in terms of the velocity-potential.

Substituting in Art. 302 (7), and putting $s = 0$, we find in the case of no disturbing forces,

$$\frac{\partial^2 s}{\partial t^2} = c^2 \left(\nabla^2 s - \frac{1}{H} \frac{\partial s}{\partial z} \right), \quad \dots \dots \dots (14)^*$$

For plane waves travelling in a vertical direction, s will be a function of z only, and therefore

$$\frac{\partial^2 s}{\partial t^2} = c^2 \left(\frac{\partial^2 s}{\partial z^2} - \frac{1}{H} \frac{\partial s}{\partial z} \right), \quad \dots \dots \dots (15)$$

If we assume a time-factor $e^{i\sigma t}$, this is satisfied by

$$\phi = A e^{mz}, \quad \dots \dots \dots (16)$$

provided

$$m^2 - \frac{m}{H} + \frac{\sigma^2}{c^2} = 0, \quad \dots \dots \dots (7)$$

or

$$m = \frac{1}{2H} \pm ik', \quad \dots \dots \dots (8)$$

where

$$k' = \frac{\sigma}{c} \left(1 - \frac{c^2}{4\sigma^2 H^2} \right)^{\frac{1}{2}}, \quad \dots \dots \dots (9)$$

The lower sign in (8) gives the case of waves propagated upwards. Expressed in real form the solution for this case is

$$s = (e^{z/2H} \cos(\sigma t - k'z), \quad \dots \dots \dots (10)$$

The wave-velocity (σ/k') varies with the frequency, but so long as σ is large compared with $c/2H$ it is approximately constant, differing from c by a small quantity of the second order. The main effect of the variation of density is on the amplitude, which increases as the waves travel upwards into the rarer regions, according to the law indicated by the exponential factor. This increase might have been foreseen without calculation; for when the variation of density within the limits of a wave-length is small, there is no appreciable reflection, and the energy per wave-length, which varies as ρa^2 (a being the amplitude), must therefore remain unaltered as the waves proceed. Since $\rho_0 \propto e^{-z/H}$, this shews that $a \propto e^{z/2H}$. As already indicated this result must in reality be greatly modified by viscosity.

When $\sigma < c/2H$, the form of the solution is changed, viz. we have

$$s = (A_1 e^{m_1 z} + A_2 e^{m_2 z}) \cos \sigma t, \quad \dots \dots \dots (11)$$

where m_1, m_2 (the two roots of (7)) are real and positive. This represents a standing oscillation, with one nodal and one 'loop' plane. For example, at

* This equation was given by Poisson, *l.c. ante* p. 463, and integrated (by means of the spherical waves) Poisson also treats (less fully) the case where (in the equilibrium condition) the temperature diminishes uniformly upwards, and the oscillations of pressure and density are connected by the adiabatic law.

where S_n is a surface-harmonic of integral order n , and

$$\sigma^2 = n(n+1) \frac{c^2}{a^2}. \quad \dots \quad (4)$$

As a numerical example, putting $c = 2.80 \times 10^4$, $2\pi a = 4 \times 10^9$ [C S], we find, in the cases $n = 1$, $n = 2$, periods of 28.1 and 16.2 hours, respectively

The tidal variations of pressure due to the gravitational action of the sun and moon are very minute. It appears from the above analogy that the equilibrium value \bar{s} of the condensation will be comparable with af/gH , where f is the quantity defined in Art. 179. Taking $af/g = 1.80$ ft (for the lunar tide), and $H = 25000$ feet, this gives for the amplitude of \bar{s} the value 7.2×10^{-5} . If the normal height of the barometer be 30 inches, this means an oscillation of only .00216 of an inch.

It will be seen on reference to Art. 212 that the analogy with the oscillations of a liquid of depth H is not disturbed when we proceed to the tidal oscillations on a *rotating* globe. The height H of the homogeneous atmosphere does not fall very far short of one of the values (29040 ft) of the depth of the ocean for which the semi-diurnal tides were calculated by Laplace*. The tides in this case were found to be direct, and to have at the equator 11.267 times their equilibrium value. Even with this factor the corresponding barometric oscillation would only amount to .0243 of an inch†

The most regular oscillations of the barometer have solar diurnal and semi-diurnal periods, and cannot be due to gravitational action, since in that case the corresponding lunar tides would be 2.28 times as great, whereas they are practically insensible.

The observed oscillations must be ascribed to the daily variation in temperature, which, when analysed into simple-harmonic constituents, will have components whose periods are respectively $1, \frac{1}{2}, \frac{1}{3}, \frac{1}{4}, \dots$ of a solar day. It is very remarkable that the second (viz the semi-diurnal) component has a considerably greater amplitude than the first. It has been suggested by Lord Kelvin that the explanation of this peculiarity is to be sought for in the closer agreement of the period of the semi-diurnal component with a free period of the earth's atmosphere than is the case with the diurnal component. This question has been made the subject of an elaborate investigation by Margules‡, taking into account the earth's rotation.

* See the table on p. 328, above.

† Cf. Laplace, "Recherches sur plusieurs points du système du monde," *Mém. de l'Acad. roy. des Sciences*, 1776 [1779] [*Oeuvres*, t. ix p. 283]. Also *Mécanique Céleste*, Livre 4^{me}, chap. v.

‡ *Wiener Ber.*, t. xcix p. 204 (1890). This paper, with several others cited in the course of this work, is included in a very useful collection edited and (where necessary) translated by Prof. Cleveland Abbe, under the title "Mechanics of the Earth's Atmosphere," *Smithsonian Miscellaneous Collections*, Washington, 1891.

CHAPTER XI.

VISCOSITY.

305 THE main theme of this Chapter is the resistance to distortion, known as 'viscosity' or 'internal friction,' which is exhibited more or less by all real fluids, but which we have hitherto neglected.

It will be convenient, following a plan already adopted on several occasions, to recall briefly the outlines of the general theory of a dynamical system subject to dissipative forces which are linear functions of the generalized velocities*. This will not only be useful as tending to bring under one point of view most of the special investigations which follow; it will sometimes indicate the general character of the results to be expected in cases which are as yet beyond our powers of calculation.

We begin with the case of one degree of freedom. The equation of motion is of the type

$$aq + b\dot{q} + cq = Q \quad \dots \dots \dots (1)$$

Here q is a generalized coordinate specifying the deviation from a position of equilibrium, a is the coefficient of inertia, and is necessarily positive, c is the coefficient of stability, and is positive in the applications which we shall consider, b is a coefficient of friction, and is positive. Since the terms on the left-hand of (1) are differently affected by changing the sign of t , the motion of a system subject to an equation of this type is not reversible.

If we put $T = \frac{1}{2}aq^2$, $V = \frac{1}{2}cq^2$, $F = \frac{1}{2}bq^2$, $\dots \dots \dots (2)$
the equation may be written

$$\frac{d}{dt}(T + V) = -2F + Q\dot{q}. \quad \dots \dots \dots (3)$$

This shews that the energy $T + V$ is increasing at a rate less than that at which the extraneous force is doing work on the system. The difference $2F$ represents the rate at which energy is being dissipated, this is always positive.

* For a fuller account of the theory reference may be made to Lord Rayleigh, *Theory of Sound*, cc. iv, v, Thomson and Tait, *Natural Philosophy* (2nd ed.), Arts. 340—345; Routh, *Advanced Rigid Dynamics*, cc vi, vii.

In *free* motion we have

$$aq + b\dot{q} + cq = 0. \quad \dots \dots (4)$$

If we assume that $q \propto e^{\lambda t}$, the solution takes different forms according to the relative importance of the frictional term. If $b^2 < 4ac$, we have

$$\lambda = -\frac{1}{2} \frac{b}{a} \pm i \left(\frac{c}{a} - \frac{1}{4} \frac{b^2}{a^2} \right)^{\frac{1}{2}}, \quad \dots (5)$$

or, say,
$$\lambda = -\frac{1}{\tau} \pm i\sigma. \quad \dots \dots (6)$$

Hence the full solution, expressed in real form, is

$$q = A e^{-t/\tau} \cos(\sigma t + \epsilon), \quad \dots \dots (7)$$

where A, ϵ are arbitrary. The type of motion which this represents may be described as a simple-harmonic vibration, with amplitude diminishing asymptotically to zero, according to the law $e^{-t/\tau}$. The time τ in which the amplitude sinks to $1/e$ of its original value is sometimes called the 'modulus of decay' of the oscillations.

If $b/2a$ be small compared with $(c/a)^{\frac{1}{2}}$, $b^2/4ac$ is a small quantity of the second order, and the 'speed' σ is then practically unaffected by the friction. This is the case whenever the time ($2\pi\tau$) in which the amplitude sinks to $e^{-2\pi}$ ($\approx \frac{1}{515}$) of its initial value is large compared with the period ($2\pi/\sigma$).

When, on the other hand, $b^2 > 4ac$, the values of λ are real and negative. Denoting them by $-\alpha_1, -\alpha_2$, we have

$$q = A_1 e^{-\alpha_1 t} + A_2 e^{-\alpha_2 t}. \quad \dots \dots (8)$$

This represents 'aperiodic motion', viz the system never passes more than once through its equilibrium position, towards which it finally creeps asymptotically.

In the critical case $b^2 = 4ac$, the two values of λ are equal, we then find by usual methods

$$q = (A + Bt) e^{-\alpha t}, \quad \dots \dots (9)$$

which may be similarly interpreted.

As the frictional coefficient b is increased, the two quantities α_1, α_2 become more and more unequal; viz one of them (α_2 , say) tends to the value b/a , and the other to the value c/b . The effect of the second term in (8) then rapidly disappears, and the residual motion is the same as if the inertia-coefficient (a) were zero.

306 We consider next the effect of a periodic extraneous force. Assuming that

$$Q \propto e^{i(\sigma t + \epsilon)}, \quad \dots \dots (10)$$

the equation (1) gives $q = \frac{Q}{c - \sigma^2 a + i\sigma b}$ (11)

If we put

$$1 - \frac{\sigma^2 a}{c} = R \cos \epsilon_1, \quad \frac{\sigma b}{c} = R \sin \epsilon_1, \quad \dots \dots \dots (12)$$

where ϵ_1 lies between 0 and 180° , we have

$$q = \frac{Q}{Rc} e^{-i\epsilon_1}. \quad \dots \dots \dots (13)$$

Taking real parts, we may say that the force

$$Q = C \cos (\sigma t + \epsilon) \quad \dots \dots \dots (14)$$

will maintain the oscillation

$$q = \frac{C}{Rc} \cos (\sigma t + \epsilon - \epsilon_1) \quad \dots \dots \dots (15)$$

Since
$$R^2 = \left(1 - \frac{\sigma^2 a^2}{c^2}\right)^2 + \frac{\sigma^2 b^2}{c^2}, \quad \dots \dots \dots (16)$$

it is easily found that if $b^2 < 4ac$ the amplitude is greatest when

$$\sigma = \left(\frac{c}{a}\right)^{\frac{1}{2}} \left(1 - \frac{1}{2} \frac{b^2}{ac}\right)^{\frac{1}{2}}, \quad \dots \dots \dots (17)$$

its value then being
$$\frac{C}{b} \left(\frac{a}{c}\right)^{\frac{1}{2}} \left(1 - \frac{1}{4} \frac{b^2}{ac}\right)^{-\frac{1}{2}}. \quad \dots \dots \dots (18)$$

In the case of relatively small friction, where $b^2/4ac$ may be treated as of the second order, the amplitude is greatest when the period of the imposed force coincides with that of the free oscillation (cf. Art. 167). The formula (18) then shews that the amplitude when a maximum bears to its 'equilibrium-value' (C/c) the ratio $(ac)^{\frac{1}{2}}/b$, which is by hypothesis large

On the other hand, when $b^2 > 4ac$ the amplitude continually increases as the speed σ diminishes, tending ultimately to the 'equilibrium-value' C/c .

It also appears from (15) and (12) that the maximum displacement follows the maximum of the force at an interval of phase equal to ϵ_1 , where

$$\tan \epsilon_1 = \frac{\sigma b}{c - \sigma^2 a}. \quad \dots \dots \dots (19)$$

If the period be longer than the free-period in the absence of friction this difference of phase lies between 0 and 90° ; in the opposite case it lies between 90° and 180° . If the frictional coefficient b be relatively small, the interval differs very little from 0 or 180° , as the case may be, unless σ be very nearly equal to the critical speed $(c/a)^{\frac{1}{2}}$. For the critical speed the phase-difference is 90° .

The rate of dissipation is $h\eta$, the mean value of which is $\frac{1}{2}(\sigma + \sigma')$ and to be

$$\frac{1}{2} \frac{h\sigma^2}{(\sigma + c\sigma') + h} \quad \text{..... (210)}$$

This is greatest when $\sigma = (c\sigma')$.

As in Art. 167, when the oscillations are very rapid the formula (210) gives

$$q = \frac{Q}{\sigma + \sigma'} \quad \text{..... (211)}$$

approximately; the *inertia* only of the system being operative.

On the other hand when σ is small, the displacement becomes nearly the equilibrium value

$$q = \frac{Q}{c} \quad \text{..... (212)}$$

307. An interesting example is furnished by the tide in an equatorial canal*.

The equation of motion, as modified by the introduction of a frictional term, is

$$\frac{d^2\xi}{dt^2} + \mu \frac{d\xi}{dt} + c \frac{d^2\xi}{dx^2} + X = 0 \quad \text{..... (1)}$$

where the notation is as in Art. 180†

In the case of *free* waves, putting $X = 0$ and assuming that

$$\xi = e^{i\lambda t + ikx} \quad \text{..... (2)}$$

we find

$$\lambda^2 + \mu\lambda + k^2c^2 = 0,$$

whence

$$\lambda = -\frac{1}{2}\mu \pm i(k^2c^2 - \frac{1}{4}\mu^2)^{\frac{1}{2}} \quad \text{..... (3)}$$

If we neglect the square of μ/kc , this gives, in real form

$$\xi = Ae^{-\frac{1}{2}\mu t} \cos\{k(ct + x) + \epsilon\} \quad \text{..... (4)}$$

The modulus of decay is $2\mu^{-1}$, and the wave-velocity is (to the first order) unaffected by the friction.

To find the forced waves due to the attraction of the moon we write, in conformity with Art. 180,

$$X = i\eta e^{i(n't + \theta/\mu + \phi)}, \quad \text{..... (5)}$$

where n' is the angular velocity of the moon relative to a fixed point on the canal, and a is the earth's radius. We find, assuming the same time factor,

$$\xi = \frac{1}{c^2 - n'^2a^2 + \frac{1}{2}\mu n'a^2} e^{i(n't + \theta/\mu + \phi)} \quad \text{..... (6)}$$

* Airy, "Tides and Waves," Arts. 315-317.

† In particular, c^2 now stands for gh , where h is the depth.

Hence, for the surface-elevation, we have

$$\eta = -h \frac{\partial \xi}{\partial x} = \frac{1}{2} \frac{Hc^2}{c^2 - n'^2 a^2 + \frac{1}{2} \mu n' a^2} e^{2n'(n't + x/a + \epsilon)}, \quad \dots \quad (7)$$

where $H = af/g$, as in Art 179

To put these expressions in real form, we write

$$\tan 2\chi = \frac{1}{2} \frac{\mu n' a^2}{c^2 - n'^2 a^2}, \quad \dots \quad (8)$$

where $0 < \chi < 90^\circ$ We thus find that to the tidal disturbing force

$$X = -f \sin 2 \left(n't + \frac{x}{a} + \epsilon \right) \quad \dots \quad (9)$$

corresponds the horizontal displacement

$$\xi = -\frac{1}{4} \frac{fa^2}{\{(c^2 - n'^2 a^2)^2 + \frac{1}{4} \mu^2 n'^4 a^4\}^{\frac{1}{2}}} \sin 2 \left(n't + \frac{x}{a} + \epsilon - \chi \right), \quad (10)$$

and the surface-elevation

$$\eta = \frac{1}{2} \frac{Hc^2}{\{(c^2 - n'^2 a^2)^2 + \frac{1}{4} \mu^2 n'^4 a^4\}^{\frac{1}{2}}} \cos 2 \left(n't + \frac{x}{a} + \epsilon - \chi \right) \quad (11)$$

Since in these expressions $n't + x/a + \epsilon$ measures the hour-angle of the moon past the meridian of any point (x) on the canal, it appears that high-water will follow the moon's transit at an interval t_1 given by $n't_1 = \chi$

If $c^2 < n'^2 a^2$, or $h/a < n'^2 a/g$, we should in the case of infinitesimal friction have $\chi = 90^\circ$, i.e. the tides would be *inverted* (cf Art 180) With sensible friction, χ will lie between 90° and 45° , and the time of high-water is *accelerated* by the time-equivalent of the angle $90^\circ - \chi$

On the other hand, when $h/a > n'^2 a/g$, so that in the absence of friction the tides would be *direct*, the value of χ lies between 0° and 45° , and the time of high-water is *retarded* by the time-equivalent of this angle

The figures on the next page shew the two cases The letters M, M' indicate the positions of the moon and 'anti-moon' (see p 340) supposed situate in the plane of the equator, and the curved arrows show the direction of the earth's rotation.


It is evident that in each case the attraction of the disturbing system on the elevated water is equivalent to a couple tending to *diminish* the angular momentum of the system composed of the earth and sea

In the present problem the amount of the couple can be easily calculated. We find, from (9) and (11), for the mean tangential force on the elevated water, per unit area of the surface,

$$\frac{1}{2\pi a} \int_0^{2\pi a} \rho X \eta dx = -\frac{1}{2} \rho h f \sin 2\chi, \quad \dots \quad (12)$$

where h is the vertical amplitude. Since the positive direction of X is east-

wards, this shews that there is on the whole a balance of westward force. If we multiply by the area of the water surface and by the tide α we get the amount of the retarding couple.



The effect of phase-differences in the composition of two tides of slightly different speeds has been already discussed in Art. 223. To apply the formulae there given to the present case we must write $a = 2n'$, $\epsilon = 2\chi$. We find, from (8), above,

$$\frac{d\epsilon}{d\sigma} = \frac{d\chi}{dn'} = \frac{\mu a^2 (c^2 + n'^2 a^2)}{4(c^2 - n'^2 a^2) + \mu^2 n'^2 a^4} \dots\dots\dots (13)*$$

If we have two tide-generating bodies with very nearly equal periods the expression gives the interval of time at which the spring tides will follow the instant of conjunction (or opposition).

The above investigation is reproduced on account of its theoretic interest, but if we apply it to the actual circumstances of the earth, the phase-differences which it is capable of explaining appear to be quite insignificant in comparison with such as actually occur. Thus if we imagine a broad equatorial oceanic belt 11250 feet deep, we have from (8), and from Art. 180,

$$\tan 2\chi = -\frac{1}{1 \cdot 311} \frac{1}{h} \frac{1}{n'\tau} = -191 \times \frac{2\pi}{n'\tau},$$

* Cf. Airy, "Tides and Waves," Arts. 328....

where $\mu = \mu_0$, the coefficient of decay of free oscillations. It seems rational to suppose that the total effect of the frictional force would be a considerable multiple of the lunar day $2\pi/\omega$, which makes the change produced by friction in the time of high water would be considerable.

$$\frac{2\pi}{\tau} \approx 22 \text{ minutes.}$$

Hence the retardation would be too slow for a phase acceleration of more than a few minutes.

It is not a good idea to compare the amount of lagging of the spring-tides as calculated from the frictional law

to the acceleration needed to keep the introduction of the frictional term $-\mu d\xi/dt$ in (1) is only a rough approximation, and to represent generally the effect of small dissipative forces; but the question of calculation still remains, suggests the question whether the large phase-accelerations which sometimes occur in the tide are not to be attributed to the inertia of the water, as affected by the curvature of its boundaries, rather than to frictional causes. (See Appendix.)

It is proposed in this article to carry the numerical illustration a step further, and to estimate the effect of the retarding couple on the Earth's rotation. We have

$$\frac{1}{2}\pi\rho_0a^2a_0^2\frac{dn}{dt} = -2\pi\rho h\omega^2\sin 2\chi.\theta,$$

where ρ_0 is the Earth's mean density, a_0 its radius of gyration, n its angular velocity of rotation, and θ the fraction of the surface which is occupied by the water. We may write then

$$\frac{dn}{dt} = -\frac{\rho}{\rho_0}\frac{h}{H^2}g^2\frac{a_0^2}{a^2}\sin 2\chi.\theta,$$

If we assume $\rho/\rho_0 = 1$, $h/H = 10$, $g = 800 \text{ cm} \times 10^{-3}$, $a_0^2 = \frac{1}{2}a^2$, $a = 2.09 \times 10^7$, $g = 32.2$, this gives with sufficient approximation,

$$\frac{dn}{dt} = -9.1 \times 10^{-12} \sin 2\chi.\theta,$$

where θ is the difference between $\sin 2\chi$ and $-\tan 2\chi$,

$$\frac{dn}{dt} = -1.75 \times 10^{-12} \frac{2\pi}{\tau} n' . \theta,$$

where n' is the retardation in radians per second per second. Expressed in seconds of arc per century the retardation is

$$\frac{dn'}{dt} = 330 \theta . \frac{n' n''}{\tau}.$$

At a latitude of 30° the retardation would be in a century about

$$1.7 \theta \frac{n' n''}{\tau} \text{ seconds of time,}$$

which is less than the error caused by using a tape measure with which it kept time at the beginning of the century. If we take θ as $\frac{1}{2}$ (which would represent very roughly the case of the tide-gate being bounded by the parallels of 30° N. and S. latitude), this gives, for a retardation of 1 second of n' , a loss of only a fraction of a second*.

* For a table of the amount of tidal retardation of the earth's rotation, on various suppositions as to the tidal phases of the tides, reference may be made to Delaunay, "Sur l'existence d'un terme dans l'équation du mouvement de la lune qui rendrait la valeur de l'équation séculaire de la

It is at least questionable whether frictional forces such as we can suppose to be at present operative are sufficient to produce any appreciable general tidal lagging, or any such retardation of the earth's rotation as is sometimes asserted on astronomical evidence. But the investigation of the tides in some case where gyrostatic as well as frictional terms would have an effect would be desirable before one could pronounce with confidence on such a point.

308 Returning to the general theory, let q_1, q_2, \dots, q_n be the coordinates of a dynamical system, which we will suppose subject to conservative forces depending on its configuration, to 'motional' forces varying as the velocities, and to given extraneous forces. The equations of small motion of such a system, on the most general assumptions we can make, will be of the type

$$\frac{d}{dt} \frac{\partial T}{\partial \dot{q}_r} + B_{r1} \dot{q}_1 + B_{r2} \dot{q}_2 + \dots = - \frac{\partial V}{\partial q_r} + Q_r, \quad \dots \quad (1)$$

where the kinetic and potential energies T, V are given by expressions of the forms

$$2T = a_{11} \dot{q}_1^2 + a_{22} \dot{q}_2^2 + \dots + 2a_{12} \dot{q}_1 \dot{q}_2 + \dots, \quad \dots \quad (2)$$

$$2V = c_{11} q_1^2 + c_{22} q_2^2 + \dots + 2c_{12} q_1 q_2 + \dots \quad (3)$$

It is to be remembered that

$$a_{rs} = a_{sr}, \quad c_{rs} = c_{sr}, \quad (4)$$

but we do not assume the equality of B_{rs} and B_{sr} .

$$\text{If we now write} \quad b_{rs} = b_{sr} = \frac{1}{2} (B_{rs} + B_{sr}), \quad \dots \quad (5)$$

$$\text{and} \quad \beta_{rs} = -\beta_{sr} = \frac{1}{2} (B_{rs} - B_{sr}), \quad \dots \quad (6)$$

the typical equation (1) takes the form

$$\frac{d}{dt} \frac{\partial T}{\partial \dot{q}_r} + \frac{\partial F}{\partial \dot{q}_r} + \beta_{r1} \dot{q}_1 + \beta_{r2} \dot{q}_2 + \dots = - \frac{\partial V}{\partial q_r} + Q_r, \quad \dots \quad (7)$$

provided

$$2F = b_{11} \dot{q}_1^2 + b_{22} \dot{q}_2^2 + \dots + 2b_{12} \dot{q}_1 \dot{q}_2 + \dots \quad (8)$$

From the equations in this form we derive

$$\frac{d}{dt} (T + V) + 2F = \Sigma Q_r \dot{q}_r, \quad \dots \quad (9)$$

The right-hand side expresses the rate at which the extraneous forces are doing work. Part of this work goes to increase the total energy $T + V$ of the system, the remainder is, from the present point of view, dissipated, at the rate $2F$. In the application to natural problems the function F is essentially positive, it is called by Lord Rayleigh*, by whom it was first formally employed, the 'Dissipation-Function'.

Lune," *Comptes Rendus*, t. lxi (1865), and Sir W. Thomson, "On the Observations and Calculations required to find the Tidal Retardation of the Earth's Rotation," *Phil Mag* (4), t. xxxi p. 533 (1866) [*Math and Phys. Papers*, t. iii. p. 337]. The first estimate of the kind appears to have been made by Ferrel, in 1853.

* "Some General Theorems relating to Vibrations," *Proc Lond. Math. Soc*, t. iv. p. 357 (1873) [*Sc Papers*, t. i p. 170]; *Theory of Sound*, Art 81

The relatively small variations of the remaining coordinates are then given by the remaining equations of the system (15). For example, with the same approximations,

$$a_s q_s + b_{rs} q_r + c_s q_s = 0, \quad \dots \quad (19)$$

whence

$$q_s = \frac{\sigma b_{1s}}{c_s - \sigma^2 a_s} A e^{-t/\tau} \sin(\sigma t + \epsilon) \quad \dots \quad (20)$$

Except in the case of approximate equality of period between two fundamental modes, the elliptic orbits of the particles will on the present suppositions be very flat

$$\text{If we were to assume that } q_r = a \cos(\sigma t + \epsilon), \quad (21)$$

where σ has the same value as in the case of no friction, whilst a varies slowly with the time, and that the variations of the other coordinates are relatively small, we should find

$$T + V = \frac{1}{2} a_r q_r^2 + \frac{1}{2} c_r q_r^2 = \frac{1}{2} \sigma^2 a^2, \quad \dots \quad (22)$$

nearly. Again, the dissipation is $2F = b_{rr} q_r^2$,

$$\text{the mean value of which is } \frac{1}{2} \sigma^2 b_{rr} a^2, \quad \dots \quad (23)$$

approximately. Hence equating the rate of decay of the energy to the mean value of the dissipation, we get

$$\frac{da}{dt} = -\frac{1}{2} \frac{b_{rr}}{a_r} a, \quad \dots \quad (24)$$

whence

$$a = a_0 e^{-t/\tau}, \quad \dots \quad (25)$$

if

$$\tau^{-1} = \frac{1}{2} \frac{b_{rr}}{a_{rr}}, \quad \dots \quad (26)$$

as in Art 305. This method of ascertaining the rate of decay of the oscillations is sometimes useful when the complete determination of the character of the motion, as affected by friction, would be difficult (cf. Arts 331, 338).

When the frictional coefficients are relatively great, the inertia of the system becomes ineffective, and the most appropriate system of coordinates is that which reduces F and V simultaneously to sums of squares, say

$$\left. \begin{aligned} 2F &= b_1 \dot{q}_1^2 + b_2 \dot{q}_2^2 + \dots + b_n \dot{q}_n^2, \\ 2V &= c_1 q_1^2 + c_2 q_2^2 + \dots + c_n q_n^2. \end{aligned} \right\} \quad (27)$$

The equations of free-motion are then of the type

$$b_r \ddot{q}_r + c_r q_r = 0, \quad \dots \quad (28)$$

whence

$$q_r = C e^{-t/\tau}, \quad \dots \quad (29)$$

if

$$\tau = \frac{b_r}{c_r} \quad \dots \quad (30)$$

310. When gyrostatic as well as frictional terms are present in the fundamental equations, the theory is naturally more complicated. It will be sufficient here to consider the case of *two* degrees of freedom, by way of further elucidation of a point discussed in Art 205.

The equations of motion are now of the types

$$\left. \begin{aligned} a_1 \ddot{q}_1 + b_{11} \dot{q}_1 + (b_{12} + \beta) \dot{q}_2 + c_1 q_1 &= Q_1, \\ a_2 \ddot{q}_2 + (b_{21} - \beta) \dot{q}_1 + b_{22} \dot{q}_2 + c_2 q_2 &= Q_2. \end{aligned} \right\} \dots \quad (1)$$

To determine the modes of free motion we put $Q_1=0$, $Q_2=0$, and assume that q_1 and q_2 vary as $e^{\lambda t}$. This leads to the biquadratic in λ

$$a_1 a_2 \lambda^4 + (a_2 b_{11} + a_1 b_{22}) \lambda^3 + (a_2 c_1 + a_1 c_2 + \beta^2 + b_{11} b_{22} - b_{12}^2) \lambda^2 + (b_{11} c_2 + b_{22} c_1) \lambda + c_1 c_2 = 0 \quad (2)$$

There is no difficulty in shewing, with the help of criteria given by Routh*, that if, as in our case, the quantities

$$a_1, a_2, b_{11}, b_{22}, b_{11} b_{22} - b_{12}^2$$

are all positive, the necessary and sufficient conditions that this biquadratic should have the real parts of its roots all negative are that c_1, c_2 should both be positive

If we neglect terms of the second order in the frictional coefficients, the same conclusion may be attained more directly as follows. On this hypothesis the roots of (2) are, approximately,

$$\lambda = -a_1 \pm i\sigma_1, \quad -a_2 \pm i\sigma_2, \quad (3)$$

where σ_1, σ_2 are, to the first order, the same as in the case of no friction, viz they are the roots of

$$a_1 a_2 \sigma^4 - (a_2 c_1 + a_1 c_2 + \beta^2) \sigma^2 + c_1 c_2 = 0, \quad (4)$$

whilst a_1, a_2 are determined by

$$a_1 + a_2 = \frac{1}{2} \left(\frac{b_{11}}{a_1} + \frac{b_{22}}{a_2} \right), \quad \frac{a_1}{\sigma_1^2} + \frac{a_2}{\sigma_2^2} = \frac{1}{2} \left(\frac{b_{11}}{c_1} + \frac{b_{22}}{c_2} \right). \quad (5)$$

It is evident that, if σ_1 and σ_2 are to be real, c_1, c_2 must have the same sign, and that if a_1, a_2 are to be positive, this sign must be +. Conversely, if c_1, c_2 are both positive, the values of σ_1^2, σ_2^2 are real and positive, and the quantities $c_1/a_1, c_2/a_2$ both lie in the interval between them. It then easily follows from (5) that a_1, a_2 are both positive†

If one of the coefficients c_1, c_2 (say c_2) be zero, one of the values of σ (say σ_2) is zero, indicating a free mode of infinitely long period. We then have

$$\sigma_1^2 = \frac{c_1}{a_1} + \frac{\beta^2}{a_1 a_2}, \quad a_2 = \frac{b_{22} c_1}{a_2 c_1 + \beta^2}. \quad (6)$$

As in Art. 205 we could easily write down the expressions for the forced oscillations in the general case where Q_1, Q_2 vary as $e^{i\sigma t}$, but we shall here consider more particularly the case where $c_2=0$ and $Q_2=0$. The equations (1) then give

$$\left. \begin{aligned} (c_1 - \sigma^2 a_1 + i\sigma b_{11}) \dot{q}_1 + (b_{12} + \beta) \dot{q}_2 &= Q_1, \\ i\sigma (b_{12} - \beta) \dot{q}_1 + (i\sigma a_2 + b_{22}) \dot{q}_2 &= 0 \end{aligned} \right\} \quad (7)$$

* *Advanced Rigid Dynamics*, Art. 287.

† A simple example of the above theory is supplied by the case of a particle in an ellipsoidal bowl rotating about a principal axis, which is vertical. If the bowl be frictionless, the equilibrium of the particle when at the lowest point will be stable unless the period of the rotation lie between the periods of the two fundamental modes of oscillation (one in each principal plane) of the particle when the bowl is at rest. But if there be friction of motion between the particle and the bowl, there will be 'secular' stability only so long as the speed of the rotation is less than that of the slower of the two modes referred to. If the rotation be more rapid, the particle will gradually work its way outwards into a position of relative equilibrium in which it rotates with the bowl like the bob of a conical pendulum. In this state the system made up of the particle and the bowl has less energy for the same angular momentum than when the particle was at the bottom. Cf. Art. 250.

$$\text{Hence } q_1 = \frac{\imath \sigma a_2 + b_{22}}{-a_1 a_2 \imath \sigma^3 - (a_2 b_{11} + a_1 b_{22}) \sigma^2 + (a_2 c_1 + \beta^2 + b_{11} b_{22} - b_{12}^2) \imath \sigma + b_{22} c_1} Q_1. \quad (8)$$

$$\text{This may also be written } q_1 = \frac{\imath \sigma a_2 + b_{22}}{a_1 a_2 \{(\imath \sigma + a_1)^2 + \sigma_1^2\} (\imath \sigma + a_2)} Q_1 \quad (9)$$

Our main object is to examine the case of a disturbing force of long period, for the sake of its bearing on Laplace's argument as to the fortnightly tide (Art 216). We will therefore suppose that the ratio σ_1/σ , as well as σ_1/a_1 , is large. The formula then reduces to

$$q_1 = \frac{\imath \sigma a_2 + b_{22}}{a_1 a_2 \sigma_1^2 (\imath \sigma + a_2)} Q_1 = \frac{\imath \sigma a_2 + b_{22}}{b_{22} c_1 (\imath \sigma/a_2 + 1)} Q_1 \quad (10)$$

Everything now turns on the values of the ratios σ/a_2 and $\sigma a_2/b_{22}$. If σ be so small that these may be both neglected, we have

$$q_1 = \frac{Q_1}{c_1}, \quad (11)$$

in agreement with the equilibrium theory. The assumption here made is that the period of the imposed force is long compared with the time in which free motions would, owing to friction, fall to $e^{-2\pi}$ of their initial amplitudes. This condition is evidently far from being fulfilled in the case of the fortnightly tide. If, as is more in agreement with the actual state of things, we assume σ/a_2 and $\sigma a_2/b_{22}$ to be large, we obtain

$$q_1 = \frac{a_2 a_2}{b_{22} c_1} Q_1 = \frac{a_2}{a_2 c_1 + \beta^2} Q_1, \quad (12)$$

as in Art 205 (24)

Viscosity.

311 We proceed to consider the special kind of resistance which is met with in fluids. The methods we shall employ are of necessity the same as are applicable to the resistance to distortion, known as 'elasticity,' which is characteristic of solid bodies. The two classes of phenomena are of course physically distinct, the latter depending on the actual changes of shape produced, the former on the *rate* of change of shape, but the mathematical methods appropriate to them are to a great extent identical.

If we imagine three planes to be drawn through any point P perpendicular to the axes of x , y , z , respectively, the three components of the stress, per unit area, exerted across the first of these planes may be denoted by p_{xx} , p_{xy} , p_{xz} , respectively, those of the stress across the second plane by p_{yx} , p_{yy} , p_{yz} ; and those of the stress across the third plane by p_{zx} , p_{zy} , p_{zz} *. If we fix our attention on an element $\delta x \delta y \delta z$ having its centre at P , we find, on taking moments, and dividing by $\delta x \delta y \delta z$,

$$p_{yz} = p_{zy}, \quad p_{xx} = p_{xx}, \quad p_{xy} = p_{yx},$$

* In conformity with the usual practice in the theory of Elasticity, we reckon a *tension* as positive, a *pressure* as negative. Thus in the case of a frictionless fluid we have

$$p_{xx} = p_{yy} = p_{zz} = -p.$$

the extraneous forces and the kinetic reactions being omitted, since they are of a higher order of small quantities than the surface tractions. These equalities reduce the nine components of stress to six, in the case of a viscous fluid they will also follow independently from the expressions for p_{yz}, p_{zx}, p_{xy} in terms of the rates of distortion, to be given presently (Art 313)

312 It appears from Arts. 1, 2 that in a fluid the deviation of the state of stress denoted by p_{xx}, p_{xy}, \dots from one of pressure uniform in all directions depends entirely on the motion of distortion in the neighbourhood of P , i.e. on the six quantities a, b, c, f, g, h by which this distortion was in Art 30 shewn to be specified. Before endeavouring to express p_{xx}, p_{xy}, \dots as functions of these quantities, it will be convenient to establish certain formulae of transformation

Let us draw Px', Py', Pz' in the directions of the principal axes of distortion at P , and let a', b', c' be the rates of extension along these lines Further let the mutual configuration of the two sets of axes, x, y, z and x', y', z' , be specified in the usual manner by the annexed scheme of direction-cosines. We have, then,

	x	y	z
x'	$l_1,$	$m_1,$	$n_1,$
y'	$l_2,$	$m_2,$	$n_2,$
z'	$l_3,$	$m_3,$	$n_3.$

$$\frac{\partial u}{\partial x} = \left(l_1 \frac{\partial}{\partial x'} + l_2 \frac{\partial}{\partial y'} + l_3 \frac{\partial}{\partial z'} \right) (l_1 u' + l_2 v' + l_3 w') = l_1^2 \frac{\partial u'}{\partial x'} + l_2^2 \frac{\partial v'}{\partial y'} + l_3^2 \frac{\partial w'}{\partial z'} .$$

Hence

$$\left. \begin{aligned} a &= l_1^2 a' + l_2^2 b' + l_3^2 c', \\ b &= m_1^2 a' + m_2^2 b' + m_3^2 c', \\ c &= n_1^2 a' + n_2^2 b' + n_3^2 c', \end{aligned} \right\} \dots\dots\dots (1)$$

the last two relations being written down from symmetry We notice that

$$a + b + c = a' + b' + c', \quad \dots\dots\dots (2)$$

as we should expect, since either side measures the ‘expansion’ (Art 7).

Again

$$\begin{aligned} \frac{\partial w}{\partial y} + \frac{\partial v}{\partial z} &= \left(m_1 \frac{\partial}{\partial x'} + m_2 \frac{\partial}{\partial y'} + m_3 \frac{\partial}{\partial z'} \right) (n_1 u' + n_2 v' + n_3 w') \\ &+ \left(n_1 \frac{\partial}{\partial x'} + n_2 \frac{\partial}{\partial y'} + n_3 \frac{\partial}{\partial z'} \right) (m_1 u' + m_2 v' + m_3 w'), \end{aligned}$$

and this, with the two corresponding formulae, gives

$$\left. \begin{aligned} f &= m_1 n_1 a' + m_2 n_2 b' + m_3 n_3 c', \\ g &= n_1 l_1 a' + n_2 l_2 b' + n_3 l_3 c', \\ h &= l_1 m_1 a' + l_2 m_2 b' + l_3 m_3 c'. \end{aligned} \right\} \dots\dots\dots (3)$$

313 From the symmetry of the circumstances it is plain that the stresses exerted at P across the planes $y'z'$, $z'x'$, $x'y'$ must be wholly perpendicular to these planes. Let us denote them by p_1 , p_2 , p_3 respectively. In the figure of Art 2 let ABC now represent a plane drawn perpendicular to x , infinitely close to P , meeting the axes of x' , y' , z' in A , B , C , respectively; and let Δ denote the area ABC . The areas of the remaining faces of the tetrahedron $PABC$ will then be $l_1\Delta$, $l_2\Delta$, $l_3\Delta$. Resolving parallel to x the forces acting on the tetrahedron, we find

$$p_{xx}\Delta = p_1l_1\Delta \cdot l_1 + p_2l_2\Delta \cdot l_2 + p_3l_3\Delta \cdot l_3,$$

the external impressed forces and the resistances to acceleration being omitted for the same reason as before. Hence, and by similar reasoning,

$$\left. \begin{aligned} p_{xx} &= p_1l_1^2 + p_2l_2^2 + p_3l_3^2, \\ p_{yy} &= p_1m_1^2 + p_2m_2^2 + p_3m_3^2, \\ p_{zz} &= p_1n_1^2 + p_2n_2^2 + p_3n_3^2. \end{aligned} \right\} \dots\dots\dots (1)$$

We notice that

$$p_{xx} + p_{yy} + p_{zz} = p_1 + p_2 + p_3. \dots\dots\dots (2)$$

Hence the arithmetic mean of the normal pressures on any three mutually perpendicular planes through the point P is the same. We shall denote this mean pressure by p^* .

Again, resolving parallel to y , we obtain the third of the following symmetrical system of equations.

$$\left. \begin{aligned} p_{yz} &= p_1m_1n_1 + p_2m_2n_2 + p_3m_3n_3, \\ p_{zx} &= p_1n_1l_1 + p_2n_2l_2 + p_3n_3l_3, \\ p_{xy} &= p_1l_1m_1 + p_2l_2m_2 + p_3l_3m_3. \end{aligned} \right\} \dots\dots\dots (3)$$

These shew that

$$p_{yz} = p_{zy}, \quad p_{zx} = p_{xz}, \quad p_{xy} = p_{yx},$$

as was proved independently in Art. 311.

If in the same figure we suppose PA , PB , PC to be drawn parallel to x , y , z respectively, whilst ABC is any plane drawn near P , whose direction-cosines are l , m , n , we find in the same way that the components (p_{hx} , p_{hy} , p_{hz}) of the stress exerted across this plane are

$$\left. \begin{aligned} p_{hx} &= lp_{xx} + mp_{xy} + np_{xz}, \\ p_{hy} &= lp_{yx} + mp_{yy} + np_{yz}, \\ p_{hz} &= lp_{zx} + mp_{zy} + np_{zz} \end{aligned} \right\} \dots\dots\dots (4)$$

* The question of course remains open as to whether, in the case of a gas, the mean pressure is a function of the density and temperature only (as in the statical condition to which Boyle's and Dalton's laws in the first instance relate), or whether it depends also on the rate of expansion at the point (x , y , z). See Art 341 *infra*.

314 Now p_1, p_2, p_3 differ from $-p$ by quantities depending on the motion of distortion, which must therefore be functions of a', b', c' , only. The simplest hypothesis we can frame on this point is that these functions are linear. We write therefore

$$\left. \begin{aligned} p_1 &= -p + \lambda (a' + b' + c') + 2\mu a', \\ p_2 &= -p + \lambda (a' + b' + c') + 2\mu b', \\ p_3 &= -p + \lambda (a' + b' + c') + 2\mu c', \end{aligned} \right\} \quad \dots (1)$$

where λ, μ are constants depending on the nature of the fluid, and on its physical state, this being the most general assumption consistent with the above suppositions, and with symmetry. Substituting these values of p_1, p_2, p_3 in (1) and (3) of Art. 313, and making use of the results of Art. 312, we find

$$\left. \begin{aligned} p_{xx} &= -p + \lambda (a + b + c) + 2\mu a, \\ p_{yy} &= -p + \lambda (a + b + c) + 2\mu b, \\ p_{zz} &= -p + \lambda (a + b + c) + 2\mu c, \end{aligned} \right\} \quad \dots \dots \dots (2)$$

$$p_{yz} = 2\mu f, \quad p_{zx} = 2\mu g, \quad p_{xy} = 2\mu h \quad \dots \dots \dots (3)$$

The definition of p adopted in Art. 313 implies the relation

$$3\lambda + 2\mu = 0, \quad \dots \dots \dots (4)$$

whence, finally, introducing the values of a, b, c, f, g, h from Art. 30

$$\left. \begin{aligned} p_{xx} &= -p - \frac{2}{3}\mu \left(\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} \right) + 2\mu \frac{\partial u}{\partial x}, \\ p_{yy} &= -p - \frac{2}{3}\mu \left(\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} \right) + 2\mu \frac{\partial v}{\partial y}, \\ p_{zz} &= -p - \frac{2}{3}\mu \left(\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} \right) + 2\mu \frac{\partial w}{\partial z}, \end{aligned} \right\} \quad \dots \dots \dots (5)$$

$$\left. \begin{aligned} p_{yz} &= \mu \left(\frac{\partial w}{\partial y} + \frac{\partial v}{\partial z} \right) = p_{zy}, \\ p_{zx} &= \mu \left(\frac{\partial u}{\partial z} + \frac{\partial w}{\partial x} \right) = p_{xz}, \\ p_{xy} &= \mu \left(\frac{\partial v}{\partial x} + \frac{\partial u}{\partial y} \right) = p_{yx}. \end{aligned} \right\} \quad \dots \dots \dots (6)$$

The constant μ is called the 'coefficient of viscosity'. Its physical meaning may be illustrated by reference to the case of a fluid in what is called 'laminar' motion (Art. 30), i.e. the fluid moves in a system of parallel planes, the velocity being in direction everywhere the same, and in magnitude proportional to the distance from some fixed plane of the system. Each stratum of fluid will then exert on the one next to it a tangential traction, opposing the relative motion, whose amount per unit area is μ times the

variation of velocity per unit distance perpendicular to the planes. In symbols, if $u = \alpha y$, $v = 0$, $w = 0$, we have

$$p_{xx} = p_{yy} = p_{zz} = -p, \quad p_{yz} = 0, \quad p_{zx} = 0, \quad p_{xy} = \mu\alpha.$$

If $[M]$, $[L]$, $[T]$ denote the units of mass, length, and time, the dimensions of the p 's are $[ML^{-1}T^{-2}]$, and those of the rates of distortion (α , b , c , ...) are $[T^{-1}]$, so that the dimensions of μ are $[ML^{-1}T^{-1}]$.

The stresses in different fluids, under similar circumstances of motion, will be proportional to the corresponding values of μ ; but if we wish to compare their effects in modifying the existing motion we have to take account of the ratio of these stresses to the inertia of the fluid. From this point of view, the determining quantity is the ratio μ/ρ , it is therefore usual to denote this by a special symbol ν , called by Maxwell the 'kinematic coefficient' of viscosity. The dimensions of ν are $[L^2T^{-1}]^*$.

It will be noticed that the hypothesis made above that the stresses p_{xx} , p_{xy} , ... are *linear* functions of the rates of strain α , b , c , ... is of a purely tentative character, and that although there is considerable *à priori* probability that it will represent the facts accurately in the case of infinitely small motions, we have so far no assurance that it will hold generally. It has however been pointed out by Prof. Osborne Reynolds† that the equations based on this hypothesis have been put to a very severe test in the experiments of Poiseuille and others, to be referred to presently (Art 319). Considering the very wide range of values of the rates of distortion over which these experiments extend, we can hardly hesitate to accept the equations in question as a complete statement of the laws of viscosity. In the case of gases we have additional grounds for this assumption in the investigations of the kinetic theory by Maxwell‡.

The practical determination of μ (or ν) is a matter of some difficulty. Without entering into the details of experimental methods, we quote a few of the best-established results. The calculations of von Helmholtz§, based on Poiseuille's observations, give for water

$$\mu = \frac{0178}{1 + 0337\theta + 000221\theta^2},$$

in c.g.s. units, where θ is the temperature Centigrade. The viscosity, as in the case of all liquids as yet investigated, diminishes rapidly as the temperature rises, thus at 17°C the value is $\mu_{17} = 0109$.

* In compressible fluids there may, on a certain view, be a second coefficient of viscosity, involved in the expression for the mean pressure p as depending on the physical state, and the rate of expansion. See Arts 313, 341.

† "On the Theory of Lubrication, &c.," *Phil. Trans.*, t. clxxvii p. 157 (1886) [*Sc. Papers*, t. ii p. 228].

‡ "On the Dynamical Theory of Gases," *Phil. Trans.*, t. clvii p. 49 (1866) [*Sc. Papers*, t. ii p. 26].

§ "Ueber Reibung tropfbarer Flüssigkeiten," *Wien Sitzungsber.*, t. xl. p. 607 (1860) [*Ges. Abh.* t. i p. 172].

For mercury Koch* found

$$\mu_0 = 01697, \text{ and } \mu_{10} = 01633,$$

respectively

In gases, the value of μ is found to be sensibly independent of the pressure, within very wide limits, but to *increase* somewhat with rise of temperature Maxwell found as the result of his experiments on vibrating disks†,

$$\mu = 0001878(1 + 00366 \theta),$$

this makes μ proportional to the absolute temperature as measured by the air-thermometer Subsequent observers have found a somewhat smaller value for the first factor, and a less rapid increase with temperature We may take perhaps as a fairly approximate value

$$\mu_0 = 000170$$

for the temperature 0°C For air at atmospheric pressure, assuming $\rho = 00129$ this gives

$$\nu_0 = 132$$

The value of ν varies inversely as the pressure.‡

315 We have still to inquire into the dynamical conditions to be satisfied at the boundaries

At a free surface, or at the surface of contact of two dissimilar fluids, the three components of stress across the surface must be continuous§ The resulting conditions can easily be written down with the help of Art 313 (4).

A more difficult question arises as to the state of things at the surface of contact of a fluid with a solid It appears probable that in all ordinary cases there is no motion, relative to the solid, of the fluid immediately in contact with it. The contrary supposition would imply an infinitely greater resistance to the sliding of one portion of the fluid past another than to the sliding of the fluid over a solid||.

If however we wish, temporarily, to leave this point open, the most natural supposition to make is that the slipping is resisted by a tangential force proportional to the relative velocity If we consider the motion of a small film of fluid, of thickness infinitely small compared with its lateral dimensions, in contact with the solid, it is evident that the tangential traction on its inner surface must ultimately balance the force exerted on its outer surface by the solid The former force may be calculated from Art. 313 (4); the latter is in a direction opposite to the relative velocity, and proportional to it The constant (β , say) which expresses the ratio of the tangential force to the relative velocity may be called the 'coefficient of sliding friction'

* *Wied Ann*, t. xiv (1881)

† "On the Viscosity or Internal Friction of Air and other Gases," *Phil Trans*, t. clvi p 249 (1866) [*Sc Papers*, t. ii. p 1] See also Tomlinson, "The Coefficient of Viscosity of Air," *Phil Trans*, t. clxxvii p 767 (1886) [Stokes' *Math and Phys Papers*, t. v p 180].

‡ A very full account of the results obtained by various experimenters is given in Winkelmann's *Handbuch der Physik*, t. i, Art 'Reibung'

§ This statement requires an obvious modification when capillarity is taken into account Cf Art. 332

|| Stokes, *l c post* p 539.

316. The equations of motion of a viscous fluid are obtained by considering, as in Art. 6, a rectangular element $\delta x \delta y \delta z$ having its centre at P . Taking, for instance, the resolution parallel to x , the difference of the normal tractions on the two yz -faces gives $(\partial p_{xx}/\partial x) \delta x \delta y \delta z$. The tangential tractions on the two xz -faces contribute $(\partial p_{yx}/\partial y) \delta y \delta z \delta x$, and the two xy -faces give in like manner $(\partial p_{zx}/\partial z) \delta z \delta x \delta y$. Hence, with our usual notation,

$$\left. \begin{aligned} \rho \frac{Du}{Dt} &= \rho X + \frac{\partial p_{xx}}{\partial x} + \frac{\partial p_{yx}}{\partial y} + \frac{\partial p_{zx}}{\partial z}, \\ \rho \frac{Dv}{Dt} &= \rho Y + \frac{\partial p_{xy}}{\partial x} + \frac{\partial p_{yy}}{\partial y} + \frac{\partial p_{zy}}{\partial z}, \\ \rho \frac{Dw}{Dt} &= \rho Z + \frac{\partial p_{xz}}{\partial x} + \frac{\partial p_{yz}}{\partial y} + \frac{\partial p_{zz}}{\partial z}. \end{aligned} \right\} \dots\dots\dots (1)$$

Substituting the values of p_{xx} , p_{xy} , ... from Art. 314 (5), (6), we find

$$\left. \begin{aligned} \rho \frac{Du}{Dt} &= \rho X - \frac{\partial p}{\partial x} + \frac{1}{3} \mu \frac{\partial \theta}{\partial x} + \mu \nabla^2 u, \\ \rho \frac{Dv}{Dt} &= \rho Y - \frac{\partial p}{\partial y} + \frac{1}{3} \mu \frac{\partial \theta}{\partial y} + \mu \nabla^2 v, \\ \rho \frac{Dw}{Dt} &= \rho Z - \frac{\partial p}{\partial z} + \frac{1}{3} \mu \frac{\partial \theta}{\partial z} + \mu \nabla^2 w, \end{aligned} \right\} \dots\dots\dots (2)$$

where
$$\theta = \frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z}, \dots\dots\dots (3)$$

and ∇^2 has its usual meaning.

When the fluid is incompressible, these reduce to

$$\left. \begin{aligned} \rho \frac{Du}{Dt} &= \rho X - \frac{\partial p}{\partial x} + \mu \nabla^2 u, \\ \rho \frac{Dv}{Dt} &= \rho Y - \frac{\partial p}{\partial y} + \mu \nabla^2 v, \\ \rho \frac{Dw}{Dt} &= \rho Z - \frac{\partial p}{\partial z} + \mu \nabla^2 w. \end{aligned} \right\} \dots\dots\dots (4)$$

These dynamical equations were first obtained by Navier* and Poisson† on various considerations as to the mutual action of the ultimate molecules of fluids. The method above adopted, which is free from all hypothesis

* "Mémoire sur les Loix du Mouvement des Fluides," *Mém. de l'Acad. des Sciences*, t. vi. p. 389 (1822)

† "Mémoire sur les Équations générales de l'Équilibre et du Mouvement des Corps solides élastiques et des Fluides," *Journ. de l'École Polytechn.*, t. xiii. p. 1 (1829)

of this kind, appears to be due in principle to de Saint-Venant* and Stokes†

The equations (4) admit of an interesting interpretation. The first of them, for example, may be written

$$\frac{Du}{Dt} = X - \frac{1}{\rho} \frac{\partial p}{\partial x} + \nu \nabla^2 u \quad (5)$$

The first two terms on the right hand express the rate of variation of u in consequence of the external forces and of the instantaneous distribution of pressure, and have the same forms as in the case of a frictionless liquid. The remaining term $\nu \nabla^2 u$, due to viscosity, gives an additional variation following the same law as that of temperature in Thermal Conduction, or of density in the theory of Diffusion. This variation is in fact proportional to the (positive or negative) excess of the mean value of u through a small sphere of given radius surrounding the point (x, y, z) over its value at that point‡. In connection with this analogy it is interesting to note that the value of ν for water is of the same order of magnitude as that (0.01249) found by Dr Everett for the thermometric conductivity of the Greenwich gravel.

When the forces X, Y, Z have a potential Ω , the equations (4) may be written

$$\left. \begin{aligned} \frac{\partial u}{\partial t} - 2v\zeta + 2w\eta &= -\frac{\partial X'}{\partial x} + \nu \nabla^2 u, \\ \frac{\partial v}{\partial t} - 2w\xi + 2u\zeta &= -\frac{\partial X'}{\partial y} + \nu \nabla^2 v, \\ \frac{\partial w}{\partial t} - 2u\eta + 2v\xi &= -\frac{\partial X'}{\partial z} + \nu \nabla^2 w, \end{aligned} \right\} \dots\dots\dots (6)$$

where

$$X = \frac{p}{\rho} + \frac{1}{2}q^2 + \Omega, \quad \dots \dots \dots (7)$$

q denoting the resultant velocity, and ξ, η, ζ the components of the angular velocity of the fluid. If we eliminate X' by cross-differentiation, we find

$$\left. \begin{aligned} \frac{D\xi}{Dt} &= \xi \frac{\partial u}{\partial x} + \eta \frac{\partial u}{\partial y} + \zeta \frac{\partial u}{\partial z} + \nu \nabla^2 \xi, \\ \frac{D\eta}{Dt} &= \xi \frac{\partial v}{\partial x} + \eta \frac{\partial v}{\partial y} + \zeta \frac{\partial v}{\partial z} + \nu \nabla^2 \eta, \\ \frac{D\zeta}{Dt} &= \xi \frac{\partial w}{\partial x} + \eta \frac{\partial w}{\partial y} + \zeta \frac{\partial w}{\partial z} + \nu \nabla^2 \zeta. \end{aligned} \right\} \dots \dots \dots (8)$$

The first three terms on the right hand of each of these equations express, as in Art 146, the rates at which ξ, η, ζ vary for a given particle, when the vortex-lines move with the fluid, and the strengths of the vortices remain constant. The additional variation of these quantities, due to viscosity, is given by the last terms, and follows the law of conduction of heat. It is evident from this analogy that vortex-motion cannot originate in the interior of a viscous liquid, but must be diffused inwards from the boundary.

* *Comptes Rendus*, t. xvii. p. 1240 (1843).

† "On the Theories of the Internal Friction of Fluids in Motion, &c.," *Camb. Trans.*, t. viii. p. 287 (1845) [*Math. and Phys. Papers*, t. i. p. 75].

‡ Maxwell, "On the Mathematical Classification of Physical Quantities," *Proc. Lond. Math. Soc.*, t. iii. p. 224 (1871) [*Sc. Papers*, t. ii. p. 257], *Electricity and Magnetism*, Art. 26.

317. To compute the rate of dissipation of energy, due to viscosity, we consider first the portion of fluid which at time t occupies a rectangular element $\delta x \delta y \delta z$ having its centre at (x, y, z) . Calculating the rates at which work is being done by the tractions on the pairs of opposite faces, we obtain

$$\left\{ \frac{\partial}{\partial x} (p_{xx}u + p_{xy}v + p_{xz}w) + \frac{\partial}{\partial y} (p_{yx}u + p_{yy}v + p_{yz}w) + \frac{\partial}{\partial z} (p_{zx}u + p_{zy}v + p_{zz}w) \right\} \delta x \delta y \delta z. \quad \dots\dots (1)$$

The terms

$$\left\{ \left(\frac{\partial p_{xx}}{\partial x} + \frac{\partial p_{yx}}{\partial y} + \frac{\partial p_{zx}}{\partial z} \right) u + \left(\frac{\partial p_{xy}}{\partial x} + \frac{\partial p_{yy}}{\partial y} + \frac{\partial p_{zy}}{\partial z} \right) v + \left(\frac{\partial p_{xz}}{\partial x} + \frac{\partial p_{yz}}{\partial y} + \frac{\partial p_{zz}}{\partial z} \right) w \right\} \delta x \delta y \delta z \quad \dots\dots\dots (2)$$

express, by Art. 316 (1), the rate at which the tractions on the faces are doing work on the element as a whole, in increasing its kinetic energy and in compensating the work done against the extraneous forces X, Y, Z . The remaining terms express the rate at which work is being done in changing the volume and shape of the element. They may be written

$$(p_{xx}a + p_{yy}b + p_{zz}c + 2p_{yz}f + 2p_{zx}g + 2p_{xy}h) \delta x \delta y \delta z, \quad \dots\dots\dots (3)$$

where a, b, c, f, g, h have the same meanings as in Arts. 30, 314. Substituting from Art. 314 (2), (3), we get

$$\begin{aligned} & -p(a + b + c) \delta x \delta y \delta z \\ & + \left\{ -\frac{2}{3}\mu(a + b + c)^2 + 2\mu(a^2 + b^2 + c^2 + 2f^2 + 2g^2 + 2h^2) \right\} \delta x \delta y \delta z. \quad \dots (4) \end{aligned}$$

It will be sufficient for the present to consider the case where there is no variation of density, so that

$$a + b + c = 0. \quad \dots\dots\dots (5)$$

The expression (4) then reduces to

$$2\mu(a^2 + b^2 + c^2 + 2f^2 + 2g^2 + 2h^2) \delta x \delta y \delta z, \quad \dots\dots\dots (6)$$

which accordingly represents the rate at which mechanical energy is disappearing. On the principles established by Joule, the energy thus apparently lost takes the form of heat, developed in the element.

If we integrate over the whole volume of the liquid, we find, for the total rate of dissipation,

$$2F = \iiint \Phi dx dy dz, \quad \dots\dots\dots (7)$$

where

$$\Phi = \mu \left\{ 2 \left(\frac{\partial u}{\partial x} \right)^2 + 2 \left(\frac{\partial v}{\partial y} \right)^2 + 2 \left(\frac{\partial w}{\partial z} \right)^2 + \left(\frac{\partial w}{\partial y} + \frac{\partial v}{\partial z} \right)^2 + \left(\frac{\partial u}{\partial z} + \frac{\partial w}{\partial x} \right)^2 + \left(\frac{\partial v}{\partial x} + \frac{\partial u}{\partial y} \right)^2 \right\} \quad \dots (8)^*$$

If we subtract from this the expression

$$2\mu \left(\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} \right)^2,$$

which is zero on the present hypothesis, we obtain

$$\Phi = \mu \left\{ \left(\frac{\partial u}{\partial y} - \frac{\partial v}{\partial z} \right)^2 + \left(\frac{\partial u}{\partial z} - \frac{\partial w}{\partial x} \right)^2 + \left(\frac{\partial v}{\partial x} - \frac{\partial w}{\partial y} \right)^2 \right\} - 4\mu \left(\frac{\partial v}{\partial y} \frac{\partial w}{\partial z} - \frac{\partial v}{\partial z} \frac{\partial w}{\partial y} + \frac{\partial w}{\partial z} \frac{\partial u}{\partial x} - \frac{\partial w}{\partial x} \frac{\partial u}{\partial z} + \frac{\partial u}{\partial x} \frac{\partial v}{\partial y} - \frac{\partial u}{\partial y} \frac{\partial v}{\partial x} \right) \quad \dots (9)$$

If we integrate this over a region such that u, v, w vanish at every point of the boundary, as in the case of a liquid filling a closed vessel, on the hypothesis of no slipping, the terms due to the second line vanish (after a partial integration), and we obtain

$$2F = \iiint \Phi dx dy dz = 4\mu \iiint (\xi^2 + \eta^2 + \zeta^2) dx dy dz \quad \dots \dots (10)^+$$

In the general case, when no limitation is made as to the boundary conditions, the formula (9) leads to

$$2F = 4\mu \iiint (\xi^2 + \eta^2 + \zeta^2) dx dy dz - \mu \iint \frac{\partial}{\partial n} \frac{q^2}{\partial n} dS + 4\mu \iint \int \left| \begin{matrix} l, & m, & n \\ u, & v, & w \\ \xi, & \eta, & \zeta \end{matrix} \right| dS, \quad \dots (11)$$

where, in the former of the two surface-integrals, δn denotes an element of the normal, and, in the latter, l, m, n are the direction-cosines of the normal, drawn inwards in each case from the surface-element δS .

When the motion considered is irrotational, this formula reduces to

$$2F = -\mu \iint \frac{\partial}{\partial n} \frac{q^2}{\partial n} dS, \quad \dots \dots \dots (12)$$

simply. In the particular case of a spherical boundary this expression follows independently from Art. 44 (5).

It appears from (8) that F cannot vanish unless

$$a=b=c=0, \text{ and } f=g=h=0,$$

at every point of the fluid. It follows, on reference to Art 30, that the only condition under which a liquid can be in motion without dissipation of energy by viscosity is that there must be nowhere any extension or contraction of linear elements, in other words, the motion must consist of a translation and a rotation of the mass as a whole, as in the case of a rigid body.

* Stokes, "On the Effect of the Internal Friction of Fluids on the Motion of Pendulums," *Camb. Trans.*, t. ix p [8] (1851) [*Sc. Papers*, t iii p 1]

+ Bolyeff, "Eingige Betrachtungen über die Gleichungen der Hydrodynamik," *Math Ann*, t. vi. p. 72 (1873); Forsyth, "On the Motion of a Viscous Incompressible Fluid," *Mess. of Math*, t. ix. (1880).

Problems of Steady Motion.

318. The first application which we shall consider is to the steady motion of liquid, under pressure, between two fixed parallel planes.

Let the origin be taken half-way between the planes, and the axis of z perpendicular to them. We assume, in the first instance, that u is a function of z only, and that $v, w = 0$. Since the traction parallel to x on any plane perpendicular to y is equal to $\mu \partial u / \partial z$, the difference of the tractions on the two faces of a stratum of unit area and thickness δz gives a resultant $\mu \partial^2 u / \partial z^2 \cdot \delta z$. This must be balanced by the normal pressures, which give a resultant $-\partial p / \partial x$ per unit volume of the stratum. Hence

$$\mu \frac{\partial^2 u}{\partial z^2} = \frac{\partial p}{\partial x} \quad \dots\dots\dots (1)$$

Also, since there is no motion parallel to y , $\partial p / \partial z$ must vanish. These results might of course have been obtained immediately from the general equations of Art. 316.

It follows that the pressure-gradient $\partial p / \partial x$ is an absolute constant. Hence (1) gives

$$u = A + Bz + \frac{1}{2\mu} z^2 \frac{\partial p}{\partial x}, \quad \dots\dots\dots (2)$$

and determining the constants so as to make $u = 0$ for $z = \pm h$, we find

$$u = -\frac{1}{2\mu} (h^2 - z^2) \frac{\partial p}{\partial x}. \quad \dots\dots\dots (3)$$

Hence

$$\int_{-h}^h u dz = -\frac{3\mu}{2h^3} \frac{\partial p}{\partial x}. \quad \dots\dots\dots (4)$$

When, as in Prof. Hele Shaw's experiments*, a liquid flows in two dimensions between close parallel plates, we may write

$$\mu \frac{\partial^2 u}{\partial z^2} = \frac{\partial p}{\partial x}, \quad \mu \frac{\partial^2 v}{\partial z^2} = \frac{\partial p}{\partial y}, \quad \dots\dots\dots (5)$$

provided we neglect the rates of variation of u, v with respect to x, y in comparison with their rates of variation with respect to z . Also, assuming that $w = 0$ everywhere, we have $\partial p / \partial z = 0$, i.e. p is a function of x and y only. The conditions of no slipping at the planes $z = \pm h$ are satisfied if we write

$$u = \frac{3}{2} \left(1 - \frac{z^2}{h^2}\right) u', \quad v = \frac{3}{2} \left(1 - \frac{z^2}{h^2}\right) v'. \quad \dots\dots\dots (6)$$

The quantities u', v' here denote the mean velocities along a line parallel to z , and are assumed to be functions of x, y only. Substituting in (5) we find

$$\frac{\partial p}{\partial x} = -\frac{3\mu}{h^2} u', \quad \frac{\partial p}{\partial y} = -\frac{3\mu}{h^2} v' \quad \dots\dots\dots (7)$$

* Referred to in the footnote on p. 80.

Hence u' , v' may be regarded as the components of an irrotational motion of a liquid in two dimensions, in which the velocity-potential is

$$\phi = \frac{h^2}{3\mu} p. \quad \dots \dots \dots (8)$$

The kinematical conditions, when the liquid is forced by pressure past an obstacle having the form of a lamina of thickness $2h$ placed between the plates, are accordingly identical, for the most part, with those relating to the two-dimensional flow of a *frictionless* fluid past a cylinder whose section has the shape of the lamina. The statement is made with a slight qualification, since the equations (5) must cease to hold at distance from the obstacle comparable with h , owing to the fact that the viscous liquid cannot glide past the surface of the obstacle, as a perfect fluid would do. But the configurations of the stream-lines in the two problems can be made as nearly the same as we choose by taking the plates sufficiently close together*

319 The investigation of the steady flow of a liquid through a straight pipe of uniform circular section is equally simple, and physically more important.

If we take the axis of z coincident with the axis of the tube, and assume that the velocity is everywhere parallel to z , and a function of the distance (r) from this axis, the tangential stress across a plane perpendicular to r will be $\mu \partial w / \partial r$. Hence, considering a cylindrical shell of fluid, whose bounding radii are r and $r + \delta r$, and whose length is l , the difference of the tangential tractions on the two curved surfaces gives a retarding force

$$-\frac{\partial}{\partial r} \left(\mu \frac{\partial w}{\partial r} \cdot 2\pi r l \right) \delta r.$$

On account of the steady character of the motion, this must be balanced by the normal pressures on the ends of the shell. Since $\partial w / \partial z = 0$, the difference of these normal pressures is equal to

$$(p_1 - p_2) 2\pi r \delta r,$$

where p_1 , p_2 are the values of p (the mean pressure) at the two ends. Hence

$$\frac{\partial}{\partial r} \left(r \frac{\partial w}{\partial r} \right) = -\frac{p_1 - p_2}{\mu l} \cdot r. \quad \dots \dots (1)$$

Again, if we resolve along the radius the forces acting on a rectangular element, we find $\partial p / \partial r = 0$, so that the mean pressure is uniform over each section of the pipe

The equation (1) might have been obtained from Art. 316 (4) by direct transformation of coordinates, putting

$$r = (x^2 + y^2)^{\frac{1}{2}}$$

* Stokes, "Mathematical Proof of the Identity of the Stream-Lines obtained by means of a Viscous Film with those of a Perfect Fluid moving in Two Dimensions," *Brit Ass Rep.*, 1898, p. 143 [*Math. and Phys. Papers*, t. v. p. 278]

The integral of (1) is

$$w = -\frac{p_1 - p_2}{4\mu l} r^2 + A \log r + B \quad \dots \dots \dots (2)$$

Since the velocity must be finite at the axis, we must have $A = 0$; and if we determine B on the hypothesis that there is no slipping at the wall of the pipe ($r = a$, say), we obtain

$$w = \frac{p_1 - p_2}{4\mu l} (a^2 - r^2). \quad \dots \dots \dots (3)$$

This gives, for the flux across any section,

$$\int_0^a w \, 2\pi r dr = \frac{\pi a^4}{8\mu} \cdot \frac{p_1 - p_2}{l} \quad \dots \dots \dots (4)$$

It has been assumed, for shortness, that the flow takes place under pressure only. If we have an extraneous force X acting parallel to the length of the pipe, the flux will be

$$\frac{\pi a^4}{8\mu} \left(\frac{p_1 - p_2}{l} + \rho X \right) \quad \dots \dots \dots (5)$$

In practice, X is the component of gravity in the direction of the length

The formula (4) contains exactly the laws found experimentally by Poiseuille* in his researches on the flow of water through capillary tubes, viz that the time of efflux of a given volume of water is directly as the length of the tube, inversely as the difference of pressure at the two ends, and inversely as the fourth power of the diameter.

This last result is of great importance as furnishing a conclusive proof that there is in these experiments no appreciable slipping of the fluid in contact with the wall. If we were to assume a slipping-coefficient β , as explained in Art 315, the surface-condition would be

$$-\mu \frac{\partial w}{\partial r} = \beta w,$$

or

$$w = -\lambda \frac{\partial w}{\partial r}, \quad \dots \dots \dots (6)$$

if $\lambda = \mu/\beta$. This determines B , in (2), so that

$$w = \frac{p_1 - p_2}{4\mu l} (a^2 - r^2 + 2\lambda a) \quad \dots \dots \dots (7)$$

If λ/a be small, this gives sensibly the same law of velocity as in a tube of radius $a + \lambda$, on the hypothesis of no slipping. The corresponding value of the flux is

$$\frac{\pi a^4}{8\mu} \cdot \frac{p_1 - p_2}{l} \cdot \left(1 + 4 \frac{\lambda}{a} \right) \quad \dots \dots \dots (8)$$

If λ were more than a very minute fraction of a in the narrowest tubes employed by Poiseuille [$a = 0.015$ cm] a deviation from the law of the fourth power of the diameter,

* "Recherches expérimentales sur le mouvement des liquides dans les tubes de très petits diamètres," *Comptes Rendus*, tt xi, xii (1840-1), *Mém des Sav Étrangers*, t ix (1846).

which was found to hold very exactly, would become apparent. This is sufficient to exclude the possibility of values of λ such as 235 cm, which were inferred by Helmholtz and Piotrowski from their experiments on the torsional oscillations of a metal globe filled with water, described in the paper already cited*.

The assumption of no slipping being thus justified, the comparison of the formula (4) with experiment gives a very direct means of determining the value of the coefficient μ for various fluids.

It is easily found from (3) and (4) that the rate of shear close to the wall of the tube is equal to $4w_0/a$, where w_0 is the mean velocity over the cross-section. As a numerical example, we may take a case given by Poiseuille, where a mean velocity of 126.6 c.s. was obtained in a tube of .01134 cm. diameter. This makes $4w_0/a = 89300$, if the unit of time be the second.

320. Some theoretical results for sections other than circular may be briefly noticed.

1°. The solution for a channel of *annular* section is readily deduced from equation (2) of the preceding Art, with A retained. Thus if the boundary-conditions be that $w=0$ for $r=a$ and $r=b$, we find

$$w = \frac{p_1 - p_2}{4\mu l} \left\{ \alpha^2 - r^2 + \frac{b^2 - \alpha^2}{\log b/a} \log \frac{r}{a} \right\}, \quad \dots \dots (1)$$

giving a flux
$$\int_a^b w \cdot 2\pi r dr = \frac{\pi}{8\mu} \frac{p_1 - p_2}{l} \left\{ b^4 - \alpha^4 - \frac{(b^2 - \alpha^2)^2}{\log b/a} \right\} \dots \dots (2)$$

2°. It has been pointed out by Greenhill† that the analytical conditions of the present problem are similar to those which determine the motion of a frictionless liquid in a rotating prismatic vessel of the same form of section (Art. 72). If the axis of z be parallel to the length of the pipe, and if we assume that w is a function of x, y only, then in the case of steady motion the equations reduce to

$$\left. \begin{aligned} \frac{\partial p}{\partial x} = 0, \quad \frac{\partial p}{\partial y} = 0, \\ \mu \nabla_1^2 w = \frac{\partial p}{\partial z}, \end{aligned} \right\} \dots \dots \dots (3)$$

where $\nabla_1^2 = \partial^2/\partial x^2 + \partial^2/\partial y^2$. Hence, denoting by P the constant pressure-gradient ($-\partial p/\partial z$), we have

$$\nabla_1^2 w = -\frac{P}{\mu}, \quad \dots \dots \dots (4)$$

with the condition that $w=0$ at the boundary. If we write $\psi - \frac{1}{2}\omega(x^2 + y^2)$ for w , and 2ω for P/μ , we reproduce the conditions of the Art. referred to. This proves the analogy in question.

In the case of an elliptic section of semi-axes a, b , we assume

$$w = C \left(1 - \frac{x^2}{a^2} - \frac{y^2}{b^2} \right), \quad \dots \dots \dots (5)$$

* For a fuller discussion of this point see Whetham, "On the alleged Slipping at the Boundary of a Liquid in Motion," *Phil. Trans.*, A. t. clxxx. p. 559 (1890).

† "On the Flow of a Viscous Liquid in a Pipe or Channel," *Proc. Lond. Math. Soc.*, t. xiii. p. 43 (1881).

which will satisfy (4) provided

$$C = \frac{P}{2\mu} \cdot \frac{\alpha^2 b^2}{\alpha^2 + b^2} \quad \dots \dots \dots (6)$$

The discharge per second is therefore

$$\iint w dx dy = \frac{P}{4\mu} \cdot \frac{\pi \alpha^3 b^3}{\alpha^2 + b^2} \quad \dots \quad (7)^*$$

This bears to the discharge through a circular pipe of the same sectional area the ratio $2ab/(\alpha^2 + b^2)$. For small values of the eccentricity (e) this fraction differs from unity by a quantity of the order e^4 . Hence considerable variations may exist in the shape of the section without seriously affecting the discharge, provided the sectional area be unaltered. Even when $\alpha/b = 8/7$, the discharge is diminished by less than one per cent.

321 We consider next some simple cases of steady rotatory motion

The first is that of two-dimensional rotation about the axis of z , the angular velocity being a function of the distance (r) from this axis. Writing

$$u = -\omega y, \quad v = \omega x, \quad \dots \dots \dots (1)$$

we find that the rates of extension along and perpendicular to the radius vector are zero, whilst the rate of shear in the plane xy is $r d\omega/dr$. Hence the moment, about the axis, of the tangential forces on a cylindrical surface of radius r , is per unit length of the axis, $= \mu r d\omega/dr \cdot 2\pi r \cdot r$. On account of the steady motion, the fluid included between two coaxial cylinders is neither gaining nor losing angular momentum, so that the above expression must be independent of r . This gives

$$\omega = \frac{A}{r^2} + B \quad \dots \dots \dots (2)$$

If the fluid extend to infinity, while the internal boundary is that of a solid cylinder of radius a , whose angular velocity is ω_0 , we have

$$\omega = \omega_0 \frac{a^2}{r^2} \quad \dots \dots \dots (3)$$

The frictional couple on the cylinder is therefore

$$-4\pi\mu a^2 \omega_0 \quad \dots \dots \dots (4)$$

If the fluid were bounded externally by a fixed coaxial cylindrical surface of radius b we should find

$$\omega = \frac{a^2}{r^2} \cdot \frac{b^2 - r^2}{b^2 - a^2} \omega_0, \quad \dots \dots \dots (5)$$

which gives a frictional couple

$$-4\pi\mu \cdot \frac{a^2 b^2}{b^2 - a^2} \cdot \omega_0 \quad \dots \dots \dots (6)^\dagger$$

* This, with corresponding results for some other forms of section, appears to have been obtained by Boussinesq in 1868, see Hicks, *Brit Ass Rep*, 1882, p. 63.

† This problem was first treated, not quite accurately, by Newton, *Principia*, Lib. II, Prop. 51. The above results were given substantially by Stokes, *l. cc. ante* pp. 539, 541.

322 A similar solution, restricted however to the case of infinitely small motions, can be obtained for the steady motion of a fluid surrounding a solid sphere which is made to rotate uniformly about a diameter. Taking the centre as origin, and the axis of rotation as axis of x , we assume

$$u = -\omega y, \quad v = \omega x, \quad w = 0, \quad \dots \dots (1)$$

where ω is a function of the radius vector r , only. If we put

$$P = \int \omega r dr, \quad \dots \dots \dots (2)$$

these equations may be written

$$u = -\frac{\partial P}{\partial y}, \quad v = \frac{\partial P}{\partial x}, \quad w = 0, \quad \dots \dots (3)$$

and it appears on substitution in Art 316 (4) that, provided we neglect the terms of the second order in the velocities, the equations are satisfied by

$$p = \text{const}, \quad \nabla^2 P = \text{const} \quad \dots \dots \dots (4)$$

The latter equation may be written

$$\frac{d^2 P}{dr^2} + \frac{2}{r} \frac{dP}{dr} = \text{const.}, \quad \text{or} \quad r \frac{d\omega}{dr} + 3\omega = \text{const.}, \quad \dots \dots (5)$$

whence

$$\omega = \frac{A}{r^3} + B \quad \dots \dots \dots (6)$$

If the fluid extend to infinity and is at rest there, whilst ω_0 is the angular velocity of the rotating sphere ($r = a$), we have

$$\omega = \frac{a^3}{r^3} \omega_0. \quad \dots \dots \dots (7)$$

If the external boundary be a fixed concentric sphere of radius b the solution is

$$\omega = \frac{a^3}{r^3} \frac{b^3 - r^3}{b^3 - a^3} \omega_0. \quad \dots \dots \dots (8)$$

The retarding couple on the sphere may be calculated directly by means of the formulae of Art 314, or, perhaps more simply, by means of the Dissipation Function of Art 317. We find without difficulty that the rate of dissipation of energy is

$$\mu \iiint (x^2 + y^2) \left(\frac{d\omega}{dr} \right)^2 dx dy dz = 3\pi\mu \int_a^b r^4 \left(\frac{d\omega}{dr} \right)^2 dr = 8\pi\mu \frac{a^3 b^3}{b^3 - a^3} \omega_0^2 \quad (9)$$

If N denote the couple which must be applied to the sphere to maintain the rotation, this expression must be equivalent to $N\omega_0$, whence

$$N = 8\pi\mu \frac{a^3 b^3}{b^3 - a^3} \omega_0, \quad \dots \dots \dots (10)$$

or, in the case corresponding to (7), where $b = \infty$,

$$N = 8\pi\mu a^3 \omega_0 \quad \dots \dots \dots (11)^*$$

* Kirchhoff, *Mechanik*, c. xxvi

The neglect of the terms of the second order in this problem involves a more serious limitation of its practical value than might be expected. It is not difficult to ascertain that the assumption virtually made is that the ratio $\omega_0 a^2/\nu$ is small. If we put $\nu = 0.018$ (water), and $a = 10$, we find that the equatorial velocity $\omega_0 a$ must be small compared with 0.018 (c.s.)*

When the terms of the second order are sensible, no steady motion of the above kind is possible. The sphere then acts like a centrifugal fan, the motion at a distance from the sphere consisting of a flow outwards from the equator and inwards towards the poles, superposed on a motion of rotation†

It appears from Art. 316 that the equations of motion may be written

$$\frac{\partial u}{\partial t} - 2v\zeta + 2w\eta = X - \frac{\partial \chi'}{\partial x} + \nu \nabla^2 u, \quad \dots \dots \dots (12)$$

where

$$\chi' = \frac{p}{\rho} + \frac{1}{2}q^2 \quad \dots \dots \dots (13)$$

Hence a steady motion which satisfies the conditions of any given problem, when the terms of the second order are neglected, will hold when these are retained, provided we introduce the constraining forces

$$X = 2(w\eta - v\zeta), \quad Y = 2(u\zeta - w\xi), \quad Z = 2(v\xi - u\eta) \quad \dots \dots (14)^\ddagger$$

The only change is that the pressure p is diminished by $\frac{1}{2}\rho q^2$. These forces are everywhere perpendicular to the stream-lines and to the vortex-lines, and their intensity is given by the product $2q\omega \sin \chi$, where ω is the angular velocity of the fluid element, and χ is the angle between the direction of the velocity q and the axis of the rotation ω .

In the problem investigated in this Art. it is evident *à priori* that the constraining forces

$$X = -\omega^2 x, \quad Y = -\omega^2 y, \quad Z = 0 \quad \dots \dots \dots (15)$$

would make the solution rigorous. It may easily be verified that these expressions differ from (14) by terms of the forms $-\partial\Omega/\partial x$, $-\partial\Omega/\partial y$, $-\partial\Omega/\partial z$, respectively, which will only modify the pressure.

323. The motion of a viscous incompressible fluid, when the effects of inertia are insensible, can be treated in a very general manner, in terms of spherical harmonic functions.

It will be convenient, in the first place, to investigate the general solution of the following system of equations

$$\nabla^2 u' = 0, \quad \nabla^2 v' = 0, \quad \nabla^2 w' = 0, \quad \dots \dots \dots (1)$$

$$\frac{\partial u'}{\partial x} + \frac{\partial v'}{\partial y} + \frac{\partial w'}{\partial z} = 0 \quad \dots \dots \dots (2)$$

The functions u' , v' , w' may be expanded in series of solid harmonics, and

* Cf. Lord Rayleigh, "On the Flow of Viscous Liquids, especially in two Dimensions," *Phil. Mag.* (4), t. xxxvi p. 354 (1893) [*Sc. Papers*, t. iv. p. 78]

† Stokes, *l.c.* ante p. 539.

‡ Lord Rayleigh, *l.c.*

it is plain that the terms of algebraical degree n in these expansions, say u_n', v_n', w_n' , must separately satisfy (2). The equations (1) may therefore be put in the forms

$$\left. \begin{aligned} \frac{\partial}{\partial y} \left(\frac{\partial v_n'}{\partial x} - \frac{\partial u_n'}{\partial y} \right) &= \frac{\partial}{\partial z} \left(\frac{\partial u_n'}{\partial z} - \frac{\partial w_n'}{\partial x} \right), \\ \frac{\partial}{\partial z} \left(\frac{\partial w_n'}{\partial y} - \frac{\partial v_n'}{\partial z} \right) &= \frac{\partial}{\partial x} \left(\frac{\partial v_n'}{\partial x} - \frac{\partial u_n'}{\partial y} \right), \\ \frac{\partial}{\partial x} \left(\frac{\partial u_n'}{\partial z} - \frac{\partial w_n'}{\partial x} \right) &= \frac{\partial}{\partial y} \left(\frac{\partial w_n'}{\partial y} - \frac{\partial v_n'}{\partial z} \right) \end{aligned} \right\} \dots \dots \dots (3)$$

Hence

$$\frac{\partial w_n'}{\partial y} - \frac{\partial v_n'}{\partial z} = \frac{\partial \chi_n}{\partial x}, \quad \frac{\partial u_n'}{\partial z} - \frac{\partial w_n'}{\partial x} = \frac{\partial \chi_n}{\partial y}, \quad \frac{\partial v_n'}{\partial x} - \frac{\partial u_n'}{\partial y} = \frac{\partial \chi_n}{\partial z}, \dots (4)$$

where χ_n is some function of x, y, z , and it further appears from these relations that $\nabla^2 \chi_n = 0$, so that χ_n is a solid harmonic of degree n .

From (4) we also obtain

$$z \frac{\partial \chi_n}{\partial y} - y \frac{\partial \chi_n}{\partial z} = x \frac{\partial u_n'}{\partial x} + y \frac{\partial u_n'}{\partial y} + z \frac{\partial u_n'}{\partial z} + u_n' - \frac{\partial}{\partial x} (xu_n' + yv_n' + zw_n'), \dots (5)$$

with two similar equations. Now it follows from (1) and (2) that

$$\nabla^2 (xu_n' + yv_n' + zw_n') = 0, \quad \dots \dots \dots (6)$$

so that we may write

$$xu_n' + yv_n' + zw_n' = \phi_{n+1}, \quad \dots \dots \dots (7)$$

where ϕ_{n+1} is a solid harmonic of degree $n+1$. Hence (5) may be written

$$(n+1) u_n' = \frac{\partial \phi_{n+1}}{\partial x} + z \frac{\partial \chi_n}{\partial y} - y \frac{\partial \chi_n}{\partial z}. \quad \dots \dots \dots (8)$$

The factor $n+1$ may be dropped without loss of generality, and we obtain as the solution of the proposed system of equations.

$$\left. \begin{aligned} u' &= \Sigma \left(\frac{\partial \phi_n}{\partial x} + z \frac{\partial \chi_n}{\partial y} - y \frac{\partial \chi_n}{\partial z} \right), \\ v' &= \Sigma \left(\frac{\partial \phi_n}{\partial y} + x \frac{\partial \chi_n}{\partial z} - z \frac{\partial \chi_n}{\partial x} \right), \\ w' &= \Sigma \left(\frac{\partial \phi_n}{\partial z} + y \frac{\partial \chi_n}{\partial x} - x \frac{\partial \chi_n}{\partial y} \right), \end{aligned} \right\} \dots \dots \dots (9)$$

where the harmonics ϕ_n, χ_n are arbitrary*.

* Cf. Borchardt, "Untersuchungen über die Elasticität fester Körper unter Berücksichtigung der Wärme," *Berl. Monatsber.*, Jan 9, 1873 [*Gesammelte Werke*, Berlin, 1888, p 245]. The investigation in the text is from a paper "On the Oscillations of a Viscous Spheroid," *Proc. Lond. Math. Soc.*, t xiii p 51 (1881).

324 If we neglect the inertia-terms, the equations of motion of a viscous liquid reduce, in the absence of extraneous forces, to the forms

$$\mu \nabla^2 u = \frac{\partial p}{\partial x}, \quad \mu \nabla^2 v = \frac{\partial p}{\partial y}, \quad \mu \nabla^2 w = \frac{\partial p}{\partial z}, \quad \dots \dots (1)$$

with
$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 0 \quad \dots \dots \dots (2)$$

By differentiation we obtain

$$\nabla^2 p = 0, \quad \dots \dots \dots (3)$$

so that p can be expanded in a series of solid harmonics, thus

$$p = \Sigma p_n. \quad \dots \dots \dots (4)$$

The terms of the solution which involve harmonics of different algebraical degrees will be independent. To obtain the terms in p_n we assume

$$\left. \begin{aligned} u &= A r^2 \frac{\partial p_n}{\partial x} + B r^{2n+3} \frac{\partial}{\partial x} \frac{p_n}{r^{2n+1}}, \\ v &= A r^2 \frac{\partial p_n}{\partial y} + B r^{2n+3} \frac{\partial}{\partial y} \frac{p_n}{r^{2n+1}}, \\ w &= A r^2 \frac{\partial p_n}{\partial z} + B r^{2n+3} \frac{\partial}{\partial z} \frac{p_n}{r^{2n+1}}, \end{aligned} \right\} \quad \dots \dots \dots (5)$$

where $r^2 = x^2 + y^2 + z^2$. The terms multiplied by B are solid harmonics of degree $n+1$, by Arts. 81, 83. Now

$$\nabla^2 \left(r^2 \frac{\partial p_n}{\partial x} \right) = r^2 \nabla^2 \frac{\partial p_n}{\partial x} + 4 \left(x \frac{\partial}{\partial x} + y \frac{\partial}{\partial y} + z \frac{\partial}{\partial z} \right) \frac{\partial p_n}{\partial x} + \frac{\partial p_n}{\partial x} \nabla^2 r^2 = 2(2n+1) \frac{\partial p_n}{\partial x}.$$

Hence the equations (1) are satisfied, provided

$$A = \frac{1}{2(2n+1)\mu}. \quad \dots \dots \dots (6)$$

Also, substituting in (2), we find

$$2nA - (n+1)(2n+3)B = 0,$$

whence

$$B = \frac{n}{(n+1)(2n+1)(2n+3)\mu}. \quad \dots \dots \dots (7)$$

Hence the general solution of the system (1) and (2) is

$$\left. \begin{aligned} u &= \frac{1}{\mu} \Sigma \left\{ \frac{r^2}{2(2n+1)} \frac{\partial p_n}{\partial x} + \frac{n r^{2n+3}}{(n+1)(2n+1)(2n+3)} \frac{\partial}{\partial x} \frac{p_n}{r^{2n+1}} \right\} + u', \\ v &= \frac{1}{\mu} \Sigma \left\{ \frac{r^2}{2(2n+1)} \frac{\partial p_n}{\partial y} + \frac{n r^{2n+3}}{(n+1)(2n+1)(2n+3)} \frac{\partial}{\partial y} \frac{p_n}{r^{2n+1}} \right\} + v', \\ w &= \frac{1}{\mu} \Sigma \left\{ \frac{r^2}{2(2n+1)} \frac{\partial p_n}{\partial z} + \frac{n r^{2n+3}}{(n+1)(2n+1)(2n+3)} \frac{\partial}{\partial z} \frac{p_n}{r^{2n+1}} \right\} + w', \end{aligned} \right\} \quad (8)$$

where u' , v' , w' have the forms given in (9) of the preceding Art.*

* This investigation is derived, with some modifications, from various sources Cf. Thomson and Tait, *Natural Philosophy*, Art 736, Borchardt, *l.c.*, Oberbeck, "Ueber stationäre Flüssigkeitsbewegungen mit Berücksichtigung der inneren Reibung," *Crelle*, t lxxxix p 62 (1876).

The formulae (8) make

$$xu + yv + zw = \frac{1}{\mu} \sum \frac{nr^2}{2(2n+3)} p_n + \sum n \phi_n. \quad \dots\dots\dots (9)$$

Also, if we denote by ξ, η, ζ the components of the angular velocity of the fluid (Art 30), we find

$$\left. \begin{aligned} 2\xi &= \frac{1}{\mu} \sum \frac{1}{(n+1)} \left(y \frac{\partial p_n}{\partial z} - z \frac{\partial p_n}{\partial y} \right) + \sum (n+1) \frac{\partial \chi_n}{\partial x}, \\ 2\eta &= \frac{1}{\mu} \sum \frac{1}{(n+1)} \left(z \frac{\partial p_n}{\partial x} - x \frac{\partial p_n}{\partial z} \right) + \sum (n+1) \frac{\partial \chi_n}{\partial y}, \\ 2\zeta &= \frac{1}{\mu} \sum \frac{1}{(n+1)} \left(x \frac{\partial p_n}{\partial y} - y \frac{\partial p_n}{\partial x} \right) + \sum (n+1) \frac{\partial \chi_n}{\partial z} \end{aligned} \right\} \dots\dots (10)$$

These make $2(x\xi + y\eta + z\zeta) = \sum n(n+1) \chi_n \quad \dots\dots\dots (11)$

325. The results of Arts 323, 324 can be applied to the solution of a number of problems where the boundary conditions have relation to spherical surfaces. The most interesting cases fall under one or other of two classes, viz. we either have

$$xu + yv + zw = 0, \quad \dots\dots\dots (1)$$

everywhere, and therefore $p_n = 0, \phi_n = 0$, or

$$x\xi + y\eta + z\zeta = 0, \quad \dots\dots\dots (2)$$

and therefore $\chi_n = 0$

1°. Let us investigate the steady motion of a liquid past a fixed spherical obstacle. If we take the origin at the centre, and the axis of x parallel to the flow, the boundary conditions are that $u=0, v=0, w=0$ for $r=a$ (the radius), and $u=U, v=0, w=0$ for $r=\infty$. It is obvious that the vortex-lines will be circles about the axis of x , so that the relation (2) will be fulfilled. Again, the equation (9) of Art 324, taken in conjunction with the condition to be satisfied at infinity, shews that as regards the functions p_n and ϕ_n we are limited to surface-harmonics of the first order, and therefore to the cases $n=1, n=-2$. Also, we must evidently have $p_1=0$. Assuming, then,

$$p_{-2} = A \frac{x}{r^3}, \quad \phi_1 = Ux, \quad \phi_{-2} = B \frac{x}{r^3}, \quad \dots\dots\dots (3)$$

we find

$$\left. \begin{aligned} u &= -\frac{A}{6\mu r^3} (r^2 - 3x^2) + \frac{2A}{3\mu r} + \frac{B}{r^5} (r^2 - 3x^2) + U, \\ v &= \frac{A}{2\mu r^3} xy - \frac{3B}{r^5} xy, \\ w &= \frac{A}{2\mu r^3} xz - \frac{3B}{r^5} xz \end{aligned} \right\} \dots\dots\dots (4)$$

The condition of no slipping at the surface $r=a$ gives

$$\begin{aligned} \frac{2A}{3\mu a} + U &= 0, & \frac{A}{2\mu a} - \frac{3B}{a^3} &= 0, \\ \text{or } A &= -\frac{3}{2}\mu Ua, & B &= -\frac{1}{4}Ua^3 \quad \dots\dots\dots (5) \end{aligned}$$

Hence

$$\left. \begin{aligned} u &= -\frac{3}{4} \frac{Ua}{r^3} \left(1 - \frac{\alpha^2}{r^2}\right) x^2 + U \left(1 - \frac{3}{4} \frac{\alpha}{r} - \frac{1}{4} \frac{\alpha^3}{r^3}\right), \\ v &= -\frac{3}{4} \frac{Ua}{r^3} \left(1 - \frac{\alpha^2}{r^2}\right) xy, \\ w &= -\frac{3}{4} \frac{Ua}{r^3} \left(1 - \frac{\alpha^2}{r^2}\right) xz \end{aligned} \right\} \quad . \quad . \quad . \quad . \quad (6)$$

These make

$$xu + yv + zw = U \left(1 - \frac{3}{4} \frac{\alpha}{r} + \frac{1}{4} \frac{\alpha^3}{r^3}\right) x, \quad . \quad (7)$$

$$\xi = 0, \quad \eta = \frac{3}{4} \frac{Ua}{r^3} z, \quad \zeta = -\frac{3}{4} \frac{Ua}{r^3} y \quad . \quad . \quad . \quad (8)$$

The components of stress across the surface of a sphere of radius r are, by Art 313,

$$\left. \begin{aligned} p_{rx} &= \frac{x}{r} p_{xx} + \frac{y}{r} p_{xy} + \frac{z}{r} p_{xz}, \\ p_{ry} &= \frac{x}{r} p_{yx} + \frac{y}{r} p_{yy} + \frac{z}{r} p_{yz}, \\ p_{rz} &= \frac{x}{r} p_{zx} + \frac{y}{r} p_{zy} + \frac{z}{r} p_{zz} \end{aligned} \right\} \quad . \quad . \quad . \quad (9)$$

If we substitute the values of p_{xx} , p_{xy} , p_{xz} , .., from Art 314, we find

$$\left. \begin{aligned} xp_{xx} + yp_{xy} + zp_{xz} &= -xp + \mu \left(r \frac{\partial}{\partial r} - 1\right) u + \mu \frac{\partial}{\partial x} (xu + yv + zw), \\ xp_{yx} + yp_{yy} + zp_{yz} &= -yp + \mu \left(r \frac{\partial}{\partial r} - 1\right) v + \mu \frac{\partial}{\partial y} (xu + yv + zw), \\ xp_{zx} + yp_{zy} + zp_{zz} &= -zp + \mu \left(r \frac{\partial}{\partial r} - 1\right) w + \mu \frac{\partial}{\partial z} (xu + yv + zw) \end{aligned} \right\} \quad . \quad . \quad (10)$$

In the present case we have

$$p = p_0 + p_{-2} = p_0 - \frac{3}{2} \frac{\mu Ua}{r^3} x \quad . \quad . \quad . \quad (11)$$

We thus obtain, for the component tractions on the surface $r = a$,

$$p_{rx} = -\frac{x}{a} p_0 + \frac{3}{2} \frac{\mu U}{a}, \quad p_{ry} = -\frac{y}{a} p_0, \quad p_{rz} = -\frac{z}{a} p_0 \quad . \quad . \quad . \quad (12)$$

If δS denote an element of the surface, we find

$$\iint p_{rx} dS = 6\pi\mu Ua, \quad \iint p_{ry} dS = 0, \quad \iint p_{rz} dS = 0 \quad . \quad . \quad (13)$$

The resultant force on the sphere is therefore parallel to x , and equal to $6\pi\mu a U$.

The character of the motion may be most concisely expressed by means of the stream-function of Art 94. If we put $x = r \cos \theta$, the flux ($2\pi\psi$) through a circle with Ox as axis, whose radius subtends an angle θ at O , is given by

$$\psi = -\frac{1}{2} U \left(1 - \frac{3}{2} \frac{\alpha}{r} + \frac{1}{2} \frac{\alpha^3}{r^3}\right) r^2 \sin^2 \theta, \quad . \quad . \quad . \quad (14)$$


as is evident at once from (7)

If we impress on everything a velocity $-U$ in the direction of x , we get the case of a sphere moving steadily through a viscous fluid which is at rest at infinity. The stream-function is then

$$\psi = \frac{3}{4} Uar \left(1 - \frac{1}{2} \frac{\alpha^2}{r^2}\right) \sin^2 \theta \quad . \quad . \quad . \quad (15)^*$$

* This problem was first solved by Stokes, in terms of the stream-function, *l c. ante* p. 541.

The following diagram shews the stream-lines $\psi = \text{const}$, in this case, for a series of equidistant values of ψ . The contrast with the case of a frictionless liquid, delineated on p 121, is remarkable, but it must be remembered that the fundamental assumptions are very different. In the former case inertia was predominant, and viscosity neglected, in the present problem these circumstances are reversed



If X be the extraneous force acting on the sphere, this must balance the resistance, whence

$$X = 6\pi\mu a U \quad \dots \dots \dots (16)$$

It is to be noticed that the formula (15) makes the momentum and the energy of the fluid both infinite*. The steady motion here investigated could therefore only be fully established by a constant force X acting on the sphere through an infinite distance

The whole of this investigation is based on the assumption that the inertia-terms $u\partial u/\partial x$, ... in the fundamental equations (4) of Art. 316 may be neglected in comparison with $\nu\nabla^2 u$, ... It easily follows from (6) above that Ua must be small compared with ν . This condition can always be realized by making U or a sufficiently small, but in the case of mobile fluids like water this restricts us to velocities or dimensions which are, from a practical point of view, exceedingly minute. Thus even for a sphere of a millimetre radius

* Lord Rayleigh, *Phil Mag.* (5), t. xxi p. 374 (footnote) (1886) [*Sc. Papers*, t. ii p 480]

where

$$\Delta = \{(a^2 + \lambda)(b^2 + \lambda)(c^2 + \lambda)\}^{\frac{1}{2}}, \quad (3)$$

and the lower limit is the positive root of

$$\frac{x^2}{a^2 + \lambda} + \frac{y^2}{b^2 + \lambda} + \frac{z^2}{c^2 + \lambda} = 1 \quad \dots \quad (4)$$

This makes
$$\frac{\partial \Omega}{\partial x} = 2\pi a x, \quad \frac{\partial \Omega}{\partial y} = 2\pi \beta y, \quad \frac{\partial \Omega}{\partial z} = 2\pi \gamma z, \quad \dots \quad (5)$$

where
$$a = abc \int_{\lambda}^{\infty} \frac{d\lambda}{(a^2 + \lambda) \Delta}, \quad \beta = abc \int_{\lambda}^{\infty} \frac{d\lambda}{(b^2 + \lambda) \Delta}, \quad \gamma = \int_{\lambda}^{\infty} \frac{d\lambda}{(c^2 + \lambda) \Delta} \quad (6)$$

We will also write
$$\chi = abc \int_{\lambda}^{\infty} \frac{d\lambda}{\Delta}; \quad \dots \quad (7)$$

it has been shewn in Art 113 that this satisfies $\nabla^2 \chi = 0$

If the fluid be streaming past the ellipsoid, regarded as fixed, with the general velocity U in the direction of x , we assume*

$$u = A \frac{\partial^2 \Omega}{\partial x^2} + B \left(x \frac{\partial \chi}{\partial x} - \chi \right) + U, \quad v = A \frac{\partial^2 \Omega}{\partial x \partial y} + B x \frac{\partial \chi}{\partial y}, \quad w = A \frac{\partial^2 \Omega}{\partial x \partial z} + B x \frac{\partial \chi}{\partial z} \quad (8)$$

These satisfy the equation of continuity, in virtue of the relations

$$\nabla^2 \Omega = 0, \quad \nabla^2 \chi = 0;$$

and they evidently make $u = U, v = 0, w = 0$ at infinity. Again, they make

$$\nabla^2 u = 2B \frac{\partial^2 \chi}{\partial x^2}, \quad \nabla^2 v = 2B \frac{\partial^2 \chi}{\partial x \partial y}, \quad \nabla^2 w = 2B x \frac{\partial^2 \chi}{\partial x \partial z}, \quad \dots \quad (9)$$

so that the equations (1) of Art 324 are satisfied by

$$p = 2B\mu \frac{\partial \chi}{\partial x} + \text{const} \quad \dots \quad (10)$$

It remains to shew by a proper choice of A, B we can make $u, v, w = 0$ at the surface (1). The conditions $v = 0, w = 0$ require

$$\left[2\pi A \frac{da}{d\lambda} + B \frac{d\chi}{d\lambda} \right]_{\lambda=0} = 0, \quad \text{or} \quad 2\pi \frac{A}{a^2} + B = 0. \quad \dots \quad (11)$$

With the help of this relation, the condition $u = 0$ reduces to

$$2\pi A a_0 - B \chi_0 + U = 0, \quad \dots \quad (12)$$

where the suffix denotes that the lower limit in the integrals (6) and (7) is to be replaced by zero. Hence

$$\pi A = -\frac{1}{2} B a^2, \quad B = -\frac{U}{\chi_0 + a_0 a^2} \quad \dots \quad (13)$$

At a great distance r from the origin we have

$$\Omega = -\frac{1}{3} \frac{\pi abc}{r}, \quad \chi = \frac{2abc}{r}$$

whence it appears, on comparison with the equations (4) of the preceding Art, that the disturbance is the same as would be produced by a sphere of radius R , determined by

$$\frac{4}{3} UR = 2abcB, \quad \text{or} \quad R = \frac{8}{3} \frac{abc}{\chi_0 + a_0 a^2} \quad \dots \quad (14)$$

* Oberbeck, *l c ante* p 550

and by a partial integration, remembering that u', v', w' vanish at the boundary, this becomes

$$- \iiint \left\{ u' \left(\frac{\partial p_{xx}}{\partial x} + \frac{\partial p_{xy}}{\partial y} + \frac{\partial p_{xz}}{\partial z} \right) + \dots \right\} dx dy dz, \quad \text{or} \quad \iiint \rho (Xu' + Yv' + Zw') dx dy dz,$$

by Art 316 If the extraneous forces X, Y, Z have a single-valued potential, this vanishes, in virtue of the equation of continuity, by Art 42 (4)

Under these conditions the dissipation in the altered motion is equal to

$$\iiint \Phi dx dy dz + \iiint \Phi' dx dy dz, \quad . \quad . \quad (3)$$

or $2(F + F')$ That is, it exceeds the dissipation in the steady motion by the essentially positive quantity $2F'$ which represents the dissipation in the motion u', v', w'

In other words, provided the inertia-terms may be neglected, the steady motion of a liquid under constant forces having a single-valued potential is characterized by the property that the dissipation in any region is less than in any other motion consistent with the same values of u, v, w at the boundary of this region

It follows that, with prescribed velocities over the boundary, there is only one type of steady motion in the region *

2° If u, v, w refer to any motion whatever in the given region, we have

$$2\dot{F} = \iiint \dot{\Phi} dx dy dz = 2 \iiint (p_{xx}\dot{a} + p_{xy}\dot{b} + p_{xz}\dot{c} + 2p_{yz}\dot{f} + 2p_{zx}\dot{g} + 2p_{xy}\dot{h}) dx dy dz, \quad (4)$$

since the formula (2) holds when dots take the place of accents

The treatment of this integral is the same as before If we suppose that u, \dot{v}, w vanish over the bounding surface Σ , we find

$$\begin{aligned} \dot{F} &= - \iiint \left\{ u \left(\frac{\partial p_{xx}}{\partial x} + \frac{\partial p_{xy}}{\partial y} + \frac{\partial p_{xz}}{\partial z} \right) + \dots \right\} dx dy dz \\ &= - \rho \iiint (u^2 + \dot{v}^2 + \dot{w}^2) dx dy dz + \rho \iiint (Xu + Yv + Zw) dx dy dz \quad . \quad . \quad (5) \end{aligned}$$

The latter integral vanishes when the extraneous forces have a single-valued potential, so that

$$F = - \rho \iiint (u^2 + v^2 + w^2) dx dy dz \quad . \quad . \quad . \quad (6)$$

This is essentially negative, so that F continually diminishes, the process ceasing only when $u=0, v=0, w=0$, that is, when the motion has become steady.

Hence when the velocities over the boundary Σ are maintained constant, the motion in the interior will tend to become steady The type of steady motion ultimately attained is therefore stable, as well as unique†

It has been shewn by Lord Rayleigh‡ that the above theorem can be extended so as to apply to any dynamical system devoid of potential energy, in which the kinetic energy (T) and the dissipation-function (F) can be expressed as quadratic functions of the generalized velocities, with constant coefficients

If the extraneous forces have not a single-valued potential, or if instead of given velocities we have given tractions over the boundary, the theorems require a slight modi-

* Helmholtz, "Zur Theorie der stationären Ströme in reibenden Flüssigkeiten," *Verh. d. naturhist-med Vereins*, Oct 30, 1868 [*Wiss Abh*, t 1 p 223]

† Korteweg, "On a General Theorem of the Stability of the Motion of a Viscous Fluid," *Phil. Mag.* (5), t xvi p 112 (1883)

‡ *l c ante* p 548.

location. The excess of the dissipation over *above* the rate at which work is done is due by the extraneous forces (including the tractions on the boundary) tend to a minimum, which is only attained when the motion is steady.*

Periodic Motion.

328 We next examine the influence of viscosity in various problems of small oscillations.

We begin with the case of 'laminar' motion, as this will enable us to illustrate some points of great importance, without elaborate mathematics. If we assume that $v = 0$, $w = 0$, whilst u is a function of y only, the equations (4) of Art. 316 require that $p = \text{const.}$, and

$$\frac{\partial u}{\partial t} = \nu \frac{\partial^2 u}{\partial y^2} \dots \dots \dots (1)$$

This has the same form as the equation of linear motion of heat. In the case of simple harmonic motion, assuming a time factor $e^{i\sigma t}$ † we have

$$\frac{\partial u}{\partial y} = \frac{ia}{\nu} e^{i\sigma t} \dots \dots \dots (2)$$

the solution of which is

$$u = Ae^{(1+i)\sigma y/\nu} + Be^{-\sigma(1+i)y/\nu} \dots \dots \dots (3)$$

provided

$$\sigma^2 = \left(\frac{\eta}{2\nu}\right)^2 \dots \dots \dots (4)$$

Let us first suppose that the fluid lies on the positive side of the plane xz , and that the motion is due to a prescribed oscillation

$$u = ae^{i\sigma t} \dots \dots \dots (5)$$

of a rigid surface coincident with this plane. If the fluid extend to infinity in the direction of y -positive, the first term in (3) is excluded, and, determining B by the boundary condition (5), we have

$$u = ae^{i\sigma t} e^{-(1+i)\sigma y/\nu} \dots \dots \dots (6)$$

or, taking the real part,

$$u = ae^{-\sigma y/\nu} \cos(\sigma t - \sigma y/\nu) \dots \dots \dots (7)$$

corresponding to a prescribed motion

$$u = a \cos(\sigma t + \epsilon) \dots \dots \dots (8)$$

at the boundary‡.

The formula (7) represents a wave of transversal vibrations propagated inwards from the boundary with the velocity σ/δ , but with rapidly diminishing amplitude, the falling off within a wave-length being in the ratio $e^{-\pi/2} \text{ or } \frac{1}{\sqrt{2}}$.

* Cf. Helmholtz, *loc.*

† Stokes, *loc. ante* p. 544.

The linear magnitude

$$\frac{2\pi}{\beta} \quad \text{or} \quad \left(4\pi\nu \frac{2\pi}{\sigma}\right)^{\frac{1}{2}}$$

is of great importance in all problems of oscillatory motion which do not involve changes of density, as indicating the extent to which the effects of viscosity penetrate into the fluid. In the case of air ($\nu = 13$) its value is $1.28P^{\frac{1}{2}}$ centimetres, if P be the period of oscillation in seconds. For water the corresponding value is $47P^{\frac{1}{2}}$. We shall have further illustrations, presently, of the fact that the influence of viscosity extends only to a short distance from the surface of a body performing small oscillations with sufficient frequency.

The retarding force on the rigid plane is, per unit area,

$$\begin{aligned} -\mu \left[\frac{\partial u}{\partial y} \right]_{y=0} &= \mu\beta a \{ \cos(\sigma t + \epsilon) - \sin(\sigma t + \epsilon) \} \\ &= \rho\nu^{\frac{1}{2}}\sigma^{\frac{1}{2}}a \cos(\sigma t + \epsilon + \tfrac{1}{4}\pi) \quad \dots \quad (9) \end{aligned}$$

The force has its maxima at intervals of one-eighth of a period before the oscillating plane passes through its mean position.

On the forced oscillation above investigated we may superpose any of the normal modes of free motion of which the system is capable. If we assume that

$$u = A \cos my + B \sin my, \quad \dots \quad (10)$$

$$\text{and substitute in (1), we find} \quad \frac{\partial u}{\partial t} = -\nu m^2 u, \quad \dots \quad (11)$$

whence we obtain the solution

$$u = \Sigma (A \cos my + B \sin my) e^{-\nu m^2 t} \quad \dots \quad (12)$$

The admissible values of m , and the ratios A/B are as a rule determined by the boundary conditions. The arbitrary constants which remain are then to be found in terms of the initial conditions, by Fourier's methods.

In the case of a fluid extending from $y = -\infty$ to $y = +\infty$, all real values of m are admissible. The solution, in terms of the initial conditions, can in this case be immediately written down by Fourier's Theorem (Art. 236 (4)). Thus

$$u = \frac{1}{\pi} \int_0^\infty dm \int_{-\infty}^\infty f(\lambda) \cos m(y-\lambda) e^{-\nu m^2 t} d\lambda, \quad (13)$$

$$\text{if} \quad u = f(y) \quad \dots \quad (14)$$

be the arbitrary initial distribution of velocity.

The integration with respect to m can be effected by the known formula

$$\int_0^\infty e^{-\alpha x^2} \cos \beta x dx = \frac{1}{2} \left(\frac{\pi}{\alpha} \right)^{\frac{1}{2}} e^{-\beta^2/4\alpha} \quad \dots \quad (15)$$

We thus find

$$u = \frac{1}{2(\pi\nu t)^{\frac{1}{2}}} \int_{-\infty}^\infty e^{-(y-\lambda)^2/4\nu t} f(\lambda) d\lambda \quad \dots \quad (16)$$

As a particular case, let us suppose that $f(y) = \pm U$, where the upper or lower sign is to be taken according as y is positive or negative. This will represent the case of an

initial surface of discontinuity coincident with the plane $y=0$. After the first instant, the velocity at this surface will be zero on both sides. We find

$$u = \frac{U}{2(\pi\nu t)^{\frac{1}{2}}} \int_0^{\infty} \{e^{-(y-\lambda)^2/4\nu t} - e^{-(y+\lambda)^2/4\nu t}\} d\lambda \quad (17)$$

By a change of variables, and easy reductions, this can be brought to the form

$$u = 2 \frac{U}{\pi^{\frac{1}{2}}} \text{Erf} \frac{y}{2\nu^{\frac{1}{2}} t^{\frac{1}{2}}}, \quad \dots \quad (18)^*$$

where in Glaisher's (revised) notation†

$$\text{Erf } x = \int_0^x e^{-x^2} dx \quad \dots \quad (19)$$

The function $2\pi^{-\frac{1}{2}} \text{Erf } x$ was tabulated by Encke‡. It appears that u will equal $\frac{1}{2}U$ when $y/2\nu^{\frac{1}{2}} t^{\frac{1}{2}} = 4.769$. For water, this gives, in seconds and centimetres,

$$t = 61.8 y^2$$

The corresponding result for air is $t = 8.3 y^2$.

These results indicate how rapidly a surface of discontinuity in a viscous fluid would be obliterated, if indeed it could ever be formed.

The angular velocity (ζ) of the fluid is given by

$$2\zeta = -\frac{\partial u}{\partial y} = -\frac{U}{(\pi\nu t)^{\frac{1}{2}}} e^{-y^2/4\nu t} \quad \dots \quad (20)$$

This represents the diffusion of the angular velocity, which is initially confined to a vortex-sheet coincident with the plane $y=0$, into the fluid on either side.

329 When the fluid does not extend to infinity, but is bounded by a fixed rigid plane $y=h$, then, in determining the motion due to a forced oscillation of the plane $y=0$, both terms of (3) are required, and the boundary conditions give

$$A + B = a, \quad A e^{(1+i)\beta h} + B e^{-(1+i)\beta h} = 0, \quad \dots \quad (21)$$

whence

$$u = a \frac{\sinh(1+i)\beta(h-y)}{\sinh(1+i)\beta h} e^{i(\sigma t + \epsilon)}, \quad \dots \quad (22)$$

as is easily verified. This gives for the retarding force per unit area on the oscillating plane

$$-\mu \left[\frac{\partial u}{\partial y} \right]_{y=0} = \mu(1+i)\beta a \coth(1+i)\beta h \cdot e^{i(\sigma t + \epsilon)}. \quad \dots \quad (23)$$

The real part of this expression may be reduced to the form

$$\sqrt{2}\mu\beta a \frac{\sinh 2\beta h \cos(\sigma t + \epsilon + \frac{1}{4}\pi) + \sin 2\beta h \sin(\sigma t + \epsilon + \frac{1}{4}\pi)}{\cosh 2\beta h - \cos 2\beta h} \quad \dots \quad (24)$$

* Lord Rayleigh, "On the Stability, or Instability, of certain Fluid Motions," *Proc. Lond. Math. Soc.*, t. xi. p. 57 (1880) [*Sc. Papers*, t. i. p. 474].

† See *Phil. Mag.* (4), t. xli. p. 294 (1871), and *Encyc. Britann.*, 9th ed., Art. "Tables."

‡ *Berl. Ast. Jahrbuch*, 1834. The table has been reprinted by De Morgan, *Encyc. Metrop.*, Art. "Probabilities," and Lord Kelvin, *Math. and Phys. Papers*, t. iii. p. 434.

or, on rejecting the imaginary part,


$$u = \frac{f}{\sigma} \sin(\sigma t + \epsilon) - \frac{f}{\sigma} e^{-\beta y} \sin(\sigma t - \beta y + \epsilon). \quad \dots (7)$$

This might have been obtained directly, as the solution of (2) satisfying the conditions that $u = 0$ for $y = 0$, and

$$u = \frac{f}{\sigma} \sin(\sigma t + \epsilon)$$

for large values of βy

The curves A, B, C, D, E, F in the accompanying figure represent successive forms assumed by the same line of particles at intervals of one-tenth of a period. To complete the series it would be necessary to add the *images* of E, D, C, B with respect to the vertical through O . The whole system of curves may be regarded as successive aspects of a properly shaped spiral revolving uniformly about a vertical axis through O . The vertical range of the diagram is one wave-length ($2\pi/\beta$) of the lammar disturbance



As a numerical illustration we note that if $\nu = 0.178$, and $2\pi/\sigma = 12$ hours, we find $\beta^{-1} = 15.6$ centimetres. This indicates how utterly insensible must be the *direct* action of viscosity on oceanic tides. There can be little doubt that such dissipation of energy by 'tidal friction' as at present takes

phase is to be attributed mainly to the eddying motion produced by the acceleration of tidal currents in shallow water*. (Cf. Art. 344.)

When $2h$ is small the real part of (4) gives

$$u = \frac{f}{2\nu} g(2h - g) \cos(at + \epsilon), \dots\dots\dots(8)$$

the sheets being in the same phase with the force, and varying inversely as ν .

331 To find the effect of viscosity on free waves on deep water we may make use of the Dissipation Function of Art. 317, in any of the forms there given, the simplest for our purpose being

$$2D = \mu \iint \left(\frac{\partial}{\partial x} \right)^2 \eta^2 dS, \dots\dots\dots(1)$$

where, by Art. 309, the dissipation may, under a certain restriction, be calculated as if the motion were irrotational.

To put the calculation in a form which shall apply at once to the case where capillary as well as gravitational forces are taken into account, we recall that, corresponding to the surface elevation

$$\eta = \alpha \sin k(x - ct), \dots\dots\dots(2)$$

we have $\phi = acd^2 \cos k(x - ct), \dots\dots\dots(3)$

and this makes $\nabla^2 \phi = -c \phi$ for $\mu = 0$. Hence

$$\eta = \alpha \{ 1 + \frac{1}{2} k^2 c^2 \alpha^2 \}, \dots\dots\dots(4)$$

and the dissipation is, by (1),

$$2\mu k^2 c \alpha, \dots\dots\dots(5)$$

per unit area of the surface. The kinetic energy,

$$\frac{1}{2} \rho \iint \left(\frac{\partial \phi}{\partial t} \right)^2 dS, \dots\dots\dots(6)$$

has a mean value $\frac{1}{2} \rho k^2 \alpha^2$ per unit area. The total energy, being double of this, is

$$\rho k^2 c \alpha^2, \dots\dots\dots(7)$$

Hence, equating the rate of decay of the energy to the dissipation, we have

$$\frac{d}{dt} (\rho k^2 c \alpha^2) = 2\mu k^2 c \alpha, \dots\dots\dots(8)$$

* The feeble influence of viscosity on "regular" motions of water on a large scale has been further emphasized by H. Hsueh, "On the Influence of Viscosity on Waves and Currents," *Acta Phys. Math. Sinica*, vol. 1, p. 264 (1959). We may also refer to Zoppritz' discussion of dust currents in "Hydrodynamische Probleme in Beziehung zur Theorie der Meeresströmungen," *Arch. Physik.*, vii, p. 383 (1878).

$$\text{or} \quad \frac{d\alpha}{dt} = -2\nu k^2 \alpha, \quad \dots\dots\dots (9)$$

$$\text{whence} \quad \alpha = \alpha_0 e^{-2\nu k^2 t}, \quad \dots\dots\dots (10)$$

The modulus of decay, τ , is therefore given by $\tau = 1/2\nu k^2$, or, in terms of the wave-length (λ),

$$\tau = \frac{\lambda^2}{8\pi^2\nu}, \quad \dots\dots\dots (11)^*$$

In the case of water, this gives

$$\tau = 712\lambda^2 \text{ seconds,}$$

if λ be expressed in centimetres. It follows that capillary waves are very rapidly extinguished by viscosity, whilst for a wave-length of one metre τ would be about 2 hours.

The above method rests on the assumption that $\sigma\tau$ is moderately large, where $\sigma (=kc)$ denotes the 'speed.' In mobile fluids such as water this condition is fulfilled for all but excessively minute wave-lengths.

The method fails for another reason when the depth is less than (say) half the wave-length. Owing to the practically infinite resistance to slipping at the bottom, the dissipation can no longer be calculated as if the motion were irrotational.

332. The direct calculation of the effect of viscosity on water waves can be conducted as follows.

If the axis of y be drawn vertically upwards, and if we assume that the motion is confined to the two dimensions x, y , we have

$$\frac{\partial u}{\partial t} = -\frac{1}{\rho} \frac{\partial p}{\partial x} + \nu \nabla^2 u, \quad \frac{\partial v}{\partial t} = -\frac{1}{\rho} \frac{\partial p}{\partial y} - g + \nu \nabla^2 v, \quad \dots\dots\dots (1)$$

$$\text{with} \quad \frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0. \quad \dots\dots\dots (2)$$

These are satisfied by

$$u = -\frac{\partial \phi}{\partial x} - \frac{\partial \psi}{\partial y}, \quad v = -\frac{\partial \phi}{\partial y} + \frac{\partial \psi}{\partial x}, \quad \dots\dots\dots (3)$$

$$\text{and} \quad p = \frac{\partial \phi}{\partial t} - gy, \quad \dots\dots\dots (4)$$

$$\text{provided} \quad \nabla_1^2 \phi = 0, \quad \frac{\partial \psi}{\partial t} = \nu \nabla_1^2 \psi, \quad \dots\dots\dots (5)$$

$$\text{where} \quad \nabla_1^2 = \frac{\partial^2}{\partial x^2} + \frac{\partial^2}{\partial y^2}.$$

* Stokes, *l.c. ante* p. 541. (Through an oversight in the calculation the value obtained for τ was too small by one-half.)

To determine the 'normal modes' which are periodic in respect of x with a prescribed wave-length $2\pi/k$, we assume a time-factor e^{at} and a space-factor e^{ikx} . The solutions of (5) are then

$$\phi = (Ae^{ky} + Be^{-ky}) e^{ikx+at}, \quad \psi = (Ce^{my} + De^{-my}) e^{ikx+at}, \quad (6)$$

with
$$m^2 = k^2 + \frac{\alpha}{\nu}. \quad \dots \quad (7)$$

The boundary-conditions will supply equations which are sufficient to determine the nature of the various modes, and the corresponding values of α

In the case of infinite depth one of these conditions takes the form that the motion must be finite for $y = -\infty$. Excluding for the present the cases where m is pure-imaginary, this requires that $B = 0, D = 0$, provided m denote that root of (7) which has its real part positive. Hence

$$u = -(ikAe^{ky} + mCe^{my}) e^{ikx+at}, \quad v = -(kAe^{ky} - ikCe^{my}) e^{ikx+at}. \quad (8)$$

If η denote the elevation at the free surface, we must have $\partial\eta/\partial t = v$. If the origin of y be taken in the undisturbed level, this gives

$$\eta = -\frac{k}{\alpha} (A - iC) e^{ikx+at} \quad \dots \quad (9)$$

If T_1 denote the surface-tension, the stress-conditions at the surface are evidently

$$p_{yy} = T_1 \frac{\partial^2 \eta}{\partial x^2}, \quad p_{xy} = 0, \quad \dots \quad (10)$$

to the first order, since the inclination of the surface to the horizontal is assumed to be infinitely small.

Now
$$p_{yy} = -p + 2\mu \frac{\partial v}{\partial y}, \quad p_{xy} = \mu \left(\frac{\partial v}{\partial x} + \frac{\partial u}{\partial y} \right), \quad \dots \quad (11)$$

whence, by (4) and (6) we find, at the surface,

$$\begin{aligned} \frac{p_{yy}}{\rho} - T_1 \frac{\partial^2 \eta}{\partial x^2} &= -\frac{\partial \phi}{\partial t} + (g + T'k^2) \eta + 2\nu \frac{dv}{dy} \\ &= -\frac{1}{\alpha} \{ (\alpha^2 + 2\nu k^2 \alpha + gk + T'k^3) A - i(gk + T'k^3 + 2\nu k m \alpha) C \}, \dots (12) \end{aligned}$$

$$\frac{p_{xy}}{\rho} = -\{ 2\nu k^2 A + (\alpha + 2\nu k^2) C \}, \quad \dots (13)$$

where $T' = T_1/\rho$, the common factor e^{ikx+at} being understood

Substituting in (10), and eliminating the ratio A/C , we obtain

$$(\alpha + 2\nu k^2)^2 + gk + T'k^3 = 4\nu^2 k^3 m \quad \dots (14)$$

If we eliminate m by means of (7), we get a biquadratic in α , but only those roots are admissible which give a positive value to the real part of the left-hand member of (14), and so make the real part of m positive.

If we write, for shortness,

$$gk + T'k^3 = \sigma^2, \quad \frac{\nu k^2}{\sigma} = \theta, \quad \alpha + 2\nu k^2 = x\sigma, \quad \dots \quad (15)$$

the biquadratic in question takes the form

$$(x^2 + 1)^2 = 16\theta^3(x - \theta) \quad \dots \quad (16)$$

It is not difficult to shew that this has always two roots (both complex) which violate the restriction just stated, and two admissible roots which may be real or complex according to the magnitude of the ratio θ . If λ be the wave-length, and $c (= \sigma/k)$ the wave-velocity in the absence of friction, we have

$$\theta = \frac{\nu k}{c} = \frac{2\pi\nu}{c\lambda} \quad \dots \quad (17)$$

Now, for water, if c_m denote the minimum wave-velocity of Art. 264, we find $2\pi\nu/c_m = 0.048$ cm, so that except for very minute wave-lengths θ is a small number. Neglecting the square of θ , we have $x = \pm i$, and

$$\alpha = -2\nu k^2 \pm i\sigma. \quad \dots \quad (18)$$

The condition $p_{xy} = 0$ shews that

$$\frac{C}{A} = -\frac{2\nu\nu k^2}{\alpha + 2\nu k^2} = \mp \frac{2\nu k^2}{\sigma}, \quad \dots \quad (19)$$

which is, under the same circumstances, very small. Hence the motion is approximately irrotational, with a velocity-potential

$$\phi = A e^{-2\nu k^2 t + k y + i(kx \pm \sigma t)} \quad \dots \quad (20)$$

If we put $\alpha = \mp kA/\sigma$, the equation (9) of the free surface becomes, approximately, on taking the real part,

$$\eta = a e^{-2\nu k^2 t} \sin(kx \pm \sigma t) \quad \dots \quad (21)$$

The wave-velocity is σ/k , or $(g/k + T'k)^{\frac{1}{2}}$, as in Art. 264, and the law of decay is that investigated independently in the last Art.*

To examine more closely the character of the motion, as affected by viscosity, we may calculate the angular velocity (ω) at any point of the fluid. This is given by

$$\begin{aligned} 2\omega &= \frac{\partial v}{\partial x} - \frac{\partial u}{\partial y} = \nabla^2 \psi = \frac{a}{\nu} \psi \\ &= \frac{a}{\nu} C e^{my + i kx + \alpha t} \quad \dots \quad (22) \end{aligned}$$

Now, from (7) and (18), we have, approximately,

$$m = (1 \pm i)\beta, \quad \text{where} \quad \beta = \left(\frac{\sigma}{2\nu}\right)^{\frac{1}{2}}.$$

* Similar results were obtained by Basset, *Hydrodynamics*, t. II., Arts 520—522 (1888), who also treats the case of finite depth. Reference may also be made to Hough, *loc. ante* p. 563, where the case of a spherical sheet of water is considered.

With the same notation as before, we find

$$\omega = \mp \sigma k a e^{-2\nu k^2 t + \beta y} \sin \{k v \pm (\sigma t + \beta y)\} \tag{23}$$

This diminishes rapidly from the surface downwards, in accordance with the thermal analogy pointed out in Art. 316. Owing to the oscillatory character of the motion, the sign of the vorticity which is being diffused inwards from the surface is continually being reversed, so that beyond a stratum of thickness comparable with $2\pi/\beta$ the effect is insensible, just as the fluctuations of temperature at the earth's surface cease to have any sensible influence at a depth of a few yards.

In the case of a very viscous fluid, such as treacle or pitch, θ may be large even when the wave-length is considerable. The admissible roots of (16) are then both real. One of them is evidently nearly equal to 2θ , and continuing the approximation we find

$$x = 2\theta - \frac{1}{2\theta} + \dots,$$

whence, neglecting capillarity, we have, by (15),

$$\alpha = -\frac{g}{2kv} \dots \dots \dots \tag{24}$$

The remaining real root is 1.09θ , nearly, which gives

$$\alpha = -.91\nu k^2 \dots \dots \dots \tag{25}$$

The former root is the more important. It represents a slow creeping of the fluid towards a state of equilibrium with a horizontal surface. The rate of recovery depends on the relation between the gravity of the fluid (which is proportional to gp) and the viscosity (μ), the influence of inertia being insensible. It appears from (7) and (15) that $m=k$, nearly, so that the motion is approximately irrotational*.

The type of motion corresponding to (25), on the other hand, depends, as to its persistence, on the relation between the inertia (ρ) and the viscosity (μ), the effect of gravity being unimportant. It dies out very rapidly.

The above investigation gives the most important of the normal modes, of the prescribed wave length, of which the system is capable. We know *a priori* that there must be an infinity of others. These correspond to pure-imaginary values of m , and are of a less persistent character. If in place of (6) we assume

$$\phi = A e^{k y} \cdot e^{i k v t + a t}, \quad \psi = (C \cos m' y + D \sin m' y) e^{i k x + a t}, \tag{26}$$

with $m'^2 = -k^2 - \frac{a}{\nu} \dots \dots \dots \tag{27}$

and carry out the investigation as before, we find

$$\left. \begin{aligned} (a^2 + 2\nu k^2 a + gk + T' k^3) A - i(gk + T' k^3) C - 2i\nu k m' a D = 0, \\ 2i k^2 A + (k^2 - m'^2) C = 0 \end{aligned} \right\} \dots \dots \tag{28}$$

* Cf. Tait, "Note on Ripples in a Viscous Liquid," *Proc. R. S. Edin.* t. xvii p. 110 (1890) [*Sc. Papers*, Cambridge, 1898-1900, t. ii. p. 313]

Any real value of m' is admissible, these equations determining the ratios $A/C/D$, and the corresponding value of a is

$$a = -\nu(k^2 + m'^2) \quad \dots \quad (29)$$

In any one of these modes the plane xy is divided horizontally and vertically into a series of quasi-rectangular compartments, within each of which the fluid circulates, gradually coming to rest as the original momentum is spent against viscosity.

By a proper synthesis of the various normal modes it must be possible to represent the decay of any arbitrary initial disturbance

333 The equations (12) and (13) of the preceding Art enable us to examine a related question of some interest, viz. the generation and maintenance of waves against viscosity, by suitable forces applied to the surface.

If the external forces p'_{xy} , p'_{xy} be given multiples of e^{ikx+at} , where k and α are prescribed, the equations in question determine A and C , and thence, by (9), the value of η . Thus we find

$$\frac{p'_{yy}}{g\rho\eta} = \frac{(\alpha^2 + 2\nu k^2\alpha + \sigma^2)A - i(\sigma^2 + 2\nu km\alpha)C}{gk(A - iC)}, \quad \dots \quad (1)$$

$$\frac{p'_{xy}}{g\rho\eta} = \frac{\alpha}{gk} \cdot \frac{2\nu k^2 A + (\alpha + 2\nu k^2)C}{A - iC}, \quad \dots \quad (2)$$

where σ^2 has been written for $gk + T'k^3$ as before

Let us first examine the effect of a purely tangential force. Assuming $p'_{yy} = 0$, we find

$$\frac{p'_{xy}}{g\rho\eta} = \frac{i\alpha}{gk} \cdot \frac{(\alpha + 2\nu k^2)^2 + \sigma^2 - 4\nu^2 k^2 m}{\alpha + 2\nu k^2 - 2\nu km} \quad \dots \quad (3)$$

If, as we shall suppose for reasons already indicated, $\nu k^2/\sigma$ and $\nu km/\sigma$ are small, the elevation will be greatest when $\alpha = \pm i\sigma$, nearly. To find the force necessary to maintain a train of waves of given amplitude, travelling in the direction of x -positive, we put $\alpha = -i\sigma$. This makes

$$\frac{p'_{xy}}{g\rho\eta} = \frac{4\nu k\sigma}{g}, \quad \text{or} \quad p'_{xy} = 4\mu k\sigma\eta, \quad \dots \quad (4)$$

approximately. Hence the force acts forwards on the crests of the waves, and backwards at the troughs, changing sign at the nodes. A force having the same distribution, but less intensity in proportion to the height of the waves than that given by (4), would only retard, without preventing, the decay of the waves by viscosity. A force having the opposite sign would accelerate this decay.

The case of purely normal force can be investigated in a similar manner. If $p'_{xy} = 0$, we have

$$\frac{p'_{yy}}{g\rho\eta} = \frac{(\alpha + 2\nu k^2)^2 + \sigma^2 - 4\nu^2 k^2 m}{gk} \quad \dots \quad (5)$$

The reader may easily satisfy himself that when there is no viscosity this coincides with the result of Art 240. If we put $\alpha = -i\sigma$, we obtain, with the same approximations as before,

$$p'_{\eta\eta} = -4\mu k\sigma\eta \quad . \quad \dots \quad (6)$$

Hence the wave-system

$$\eta = a \sin(kx - \sigma t) \quad \dots \quad (7)$$

will be maintained without increase or decrease by the pressure-distribution

$$p' = \text{const} + 4\mu h a \sigma \cos(kx - \sigma t), \quad (8)$$

applied to the surface. It appears that the pressure is greatest on the rear and least on the front slopes of the waves*.

If we call to mind the phases of the particles, revolving in their circular orbits, at different parts of a wave-profile, it is evident that the forces above investigated, whether normal or tangential, are on the whole urging the surface-particles in the directions in which they are already moving.

Owing to the irregular, eddying, character of a wind blowing over a roughened surface, it is not easy to give more than a general explanation of the manner in which it generates and maintains waves. It is not difficult to see, however, that the action of the wind will tend to produce surface forces of the kinds above investigated. When the air is moving in the direction in which the wave-form is travelling, but with a greater velocity, there will evidently be an excess of pressure on the rear-slopes, as well as a tangential drag on the exposed crests. The aggregate effect of these forces will be a surface drift, and the residual tractions, whether normal or tangential, will have on the whole the distribution above postulated. Hence the tendency will be to increase the amplitude of the waves to such a point that the dissipation balances the work done by the surface forces. In like manner waves travelling faster than the wind, or against the wind, will have their amplitude continually reduced†.

It has been shewn (Art 264) that, under the joint influence of gravity and capillarity, there is a minimum wave-velocity of 23·2 cm per sec, or 45 miles per hour. Hence a wind of smaller velocity than this is incapable of reinforcing waves accidentally started, which, if of short wave-length, must be rapidly extinguished by viscosity‡. This is in accordance with the observations of Scott Russell§, from whose paper we make the following extract:

"Let [a spectator] begin his observations in a perfect calm, when the surface of the

* This agrees with the result given at the end of Art 240, where, however, the dissipative forces were of a different kind.

† Cf. Any, "Tides and Waves," Arts. 265-272, Stokes, *Camb Trans*, t ix p [62] [*Math and Phys. Papers*, t iii p 74], Lord Rayleigh, *l c. ante* p. 548.

‡ Sir W. Thomson, *l c. ante* p 437 [*Baltimore Lectures*, p 594].

§ *l c. ante* p 445.

water is smooth and reflects like a mirror the images of surrounding objects. This appearance will not be affected by even a slight motion of the air, and a velocity of less than half a mile an hour ($8\frac{1}{2}$ m. per sec.) does not sensibly disturb the smoothness of the reflective surface. A gentle zephyr flitting along the surface from point to point, may be observed to destroy the perfection of the mirror for a moment, and on departing, the surface remains as polished as before; if the air have a velocity of about a mile an hour, the surface of the water becomes less capable of distinct reflexion, and on observing it in such a condition, it is to be noticed that the diminution of this reflecting power is owing to the presence of those minute corrugations of the superficial film which form waves of the *first order* [capillary waves].... This first stage of disturbance has this distinguishing circumstance, that the phenomena on the surface cease almost simultaneously with the intermission of the disturbing cause so that a spot which is sheltered from the direct action of the wind remains smooth, the waves of the third order being incapable of travelling apart merely to any considerable distance, except when under the continued action of the original disturbing force. This condition is the indication of present force, not of that which is past. While it remains it gives that deep blackness to the water which the sailor is accustomed to regard as the index of the presence of wind, and often as the forerunner of more.

"The second condition of wave motion is to be observed when the velocity of the wind acting on the smooth water has increased to two miles an hour. Small waves then begin to rise uniformly over the whole surface of the water; these are waves of the second order, and cover the water with considerable regularity. Capillary waves disappear from the ridges of these waves, but are to be found sheltered in the hollows between them, and on the anterior slopes of these waves. The regularity of the distribution of the secondary waves over the surface is remarkable; they begin with about an inch of amplitude, and a couple of inches long, they enlarge as the velocity or duration of the wave increases, by and by the coterminal waves unite; the ridges increase, and if the wind increase the waves become cusped, and are regular waves of the *second order* [gravity waves]*. They continue enlarging their dimensions, and the depth to which they produce the agitation increasing simultaneously with their magnitude, the surface becomes extensively covered with waves of nearly uniform magnitude."

It will be seen that our theoretical investigations give considerable insight into the incipient stages of wave-formation.

334. The calming effect of oil on water waves appears to be due to the *variations* of tension caused by the extensions and contractions of the contaminated surface†. The surface-tension of pure water is less than the sum of the tensions of the surfaces of separation of oil and air, and oil and water, respectively, so that a drop of oil thrown on water is gradually drawn out into a thin film. When the film is sufficiently thin, say not more than two millionths of a millimetre in thickness, it is found that the tension is no longer constant but is increased when the thickness is reduced by stretching, and conversely. It is evident at once from the figure on p. 347 that in

* Scott Russell's wave of the *first order* is the 'solitary wave' discussed *ante* Art. 248.

† Reynolds, "On the Effect of Oil in destroying Waves on the Surface of Water," *Brit. Ass. Rep.*, 1880 [*Sc. Papers*, t. i. p. 409]; Atken, "On the Effect of Oil on a Stormy Sea," *Proc. Roy. Soc. Edin.*, t. xii. p. 56 (1883).

oscillatory waves the tendency is for any portion of the surface to be alternately contracted and extended, according as it is above or below the mean level. The consequent variations in tension produce an alternating tangential drag on the water, with a consequent increase in the rate of dissipation of energy.

The preceding formulæ enable us to submit this explanation, to a certain extent, to the test of calculation.

It is evident beforehand that the effect of the quasi-elasticity of the oil-film will be greater the shorter the wave-length; and that if the wave-length be sufficiently small the surface will be practically inextensible, and the horizontal velocity at the surface will be annulled. We will assume this condition to be fulfilled.

The internal motion of the water will be given by the formulæ (8) of Art. 332, but the determination of the constants is different. The condition to be satisfied by the normal stress is the same as in the Art. cited, and gives

$$(a^2 + 2pk^2a + \sigma^2)A - i(\sigma^2 + 2pkma)C' = 0, \dots \dots \dots (1)$$

where

$$\sigma^2 = gk + T'k^3, \dots \dots \dots (2)$$

T' referring now to the total tension of the oil film. In place of the condition of vanishing tangential stress, we have the condition

$$u = 0 \text{ for } y = 0, \dots \dots \dots (3)$$

which give

$$ikA + mC' = 0, \dots \dots \dots (4)$$

Eliminating the ratio $A : C$, we find

$$m(a^2 + \sigma^2) - k\sigma^2 = 0, \dots \dots \dots (5)$$

or, on eliminating m by means of the equation

$$m^2 = k^2 + \frac{a}{\nu}, \dots \dots \dots (6)$$

$$\left(\frac{a}{\nu} + k^2\right)(a^2 + \sigma^2)^2 - k^2\sigma^4 = 0, \dots \dots \dots (7)$$

This equation has an extraneous root $a = 0$, and other roots are inadmissible as giving, when substituted in (5), negative values to the real part of m . If $\nu k^2/\sigma$ is small, the relevant roots are, to a first approximation, $a = \pm i\sigma$, and to a second

$$a = \pm i\sigma + \frac{\nu^{\frac{1}{2}}k\sigma^{\frac{1}{2}}}{2\sqrt{2}}, \dots \dots \dots (8)$$

where the correction to the 'speed' σ of the oscillations is neglected. The modulus of decay is therefore

$$\tau = \frac{2\sqrt{2}}{\nu^{\frac{1}{2}}k\sigma^{\frac{1}{2}}}, \dots \dots \dots (9)$$

The ratio of this to the modulus obtained on the hypothesis of *constant* surface-tension (viz. $1/2pk^2$) is $4\sqrt{2}(\nu k^2/\sigma)^{\frac{1}{2}}$, which is by hypothesis small*.

335. Problems of periodic motion in three dimensions, having special relation to *spherical* surfaces, may be treated in a general manner, as follows.

* This investigation is abbreviated from that given in the preceding edition.

It is convenient to give, first, the general solution of the system of equations

$$(\nabla^2 + h^2) u' = 0, \quad (\nabla^2 + h^2) v' = 0, \quad (\nabla^2 + h^2) w' = 0, \quad (1)$$

$$\frac{\partial u'}{\partial x} + \frac{\partial v'}{\partial y} + \frac{\partial w'}{\partial z} = 0, \quad \dots \dots \quad (2)$$

in terms of spherical harmonics. This is an extension of the problem considered in Art 323. We will consider only, in the first instance, cases where u' , v' , w' are finite at the origin

The solutions fall naturally into two distinct classes. If r denote the radius vector, the typical solution of the First Class is

$$\left. \begin{aligned} u' &= \psi_n(hr) \left(y \frac{\partial}{\partial z} - z \frac{\partial}{\partial y} \right) \chi_n, \\ v' &= \psi_n(hr) \left(z \frac{\partial}{\partial x} - x \frac{\partial}{\partial z} \right) \chi_n, \\ w' &= \psi_n(hr) \left(x \frac{\partial}{\partial y} - y \frac{\partial}{\partial x} \right) \chi_n, \end{aligned} \right\} \dots \dots \dots (3)$$

where χ_n is a solid harmonic of positive degree n , and ψ_n is defined as in Art. 287 (7). It is easily verified, on reference to Arts 286, 287, that the above expressions do in fact satisfy (1) and (2)

It is to be noticed that this solution makes

$$xu' + yv' + zw' = 0 \quad \dots \dots \dots (4)$$

The typical solution of the Second Class is

$$\left. \begin{aligned} u' &= (n+1) \psi_{n-1}(hr) \frac{\partial \phi_n}{\partial x} - n \psi_{n+1}(hr) h^2 r^{2n+3} \frac{\partial}{\partial x} \frac{\phi_n}{r^{2n+1}}, \\ v' &= (n+1) \psi_{n-1}(hr) \frac{\partial \phi_n}{\partial y} - n \psi_{n+1}(hr) h^2 r^{2n+3} \frac{\partial}{\partial y} \frac{\phi_n}{r^{2n+1}}, \\ w' &= (n+1) \psi_{n-1}(hr) \frac{\partial \phi_n}{\partial z} - n \psi_{n+1}(hr) h^2 r^{2n+3} \frac{\partial}{\partial z} \frac{\phi_n}{r^{2n+1}}, \end{aligned} \right\} \quad (5)$$

where ϕ_n is a solid harmonic of positive degree n . The coefficients of $\psi_{n-1}(hr)$ and $\psi_{n+1}(hr)$ in these expressions are solid harmonics of degrees $n-1$ and $n+1$ respectively, so that the equations (1) are satisfied. To verify that (2) is also satisfied we need the formulae of reduction

$$\psi_n'(\xi) = -\xi \psi_{n+1}(\xi), \quad \dots \dots \dots (6)$$

$$\xi \psi_n'(\xi) + (2n+1) \psi_n(\xi) = \psi_{n-1}(\xi), \quad \dots \dots \dots (7)$$

which are repeated from Art. 287

The formulae (5) make

$$xu' + yv' + zw' = n(n+1)(2n+1) \psi_n(hr) \phi_n, \quad \dots \dots (8)$$

the reduction being effected by means of (6) and (7)

If we write

$$2\xi' = \frac{\partial w'}{\partial y} - \frac{\partial v'}{\partial z}, \quad 2\eta' = \frac{\partial u'}{\partial z} - \frac{\partial w'}{\partial x}, \quad 2\zeta' = \frac{\partial v'}{\partial x} - \frac{\partial u'}{\partial y}, \quad \dots (9)$$

we find, in the solutions of the First Class,

$$\left. \begin{aligned} 2\xi' &= -\frac{1}{2n+1} \left\{ (n+1) \psi_{n-1}(hr) \frac{\partial \chi_n}{\partial x} - n \psi_{n+1}(hr) h^2 r^{2n+3} \frac{\partial}{\partial x} \frac{\chi_n}{r^{2n+1}} \right\}, \\ 2\eta' &= -\frac{1}{2n+1} \left\{ (n+1) \psi_{n-1}(hr) \frac{\partial \chi_n}{\partial y} - n \psi_{n+1}(hr) h^2 r^{2n+3} \frac{\partial}{\partial y} \frac{\chi_n}{r^{2n+1}} \right\}, \\ 2\zeta' &= -\frac{1}{2n+1} \left\{ (n+1) \psi_{n-1}(hr) \frac{\partial \chi_n}{\partial z} - n \psi_{n+1}(hr) h^2 r^{2n+3} \frac{\partial}{\partial z} \frac{\chi_n}{r^{2n+1}} \right\}. \end{aligned} \right\} \dots (10)$$

$$\text{These make} \quad 2(x\xi' + y\eta' + z\zeta') = -n(n+1) \psi_n(hr) \chi_n. \quad \dots (11)$$

In the solutions of the Second Class, we have

$$\left. \begin{aligned} 2\xi' &= -(2n+1) h^2 \psi_n(hr) \left(y \frac{\partial}{\partial z} - z \frac{\partial}{\partial y} \right) \phi_n, \\ 2\eta' &= -(2n+1) h^2 \psi_n(hr) \left(z \frac{\partial}{\partial x} - x \frac{\partial}{\partial z} \right) \phi_n, \\ 2\zeta' &= -(2n+1) h^2 \psi_n(hr) \left(x \frac{\partial}{\partial y} - y \frac{\partial}{\partial x} \right) \phi_n, \end{aligned} \right\} \dots (12)$$

$$\text{and therefore} \quad x\xi' + y\eta' + z\zeta' = 0 \quad \dots (13)$$

In the derivation of these results use has been made of (6), and of the formulae

$$\left. \begin{aligned} x\chi_n &= \frac{r^2}{2n+1} \left(\frac{\partial \chi_n}{\partial x} - r^{2n+1} \frac{\partial}{\partial x} \frac{\chi_n}{r^{2n+1}} \right), \\ y\chi_n &= \frac{r^2}{2n+1} \left(\frac{\partial \chi_n}{\partial y} - r^{2n+1} \frac{\partial}{\partial y} \frac{\chi_n}{r^{2n+1}} \right), \\ z\chi_n &= \frac{r^2}{2n+1} \left(\frac{\partial \chi_n}{\partial z} - r^{2n+1} \frac{\partial}{\partial z} \frac{\chi_n}{r^{2n+1}} \right), \end{aligned} \right\} \dots (14)$$

which are easily seen to hold, whatever the form of χ_n

To shew that the aggregate of the solutions of the types (3) and (5), with all integral values of n , and all possible forms of the harmonics ϕ_n, χ_n , constitutes the *complete* solution of the proposed system of equations (1) and (2), we remark in the first place that the equations in question imply

$$(\nabla^2 + h^2)(xu' + yv' + zw') = 0, \quad \dots (15)$$

and

$$(\nabla^2 + h^2)(x\xi' + y\eta' + z\zeta') = 0 \quad \dots (16)$$

It is evident from Arts 286, 287, that the complete solution of these, subject to the condition of finiteness at the origin, is contained in the equations (8) and (11), above, if these be generalized by prefixing the sign Σ of summation with respect to n . Now when $xu' + yv' + zw'$ and $x\xi' + y\eta' + z\zeta'$ are given throughout any space, the values of u', v', w' are rendered by (2) completely

determinate. For if there were two sets of values, say u', v', w' and u'', v'', w'' , both satisfying the prescribed conditions, then, writing

$$u_1 = u' - u'', \quad v_1 = v' - v'', \quad w_1 = w' - w'',$$

we should have

$$\left. \begin{aligned} xu_1 + yv_1 + zw_1 &= 0, \\ x\xi_1 + y\eta_1 + z\zeta_1 &= 0, \\ \frac{\partial u_1}{\partial x} + \frac{\partial v_1}{\partial y} + \frac{\partial w_1}{\partial z} &= 0. \end{aligned} \right\} \dots \dots \dots (17)$$

If u_1, v_1, w_1 be regarded as the component velocities of a liquid, the first of these shews that the lines of flow are closed curves lying on a system of concentric spherical surfaces. Hence the 'circulation' (Art. 31) in any such line has a finite value. On the other hand, the second equation shews, by Art. 32, that the circulation in any circuit drawn on one of the above spherical surfaces is zero. These conclusions are irreconcilable unless u_1, v_1, w_1 are all zero.

Hence, in the present problem, whenever the functions ϕ_n and χ_n have been determined by (8) and (11), the values of u', v', w' follow uniquely as in (3) and (5).

When the region contemplated is bounded *internally* by a spherical surface, the condition of finiteness when $r=0$ is no longer imposed, and we have an additional system of solutions in which the functions $\psi_n(\xi)$ are replaced by $\Psi_n(\xi)$, in accordance with Art. 287*.

336. The equations of small motion of an incompressible fluid are, in the absence of extraneous forces,

$$\frac{\partial u}{\partial t} = -\frac{1}{\rho} \frac{\partial p}{\partial x} + \nu \nabla^2 u, \quad \frac{\partial v}{\partial t} = -\frac{1}{\rho} \frac{\partial p}{\partial y} + \nu \nabla^2 v, \quad \frac{\partial w}{\partial t} = -\frac{1}{\rho} \frac{\partial p}{\partial z} + \nu \nabla^2 w, \dots (1)$$

with

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 0. \dots \dots \dots (2)$$

* Advantage is here taken of an improvement introduced by Love, "The Free and Forced Vibrations of an Elastic Spherical Shell containing a given Mass of Liquid," *Proc. Lond. Math. Soc.*, t. xix. p. 170 (1888).

The foregoing investigation is taken, with slight changes of notation, from the following papers: "On the Oscillations of a Viscous Spheroid," *Proc. Lond. Math. Soc.*, t. xvi. p. 51 (1881); "On the Vibrations of an Elastic Sphere," *Proc. Lond. Math. Soc.*, t. xiii. p. 189 (1882); "On the Motion of a Viscous Fluid contained in a Spherical Vessel," *Proc. Lond. Math. Soc.*, t. vi. p. 27 (1884). The method has since been applied by the author, and by other writers, to a great variety of physical problems. It has until recently been overlooked that substantially the same analysis had been given by Clebsch in the paper "Ueber die Reflexion an einer Kugelfläche," to which reference has already been made on pp. 102, 487, of this edition. The fact that Clebsch failed (confessedly) in the primary object of his investigation, which was to treat a problem of Physical Optics independently of the assumptions of the 'geometrical' theory, has perhaps contributed to the unjust neglect into which his paper has fallen. The analytical difficulties which he found insuperable, when the wave-length is small compared with the circumference of the sphere, are identical with those alluded to on p. 496 *ante*.

If we assume that u, v, w all vary as e^{ρ} , the equations (1) may be written

$$(\nabla^2 + h^2)u = \frac{1}{\mu} \frac{\partial p}{\partial x}, \quad (\nabla^2 + h^2)v = \frac{1}{\mu} \frac{\partial p}{\partial y}, \quad (\nabla^2 + h^2)w = \frac{1}{\mu} \frac{\partial p}{\partial z}, \quad \dots (3)$$

where
$$h^2 = -\frac{\alpha}{\rho}. \quad \dots \dots \dots (4)$$

From (2) and (3) we deduce

$$\nabla^2 p = 0. \quad \dots \dots \dots (5)$$

Hence a particular solution of (3) and (2) is

$$u = \frac{1}{h\mu} \frac{\partial p}{\partial x}, \quad v = \frac{1}{h\mu} \frac{\partial p}{\partial y}, \quad w = \frac{1}{h\mu} \frac{\partial p}{\partial z}; \quad \dots \dots \dots (6)$$

and the general solution is

$$u = \frac{1}{h\mu} \frac{\partial p}{\partial x} + u', \quad v = \frac{1}{h\mu} \frac{\partial p}{\partial y} + v', \quad w = \frac{1}{h\mu} \frac{\partial p}{\partial z} + w', \quad \dots (7)$$

where u', v', w' are determined by the conditions of the preceding Art.

Hence the solutions in spherical harmonics, subject to the condition of finiteness at the origin, fall into two classes.

In the First Class we have

$$\left. \begin{aligned} p &= \text{const.} \\ u &= \psi_n(hr) \left(y \frac{\partial}{\partial x} - z \frac{\partial}{\partial y} \right) \chi_n, \\ v &= \psi_n(hr) \left(z \frac{\partial}{\partial x} - x \frac{\partial}{\partial z} \right) \chi_n, \\ w &= \psi_n(hr) \left(x \frac{\partial}{\partial y} - y \frac{\partial}{\partial x} \right) \chi_n, \end{aligned} \right\} \quad \dots \dots \dots (8)$$

and therefore
$$xu + yv + zw = 0. \quad \dots \dots \dots (9)$$

In the Second Class we have

$$\left. \begin{aligned} p &= p_n, \\ u &= \frac{1}{h\mu} \frac{\partial p_n}{\partial x} + (n+1) \psi_{n-1}(hr) \frac{\partial \phi_n}{\partial x} - n \psi_{n-1}(hr) h r^{n+1} \frac{\partial}{\partial x} \left(\frac{\phi_n}{r^{n+1}} \right), \\ v &= \frac{1}{h\mu} \frac{\partial p_n}{\partial y} + (n+1) \psi_{n-1}(hr) \frac{\partial \phi_n}{\partial y} - n \psi_{n-1}(hr) h r^{n+1} \frac{\partial}{\partial y} \left(\frac{\phi_n}{r^{n+1}} \right), \\ w &= \frac{1}{h\mu} \frac{\partial p_n}{\partial z} + (n+1) \psi_{n-1}(hr) \frac{\partial \phi_n}{\partial z} - n \psi_{n-1}(hr) h r^{n+1} \frac{\partial}{\partial z} \left(\frac{\phi_n}{r^{n+1}} \right), \end{aligned} \right\} \quad \dots (10)$$

and
$$x\xi + y\eta + z\xi = 0, \quad \dots \dots \dots (11)$$

where ξ, η, ξ denote the component rotations of the fluid at the point (x, y, z) . The symbols χ_n, ϕ_n, p_n stand for solid harmonics of the degrees indicated.

The component tractions on the surface of a sphere of radius r are given as in Art 325 by

$$\left. \begin{aligned} rp_{rx} &= -xp + \mu \left(r \frac{\partial}{\partial r} - 1 \right) u + \mu \frac{\partial}{\partial x} (xu + yv + zw), \\ rp_{ry} &= -yp + \mu \left(r \frac{\partial}{\partial r} - 1 \right) v + \mu \frac{\partial}{\partial y} (xu + yv + zw), \\ rp_{rz} &= -zp + \mu \left(r \frac{\partial}{\partial r} - 1 \right) w + \mu \frac{\partial}{\partial z} (xu + yv + zw) \end{aligned} \right\} . \quad (12)$$

In the solutions of the First Class we find without difficulty

$$\left. \begin{aligned} rp_{rx} &= -xp + P_n \left(y \frac{\partial \chi_n}{\partial z} - z \frac{\partial \chi_n}{\partial y} \right), \\ rp_{ry} &= -yp + P_n \left(z \frac{\partial \chi_n}{\partial x} - x \frac{\partial \chi_n}{\partial z} \right), \\ rp_{rz} &= -zp + P_n \left(x \frac{\partial \chi_n}{\partial y} - y \frac{\partial \chi_n}{\partial x} \right), \end{aligned} \right\} \dots\dots\dots (13)$$

$$\text{where} \quad P_n = \mu \{ hr \psi'_n(hr) + (n-1) \psi_n(hr) \}. \quad \dots\dots (14)$$

To obtain the corresponding formulae for the solutions of the Second Class, we remark first that the terms in p_n give

$$-xp_n + \frac{1}{h^2} \left(r \frac{\partial}{\partial r} - 1 \right) \frac{\partial p_n}{\partial x} + \frac{n}{h^2} \frac{\partial p_n}{\partial x} = \left(\frac{2(n-1)}{h^2} - \frac{r^2}{2n+1} \right) \frac{\partial p_n}{\partial x} + \frac{r^{2n+3}}{2n+1} \frac{\partial}{\partial x} \frac{p_n}{r^{2n+1}} \quad \dots\dots (15)$$

The remaining terms involve

$$\begin{aligned} \left(r \frac{\partial}{\partial r} - 1 \right) u' &= (n+1) \{ hr \psi'_{n-1}(hr) + (n-2) \psi_{n-1}(hr) \} \frac{\partial \phi_n}{\partial x} \\ &\quad - n \{ hr \psi'_{n+1}(hr) + n \psi_{n+1}(hr) \} h^2 r^{2n+3} \frac{\partial}{\partial x} \frac{\phi_n}{r^{2n+1}}, \end{aligned} \quad (16)$$

and

$$\begin{aligned} \frac{\partial}{\partial x} (xu' + yv' + zw') &= n(n+1)(2n+1) \frac{\partial}{\partial x} \psi_n(hr) \phi_n \\ &= n(n+1) \left\{ \psi_{n-1}(hr) \frac{\partial \phi_n}{\partial x} + \psi_{n+1}(hr) h^2 r^{2n+3} \frac{\partial}{\partial x} \frac{\phi_n}{r^{2n+1}} \right\} \end{aligned} \quad (17)$$

Various reductions have here been effected by means of Art 335 (6) (7) (14)

Hence, and by symmetry, we obtain

$$\left. \begin{aligned} rp_{rx} &= A_n \frac{\partial p_n}{\partial x} + B_n r^{2n+1} \frac{\partial}{\partial x} \frac{p_n}{r^{2n+1}} + C_n \frac{\partial \phi_n}{\partial x} + D_n r^{2n+1} \frac{\partial}{\partial x} \frac{\phi_n}{r^{2n+1}}, \\ rp_{ry} &= A_n \frac{\partial p_n}{\partial y} + B_n r^{2n+1} \frac{\partial}{\partial y} \frac{p_n}{r^{2n+1}} + C_n \frac{\partial \phi_n}{\partial y} + D_n r^{2n+1} \frac{\partial}{\partial y} \frac{\phi_n}{r^{2n+1}}, \\ rp_{rz} &= A_n \frac{\partial p_n}{\partial z} + B_n r^{2n+1} \frac{\partial}{\partial z} \frac{p_n}{r^{2n+1}} + C_n \frac{\partial \phi_n}{\partial z} + D_n r^{2n+1} \frac{\partial}{\partial z} \frac{\phi_n}{r^{2n+1}}, \end{aligned} \right\} \quad (18)$$

where

$$\left. \begin{aligned} A_n &= \frac{2(n-1)}{h^2} - \frac{r^2}{2n+1}, \\ B_n &= \frac{r^2}{2n+1}, \\ C_n &= \mu(n+1) \{hr\psi'_{n-1}(hr) + 2(n-1)\psi_{n-1}(hr)\}, \\ D_n &= -\mu nh^2 r^2 \{hr\psi'_{n+1}(hr) - \psi_{n+1}(hr)\} \end{aligned} \right\} \dots \quad (19)$$

337 The general formulae being once established, the application to special problems is easy

1° We may first investigate the decay of the motion of a viscous fluid contained in a spherical vessel which is at rest

The boundary conditions are that

$$u=0, \quad v=0, \quad w=0, \quad \dots \quad (1)$$

for $r=a$, the radius of the vessel. In the modes of the First Class, represented by Art 336 (8), these conditions are satisfied by

$$\psi_n(ha)=0 \quad \dots \quad (2)$$

The roots of this are all real, and the corresponding values of the modulus of decay (τ) are given by

$$\tau = -\frac{1}{\alpha} = \frac{\alpha^2}{\nu} (ha)^{-2} \quad \dots \quad (3)$$

The modes $n=1$ are of a rotatory character, the equation (2) then takes the form

$$\tan ha = ha, \quad \dots \quad (4)$$

the lowest root of which is $ha=4.493$ Hence

$$\tau = 0.495 \frac{a^2}{\nu}$$

In the case of water, we have $\nu=0.18$ c s, and

$$\tau = 2.75 a^2 \text{ seconds,}$$

if a be expressed in centimetres

The modes of the Second Class are given by Art 336 (10). The surface conditions may be expressed by saying that the following three functions of x, y, z , viz

$$\left. \begin{aligned} \mathbf{u} &= \frac{1}{h^2 \mu} \frac{\partial p_n}{\partial x} + (n+1) \psi_{n-1}(ha) \frac{\partial \phi_n}{\partial x} - n \psi_{n+1}(ha) h^2 r^{2n+3} \frac{\partial}{\partial x} \frac{\phi_n}{r^{2n+1}}, \\ \mathbf{v} &= \frac{1}{h^2 \mu} \frac{\partial p_n}{\partial y} + (n+1) \psi_{n-1}(ha) \frac{\partial \phi_n}{\partial y} - n \psi_{n+1}(ha) h^2 r^{2n+3} \frac{\partial}{\partial y} \frac{\phi_n}{r^{2n+1}}, \\ \mathbf{w} &= \frac{1}{h^2 \mu} \frac{\partial p_n}{\partial z} + (n+1) \psi_{n-1}(ha) \frac{\partial \phi_n}{\partial z} - n \psi_{n+1}(ha) h^2 r^{2n+3} \frac{\partial}{\partial z} \frac{\phi_n}{r^{2n+1}}, \end{aligned} \right\} \quad (5)$$

must severally vanish when $r=a$. Now these functions, as they stand, are sums of solid harmonics, and so satisfy the equations

$$\nabla^2 \mathbf{u}=0, \quad \nabla^2 \mathbf{v}=0, \quad \nabla^2 \mathbf{w}=0, \quad \dots \quad (6)$$

If the viscosity be so small that $\beta\alpha$ is considerable, then, keeping only the most important term, we have, for points near the surface,

$$\psi_1(hr) = -\frac{1}{2h^2} e^{(1-i)\beta r}, \quad (19)$$

and therefore, for the angular velocity (14),

$$\alpha \frac{r^2}{2} e^{-\beta(r-r)} e^{i\{\sigma t - \beta(r-r) + \epsilon\}}, \quad (20)$$

the real part of which is

$$\alpha \frac{r^2}{2} e^{-\beta(r-r)} \cos\{\sigma t - \beta(r-r) + \epsilon\} \quad (21)$$

As in the case of laminar motion (Art. 328), this represents a system of waves travelling inwards from the surface with rapidly diminishing amplitude

When, on the other hand, the viscosity is very great, $\beta\alpha$ is small, and the formula (14) reduces to

$$\omega \cos(\sigma t + \epsilon), \quad (22)$$

nearly, when the imaginary part is rejected. This shews that the fluid now moves almost bodily with the sphere

The stress-components at the surface of the sphere are given by Art. 336 (13). In the present case the formulae reduce to

$$p_{xx} = -\frac{1}{\alpha} p + \mu Ch\psi_1'(hr)y, \quad p_{xy} = -\frac{1}{\alpha} p - \mu Ch\psi_1'(hr)x, \quad p_{xz} = -\frac{z}{\alpha} p. \quad (23)$$

If δS denote an element of the surface, these give a couple

$$N = -\iint (x p_{xy} - y p_{xx}) \delta S = C\mu h\psi_1'(h\alpha) \iint (x^2 + y^2) \delta S = \frac{4}{3}\pi\mu\alpha^3 \frac{h^2\alpha^2\psi_1'(h\alpha)}{\psi_1(h\alpha)} \omega, \quad (24)$$

by (13) and Art. 335 (6)

In the case of small viscosity, where $\beta\alpha$ is large, we find, on reference to Art. 287 (8), putting $h\alpha = (1-i)\beta\alpha$, that

$$2i\psi_n(h\alpha) = \left(-\frac{d}{\zeta d\zeta}\right)^n \frac{e^{i\zeta}}{\zeta}, \quad (25)$$

approximately, where $\zeta = (1-i)\beta\alpha$. This leads to

$$N = -\frac{4}{3}\pi\mu\alpha^3(1+i)\beta\alpha\omega. \quad (26)$$

If we take account of the time-factor in (15), this is equivalent to

$$N = -\frac{4}{3}\pi\rho\alpha^5(\beta\alpha)^{-1} \frac{d\omega}{dt} - \frac{4}{3}\pi\mu\alpha^3(\beta\alpha)\omega. \quad (27)$$

The first term has the effect of a slight addition to the inertia of the sphere, the second gives a frictional force varying as the velocity

338 The general formulae of Arts. 335, 336 may be further applied to discuss the effect of viscosity on the oscillations of a mass of liquid about the spherical form. The principal result of the investigation can, however, be obtained more simply by the method of Art. 331.

It was shewn in Art 259 that when viscosity is neglected, the velocity-potential in any fundamental mode is of the form

$$\phi = A \frac{r^n}{a^n} S_n \cdot \cos(\sigma t + \epsilon), \quad \dots \dots \dots (1)$$

where S_n is a surface harmonic. This gives for twice the kinetic energy included within a sphere of radius r the expression

$$\rho \iint \phi \frac{\partial \phi}{\partial r} r^2 d\omega = \rho n a \left(\frac{r}{a}\right)^{2n+1} \iint S_n^2 d\omega A^2 \cos^2(\sigma t + \epsilon), \quad \dots \dots (2)$$

if $\delta\omega$ denote an elementary solid angle, and therefore for the total kinetic energy

$$T = \frac{1}{2} \rho n a \iint S_n^2 d\omega A^2 \cos^2(\sigma t + \epsilon) \quad \dots \dots (3)$$

The potential energy must therefore be

$$V = \frac{1}{2} \rho n a \iint S_n^2 d\omega A^2 \sin^2(\sigma t + \epsilon), \quad (4)$$

and the total energy is

$$T + V = \frac{1}{2} \rho n a \iint S_n^2 d\omega A^2 \quad \dots \dots \dots (5)$$

Again, the dissipation in a sphere of radius r , calculated on the assumption that the motion is irrotational, is, by Art 317 (12),

$$\mu \iint \frac{\partial}{\partial t} \frac{q^2}{r^2} r^2 d\omega = \mu r^2 \frac{\partial}{\partial t} \iint q^2 d\omega \quad \dots \dots (6)$$

Now

$$r^2 \iint q^2 d\omega = \frac{\partial}{\partial t} \iint \phi \frac{\partial \phi}{\partial r} r^2 d\omega, \quad \dots \dots \dots (7)$$

each side, when multiplied by $\rho \delta r$ being double the kinetic energy of the fluid contained between two spheres of radii r and $r + \delta r$. Hence, from (2),

$$\iint q^2 d\omega = \frac{n(2n+1)}{a^2} \left(\frac{r}{a}\right)^{2n-2} \iint S_n^2 d\omega A^2 \cos^2(\sigma t + \epsilon)$$

Substituting in (6), and putting $r=a$, we have, for the total dissipation,

$$2\bar{F} = 2n(n-1)(2n+1) \frac{\mu}{a} \iint S_n^2 d\omega A^2 \cos^2(\sigma t + \epsilon), \quad \dots \dots (8)$$

the mean value of which, per unit time, is

$$2\bar{F} = n(n-1)(2n+1) \frac{\mu}{a} \iint S_n^2 d\omega A^2 \quad \dots \dots (9)$$

If the effect of viscosity be represented by a gradual variation of the coefficient A , we must have

$$\frac{d}{dt}(T + V) = -2\bar{F}, \quad \dots \dots \dots (10)$$

whence, substituting from (5) and (9),

$$\frac{dA}{dt} = -(n-1)(2n+1) \frac{\nu}{a^2} A \quad \dots \dots \dots (11)$$

This shews that $A \propto e^{-t/\tau}$, where

$$\tau = \frac{1}{(n-1)(2n+1)} \frac{a^2}{\nu} \quad \dots \dots \dots (12)^*$$

The most remarkable feature of this result is the excessively minute extent to which the oscillations of a globe of moderate dimensions are affected by such a degree of viscosity

* *Proc Lond Math Soc*, t xiii pp. 61, 65 (1881)

as is ordinarily met with in nature For a globe of the size of the earth, and of the same kinematic viscosity as water, we have, on the c g s system, $\alpha = 6.37 \times 10^8$, $\nu = 0.178$, and the value of τ for the gravitational oscillation of longest period ($n=2$) is therefore

$$\tau = 1.44 \times 10^{11} \text{ years}$$

Even with the value found by Darwin* for the viscosity of pitch near the freezing temperature, viz $\mu = 1.3 \times 10^8 \times g$, we find, taking $g = 980$, the value

$$\tau = 180 \text{ hours}$$

for the modulus of decay of the slowest oscillation of a globe of the size of the earth, having the density of water and the viscosity of pitch Since this is still large compared with the period of 1 h 34 m found in Art 259, it appears that such a globe would oscillate almost like a perfect fluid

The above investigation does not involve any special assumption as to the nature of the forces which produce the tendency to the spherical form The result applies, therefore, equally well to the vibrations of a liquid globule under the surface-tension of the bounding film The modulus of decay of the slowest oscillation of a globule of water is, in seconds, $\tau = 11.2\alpha^2$, where the unit of α is the centimetre

The same method, applied to the case of a spherical bubble, gives

$$\tau = \frac{1}{(n+2)(2n+1)} \frac{\alpha^2}{\nu}, \quad \dots \quad (13)$$

where ν is the viscosity of the surrounding liquid If this be water we have, for $n=2$, $\tau = 2.8\alpha^2$.

The formula (12) includes of course the case of waves on a plane surface When n is very great we find, putting $\lambda = 2\pi\alpha/n$,

$$\tau = \frac{\lambda^2}{8\pi^2\nu}, \quad \dots \quad (14)$$

in agreement with Art 331

The above results all postulate that $2\pi\tau$ is a considerable multiple of the period The opposite extreme, where the viscosity is so great that the motion is aperiodic, can be investigated by the method of Arts 323, 324, the effects of inertia being disregarded In the case of a highly viscous globe returning to the spherical form under the influence of gravitation, it appears that

$$\tau = -\frac{2(n+1)^2+1}{n} \frac{\nu}{ga}, \quad \dots \quad (15)$$

a result first given by Darwin (l c) Cf Art 332 (24)

339 Problems of periodic motion of a liquid in the space between two concentric spheres require for their treatment additional solutions of the equations of Art 336, in which p is of the form p_{-n-1} , and the functions $\psi_n(hr)$ which occur in the complementary functions u' , v' , w' are to be replaced by $\Psi_n(hr)$

The question is simplified, when the radius of the second sphere is

* "On the Bodily Tides of Viscous and Semi-Elastic Spheroids," *Phil Trans*, t clxx p 1 (1878)

infinite, by the condition that the fluid is at rest at infinity. It was shewn in Art. 287 that the functions $\psi_n(\zeta)$, $\Psi_n(\zeta)$ are both included in the form

$$\left(\frac{d}{\zeta d\zeta}\right)^n \frac{Ae^{i\zeta} + Be^{-i\zeta}}{\zeta}. \quad \dots \dots \dots (1)$$

In the present applications, we have $\zeta = hr$, where h is defined by Art 336 (4), and we will suppose, for definiteness, that that value of h is adopted which makes the real part of $i h$ positive. The condition of zero motion at infinity then requires that $A = 0$, and we have to deal only with the function

$$f_n(\zeta) = \left(-\frac{d}{\zeta d\zeta}\right)^n \frac{e^{-i\zeta}}{\zeta}, \quad \dots \dots \dots (2)$$

introduced in Art. 287. It was there pointed out that the formulae of reduction for $f_n(\zeta)$ are exactly the same as for $\psi_n(\zeta)$ and $\Psi_n(\zeta)$, and the general solution of the equations of small periodic motion of a viscous liquid, for the space external to a sphere, is therefore given at once by Art 336 (8), (10), with p_{-n-1} written for p_n , and $f_n(hr)$ for $\psi_n(hr)$

1° The rotatory oscillations of a sphere surrounded by an infinite mass of liquid are included in the solutions of the First Class, with $n=1$. As in Art 337, 2°, we put $\chi_1 = Cz$, and find

$$u = Cf_1(hr)y, \quad v = -Cf_1(hr)x, \quad w = 0, \quad \dots \dots \dots (3)$$

with the condition

$$Cf_1(ha) = -\omega, \quad \dots \dots \dots (4)$$

a being the radius, and ω the angular velocity of the sphere, which we suppose given by the formula

$$\omega = ae^{i(\sigma t + \epsilon)} \quad \dots \dots \dots (5)$$

Putting $h = (1-i)\beta$, where $\beta = (\sigma/2\nu)^{\frac{1}{2}}$, we find that the particles on a concentric sphere of radius r are rotating together with the angular velocity

$$\frac{f_1(hr)}{f_1(ha)} \omega = \frac{aa^3}{r^3} \frac{1+ihr}{1+iha} e^{-\beta(r-a)} e^{i\{\sigma t - \beta(r-a) + \epsilon\}}, \quad \dots \dots \dots (6)$$

where the values of $f_1(hr)$, $f_1(ha)$ have been substituted from Art 287 (15). The real part of (6) is

$$\frac{a}{1+2\beta a+2\beta^2 a^2} \frac{\alpha^3}{r^3} e^{-\beta(r-a)} [\{1+\beta(a+r)+2\beta^2 ar\} \cos \{\sigma t - \beta(r-a) + \epsilon\} - \beta(r-a) \sin \{\sigma t - \beta(r-a) + \epsilon\}], \quad (7)$$

corresponding to an angular velocity

$$\omega = a \cos(\sigma t + \epsilon) \quad \dots \dots \dots (8)$$

of the sphere

The couple on the sphere is found in the same way as in Art 337 to be

$$N = -\frac{8}{3} \pi \mu a^3 \omega \frac{h^2 a^2 f_2(ha)}{f_1(ha)} = -\frac{8}{3} \pi \mu a^3 \omega \frac{3+3iha-h^2 a^2}{1+iha}. \quad (9)$$

Putting $ha = (1-i)\beta a$, and separating the real and imaginary parts we find

$$N = -\frac{8}{3} \pi \mu a^3 \omega \frac{(3+6\beta a+6\beta^2 a^2+2\beta^3 a^3)+2i\beta^2 a^2(1+\beta a)}{1+2\beta a+2\beta^2 a^2} \quad (10)$$

This is equivalent to

$$N = -\frac{1}{2}\pi\rho a^5 \frac{1+\beta a}{1+2\beta a+2\beta^2 a^2} \frac{d\omega}{dt} - \frac{1}{2}\pi\mu a^3 \frac{3+6\beta a+6\beta^2 a^2+2\beta^3 a^3}{1+2\beta a+2\beta^2 a^2} \omega \quad (11)$$

The interpretation is similar to that of Art 337 (27)*

When the period ($2\pi/\sigma$) is infinitely long, this reduces to

$$N = -8\pi\mu a^3 \omega, \quad \dots \quad (12)$$

in agreement with Art 322 (11).

2°. In the case of a ball pendulum oscillating in an infinite mass of fluid, which we treat as incompressible, we take the origin at the mean position of the centre, and the axis of x in the direction of the oscillation

The conditions to be satisfied at the surface are then

$$u = U, \quad v = 0, \quad w = 0, \quad \dots \quad (13)$$

for $r = a$ (the radius), where U denotes the velocity of the sphere. It is evident that we are concerned only with a solution of the Second Class, and the formulae (10) of Art 336, when modified as aforesaid, make

$$xu + yv + zw = -\frac{n+1}{h^2\mu} p_{-n-1} + n(n+1)(2n+1)f_n(hr)\phi_n \quad (14)$$

By comparison with (13), it appears that this must involve surface harmonics of the *first order* only. We therefore put $n=1$, and assume

$$p_{-2} = A \frac{x}{r^3}, \quad \phi_1 = Bx \quad \dots \quad (15)$$

Hence

$$\left. \begin{aligned} u &= \frac{1}{h^2\mu} \frac{\partial}{\partial x} \frac{x}{r^3} + 2Bf_0(hr) - Bf_2(hr) \frac{h^2r^5}{h^2r^5} \frac{\partial}{\partial x} \frac{x}{r^3}, \\ v &= \frac{1}{h^2\mu} \frac{\partial}{\partial y} \frac{x}{r^3} - Bf_2(hr) \frac{h^2r^5}{h^2r^5} \frac{\partial}{\partial y} \frac{x}{r^3}, \\ w &= \frac{1}{h^2\mu} \frac{\partial}{\partial z} \frac{x}{r^3} - Bf_2(hr) \frac{h^2r^5}{h^2r^5} \frac{\partial}{\partial z} \frac{x}{r^3} \end{aligned} \right\} \dots \dots \dots (16)$$

The conditions (13) are therefore satisfied if

$$A = \mu h^4 a^5 f_2(ha) B, \quad 2f_0(ha) B = U \quad \dots \quad (17)$$

The character of the motion, which is evidently symmetrical about the axis of x , can be most concisely expressed by means of the stream-function. From (14) or (16) we find

$$xu + yv + zw = -\frac{2A}{h^2\mu} \frac{x}{r^3} + 6Bf_1(hr)x = -\frac{Ux}{f_0(ha)} \left\{ \frac{h^2a^2}{r^3} f_2(ha) - 3f_1(hr) \right\}, \quad \dots \quad (18)$$

or, substituting from Art. 287 (15),

$$xu + yv + zw = \left\{ \left(1 - \frac{3a}{ha} - \frac{3}{h^2a^2} \right) \frac{a^3}{r^3} + 3 \left(\frac{2}{hr} + \frac{1}{h^2r^2} \right) \frac{a^6}{r} e^{-h(r-a)} \right\} Ux, \quad \dots \quad (19)$$

If we put $x = r \cos \theta$, this leads, in terms of the stream-function ψ of Art 94, to

$$\psi = -\frac{1}{2} U a^2 \sin^2 \theta \left\{ \left(1 - \frac{3a}{ha} - \frac{3}{h^2a^2} \right) \frac{a}{r} + \frac{3}{ha} \left(2 + \frac{1}{hr} \right) e^{-h(r-a)} \right\} \quad \dots \quad (20)$$

* Another solution of this problem is given by Kirchhoff, *Mechanik*, c xxvi

Writing

$$U = ae^{2(\sigma t + \epsilon)}, \quad \dots \quad (21)$$

and therefore $h = (1 - i)\beta$, where $\beta = (\sigma/2\nu)^{\frac{1}{2}}$, we find, on rejecting the imaginary part of (20),

$$\begin{aligned} \psi = & -\frac{1}{2}a\alpha^2 \sin^2 \theta \left[\left\{ \left(1 + \frac{3}{2\beta\alpha}\right) \cos(\sigma t + \epsilon) + \frac{3}{2\beta\alpha} \left(1 + \frac{1}{\beta\alpha}\right) \sin(\sigma t + \epsilon) \right\} \frac{\alpha}{r} \right. \\ & \left. - \frac{3}{2\beta\alpha} \left\{ \cos\{\sigma t - \beta(r - \alpha) + \epsilon\} + \left(1 + \frac{1}{\beta\alpha}\right) \sin\{\sigma t - \beta(r - \alpha) + \epsilon\} \right\} e^{-\beta(r - \alpha)} \right] \end{aligned} \quad (22)$$

At a sufficient distance from the sphere, the part of the disturbance which is expressed by the terms in the first line of this expression is predominant. This part is irrotational, and differs only in amplitude and phase from the motion produced by a sphere oscillating in a frictionless liquid (Arts 92, 96). The terms in the second line are of the type we have already met with in the case of laminar motion (Art 328).

To calculate the resultant force (X) on the sphere, we have recourse to Art 336 (18). Substituting from (15), and rejecting all but the constant terms in p_{1z} , since the surface-harmonics of other than zero order will disappear when integrated over the sphere, we find

$$X = \iint p_{1z} dS = 4\pi \left(B_{-2} \frac{A}{\alpha} + C_1 B \alpha^2 \right), \quad \dots \quad (23)$$

where

$$B_{-2} = -\frac{1}{3}\alpha^2, \quad C_1 = 2\mu h \alpha f_0' (h\alpha), \quad \dots \quad (24)$$

by Art 336 (19). Hence, by (17),

$$\begin{aligned} X &= \frac{2\pi\mu U h \alpha^2}{f_0' (h\alpha)} \{2f_0' (h\alpha) - \frac{1}{3} h^3 \alpha^3 f_2' (h\alpha)\} = 2\pi\mu U h^2 \alpha^3 \left(\frac{1}{3} - \frac{3i}{h\alpha} - \frac{3}{h^2 \alpha^2} \right) \\ &= -2\pi\rho\alpha^3 \sigma U \left\{ \left(\frac{1}{3} + \frac{3}{2\beta\alpha} \right) i + \frac{3}{2\beta\alpha} \left(1 + \frac{1}{\beta\alpha} \right) \right\} \dots \dots \dots (25) \end{aligned}$$

This is equivalent to

$$X = -\frac{4}{3}\pi\rho\alpha^3 \left(\frac{1}{2} + \frac{9}{4\beta\alpha} \right) \frac{dU}{dt} - 3\pi\rho\alpha^3 \sigma \left(\frac{1}{\beta\alpha} + \frac{1}{\beta^2 \alpha^2} \right) U. \quad \dots \dots (26)$$

The first term gives the correction to the inertia of the sphere. This amounts to the fraction

$$\frac{1}{2} + \frac{9}{4\beta\alpha}$$

of the mass of fluid displaced, instead of $\frac{1}{2}$ as in the case of a frictionless liquid (Art 92). The second term gives a frictional force varying as the velocity*.

When the period $2\pi/\sigma$ is made infinitely long, the formula (26) reduces to

$$X = -6\pi\rho\nu\alpha U, \quad \dots \dots \dots (27)$$

in agreement with Art 325 (16), since $\beta^2 = \sigma/2\nu$.

340. A few notes may be appended on the two-dimensional problems which are analogous to those of Arts 337-339.

* This problem was first solved, in a different manner, by Stokes, *loc. ante* p 541. For other methods of treatment see O. E. Meyer, "Ueber die pendelnde Bewegung einer Kugel unter dem Einflusse der inneren Reibung des umgebenden Mediums," *Crelle*, t lxxxi. (1871), Kirchhoff, *Mechanik*, c xxvi. The more general case where the velocity of the sphere is an arbitrary function of the time has been discussed by Basset, "On the Motion of a Sphere in a Viscous Liquid," *Phil. Trans.*, t. clxxix p 43 (1887), *Hydrodynamics*, c xxii.

Terms of the second order being neglected, the equations are

$$\frac{\partial u}{\partial t} = -\frac{1}{\rho} \frac{\partial p}{\partial x} + \nu \nabla_1^2 u, \quad \frac{\partial v}{\partial t} = -\frac{1}{\rho} \frac{\partial p}{\partial y} + \nu \nabla_1^2 v, \quad \dots \quad (1)$$

with
$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} = 0$$

As in Art 332, these are satisfied by

$$u = -\frac{\partial \phi}{\partial x} - \frac{\partial \psi}{\partial y}, \quad v = -\frac{\partial \phi}{\partial y} + \frac{\partial \psi}{\partial x}, \quad \dots \quad (2)$$

and
$$p = \rho \frac{\partial \phi}{\partial t}, \quad \dots \quad (3)$$

provided
$$\nabla_1^2 \phi = 0, \quad \frac{\partial \psi}{\partial t} = \nu \nabla_1^2 \psi \quad \dots \quad (4)$$

1° It will be found that the modes of decay of an arbitrary initial motion of a liquid enclosed in a fixed circular cylinder are given, in polar coordinates, by

$$\Psi = \left\{ \frac{J_s(kr)}{J_s(ka)} - \frac{r^s}{a^s} \right\} (A \cos s\theta + B \sin s\theta) e^{-\nu k^2 t}, \quad \dots \quad (5)$$

when Ψ now stands for the stream-function of Art 59*. The condition of zero normal motion at the boundary ($r=a$) is already satisfied, and the tangential velocity $\partial \Psi / \partial r$ will also vanish there, provided

$$ka J_s'(ka) - s J_s(ka) = 0,$$

which is equivalent, by Art 297 (5), to

$$J_{s+1}(ka) = 0 \quad \dots \quad (6)$$

This determines the admissible values of k , and thence the values of the moduli of decay ($\tau = 1/\nu k^2$)

In the case of symmetry we have $s=0$. The lowest root of $J_1(ka)=0$ is $ka=3.832$, which gives

$$\tau = 0.681 \frac{a^2}{\nu}$$

If we put, for water, $\nu = 0.14$ c.g.s., we find $\tau = 4.9 a^2$ seconds, provided a be expressed in centimetres

For $s=1$, the lowest root is $ka=5.135$, whence

$$\tau = 0.379 \frac{a^2}{\nu},$$

or, for water, $\tau = 2.7 a^2$

2° In the case of periodic motion, with a time-factor $e^{i\sigma t}$, we have, from (4),

$$(\nabla_1^2 + h^2) \psi = 0, \quad \dots \quad (7)$$

provided $h^2 = -i\sigma/\nu$, or (say)

$$h = (1-i)\beta, \quad \beta = \left(\frac{\sigma}{2\nu} \right)^{\frac{1}{2}} \quad \dots \quad (8)$$

* This result is from the paper "On the Motion of a Viscous Fluid contained in a Spherical Vessel," cited on p 574. The case $s=0$ was discussed by Stearn, "On some Cases of the Varying Motion of a Viscous Fluid," *Quart. Journ. Math.*, t. xvii p 90 (1880).

The solution of (7) in polar coordinates involves Bessel's Functions with the complex argument $(1-z)\beta$. The selection of suitable functions for the various cases, and the working out of results in a practical form, involve some points of delicacy*. In view of the length of the necessary investigations, and of the fact that the problems in question are inferior in interest to those which relate to a spherical boundary, we must content ourselves with a reference to the original papers by Stokes†

One remarkable result may, however, be mentioned. When the period of a cylinder oscillating in an infinite liquid is made infinitely long, or (what comes to the same thing) if we attempt to find the steady motion produced by the translation of such a cylinder with constant velocity, we find ourselves unable to satisfy all the conditions. The physical explanation may be given in the words of Stokes. "The pressure of the cylinder on the fluid continually tends to increase the quantity of fluid which it carries with it, while the friction of the fluid at a distance from the cylinder continually tends to diminish it. In the case of a sphere, these two causes eventually counteract each other, and the motion becomes uniform. But in the case of a cylinder, the increase in the quantity of fluid carried continually gains on the decrease due to the friction of the surrounding fluid, and the quantity carried increases indefinitely as the cylinder moves on."

Viscosity in Gases

341 When variations of density have to be taken into account, the most general supposition we can make with regard to the 'mean pressure' p , consistently with our previous assumptions, is, in the case of a 'perfect' gas,

$$p = R\rho\theta - \mu'(a + b + c), \quad \dots \dots \dots (1)$$

where θ is the absolute temperature, R is a constant depending on the nature of the gas, and μ' is a second coefficient of viscosity‡. There does not appear to be any experimental evidence as to the precise value to be attributed to μ' , but according to the kinetic theory of gases $\mu' = 0$ §, and we shall for simplicity adopt this hypothesis. If it is desired to retain μ' in the formulae, the necessary corrections can be easily made.

It was shewn in Art. 317 that the work done in time δt by the tractions on the faces of an element $\delta x \delta y \delta z$, in changing the volume and shape of the element, is

$$-p(a + b + c)\delta x \delta y \delta z \delta t + \Phi \delta x \delta y \delta z \delta t, \quad \dots \dots \dots (2)$$

$$\text{where} \quad \Phi = -\frac{2}{3}\mu(a + b + c)^2 + 2\mu(a^2 + b^2 + c^2 + 2f^2 + 2g^2 + 2h^2) \quad \dots \dots \dots (3)$$

* The investigations of Art. 192 require revision when the argument is complex. The formulae (4), (5), (6), are valid, provided the real part of the argument be positive (as is secured by the choice of h in (8) above), but the derivation of the descending and ascending series (13) and (20) presents new points. Incidentally, the results obtained by equating separately real and imaginary parts would call for examination.

† *l.c. ante* p. 541.

‡ Cf. Kirchhoff, *Vorlesungen über die Theorie der Wärme*, Leipzig, 1894, c. xi, Stokes, *Math. and Phys. Papers*, t. iii p. 136.

§ Maxwell, *l.c. ante* p. 536.

Now, by Art. 7 (3),

$$a + b + c = -\frac{1}{\rho} \frac{D\rho}{Dt} = \rho \frac{D\nabla}{Dt}, \quad \dots \dots \dots (4)$$

where ∇ denotes the volume of unit mass. Hence if E be the intrinsic energy per unit mass, and $\delta Q \delta x \delta y \delta z$ the heat given out by the element in time δt , we have the equation of energy:

$$-p \frac{D\nabla}{Dt} \rho \delta x \delta y \delta z \delta t + \Phi \delta x \delta y \delta z \delta t = \frac{DE}{Dt} \rho \delta x \delta y \delta z \delta t + \delta Q \delta x \delta y \delta z \delta t. \quad (5)$$

If the same changes of density and temperature were made with infinite slowness, the amount of heat given out, say $\delta Q' \delta x \delta y \delta z$, would be determined by

$$-p \frac{D\nabla}{Dt} \rho \delta x \delta y \delta z \delta t = \frac{DE}{Dt} \rho \delta x \delta y \delta z \delta t + \delta Q' \delta x \delta y \delta z \delta t. \quad (6)$$

Comparing, we have

$$\delta Q = \delta Q' + \Phi \delta t. \quad \dots \dots \dots (7)$$

Hence when viscosity is in operation an additional amount of heat, measured by Φ per unit volume and per unit time, must be conveyed away from the element. If this additional flow of heat cannot be effected, there will be additional expansion or rise of temperature. The conclusion is that the viscosity of the gas involves the generation of heat at the rate Φ per unit volume, at the expense of other forms of energy.

If we write (3) in the form

$$\Phi = \frac{2}{3}\mu \{(b-c)^2 + (c-a)^2 + (a-b)^2\} + 4\mu (f^2 + g^2 + h^2), \quad \dots \dots \dots (8)$$

it is seen that Φ is essentially positive, and (moreover) that it cannot vanish unless

$$a = b = c, \text{ and } f = g = h = 0,$$

i.e. unless the distortion of the fluid element consists of an expansion or contraction which is the same in all directions. The conclusion that there is no dissipation of energy in this case rests of course on the assumption that the value of μ' in (1) is zero.

342. We may briefly notice the effect of viscosity on sound-waves. For consistency it is necessary to take account at the same time of heat-conduction, whose influence is of the same order of importance*, but in the first instance we follow Stokes† in examining the effect of viscosity alone.

In the case of plane waves in a laterally unlimited medium, we have, if we take the axis of x in the direction of propagation, and neglect terms of the second order in the velocity,

$$\frac{\partial u}{\partial t} = -\frac{1}{\rho_0} \frac{\partial p}{\partial x} + \frac{1}{3}\nu \frac{\partial^2 u}{\partial x^2}, \quad \dots \dots \dots (1)$$

* This was first remarked by Kirchhoff, "Ueber den Einfluss der Wärmeleitung in einem Gase auf die Schallbewegung," *Pogg Ann*, t. cxxxiv. p. 177 (1868) [*Ges Abh.*, t. 1 p. 540].

† *l.c. ante* p. 457.

by Art 316 (2), (3). If s denote the condensation, the equation of continuity is, as in Art 273,

$$\frac{\partial s}{\partial t} = -\frac{\partial u}{\partial x}, \quad \dots \dots \dots (2)$$

and the physical equation is, if the transfer of heat be neglected,

$$p = p_0 + c^2 \rho_0 s, \quad \dots \dots \dots (3)$$

where c is the velocity of sound in the absence of viscosity. Eliminating p and s , we have

$$\frac{\partial^2 u}{\partial t^2} = c^2 \frac{\partial^2 u}{\partial x^2} + \frac{4}{3} \nu \frac{\partial^3 u}{\partial x^2 \partial t} \quad \dots \dots \dots (4)$$

To apply this to the case of forced waves, we may suppose that at the plane $x=0$ a given vibration

$$u = ae^{i\sigma t} \quad \dots \dots \dots (5)$$

is kept up. Assuming as the solution of (4)

$$u = ae^{i\sigma t + mx}, \quad \dots \dots \dots (6)$$

we find

$$m^2 (c^2 + \frac{4}{3} i \nu \sigma) = -\sigma^2, \quad \dots \dots \dots (7)$$

whence

$$m = \pm \frac{i\sigma}{c} \left(1 - \frac{4}{3} i \frac{\nu\sigma}{c^2} \right)^{-\frac{1}{2}}. \quad \dots \dots \dots (8)$$

If we neglect the square of $\nu\sigma/c^2$, and take the lower sign, this gives

$$m = -\frac{i\sigma}{c} - \frac{2}{3} \frac{\nu\sigma^2}{c^3}. \quad \dots \dots \dots (9)$$

Substituting in (6), and taking the real part, we get, for the waves propagated in the direction of x -positive

$$u = ae^{-x/l} \cos \sigma \left(t - \frac{x}{c} \right), \quad \dots \dots \dots (10)$$

where

$$l = \frac{3}{2} \frac{c^3}{\nu\sigma^2}. \quad \dots \dots \dots (11)$$

The amplitude of the waves diminishes exponentially as they proceed, the diminution being more rapid the greater the value of σ . The wave-velocity is, to the first order of $\nu\sigma/c^2$, unaffected by the friction.

The linear magnitude l measures the distance in which the amplitude falls to $1/e$ of its original value. If λ denote the wave-length ($2\pi c/\sigma$), we have

$$\frac{2}{3} \frac{\nu\sigma}{c^2} = \frac{\lambda}{2\pi l}, \quad \dots \dots \dots (12)$$

it is assumed in the above calculation that this is a small ratio

In the case of air-waves we have $c = 332 \times 10^4$, $\nu = .132$, c g s, whence

$$\frac{\nu\sigma}{c^2} = \frac{2\pi\nu}{\lambda c} = 2.50\lambda^{-1} \times 10^{-5}, \quad l = 9.56\lambda^2 \times 10^3,$$

if λ be expressed in centimetres

To find the decay of *free* waves of any prescribed wave-length ($2\pi/k$), we assume

$$u = ae^{ikx + \alpha t}; \quad \dots \dots \dots (13)$$

and, substituting in (4), we obtain

$$\alpha^2 + \{ \nu k^2 \alpha = -k^2 c^2 \quad \dots \dots \dots (14)$$

If we neglect the square of $\nu k/c$, this gives

$$\alpha = -\frac{1}{2}\nu k^2 \pm ikc \quad \dots \dots \dots (15)$$

Hence, in real form,

$$u = ae^{-t/\tau} \cos k(x \pm ct), \quad \dots \dots \dots (16)$$

where

$$\tau = \frac{3}{2\nu k^2} \quad \dots \dots \dots (17)^*$$

343 When conductivity is to be allowed for, the dynamical equation (1), and the equation of continuity (2) are unaffected, but the physical relations must be modified

The amount of heat required to produce small changes in the volume v and (absolute) temperature θ of unit mass of a gas is

$$M\delta v + N\delta\theta,$$

where N is the specific heat at constant volume, and

$$M = (\gamma - 1) \frac{\theta_0}{v_0} N \quad \dots \dots \dots (18)$$

Multiplying this by $\rho_0 \delta x$, the mass per unit area of a thin stratum, and equating to $q \partial \theta / \partial x \cdot \delta x$, where q is the thermal conductivity, we find †

$$\frac{\partial \theta}{\partial t} + (\gamma - 1) \frac{\theta_0}{v_0} \frac{\partial v}{\partial t} = \nu' \frac{\partial^2 \theta}{\partial x^2}, \quad \dots \dots \dots (19)$$

where

$$\nu' = \frac{q}{N\rho_0}, \quad \dots \dots \dots (20)$$

i.e. ν' is the 'thermometric' conductivity‡.

* For a calculation, on the same assumptions, of the effect of viscosity in damping the vibrations of an contained within spherical and cylindrical envelopes reference may be made to the paper "On the Motion of a Viscous Fluid contained in a Spherical Vessel," cited on p. 574

† The heat generated by internal friction is here neglected, as being of the second order of small quantities. The system of exact equations is given by Kirchhoff, *Vorlesungen über die Theorie der Wärme*, c. xi

‡ Maxwell, *Theory of Heat*, c. xviii

The relation between p , ρ , θ is

$$p = p_0 \frac{\rho}{\rho_0} \frac{\theta}{\theta_0} \quad . \quad . \quad . \quad . \quad . \quad (21)$$

$$\text{If we put} \quad \rho = \rho_0(1 + s), \quad \theta = \theta_0(1 + \eta), \quad . \quad . \quad . \quad . \quad (22)$$

and neglect terms of the second order in s and η , the equations (19) and (21) may be written

$$\frac{\partial \eta}{\partial t} - (\gamma - 1) \frac{\partial s}{\partial t} = \nu' \frac{\partial^2 \eta}{\partial x^2}, \quad . \quad . \quad . \quad . \quad . \quad (23)$$

$$\text{and} \quad p = p_0(1 + s + \eta). \quad . \quad . \quad . \quad . \quad . \quad (24)$$

Substituting this value of p in (1), we have

$$\frac{\partial u}{\partial t} = -b^2 \frac{\partial s}{\partial x} - b^2 \frac{\partial \eta}{\partial x} + \frac{4}{3} \nu \frac{\partial^2 u}{\partial x^2}, \quad . \quad . \quad . \quad . \quad . \quad (25)$$

where $b, = (p_0/\rho_0)^{\frac{1}{2}}$, is the Newtonian velocity of sound (Art. 274) Eliminating s by (2), we find

$$\frac{\partial^2 u}{\partial t^2} = b^2 \frac{\partial^2 u}{\partial x^2} - b^2 \frac{\partial^2 \eta}{\partial x \partial t} + \frac{4}{3} \nu \frac{\partial^2 u}{\partial x^2 \partial t}, \quad . \quad . \quad . \quad . \quad . \quad (26)$$

$$\text{and} \quad \frac{\partial \eta}{\partial t} + (\gamma - 1) \frac{\partial u}{\partial x} = \nu' \frac{\partial^2 \eta}{\partial x^2}, \quad . \quad . \quad . \quad . \quad . \quad (27)$$

which are two simultaneous equations to determine u and η

If we now assume that u and η both vary as

$$e^{\alpha t + m x},$$

$$\text{we find} \quad \left. \begin{aligned} (\alpha^2 - b^2 m^2 - \frac{4}{3} \nu \alpha m^2) u + b^2 \alpha m \eta &= 0, \\ (\gamma - 1) m u + (\alpha - \nu' m^2) \eta &= 0, \end{aligned} \right\} \quad . \quad . \quad . \quad . \quad . \quad (28)$$

$$\text{whence} \quad \alpha^2 - \{c^2 \alpha + (\frac{4}{3} \nu + \nu') \alpha^2\} m^2 + \nu' (b^2 + \frac{4}{3} \nu \alpha) m^4 = 0, \quad . \quad . \quad . \quad . \quad (29)$$

where we have written c^2 for γb^2

We verify that if $\nu = 0$, $\nu' = 0$, we have $\alpha = \pm mc$. Also that if $\nu = 0$, $\nu' = \infty$, we have $\alpha = \pm mb$, as we should expect, since the conditions are now 'isothermal'

According to Maxwell's kinetic theory of gases

$$\nu' = \frac{1}{2} \nu, \quad . \quad . \quad . \quad . \quad . \quad (30)$$

but we shall only assume that ν' and ν are of the same order of magnitude

In the case of simple-harmonic motion we have $\alpha = i\sigma$, where $2\pi/\sigma$ is the period. We have seen that for ordinary sound-waves the ratio $\nu\sigma/c^2$ is small The equation (29) is a quadratic in m^2 , whose roots are

$$m_1^2 = \frac{\alpha^2}{c^2}, \quad m_2^2 = \frac{c^2 \alpha}{\nu' b^2}, \quad . \quad . \quad . \quad . \quad . \quad (31)$$

approximately A more accurate value of the former root is

$$m_1^2 = \frac{\alpha^2}{c^2} \left[1 - \left\{ \frac{1}{2} \nu + \left(1 - \frac{b^2}{c^2} \right) \nu' \right\} \frac{\alpha}{c^2} \right], \quad . \quad . \quad (32)$$

whence
$$m_1 = \pm \left(\frac{i\sigma}{c} + \frac{1}{l} \right), \quad (33)$$

if
$$l = \frac{c^2}{\left\{ \frac{3}{2} \nu + \frac{1}{2} \left(1 - \frac{b^2}{c^2} \right) \nu' \right\} \sigma^2} \quad . \quad . \quad (34)$$

The complete solution for $x > 0$ is found to be, approximately,

$$\left. \begin{aligned} u &= A_1 e^{i\sigma t + m_1 x} + A_2 e^{i\sigma t + m_2 x}, \\ \eta &= \frac{\gamma - 1}{c} A_1 e^{i\sigma t + m_1 x} + \frac{m_2}{2\sigma} A_2 e^{i\sigma t + m_2 x}, \end{aligned} \right\} \quad \dots \quad (35)$$

provided m_1, m_2 are chosen so as to have their real parts negative The arbitrary constants A_1, A_2 enable us to represent the effect of prescribed periodic variations of u and η at the plane $x = 0$ For ordinary frequencies the ratio $m_2/c\sigma$ is large, and the ratio A_2/A_1 accordingly usually small The second term in the value of u is then unimportant, even near the origin, and in any case it becomes insignificant in comparison with the first term for sufficiently great values of x . Its use is to represent the purely local effect of a periodic source of heat at the origin.

If we adopt the value (30) of ν' , and take $c^2/b^2 = \gamma = 1.410$, we find from (34) that the value of l is diminished by conductivity in the ratio .647

The investigation of this Art. is due substantially to Kirchhoff*, who further examined the effect on the propagation of sound-waves in a narrow tube. This problem is important for its bearing on the well-known experiments of Kundt. Lord Rayleigh has applied the same principles to explain the action of porous bodies in absorption of sound†.

Turbulent Motion.

344 It remains to call attention to the chief outstanding difficulty of our subject.

It has already been pointed out that the neglect of the terms of the second order ($v\partial u/\partial x$, &c.) seriously limits the application of many of the preceding results to fluids possessed of ordinary degrees of mobility Unless the velocities be very small, the actual motion in such cases, so far as it

* *l.c. ante* p 587 The investigation is given in Lord Rayleigh's *Theory of Sound*, 2nd ed., Arts. 348-350

† "On Porous Bodies in relation to Sound," *Phil. Mag.* (5), t. xvi p. 181 (1883) [*Sc. Papers*, t. ii. p. 220, *Theory of Sound*, Art. 351]

admits of being observed, is found to be very different from that represented by our formulae. For example, when a solid of 'easy' shape moves through a liquid, an irregular, eddying, motion is produced in a layer of the fluid next to the solid, and a widening trail of eddies is left behind, whilst the motion at a distance laterally is comparatively smooth and uniform

The mathematical disability above pointed out does not apply to cases of *rectilinear* flow, such as have been discussed in Arts 318, 319, but even here observation shews that the types of motion above investigated, though always theoretically possible, become under certain conditions unstable. The case of flow through a pipe of circular section has been made the subject of a very careful experimental study by Reynolds*, by means of filaments of coloured fluid introduced into the stream. So long as the mean velocity (w_0) over the cross-section falls below a certain limit depending on the radius of the pipe and the nature of the fluid, the flow is smooth, and in accordance with Poiseuille's laws, but when this limit is exceeded the motion becomes wildly irregular, and the tube appears to be filled with interlacing and constantly varying streams, crossing and recrossing the pipe†. It was inferred by Reynolds, from considerations of dimensions, that the aforesaid limit must be determined by the ratio of $w_0 a$ to ν , where a is the radius, and ν the (kinematic) viscosity. This was verified by experiment, the critical ratio being found to be, roughly,

$$\frac{w_0 a}{\nu} = 1000 \quad \dots \dots \dots (1)^\dagger$$

Thus for a pipe one centimetre in radius the critical velocity for water ($\nu = 0.18$) would be 18 cm. per sec.

Simultaneously with the change in the character of the motion, when the critical ratio is passed, there is a change in the relation between the pressure-gradient (dp/dz) and the mean velocity w_0 . So long as $w_0 a/\nu$ falls below the above limit, dp/dz varies as w_0 , as in Poiseuille's experiments, but when the irregular mode of flow has set in, dp/dz varies more nearly as w_0^2 .

The practical formula adopted by writers on Hydraulics, for pipes whose diameter exceeds a certain limit, is

$$R = \frac{1}{2} f \rho w_0^2, \quad \dots \dots \dots (2)$$

where R is the tangential resistance per unit area, w_0 is the mean velocity relative to the wetted surface, and f is a numerical constant depending on the nature of the surface. As a rough average value for the case of water

* "An Experimental Investigation of the Circumstances which determine whether the Motion of Water shall be Direct or Sinuous, and of the Law of Resistance in Parallel Channels," *Phil Trans.*, t. clxiv p 985 (1883) [*Sc Papers*, t. ii p 51]

† Somewhat similar observations were made by Hagen, *Berl. Abh.*, 1854, p 17

† The dependence on ν was tested by varying the temperature. The result is confirmed, for a wider range of temperature, by Coker and Clement, *Phil Trans.*, A, t. cci p. 45 (1902). See also Baines and Coker, *Proc Roy Soc.*, t. lxxiv. p 341 (1904)

moving over a clean iron surface, we may take $f' = 0.05^*$. A more complete expression for R , taking into account the influence of the diameter, was given by Darcy, as the result of very extensive observations on the flow of water through conduits[†].

The resistance, in the case of turbulent flow, is found to be sensibly independent of the temperature, and therefore of the viscosity of the fluid. This is what we should anticipate from considerations of 'dimensions,' if it be assumed that $R \propto w_0^{-1}$.

If we accept the formula (2) as the expression of observed facts, a conclusion of some interest may at once be drawn. Taking the axis of z in the general direction of the flow, if w denote the *mean* velocity (with respect to the *time*) at any point of space, we have, at the surface,

$$\mu \frac{\partial w}{\partial n} = \frac{1}{2} f \rho w_0^2,$$

if w_0 denote the general velocity of the stream, and δn an element of the normal. If we take a linear magnitude l such that

$$\frac{w_0}{l} = \frac{\partial w}{\partial n},$$

then l measures the distance between two planes moving with a relative velocity w_0 in the regular 'laminar' flow which would give the same tangential stress. We find

$$w_0 l = \frac{2\nu}{f}, \quad \dots\dots\dots(3)$$

For example, putting $\nu = 0.18$, $w_0 = 300$ [c.s.], $f' = 0.05$, we obtain $l = 0.24$ cm. § The smallness of this result suggests that in the turbulent flow of a fluid through a pipe of not too small diameter the value of w is nearly uniform over the section, falling rapidly to zero within a very minute distance of the walls||.

Applied to pipes of sufficient width, the formula (2) gives

$$= \pi a^2 \frac{dp}{dz} = 2\pi a R = \pi f \rho a w_0^2,$$

or
$$= \frac{1}{4} \frac{dp}{dz} \frac{a^2}{f} = \frac{w_0^2}{a} \cdot \dots\dots\dots(4)$$

* See Rankine, *Applied Mechanics*, Art. 638; Unwin, *Encey. Britann.*, 9th ed., Art. "Hydro-mechanics."

† *Recherches expérimentales relatives au mouvement de l'eau dans les tuyaux*, Paris, 1855. The formula is quoted by Rankine and Unwin.

‡ Lord Rayleigh, "On the Question of the Stability of the Flow of Fluids," *Phil. Mag.* (5), t. xxxiv. p. 59 (1892) [*See Papers*, t. iii. p. 575].

§ Cf. Sir W. Thomson, *Phil. Mag.* (5), t. xxiv. p. 277 (1887).

|| This was in fact found experimentally by Darcy, *l.c.* See also Morrow, "On the Distribution of Velocity in a Viscous Fluid over the Cross-Section of a Pipe, and on the Action at the Critical Velocity," *Proc. Roy. Soc. A*, t. lxxvi. p. 205 (1905).

The form of the relation which was found to hold by Reynolds, in his experiments, was

$$\frac{1}{\rho} \frac{dp}{dz} \propto \frac{\nu^{2-m} \omega_0^m}{\omega^{3-m}},$$

where $m = 1.723$ *.

The increased resistance, for velocities above a certain limit, represented by the formula (2) or (4), is no doubt due to the action of the eddies in continually bringing fresh fluid, moving with a considerable relative velocity, close up to the boundary, and so increasing the distortion-rate ($\partial w / \partial n$) greatly beyond that which would obtain in regular 'laminar' motion†.

The frictional or 'skin-resistance'‡ experienced by a solid of 'easy' shape moving through a liquid is to be accounted for on the same principles. The circumstances are however more complicated than in the case of a pipe. The friction appears to vary roughly as the square of the velocity, but it is different in different parts of the wetted area, for a reason given by W. Froude§, to whom the most exact observations on the subject are due.

Another interesting case of turbulent motion has been investigated experimentally by Mallock||

345. It must unfortunately be confessed that the theoretical explanation of the instability of linear flow under the conditions stated, and of the manner in which eddies are maintained against viscosity, is still somewhat obscure. We can only offer a brief account of the various attempts which have been made to elucidate the question.

Lord Rayleigh, in several papers¶, has set himself to examine the stability of various arrangements of vortices, such as might be produced by viscosity. The fact that, in the *disturbed* motion, viscosity is ignored does not seriously affect the physical value of the results except perhaps in cases where these would imply slipping at a rigid boundary.

* Cf Hagen, *loc. cit.* An interesting historical account of the whole matter is given by Knibbs, *Proc. Roy. Soc. N.S.W.*, t. xxxi p. 314 (1897).

† Stokes, *Math. and Phys. Papers*, t. i p. 99.

‡ So called by writers on naval architecture, to distinguish it from the 'wave-resistance' referred to in Aits. 245, 253.

§ "Experiments on the Surface-friction experienced by a Plane moving through Water," *Brit. Ass. Rep.*, 1872, p. 118. "The portion of the surface that goes first in the line of motion, in experiencing resistance from the water, must in turn communicate to the water motion, in the direction in which it is itself travelling. Consequently the portion of the water which succeeds the first will be rubbing, not against stationary water, but against water partially moving in its own direction, and cannot therefore experience as much resistance from it."

|| "Experiments on Fluid Viscosity," *Phil. Trans. A*, t. clxxxvii p. 41 (1895).

¶ "On the Stability or Instability of certain Fluid Motions," *Proc. Lond. Math. Soc.*, t. xi p. 57 (1880); t. xix p. 67 (1887), t. xxvii p. 5 (1895); "On the Question of the Stability of the Flow of Fluids," *Phil. Mag.* (5), t. xxxiv p. 59 (1892), "On the Instability of Cylindrical Fluid Surfaces," *Phil. Mag.* (5), t. xxxiv p. 177 (1892) [*Sci. Papers*, t. i p. 474; t. iii. pp. 575, 594; t. iv p. 203].

The appropriate solutions of this are

$$\left. \begin{aligned} v' &= Ae^{-ky}, & \text{for } y > h, \\ v' &= Be^{-ky} + Ce^{ky}, & \text{for } h > y > -h, \\ v' &= De^{ky}, & \text{for } y < -h \end{aligned} \right\} \quad (11)$$

The continuity of v' requires

$$\left. \begin{aligned} Ae^{-kh} &= Be^{-kh} + Ce^{kh}, \\ De^{-kh} &= Be^{kh} + Ce^{-kh} \end{aligned} \right\} \quad (12)$$

With the help of these relations, the condition (9) gives

$$\left. \begin{aligned} 2(\sigma + k\mathbf{u}) Ce^{kh} - \frac{\mathbf{u}}{h} (Be^{-kh} + Ce^{kh}) &= 0, \\ 2(\sigma - k\mathbf{u}) Be^{kh} + \frac{\mathbf{u}}{h} (Be^{kh} + Ce^{-kh}) &= 0 \end{aligned} \right\} \quad (13)$$

Eliminating the ratio B/C , we obtain

$$\sigma^2 = \frac{\mathbf{u}^2}{4h^2} \{ (2hk - 1)^2 - e^{-4kh} \} \quad (14)$$

For small values of kh this makes $\sigma^2 = -k^2\mathbf{u}^2$, as in the case of absolute discontinuity (Art 233). For large values of kh , on the other hand, $\sigma = \pm k\mathbf{u}$, indicating stability. Hence the question as to the stability for disturbances of wave-length λ depends on the ratio $\lambda/2h$. The values of the function in { } on the right-hand of (14) have been tabulated by Lord Rayleigh. It appears that there is instability if $\lambda/2h > 5$, about, and that the instability is a maximum for $\lambda/2h = 8$.

2° In the papers referred to, Lord Rayleigh has further investigated various cases of flow between parallel walls, with the view of throwing light on the conditions of stability of linear motion in a pipe. The main result is that if d^2U/dy^2 does not change sign, in other words, if the curve with y as abscissa and U as ordinate is of one curvature throughout, the motion is stable. Since, however, the disturbed motion involves slipping at the walls, it remains doubtful how far the conclusions apply to the question at present under consideration, in which the condition of no slipping appears to be fundamental.

3° The substitution of (10) for (8), when $d^2U/dy^2 = 0$, is equivalent to assuming that the rotation ζ is the same as in the undisturbed motion, since on this hypothesis we have

$$\frac{\partial u'}{\partial y} = \frac{\partial v'}{\partial x} = kv', \quad (15)$$

which, with (6), leads to the equation in question

It is to be observed, however, that when $d^2U/dy^2 = 0$, the equation (8) may be satisfied, for a particular value of y , by $\sigma + kU = 0$. For example, we may suppose that at the plane $y = 0$ a thin layer of (infinitely small) additional vorticity is introduced. We then have, on the hypothesis that the fluid is unlimited,

$$v' = Ae^{\mp ky}, \quad \dots \quad (16)$$

the upper or the lower sign being taken according as y is positive or negative. The condition (9) is then satisfied by

$$\sigma + kU_0 = 0, \quad (17)$$

$$\Delta \left(\frac{dU}{dy} \right) = 0, \quad \dots \quad (18)$$

where U_0 denotes the value of U for $y=0$. Since the superposition of a uniform velocity in the direction of x does not alter the problem, we may suppose $U_0=0$, and therefore $\sigma=0$. The disturbed motion is steady, in other words, the original state of flow is (to the first order of small quantities) *neutral* for a disturbance of this kind*.

Lord Kelvin has attacked directly the very difficult problem of determining the stability of laminar motion when viscosity is taken into account†. He concludes that the linear flow of a fluid through a pipe, or of a stream over a plane bed, is stable for infinitely small disturbances, but that for disturbances of more than a certain amplitude the motion becomes unstable, the limits of stability being narrower the smaller the viscosity‡.

346 Reynolds, in a remarkable paper§, has attacked the question from a different point of view. Taking the turbulent motion as already existing, he seeks to establish a criterion which shall decide whether the turbulent character will increase or diminish or be stationary.

For this purpose the velocity (u, v, w) is resolved into two components. We may, for instance, write

$$\bar{u} = \frac{1}{\tau} \int_{t-\frac{1}{2}\tau}^{t+\frac{1}{2}\tau} u dt, \quad \bar{v} = \frac{1}{\tau} \int_{t-\frac{1}{2}\tau}^{t+\frac{1}{2}\tau} v dt, \quad \bar{w} = \frac{1}{\tau} \int_{t-\frac{1}{2}\tau}^{t+\frac{1}{2}\tau} w dt, \quad . \quad . \quad . \quad (1)$$

so that $\bar{u}, \bar{v}, \bar{w}$ are the mean values of u, v, w at the point (x, y, z) , taken over an interval of time extending from $t - \frac{1}{2}\tau$ to $t + \frac{1}{2}\tau$. Again, we might consider the mean values at the instant t over a space S (e.g. a sphere) surrounding the point (x, y, z) , thus

$$\bar{u} = \frac{1}{S} \iiint u dx dy dz, \quad \bar{v} = \frac{1}{S} \iiint v dx dy dz, \quad \bar{w} = \frac{1}{S} \iiint w dx dy dz \quad (2)$$

Or, again, we might take a double mean, for times ranging over an interval τ , and points ranging over a space S . The actual velocities are in each case denoted by

$$u = \bar{u} + u', \quad v = \bar{v} + v', \quad w = \bar{w} + w', \quad . \quad . \quad . \quad (3)$$

where u', v', w' may be called the components of the turbulent motion. This implies that

$$\bar{u}' = 0, \quad \bar{v}' = 0, \quad \bar{w}' = 0, \quad . \quad . \quad . \quad (4)$$

where the bar placed over a symbol denotes the mean value, taken according to the particular convention adopted.

For simplicity we will adopt the definition of mean value which is embodied in the formulae (1).

* Cf. Sir W. Thomson, "On a Disturbing Infinity in Lord Rayleigh's solution for Waves in a plane Vortex Stratum," *Brit. Ass. Rep.*, 1880, p. 492. For a mathematical discussion of the differential equation (8), and of the singularities which may occur in its solution, reference may be made to Love, *Proc. Lond. Math. Soc.*, t. xxvii p. 199 (1896).

† "Rectilinear Motion of Viscous Fluid between two Parallel Planes," *Phil. Mag.* (5), t. xxiv p. 188 (1887), "Broad River flowing down an Inclined Plane Bed," *Phil. Mag.* (5), t. xxiv p. 272 (1887).

‡ A portion of the investigation has been criticised by Lord Rayleigh, *loc. ante* p. 593.

§ "On the Dynamical Theory of Incompressible Viscous Fluids and the Determination of the Criterion," *Phil. Trans. A*, t. clxxxvi p. 123 (1894) [*Sci. Papers*, t. ii p. 535].

Reynolds starts from the dynamical equations in the forms

$$\rho \frac{\partial u}{\partial t} = \rho X + \frac{\partial}{\partial x} (p_{xx} - \rho uv) + \frac{\partial}{\partial y} (p_{yx} - \rho uv) + \frac{\partial}{\partial z} (p_{zx} - \rho uw), \quad \dots, \quad (5)$$

which are seen to be equivalent to Art 316 (1) in virtue of the equation of continuity

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 0. \quad \dots \quad (6)$$

These forms are not essential to the argument, but are interesting as an application of the method employed by Maxwell* in the kinetic theory of gases. They express the rate of variation of the momentum contained in a fixed rectangular space $\delta x \delta y \delta z$, as a consequence partly of the forces acting on the substance which at the moment occupies this space, and partly of the flux of matter across the boundary, carrying its momentum with it. Thus the fluxes of x -momentum across unit areas perpendicular to Ox , Oy , Oz , are ρu , ρv , and ρw , respectively; and taking the difference of the fluxes across opposite faces of the elementary space $\delta x \delta y \delta z$, we obtain a gain of x -momentum equal to

$$-\frac{\partial}{\partial x} (\rho u \delta y \delta z) + \frac{\partial}{\partial y} (\rho v \delta x \delta z) - \frac{\partial}{\partial z} (\rho w \delta x \delta y) \quad \text{per unit time}$$

We now take the mean value of each member of the equations (5), using the substitutions (3). It is assumed that we may, without sensible error, take the mean values of \bar{u} , \bar{u}' , \bar{u}'' , \bar{u}''' , \dots to be \bar{u} , 0, 0, 0, \dots , respectively. This is not exact, but is permissible provided the fluctuations of u , v , w about their mean values are sufficiently numerous within the time-interval τ . It follows that

$$\bar{uu} = \bar{u}\bar{u} + \bar{u'u'}, \quad \bar{uv} = \bar{u}\bar{v} + \bar{u'v'}, \quad \bar{uw} = \bar{u}\bar{w} + \bar{u'w'}, \quad \dots \quad (7)$$

In this way we obtain

$$\rho \frac{\partial \bar{u}}{\partial t} = \rho X + \frac{\partial}{\partial x} (\bar{p}_{xx} - \rho \bar{u}\bar{u} - \rho \bar{u'u'}) + \frac{\partial}{\partial y} (\bar{p}_{yx} - \rho \bar{u}\bar{v} - \rho \bar{u'v'}) + \frac{\partial}{\partial z} (\bar{p}_{zx} - \rho \bar{u}\bar{w} - \rho \bar{u'w'}), \quad \dots, \quad (8)$$

whilst the equation of continuity gives

$$\frac{\partial \bar{u}}{\partial x} + \frac{\partial \bar{v}}{\partial y} + \frac{\partial \bar{w}}{\partial z} = 0 \quad \dots \quad (9)$$

These are the equations of mean motion†. It is to be noticed that the dynamical equations have the same form as the exact equations (5), provided we introduce additional stress-components

$$P_{xx} = -\rho \bar{u'u'}, \quad P_{yx} = -\rho \bar{u'v'}, \quad P_{zx} = -\rho \bar{u'w'}, \quad \dots \quad (10)$$

This recalls the explanation of gaseous viscosity by Maxwell‡.

The equations (8) may be written, in virtue of (9),

$$\left(\frac{\partial}{\partial t} + \bar{u} \frac{\partial}{\partial x} + \bar{v} \frac{\partial}{\partial y} + \bar{w} \frac{\partial}{\partial z} \right) \rho \bar{u} = \rho X + \frac{\partial}{\partial x} (\bar{p}_{xx} - \rho \bar{u'u'}) + \frac{\partial}{\partial y} (\bar{p}_{yx} - \rho \bar{u'v'}) + \frac{\partial}{\partial z} (\bar{p}_{zx} - \rho \bar{u'w'}), \quad \dots, \quad (11)$$

* *l.c. ante* p 536

† Or rather 'mean-mean-motion,' in the phraseology of Prof Reynolds. He applies the term 'mean-motion' to the system of velocities (u , v , w), to distinguish it from 'molecular motion'. The turbulent motion (u' , v' , w') is called by him 'relative-mean-motion.'

‡ *l.c.*

If we multiply these by u , \bar{v} , w in order, and add, we obtain

$$\begin{aligned} & \left(\frac{\partial}{\partial t} + u \frac{\partial}{\partial x} + v \frac{\partial}{\partial y} + \bar{w} \frac{\partial}{\partial z} \right) \frac{1}{2} \rho (\bar{u}^2 + \bar{v}^2 + \bar{w}^2) \\ & \rho (Xu + Y\bar{v} + Zw) + u \left\{ \frac{\partial}{\partial x} (\bar{p}_{xx} - \rho u' u') + \frac{\partial}{\partial y} (\bar{p}_{yx} - \rho u' v') + \frac{\partial}{\partial z} (\bar{p}_{zx} - \rho u' w') \right\} \\ & + v \left\{ \frac{\partial}{\partial x} (\bar{p}_{xy} - \rho v' u') + \frac{\partial}{\partial y} (\bar{p}_{yy} - \rho v' v') + \frac{\partial}{\partial z} (\bar{p}_{yz} - \rho v' w') \right\} \\ & + \bar{w} \left\{ \frac{\partial}{\partial x} (\bar{p}_{xz} - \rho w' u') + \frac{\partial}{\partial y} (\bar{p}_{yz} - \rho w' v') + \frac{\partial}{\partial z} (\bar{p}_{zz} - \rho w' w') \right\} \quad (12) \end{aligned}$$

Let us first suppose that there are no extraneous forces X , Y , Z , and let us apply (12) to the case of a region bounded by fixed walls at which u , v , w , and therefore also \bar{u} , \bar{v} , \bar{w} , all vanish. If we write

$$T_0 = \frac{1}{2} \rho \iiint (u^2 + \bar{v}^2 + \bar{w}^2) dx dy dz, \quad \dots \dots \dots (13)$$

we obtain, after some partial integrations,

$$\frac{dT_0}{dt} = \iiint \Phi_0 dx dy dz + \iiint \Psi dx dy dz, \quad \dots \dots \dots (14)$$

where

$$\begin{aligned} \Phi_0 = & \rho \left\{ P_{xx} \frac{\partial u}{\partial x} + P_{yy} \frac{\partial v}{\partial y} + P_{zz} \frac{\partial w}{\partial z} + P_{yz} \left(\frac{\partial w}{\partial y} + \frac{\partial v}{\partial z} \right) + \bar{p}_{xx} \left(\frac{\partial u}{\partial z} + \frac{\partial \bar{w}}{\partial x} \right) + \bar{p}_{xy} \left(\frac{\partial \bar{w}}{\partial x} + \frac{\partial \bar{u}}{\partial y} \right) \right. \\ & \left. + \mu \left\{ 2 \left(\frac{\partial u}{\partial x} \right)^2 + 2 \left(\frac{\partial v}{\partial y} \right)^2 + 2 \left(\frac{\partial w}{\partial z} \right)^2 + \left(\frac{\partial w}{\partial y} + \frac{\partial v}{\partial z} \right)^2 + \left(\frac{\partial u}{\partial z} + \frac{\partial \bar{w}}{\partial x} \right)^2 + \left(\frac{\partial v}{\partial x} + \frac{\partial \bar{u}}{\partial y} \right)^2 \right\}, \dots \dots (15) \end{aligned}$$

and

$$\Psi = \rho \left\{ u' w' \frac{\partial u}{\partial x} + v' v' \frac{\partial v}{\partial y} + w' w' \frac{\partial w}{\partial z} + v' w' \left(\frac{\partial w}{\partial y} + \frac{\partial v}{\partial z} \right) + w' u' \left(\frac{\partial \bar{w}}{\partial z} + \frac{\partial w}{\partial x} \right) + u' v' \left(\frac{\partial v}{\partial x} + \frac{\partial \bar{u}}{\partial y} \right) \right\} \dots (16)$$

The formula (14) gives the rate of variation of the energy of the mean motion (\bar{u} , \bar{v} , \bar{w}). The first term on the right hand represents the dissipation due to the mean motion alone, and is essentially negative. The second term represents the rate at which work is being done by the fictitious stresses (10).

Now if T be the true kinetic energy, we may write, in virtue of assumptions already made,

$$T = T_0 + T', \dots \dots \dots (17)$$

where

$$T' = \frac{1}{2} \rho \iiint (u'^2 + v'^2 + w'^2) dx dy dz, \quad \dots \dots \dots (18)$$

i.e. T' is the kinetic energy of the eddying motion. And, as in Art 327, it may be shewn that on the present supposition of fixed boundaries at which there is no slipping, the total dissipation is, on the average, equal to the sum of the dissipations due to the mean-motion and the eddying motion respectively. Thus

$$\frac{dT}{dt} = \iiint \Phi_0 dx dy dz - \iiint \Phi' dx dy dz, \dots \dots \dots (19)^*$$

where

$$\Phi' = \mu \left\{ 2 \left(\frac{\partial u'}{\partial x} \right)^2 + 2 \left(\frac{\partial v'}{\partial y} \right)^2 + 2 \left(\frac{\partial w'}{\partial z} \right)^2 + \left(\frac{\partial w'}{\partial y} + \frac{\partial v'}{\partial z} \right)^2 + \left(\frac{\partial u'}{\partial z} + \frac{\partial w'}{\partial x} \right)^2 + \left(\frac{\partial v'}{\partial x} + \frac{\partial u'}{\partial y} \right)^2 \right\} \dots (20)$$

* It should be noticed that we are here virtually taking the differential time-element δt to be of the order of magnitude of the interval τ employed in the definitions (1). The procedure in the text avoids the use of some very lengthy equations which appear in the original.

Comparing with (14), we have

$$\frac{d\overline{T'}}{dt} = - \iiint \overline{\Phi'} da dy dz - \iiint \Psi dv dy dz. \quad (21)$$

The sign of the expression on the right-hand determines whether the mean energy $\overline{T'}$ of the eddying motion (u', v', w') will increase or diminish. The first part, which alone involves the viscosity μ , is essentially negative, the second part depends on the inertia of the fluid, and may be positive or negative according to circumstances

When there are extraneous forces X, Y, Z to be taken into account, and when the velocities u, v, w do not necessarily vanish at the boundary of the region considered, the equation (14) requires to be amended by the addition of terms which represent partly the convection of kinetic energy of mean motion into the region, partly the work done by the forces X, Y, Z , and partly the work done at the boundary by the mean stresses $\overline{p}_{xx}, \overline{p}_{yz}, \overline{p}_{zx}, \dots$, and by the fictitious stresses $P_{xx}, P_{yz}, P_{zx}, \dots$

The equation (21), on the other hand, requires only the addition of a term representing the convection of the energy of turbulent motion across the boundary

The derivation of the remarkable formulae (19) and (21), and of the modifications just referred to, appears to be free from objection, on the conventions adopted. But, in applying these formulae to actual conditions, the restrictions and assumptions which have been introduced as to the character of the turbulent motions must be borne in mind

One or two consequences of the formula (21) may be noted*. In the first place, the relative magnitude of the two terms on the right-hand is unaffected if we reverse the signs of u', v', w' , or if we multiply them by any constant factor. The stability of a given state of mean motion should not therefore depend on the *scale* of the disturbance. On the other hand, certain combinations of u', v', w' appear to be more favourable to stability than others. Thus, in the case of disturbed laminar motion parallel to Ox , between two rigid planes $y = \pm b$, the formula (16) reduces to

$$\Psi = \rho \overline{u'v'} \frac{\partial \overline{u}}{\partial y}, \quad (22)$$

so that the types of disturbance which tend to increase are those in which (for $y > 0$) combinations of u', v' with the same sign preponderate. This indicates a tendency to equalization of the velocity in the different strata. Again, the relative importance of the second term in (21), which alone can contribute to the increase of $\overline{T'}$, is greater the greater the rates of strain $\partial \overline{u} / \partial x, \dots$, in the mean motion. This suggests a reason why a given type of mean motion does not begin to break down until a certain critical velocity is reached.

If we apply the (modified) formulae to the case of flow in a uniform cylindrical pipe, on the supposition that the pressure gradient ($-d\overline{p}/dx$) is zero, we find

$$\frac{dT_0}{dt} = \rho Z \overline{v} \pi a^2 - 2\pi \int_0^a \Phi_0 r dr + 2\pi \int_0^a \Psi_1 dr, \quad (23)$$

$$\text{and} \quad \frac{d\overline{T'}}{dt} = - \iint \overline{\Phi'} dx dy - 2\pi \int_0^a \Psi_1 dr, \quad (24)$$

$$\text{where} \quad \Phi_0 = \mu \left(\frac{\partial \overline{u}}{\partial r} \right)^2, \quad \Psi = \rho \overline{u'v'} \frac{\partial \overline{u}}{\partial r}. \quad (25)$$

* Cf Lorentz, "Over den weerstand dien een vloeistofstroom in eene cylindrische buis ondervindt," *Amst Versl*, t. vi. p. 28 (1897). This paper gives a very clear account of the whole method. Some terms are accidentally omitted from the rather complicated system of equations, but this does not affect the main conclusions.

The region here considered is that contained between two cross-sections (of area πa^2) at unit distance apart, the axis of z coincides with that of the pipe, and q denotes the velocity at right angles to this axis. It is assumed of course that $\bar{q}=0$ and $\partial \bar{w}/\partial z=0$, also that the mean state of things is in all respects the same at each section. The conditions of steady motion are obtained by equating the right-hand members of (23) and (24) to zero.

Reynolds discusses in detail the two-dimensional form of the problem, where there is a flow parallel to x between two fixed plane walls $y=\pm b$. Assuming that \bar{u} varies as b^2-y^2 , as in Art 318, he seeks to determine a minimum value of the flux consistent with the condition $d\bar{T}/dt=0$, but for this we must refer to the original paper. The result obtained is that the critical ratio $u_0 b/\nu$, where u_0 is the mean value of \bar{u} between the limits $y=\pm b$, must exceed 258*.

* A different result is obtained by Sharpe, "On the Stability of the Motion of a Viscous Liquid," *Trans Amer Math Soc*, t vi p. 496 (1905).

CHAPTER XII.

ROTATING MASSES OF LIQUID

347 THIS subject had its origin in the investigations on the theory of the Earth's Figure which began with Newton and Maclaurin, and were continued by the great French school of mathematicians which flourished near the end of the eighteenth and the beginning of the nineteenth century. It has in recent times undergone great development, at the hands, notably, of Thomson and Tait, Poincaré, and Darwin

The problem is to ascertain the possible forms of relative equilibrium of a homogeneous gravitating mass of liquid, when rotating about a fixed axis with constant angular velocity, and to determine the stability or instability of such forms

We begin with the case where the external boundary is ellipsoidal. We write down, in the first place, some formulae relating to the attraction of ellipsoids

If the density ρ be expressed in 'astronomical' measure, the gravitation-potential, at internal points, of a uniform mass enclosed by the surface

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} + \frac{z^2}{c^2} = 1 \quad (1)$$

is
$$\Omega = \pi \rho abc \int_0^\infty \left(\frac{x^2}{a^2 + \lambda} + \frac{y^2}{b^2 + \lambda} + \frac{z^2}{c^2 + \lambda} - 1 \right) \frac{d\lambda}{\Delta}, \quad (2)^*$$

where
$$\Delta = \{ (a^2 + \lambda)(b^2 + \lambda)(c^2 + \lambda) \}^{\frac{1}{2}} \quad (3)$$

This may be written

$$\Omega = \pi \rho (\alpha_0 x^2 + \beta_0 y^2 + \gamma_0 z^2 - \chi_0), \quad (4)$$

where, as in Art 114,

$$\alpha_0 = abc \int_0^\infty \frac{d\lambda}{(a^2 + \lambda)\Delta}, \quad \beta_0 = abc \int_0^\infty \frac{d\lambda}{(b^2 + \lambda)\Delta}, \quad \gamma_0 = abc \int_0^\infty \frac{d\lambda}{(c^2 + \lambda)\Delta}, \quad (5)$$

and
$$\chi_0 = abc \int_0^\infty \frac{d\lambda}{\Delta} \quad (6)$$

* For references see p 554. The sign of Ω has been changed from the usual reckoning

The potential energy of the mass is given by

$$V = \frac{1}{2} \iiint \Omega \rho dx dy dz, \quad \dots\dots\dots(7)$$

where the integrations extend over the volume. Substituting from (4) we find

$$\begin{aligned} V &= \frac{2}{3} \pi^2 \rho^2 abc \left\{ \frac{1}{15} (\alpha_0 a^2 + \beta_0 b^2 + \gamma_0 c^2) - \chi_0 \right\} \\ &\quad - \frac{2}{3} \pi^2 \rho^2 a^2 b^2 c^2 \int_0^\infty \left\{ \frac{1}{15} \left(\frac{a^2}{a^2 + \lambda} + \frac{b^2}{b^2 + \lambda} + \frac{c^2}{c^2 + \lambda} \right) - 1 \right\} \frac{d\lambda}{\Delta} \\ &= \frac{2}{3} \pi^2 \rho^2 a^2 b^2 c^2 \int_0^\infty \left\{ \frac{2}{15} \lambda d \left(\frac{1}{\Delta} \right) - \frac{2}{15} \frac{d\lambda}{\Delta} \right\} = - \frac{8}{15} \pi^2 \rho^2 a^2 b^2 c^2 \int_0^\infty \frac{d\lambda}{\Delta}. \quad \dots(8) \end{aligned}$$

This expression is negative because the zero of reckoning corresponds to a state of infinite diffusion of the mass. If we adopt as zero of potential energy that of the mass when collected into a sphere of radius $R, = (abc)^{\frac{1}{3}}$, we must add the term

$$\frac{4}{15} \pi^2 \rho^2 R^5, \quad \dots\dots\dots(9)$$

If the ellipsoid be of revolution, the integrals reduce. If it be of the *planetary* form we may put, in the notation of Art. 107,

$$a = b = \frac{(\xi^2 + 1)^{\frac{1}{2}}}{\xi} c, \quad \dots\dots\dots(10)$$

and obtain*

$$\left. \begin{aligned} \alpha_0 &= \beta_0 = \frac{(\xi^2 + 1) \xi \cot^{-1} \xi - \xi^3}{\xi^2}, \\ \gamma_0 &= 2(\xi^2 + 1)(1 - \xi \cot^{-1} \xi), \end{aligned} \right\} \quad \dots\dots\dots(11)$$

$$V = \frac{4}{15} \pi^2 \rho^2 R^5 \left\{ 1 - \left(\frac{\xi^2 + 1}{\xi^2} \right)^{\frac{1}{2}} \xi \cot^{-1} \xi \right\}, \quad \dots\dots\dots(12)$$

provided the zero of V correspond to the spherical form. If e be the eccentricity of the meridian, we have

$$e^2 = 1 - \frac{c^2}{a^2} = \frac{1}{\xi^2 + 1}, \quad \dots\dots\dots(13)$$

and the formulae may be written

$$\left. \begin{aligned} \alpha_0 = \beta_0 &= \frac{\sqrt{1 - e^2}}{e^3} \sin^{-1} e - \frac{1 - e^2}{e^3}, \\ \gamma_0 &= \frac{2}{e^2} \left\{ 1 - \sqrt{1 - e^2} \frac{\sin^{-1} e}{e} \right\}, \end{aligned} \right\} \quad \dots\dots\dots(14)$$

$$V = \frac{4}{15} \pi^2 \rho^2 R^5 \left\{ 1 - (1 - e^2)^{\frac{1}{2}} \frac{\sin^{-1} e}{e} \right\}. \quad \dots\dots\dots(15)$$

For an *ovary* ellipsoid we put (Art. 103)

$$a = b = \frac{(\xi^2 - 1)^{\frac{1}{2}}}{\xi} c, \quad \dots\dots\dots(16)$$

* Most simply by writing $c^2 + \lambda = (a^2 - c^2) u^2$.

and obtain

$$\left. \begin{aligned} \alpha_0 &= \beta_0 = \xi^2 - (\xi^2 - 1) \xi \coth^{-1} \xi, \\ \gamma_0 &= 2(\xi^2 - 1) (\xi \coth^{-1} \xi - 1), \end{aligned} \right\} \dots \dots \dots (17)$$

$$V = \frac{16}{15} \pi^2 \rho^2 R^3 \left\{ 1 - \left(\frac{\xi^2 - 1}{\xi^2} \right)^{\frac{1}{2}} \xi \coth^{-1} \xi \right\} \dots \dots (18)$$

The case of an infinitely long elliptic cylinder may also be noticed. Putting $c = \infty$ in (5), we find

$$\alpha_0 = \frac{2b}{a+b}, \quad \beta_0 = \frac{2a}{a+b}, \quad \gamma_0 = 0. \dots \dots \dots (19)$$

The energy per unit length of the cylinder is

$$V_1 = \frac{4}{15} \pi^2 \rho^2 a^2 b^2 \log \frac{(a+b)^2}{4ab}. \dots \dots \dots (20)$$

Maclaurin's Ellipsoids

348. If the ellipsoid rotate in relative equilibrium about the axis of z , with angular velocity ω , the component accelerations of the particle (x, y, z) are $-\omega^2 x, -\omega^2 y, 0$, so that the dynamical equations reduce to

$$-\omega^2 x = -\frac{1}{\rho} \frac{\partial p}{\partial x} - \frac{\partial \Omega}{\partial x}, \quad -\omega^2 y = -\frac{1}{\rho} \frac{\partial p}{\partial y} - \frac{\partial \Omega}{\partial y}, \quad 0 = -\frac{1}{\rho} \frac{\partial p}{\partial z} - \frac{\partial \Omega}{\partial z} \dots (1)$$

Hence
$$\frac{p}{\rho} = \frac{1}{2} \omega^2 (x^2 + y^2) - \Omega + \text{const.} \dots \dots \dots (2)$$

The surfaces of equal pressure are therefore given by

$$\left(\alpha_0 - \frac{\omega^2}{2\pi\rho} \right) x^2 + \left(\beta_0 - \frac{\omega^2}{2\pi\rho} \right) y^2 + \gamma_0 z^2 = \text{const} \dots \dots \dots (3)$$

In order that one of these may coincide with the external surface

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} + \frac{z^2}{c^2} = 1, \dots \dots \dots (4)$$

we must have

$$\left(\alpha_0 - \frac{\omega^2}{2\pi\rho} \right) a^2 = \left(\beta_0 - \frac{\omega^2}{2\pi\rho} \right) b^2 = \gamma_0 c^2. \dots \dots \dots (5)$$

In the case of an ellipsoid of revolution ($a = b$), these conditions reduce to one, viz.

$$\left(\alpha_0 - \frac{\omega^2}{2\pi\rho} \right) a^2 = \gamma_0 c^2 \dots \dots \dots (6)$$

Since $a^2/(a^2 + \lambda)$ is greater or less than $c^2/(c^2 + \lambda)$, according as a is greater or less than c , it follows from the forms of α_0, γ_0 given in Art. 347 (5) that the above condition can be fulfilled by a suitable value of ω for any assigned

planetary ellipsoid, but not for the ovary form. This important result is due to Maclaurin*.

If we substitute from Art. 347 (11), the condition (6) takes the form

$$\frac{\omega^2}{2\pi\rho} = (3\xi^2 + 1) \xi \cot^{-1} \xi - 3\xi^2, \quad \dots \dots \dots (7)$$

or, in the notation of Art. 107,

$$\frac{\omega^2}{4\pi\rho} = \xi q_2(\xi). \quad \dots \dots \dots (8)$$

It will be noticed that the value of ω corresponding to any prescribed ellipticity depends on the density ρ , and not on the actual size of the ellipsoid. It is easily seen that this is in accordance with the theory of 'dimensions.'

If M be the total mass, H its angular momentum about the axis of rotation, we have

$$M = \frac{4}{3}\pi\rho a^3c, \quad H = \frac{8}{5}Ma^2\omega, \quad \dots \dots \dots (9)$$

whence
$$\frac{H^2}{M^3R} = \frac{64}{25} \left(\frac{\xi^2 + 1}{\xi^2} \right)^{\frac{3}{2}} \{ (3\xi^2 + 1) \xi \cot^{-1} \xi - 3\xi^2 \}. \quad \dots \dots (10)$$

The formula (7) has been discussed, under different forms, by Simpson, d'Alembert, and (more fully) by Laplace†. It is easily seen that the right-hand side of (7) vanishes for $\xi = 0$ and $\xi = \infty$, but is otherwise finite and positive; consequently that it has a greatest value for some intermediate value of ξ . There is thus, for given density ρ , an upper limit to the angular velocities for which an ellipsoid of revolution is a possible form of relative equilibrium. A more detailed investigation is required to shew that there is only one maximum, and consequently no minimum, value of the function on the right-hand of (7) or (8).

Laplace also examined, from the same point of view, the formula for the angular momentum. It appears that the right-hand side of (10) increases continually from 0 to ∞ as ξ decreases from ∞ to 0. Hence for a given volume of given fluid there is one, and only one, form of Maclaurin's ellipsoid having a prescribed angular momentum.

These questions may also be investigated by actual computation of the functions on the right-hand sides of (7) and (10). The table on the next page, giving numerical details of a series of Maclaurin's ellipsoids, is adapted from Thomson and Tait‡. The unit of angular momentum in the last column is $M^{\frac{1}{2}}R^{\frac{3}{2}}$, where 'astronomical' units are of course implied.

* *I.e. ante* p. 293.

† *Mécanique Céleste*, Livre 3^{me}, c. in. For other references see Todhunter, *Hist. of the Theories of Attraction.*, cc. x., xvi

‡ *Natural Philosophy*, Art. 772.

The maximum value of $\omega^2/2\pi\rho$ is 2247, corresponding to $e = 9299$, $a/c = 27198$. For any smaller value of $\omega^2/2\pi\rho$ there are *two* possible

e	a/R	c/R	$\omega^2/2\pi\rho$	Angular momentum
0	1 0000	1 0000	0	0
1	1 0016	9967	0027	0255
2	1 0068	9865	0107	0514
3	1 0159	9691	0243	0787
4	1 0295	9435	0436	1085
5	1 0491	9086	0690	1417
6	1 0772	8618	1007	1804
7	1 1188	7990	1387	2283
8	1 1856	7114	1816	2934
8127	1 1973	6976	1868	3035
9	1 3189	5749	2203	4000
91	1 341	5560	2225	4156
92	1 367	5355	2241	4330
93	1 396	5131	2247	4525
94	1 431	4883	2239	4748
95	1 474	4603	2213	5008
96	1 529	4280	2160	5319
97	1 602	3895	2063	5692
98	1 713	3409	1890	6249
99	1 921	2710	1551	7121
1 00	∞	0	0	∞

ellipsoids of revolution, the eccentricity being in one case less and in the other greater than 9299

In the case of a homogeneous liquid mass of density equal to the mean density of the earth, we have

$$\frac{4}{3}\pi\rho R = 980, \quad R = 6.37 \times 10^8,$$

if the units of length and time be the centimetre and the second, whence it is found that the fastest rotation consistent with an ellipsoidal form of revolution has a period of 2 h 25 m

When ζ is great, the right-hand side of (7) reduces to $\frac{4}{15}\zeta^{-2}$ approximately. Hence in the case of a planetary ellipsoid differing infinitely little from a sphere we have, for the *ellipticity*,

$$\epsilon = \frac{a-c}{a} = \frac{1}{2}\zeta^{-2} = \frac{1}{18} \frac{\omega^2}{\pi\rho}$$

If g denote the value of gravity at the surface of a sphere of radius a , of the same density, we have $g = \frac{4}{3}\pi\rho a$, whence

$$\epsilon = \frac{5}{4} \frac{\omega^2 a}{g}$$

Putting $\omega^2 a/g = \frac{1}{231}$, we find that a homogeneous liquid globe of the same size and mass as the earth, rotating in the same period, would have an ellipticity of $\frac{1}{231}$.

Jacobi's Ellipsoids.

349. To ascertain whether an ellipsoid with three *unequal* axes is a possible form of relative equilibrium, we return to the conditions (5) of Art. 348. These are equivalent to

$$(\alpha_0 - \beta_0) a' b' + \gamma_0 c^2 (a^2 - b^2) = 0, \quad \dots \dots \dots (1)$$

and

$$\frac{\omega^2}{2\pi\rho} = \frac{\alpha_0 a' - \beta_0 b^2}{a' - b^2} \quad \dots \dots \dots (2)$$

If we substitute from Art. 347, the condition (1) may be written

$$(a^2 - b^2) \int_0^\infty \left\{ \frac{a^2 b'}{(a^2 + \lambda)(b^2 + \lambda)} - \frac{c^2}{c^2 + \lambda} \right\} \frac{d\lambda}{\Delta} = 0. \quad \dots \dots \dots (3)$$

The first factor, equated to zero, gives Maclaurin's ellipsoids, discussed in the preceding Art. The second factor gives

$$\int_0^\infty \{a'b' - (a^2 + b^2 + \lambda)c^2\} \frac{\lambda d\lambda}{\Delta^3} = 0, \quad \dots \dots \dots (4)$$

which may be regarded as an equation determining c in terms of a, b . When $c^2 = 0$, every element of the integral is positive, and when $c^2 = a^2 b^2 / (a^2 + b^2)$ every element is negative. Hence there is some value of c , less than the smaller of the two semiaxes a, b , for which the integral vanishes.

The corresponding value of ω is given by (2), which takes the form

$$\frac{\omega^2}{2\pi\rho} = abc \int_0^\infty \frac{\lambda d\lambda}{(a^2 + \lambda)(b^2 + \lambda)\Delta}, \quad \dots \dots \dots (5)$$

so that ω is real. It will be observed that as before the ratio $\omega^2/2\pi\rho$ depends only on the *shape* of the ellipsoid, and not on its absolute size*.

The equations (4) and (5) were carefully discussed by C. O. Meyer†, who shewed that when a, b are given there is only one value of c satisfying (4), and that, further, a maximum value (viz. 1871)‡ of $\omega^2/2\pi\rho$ occurs for $a = b = 1.7161 c$. The Jacobian ellipsoid then coincides with one of Maclaurin's forms. This limiting form, which is shewn on the next page, may be determined by putting

$$a = b, \quad a^2 + \lambda = (a^2 - c^2) u^2, \quad c^2 = (a^2 - c^2) \xi^2,$$

* The possibility of an ellipsoidal form with three unequal axes was first asserted by Jacobi, "Ueber die Figur des Gleichgewichts," *Pogg. Ann.*, t. xxxiii. p. 229 (1834) [*Ges. Werke*, t. ii. p. 17]; see also Liouville, "Sur la figure d'une masse fluide homogène, en équilibre, et douée d'un mouvement de rotation," *Journ. de l'École Polytechn.*, t. xiv. p. 290 (1834).

† "De aequilibrii formis ellipsoidicis," *Crelle*, t. xxiv. (1842).


‡ According to Thomson and Tait this should be 1868. See the table on the opposite page

in the second factor of (3). We find

$$\int_{\zeta}^{\infty} \left\{ \left(\frac{1 + \zeta^2}{1 + u^2} \right)^2 - \frac{\zeta^2}{u^2} \right\} \frac{du}{1 + u^2} = 0, \quad \dots \dots \dots (6)$$

whence
$$\cot^{-1} \zeta = \frac{13\zeta + 3\zeta^3}{3 + 14\zeta^2 + 3\zeta^4} \dots \dots \dots (7)^*$$

There is only one finite root, viz $\zeta = \cdot 7171$, this gives, for the eccentricity of the meridian, $e = \cdot 8127$.




Since, in the general case, the two ratios $a \ b \ c$ are subject to the condition (4), there is virtually only one variable parameter, and the Jacobian ellipsoids form what may be called a 'linear' series. The sequence of figures in the series is illustrated by the following table, computed by Darwin† As

Axes			$\frac{\omega^2}{2\pi\rho}$	Angular momentum
a/R	b/R	c/R		
1 197	1 197	698	1871	304
1 216	1 179	698	187	304
1 279	1 123	696	186	306
1 383	1 045	692	181	313
1 601	924	677	166	341
1 899	811	649	141	392
2 346	702	607	107	481
3 136	586	545	067	644
5 04	45	44	026	1 016
∞	0	0	0	∞

$\omega^2/2\pi\rho$ diminishes from its upper limit 1871, the ratio of one equatorial axis of the ellipsoid to the polar axis increases, whilst that of the other diminishes, the asymptotic form being that of an infinitely long circular cylinder rotating about an axis perpendicular to its length ($a = \infty$, $b = c$). The following figures shew two intermediate forms, the unit of length being the radius (R) of the sphere of equal volume.

* Thomson and Tait, Art. 778'. The f of these writers is equal to our ζ^{-1} .

† "On Jacobi's Figure of Equilibrium for a Rotating Mass of Fluid," *Proc Roy. Soc*, t. xli p 319 (1886)



It may be noticed that an infinitely long elliptic cylinder may rotate in relative equilibrium about its longitudinal axis. It is easily proved, with the help of the formulae (19) of Art. 347 that the angular velocity is given by

$$\frac{\omega^2}{2\pi\rho} = \frac{2ab}{(a+b)^2} \cdot \dots \dots \dots (8)^*$$

Other Special Forms

350 The problem of relative equilibrium, of which Maclaurin's and Jacobi's ellipsoids are only particular cases, has been the subject of many remarkable investigations, to which only slight reference can here be made.

The case of the annulus was first treated by Laplace†, with special reference to the theory of Saturn's rings.

The annulus is supposed to be a figure of revolution about the axis of z , and to possess an equatorial plane of symmetry passing through the origin. Further, the cross-section is taken to be an ellipse whose semiaxes parallel to Ox and Oz are a and c respectively. If C be the centre of this section, we write $OC = D$, and it is assumed that the ratios a/D , c/D are both small.

Under these conditions, the component attractions at any point in the substance of the ring are, to a first approximation, the same as if the radius D were infinite, so that we may write, in accordance with Art. 347 (19),

$$\Omega = \pi\rho (\alpha_0 x^2 + \gamma_0 z^2) + \text{const}, \quad \dots \dots \dots (1)$$

$$\text{where} \quad \alpha_0 = \frac{2c}{a+c}, \quad \gamma_0 = \frac{2a}{a+c}, \quad \dots \dots \dots (2)$$

provided the origin of x be now transferred to C . The pressure-equation is, accordingly, for points of the cross-section,

$$\frac{p}{\rho} = \frac{1}{2} \omega^2 (D+x)^2 - \Omega + \frac{S}{\sqrt{\{(D+x)^2 + z^2\}}} + \text{const}, \quad \dots \dots (3)$$

where S denotes the mass of the central attracting body at O . This may be expanded in the form

$$\frac{p}{\rho} = \frac{1}{2} \omega^2 (D^2 + 2Dx + x^2) - \pi\rho (\alpha_0 x^2 + \gamma_0 z^2) + \frac{S}{D} \left(1 + \frac{x}{D} + \frac{2x^2 - z^2}{2D^2} - \dots \right) \dots \dots (4)$$

* Matthiessen, "Neue Untersuchungen über frei rotirende Flüssigkeiten," *Schriften der Univ. zu Kiel*, t. vi (1859). This paper contains a very complete list of previous writings on the subject.

† "Mémoire sur la théorie de l'anneau de Saturne," *Mém. de l'Acad. des Sciences*, 1789 [1787] [*Mécanique Céleste*, Livre 3^{me}, c. vi].

If p is to be approximately constant over the circumference of the section

$$\frac{x^2}{a^2} + \frac{z^2}{c^2} = 1, \quad \dots \quad (5)$$

the terms in x must cancel, and the coefficients of x^2 and z^2 must be in the ratio of c^2 to a^2 . Hence

$$\omega^2 D^3 = S, \quad \dots \quad (6)$$

and

$$a^2 \left(\alpha_0 - \frac{3\omega^2}{2\pi\rho} \right) = c^2 \left(\gamma_0 + \frac{\omega^2}{2\pi\rho} \right). \quad \dots \quad (7)$$

The former of these equations shews that the period of revolution of the ring must be that proper to a satellite at the same distance, and the latter may be written

$$\frac{\omega^2}{2\pi\rho} = \frac{2ac(a-c)}{(3a^2+c^2)(a+c)}, \quad \dots \quad (8)$$

whence it appears that the equatorial diameter of the section must be the greater

The expression on the right-hand has a maximum value 1086, corresponding to $a/c = 2.594$. Hence for a fluid ring at a given distance from the central body there is an inferior limit to the density

Laplace points out that a ring such as we have imagined would be unstable even if rigid, and must *a fortiori* be unstable when fluid. It is now generally held that the constitution of the Saturnian rings is meteoric.

When the central body is absent, or its mass relatively small, the attraction of the ring at points of its substance must be calculated to a higher degree of approximation. It easily appears that the cross-section must be nearly circular, and that the angular velocity must be much less than in the previous case. It is found that, when $S = 0$,

$$\frac{\omega^2}{2\pi\rho} = \frac{a^2}{2D^2} \left(\log \frac{8D}{a} - \frac{5}{4} \right), \quad \dots \dots \dots (9)^*$$

nearly, provided a/D be small. This may be verified by a method similar to that of Art 162

It has been shewn by Dyson that a ring of this kind would be unstable for types of disturbance in which the sectional area varies with the longitude, and for such types only. Its tendency would therefore be to break up into detached masses.

Darwin has investigated† in great detail the case of two detached masses

* A slightly different result was given by Matthiessen, *l c*. The formula (9) was obtained by Mme Sophie Kowalewsky, *Astr. Nachr.*, t cxi p 37 (1885), Poincaré, *l c infra*, Dyson, *l c ante* p 149. See also Basset, *Amer. Journ. Math.*, t xi (1888).

† "On Figures of Equilibrium of Rotating Masses of Fluid," *Phil. Trans.*, A, t clxxviii p 379 (1887).

of liquid rotating in relative equilibrium about their common centre of gravity like the components of a double star. When the distance between the masses is large compared with the dimensions of either, the series of spherical harmonics in which the solution is expressed are rapidly convergent, but in other cases the approximations become very laborious*.

General Problem of Relative Equilibrium

351 The question as to the possible configurations of relative equilibrium of a rotating homogeneous liquid was taken up from a more general point of view by Poincaré, in a celebrated paper†

Consider in the first place an ordinary dynamical system of n degrees of freedom, whose constitution depends on a variable parameter λ , the potential energy V being accordingly a function of the n generalized coordinates q_1, q_2, \dots, q_n and of λ . The possible configurations of equilibrium corresponding to a prescribed value of λ are determined by n equations of the type

$$\frac{\partial V}{\partial q_r} = 0, \quad \dots \dots \dots (1)$$

and by varying λ we get one or more 'linear series' of equilibrium configurations. Such a series may be represented by a curve in an n -dimensional space, of which q_1, q_2, \dots, q_n are the Cartesian coordinates.

Again considering small deviations from any equilibrium configuration, we have

$$V = c_{11} \delta q_1^2 + c_{22} \delta q_2^2 + \dots + 2c_{12} \delta q_1 \delta q_2 + \dots \dots (2)$$

where $c_{11}, c_{22}, c_{12}, \dots$ are 'coefficients of stability' (Art 167) defined by

$$c_{rr} = \frac{\partial^2 V}{\partial q_r^2}, \quad c_{rs} = \frac{\partial^2 V}{\partial q_r \partial q_s} \quad \dots \dots \dots (3)$$

By a linear transformation of the variations $\delta q_1, \delta q_2, \dots, \delta q_n$, the expression (2) can be reduced, in an infinite number of ways, to a sum of squares; but whatever mode of reduction be adopted, the number of positive as well as of negative coefficients is, by a theorem due to Sylvester, invariable. The coefficients in the transformed expression may be called principal coefficients of stability. In order that the configuration in question may be stable, it is necessary and sufficient that these should all be positive.

As we vary λ , the several linear series will remain distinct so long as the discriminant Δ of the quadratic form (2) does not vanish, i.e. so long as no principal coefficient of stability vanishes. But if, as we follow a linear series,

* For a fuller investigation of the problems of Arts 347-350 reference may be made to Tisserand, *Traité de Mécanique Céleste*, Paris, 1889-1896, t. II.

† "Sur l'équilibre d'une masse fluide animée d'un mouvement de rotation," *Acta Math.*, t. VII. p. 259 (1885). See also his treatise *Figures d'équilibre d'une masse fluide*, Paris, 1902.

Δ vanishes and changes sign for a particular value of λ , it appears that the configuration in question is a 'form of bifurcation,' i.e. it is (as it were) the meeting point with another linear series. The case may also arise where, as λ passes through a particular value, two linear series coalesce and then become imaginary. If the configuration in question does not belong to any other linear series, we have what is called a 'limiting form' of equilibrium, and it may be shewn that Δ has different signs in the two series, in the neighbourhood of the junction. A specially important case is where two series coalesce and afterwards become imaginary, whilst a third series passes continuously through the common point.

The foregoing statements may be illustrated by the case of a system of one degree of freedom*. The positions of equilibrium are given by

$$\frac{\partial V}{\partial q}=0,$$

$$\dots\dots\dots(4)$$

which determines one or more values of q in terms of λ . If we differentiate with respect to λ , we obtain

$$\frac{\partial^2 V}{\partial q^2} \frac{dq}{d\lambda} + \frac{\partial^2 V}{\partial q \partial \lambda}=0$$

$$\dots\dots\dots(5)$$

This gives, for each linear series, a unique value of $dq/d\lambda$, and so determines the succession of equilibrium configurations, unless $\partial^2 V/\partial q^2=0$. The several series therefore remain distinct so long as the coefficient of stability does not vanish, but if $\partial^2 V/\partial q^2=0$, $dq/d\lambda$ is infinite or indeterminate according as $\partial^2 V/\partial q \partial \lambda$ is or is not different from zero. In the former case, two series in general coalesce

Let us write

$$\frac{\partial V}{\partial q}=\phi(\lambda, q),$$


$$\dots\dots\dots(6)$$

and consider the surface

$$z=\phi(x, y),$$

$$\dots\dots\dots(7)$$

where x, y, z are ordinary Cartesian coordinates. The curve $\phi(x, y)=0$ which separates




the parts of the plane xy for which z is positive from those for which z is negative, represents the various linear series of equilibrium forms. Also the parts of the curve for which

* As a simple example, take the case of a particle free to move in a smooth rigid tube in a vertical plane, the tube being capable of being set in different positions by rotation about an axis perpendicular to this plane.

the gradient $\partial z/\partial y$ is positive correspond to stable, and those for which $\partial z/\partial y$ is negative to unstable configurations

The critical points ($\partial^2 V/\partial q^2=0$) correspond to $\partial z/\partial y=0$, the tangent-line to the curve is then parallel to y , or else the point in question is a singular point on the curve. In the former case, if no other branch of the curve goes through the point of contact, we have a 'limiting form', and it is evident that there is a change from stability to instability at this point. This case is represented in the preceding figure, where the two series PA and QA coalesce in the limiting form A .

If however we have also $\partial^2 V/\partial q \partial \lambda=0$, or $\partial z/\partial n=0$, we have a singular point. The case where two series (PA and QA) coalesce and become imaginary, whilst a third series (HAK) passes through the common point and remains real, is shewn in the following diagram. In



the latter series we have a transition from stability to instability, or *vice versa*, whilst the other series are both stable or both unstable in the neighbourhood of A *

When there are n degrees of freedom, the equations of equilibrium are

$$\frac{\partial V}{\partial q_1}=0, \quad \frac{\partial V}{\partial q_2}=0, \quad , \quad \frac{\partial V}{\partial q_n}=0 \quad . \quad . \quad . \quad (8)$$

We may utilize the $n-1$ equations following the first to determine q_2, \dots, q_n in terms of q_1 and λ . Let us denote the result of substituting these values in the general expression for V by $\psi(q_1, \lambda)$. We have then,

$$\frac{\partial \psi}{\partial q_1} = \frac{\partial V}{\partial q_1} + \frac{\partial V}{\partial q_2} \frac{\partial q_2}{\partial q_1} + \dots + \frac{\partial V}{\partial q_n} \frac{\partial q_n}{\partial q_1} = \frac{\partial V}{\partial q_1}, \quad . \quad . \quad . \quad (9)$$

by (8), so that the remaining condition of equilibrium may be written

$$\frac{\partial \psi}{\partial q_1}=0 \quad . \quad . \quad . \quad . \quad . \quad . \quad (10)$$

From this we derive

$$\frac{\partial \psi}{\partial q_1^2} \frac{dq_1}{d\lambda} + \frac{\partial^2 \psi}{\partial q_1 \partial \lambda} = 0, \quad . \quad . \quad . \quad . \quad . \quad . \quad (11)$$

which shews that the sequence of equilibrium configurations is unique unless $\partial^2 \psi/\partial q_1^2=0$. The rest of the argument is then as before, with ψ substituted for V . It is easily proved that the condition $\partial^2 \psi/\partial q_1^2=0$ is analytically equivalent to $\Delta=0$ †

* The case of a simple crossing between two series, both of which are real on either side of the intersection, may be illustrated in a similar manner

† The argument is taken, with little alteration, from Poincaré's treatise

352. The bearing of these considerations on the theory of relative equilibrium of a rotating system will be apparent

In the case of equilibrium relative to a rigid frame which is constrained to rotate with constant angular velocity ω about a fixed axis, the conditions are most conveniently considered under the type

$$\frac{\partial}{\partial q_r}(V-T_0)=0, \quad \dots\dots\dots(1)$$

where V is the potential energy, and T_0 is the kinetic energy of the system when rotating as rigid in any assigned configuration $(q_1, q_2, \dots q_n)$; cf Art 202 By varying ω we get the various linear series of equilibrium configurations Moreover, if the system be subject to dissipative forces affecting all relative motions, the condition of secular stability is that $V-T_0$ should be a minimum.

When, on the other hand, the system is free, the case comes under the general theory of gyrostatic systems, and the more appropriate form of the conditions is

$$\frac{\partial}{\partial q_1}(V+K)=0, \quad \dots\dots\dots(2)$$

where K is the kinetic energy of the system when rotating, as rigid, in the configuration $(q_1, q_2, \dots q_n)$ with the component momenta corresponding to the ignored coordinates unaltered (Art. 250), and the condition of secular stability is that $V+K$ should be a minimum From the present point of view the only ignored coordinate which we need consider is an angular coordinate specifying the position in space of a plane of reference in the system, passing through the axis of rotation and therefore also through the centre of inertia. The corresponding component of momentum is the angular momentum about the axis; we shall denote this by κ . By varying κ we get the various linear series of equilibrium configurations

In the case of a rotating liquid, the generalized coordinates q_1, q_2, \dots are infinite in number, but the theory is otherwise unaltered Let us suppose, for a moment, that we have a liquid covering a rigid rotating nucleus If the nucleus be constrained to rotate with constant angular velocity, or (what comes to the same thing) if it be of preponderant inertia, we have the first form of the problem; whereas if the nucleus be free, the second form applies. The distinction between the two forms disappears when we confine ourselves to disturbances which do not affect the moment of inertia of the system with respect to the axis of rotation.

The second form of the problem is from the present point of view the more important. We pass to the case of a homogeneous rotating liquid by imagining the nucleus to become infinitely small. In this case the solution of the problem of relative equilibrium is partially known We have, first, the

linear series of Maclaurin's ellipsoids in which, as κ ranges from 0 to ∞ , a/R ranges from 1 to ∞ (Art. 348). Again, we have the two* series of Jacobian ellipsoids in which, as κ ranges from $304M^{\frac{1}{2}}R^{\frac{1}{2}}$ to ∞ , a/b ranges in one case from 1 to ∞ , and in the other from 1 to 0, where a , b denote the two equatorial semi-axes (Art. 349). When $\kappa = 304M^{\frac{1}{2}}R^{\frac{1}{2}}$, we have a form of bifurcation, and accordingly a change in the character of the stability.

353. As a simple application of the preceding theory we may examine the secular stability of Maclaurin's ellipsoid for those types of ellipsoidal disturbance in which the axis of rotation remains a principal axis†.

Let ω be the angular velocity in the state of equilibrium, and κ the angular momentum. If I denote the moment of inertia of the disturbed system, the angular velocity, if this were to rotate, as rigid, would be κ/I . Hence

$$V + K = V + \frac{1}{2}I \left(\frac{\kappa}{I} \right)^2 = V + \frac{1}{2} \frac{\kappa^2}{I}, \quad \dots \dots \dots (1)$$

and the condition of secular stability is that this expression should be a minimum. We will suppose for definiteness that the zero of reckoning of V corresponds to the state of infinite diffusion. Then in any other configuration V will be negative.

In our previous notation we have

$$I = \frac{1}{2}M(a^2 + b^2), \quad \dots \dots \dots (2)$$

c being the axis of rotation. Since $abc = R^3$, we may write

$$V + \frac{1}{2}M \frac{\kappa^2}{(a^2 + b^2)} = f(a, b), \quad \dots \dots \dots (3)$$

where $f(a, b)$ is a symmetric function of the two independent variables a , b . If we consider the surface whose ordinate is $f(a, b)$, where a , b are regarded as rectangular coordinates of a point in a horizontal plane, the configurations of relative equilibrium will correspond to points whose altitude is stationary, whilst for secular stability the altitude must further be a minimum.

For $a = \infty$, or $b = \infty$, we have $f(a, b) = 0$. For $a = 0$, we have $V = 0$, and $f(a, b) \propto 1/b^2$, and similarly for $b = 0$. For $a = 0$, $b = 0$, simultaneously, we have $f(a, b) = \infty$. It is known that, whatever the value of κ , there is always one and only one possible form of Maclaurin's ellipsoid. Hence as we follow the section of the above-mentioned surface by the plane of symmetry ($a = b$), the ordinate varies from ∞ to 0, having one and only one stationary value in the interval. It is evident that this value is negative, and a minimum‡. Hence the altitude at this point of the surface cannot be a maximum. Moreover, since there is a limit to the negative value of V , viz. when the ellipsoid becomes a sphere, there is always at least one finite point of minimum (and negative) altitude on the surface.

* The two series include the same succession of geometrical forms, but are from the present point of view to be regarded as analytically distinct.

† Poincaré, *l.c.* For a more analytical investigation see Basset, "On the Stability of Maclaurin's Liquid Spheroid," *Proc. Camb. Phil. Soc.*, t. viii. p. 23 (1892).

‡ It follows that Maclaurin's ellipsoid is always stable for a deformation such that the surface remains an ellipsoid of revolution. Thomson and Tait, *Natural Philosophy* (2nd ed.), Art. 778''

Now it appears, on reference to the tables on pp. 606, 608, that when $\kappa < 304M^{\frac{2}{3}}R^{\frac{1}{3}}$, there is one and only one ellipsoidal form of equilibrium, viz one of revolution. The preceding considerations shew that this corresponds to a point of minimum altitude, and is therefore secularly stable (for symmetrical ellipsoidal disturbances).

When $\kappa > 304M^{\frac{2}{3}}R^{\frac{1}{3}}$, there are three points of stationary altitude, viz one in the plane of symmetry, corresponding to a Maclaurin's ellipsoid, and two others symmetrically situated on opposite sides of this plane, corresponding to Jacobian forms. It is evident from topographical considerations that the altitude must be a minimum at the two last-named points, and neither maximum nor minimum at the former. Any other arrangement would involve the existence of additional points of stationary altitude.

The result of the investigation is that Maclaurin's ellipsoid is secularly stable or unstable, for ellipsoidal disturbances, according as the eccentricity e is less or greater than 8127, the eccentricity of the ellipsoid of revolution which is the starting point of Jacobi's series, whilst the Jacobian ellipsoids are all stable for such disturbances*.

The further discussion of the stability of Maclaurin's ellipsoid would carry us too far. It was shewn by Poincaré that the equilibrium is secularly stable for deformations of *all* types so long as e falls below the above-mentioned limit. This is established by shewing that there is no form of bifurcation for any ellipsoid of revolution of smaller eccentricity. It follows, from the consideration of 'exchange of stabilities,' that Jacobi's series begin by being thoroughly stable.

354 Poincaré has further examined the coefficients of stability of the series of Maclaurin's and Jacobi's ellipsoids, by the method of Lamé's functions, with the view of ascertaining what members are forms of bifurcation. He finds that there are an infinite number of such forms, and consequently an infinite number of other linear series of equilibrium configurations. In each case it is possible to assign the form of the members of the new series in the neighbourhood of the bifurcation. The question has been further discussed by Darwin†, and by Poincaré himself in a subsequent paper‡.


The case which has attracted most interest is the first bifurcation which occurs in the series of Jacobi's ellipsoids. According to Darwin†, the critical ellipsoid is that for which $a/R = 1.8858$, $b/R = .8150$, $c/R = .6507$. After this point Jacobi's ellipsoids are unstable.

* This result was stated, without proof, by Thomson and Tait, *l.c.*


† "On the Pear-shaped Figure of Equilibrium of a Rotating Mass of Liquid," *Phil. Trans. A*, t. cxviii p. 301 (1901).

‡ "Sur la Stabilité des Figures Pyriformes affectés par une Masse Fluide en Rotation," *Phil. Trans. A*, t. cxviii p. 333 (1901).

In the annexed figure*, in which the ratios a/c and b/c are taken as coordinates, the straight line HAK represents the series of Maclaurn's ellipsoids corresponding to different values of κ , whilst the branches AR , AS represent those of the Jacobian figures. The point H corresponds to



the case of the sphere, when $\kappa = 0$, and the Maclaurn series is stable from H to A , and afterwards unstable. The points P , Q indicate the stage at which the Jacobian ellipsoids become unstable. At these points new series branch off; which are probably in the first instance stable†. The first



* The diagram is constructed from the tables on pp 606, 608. A sketch is given in Poincaré's treatise

† See Poincaré, *l.c.*; and Darwin, "The Stability of the Pear-shaped Figure of Equilibrium," *Phil Trans A*, t. cc p. 251 (1902).

members of these new series have the form shewn in the lower diagrams, which are taken from the paper by Darwin just referred to

The corresponding two-dimensional problem has been discussed by Jeans*, by a special method.

Small Oscillations.

355. The small oscillations of a rotating ellipsoidal mass have been discussed by various writers.

The simplest types of disturbance which we can consider are those in which the surface remains ellipsoidal, with the axis of revolution as a principal axis. In the case of Maclaurin's ellipsoid, there are two distinct types of this character; in one of these the surface remains an ellipsoid of revolution, whilst in the other the equatorial axes become unequal, one increasing and the other decreasing, whilst the polar axis is unchanged. It was shewn by Riemann† that the latter type is unstable when the eccentricity (*e*) of the meridian section exceeds .9529. In this investigation frictional forces are not contemplated, and the criterion is one of 'ordinary' stability. We have seen (Art. 353) that practically the equilibrium is unstable when *e* exceeds .8127. The periods of Riemann's two types of oscillation (when *e* < .9529) have been calculated by Love‡, who has also discussed the two-dimensional oscillations (of elliptic type) of a rotating elliptic cylinder§

The problem of small oscillations was treated in a more general manner by Poincaré¶. It appears from Art. 206 that the equations of small motion relative to rotating axes may be written

du/dt = 2ωv, ∂ψ/∂x, ∂v/∂t + 2ωu = -∂ψ/∂y, ∂w/∂t = -∂ψ/∂z,(1)

where ψ = P/ρ + Ω - 1/2 ω²(x² + y²), (2)

* "On the Equilibrium of Rotating Liquid Cylinders," *Phil. Trans. A*, t. cc p. 67 (1902).
† "Beitrag zu den Untersuchungen über die Bewegung eines flüssigen gleichartigen Ellipsoids," *Gött. Abh.*, t. ix. p. 3 (1860) [*Math. Werke*, p. 192]. See also Basset, *Hydrodynamics*, Art. 367. Riemann also shews that Jacobi's ellipsoids are stable (in the above restricted sense) for ellipsoidal disturbances.
‡ "On the Oscillations of a Rotating Liquid Spheroid, and the Genesis of the Moon," *Phil. Mag.* (5), t. xxvii. p. 251 (1889).
§ "On the Motion of a Liquid Elliptic Cylinder under its own Attraction," *Quart. Journ. Math.*, t. xxiii. p. 153 (1888).
¶ *I.c. ante* p. 612.

if Ω denote the gravitation potential of the liquid mass. From these, and from the equation of continuity

$$\frac{\partial u}{\partial x} + \frac{\partial v}{\partial y} + \frac{\partial w}{\partial z} = 0, \quad \dots \dots \dots (3)$$

we deduce
$$\frac{\partial^2}{\partial t^2} \nabla^2 \psi + 4\omega^2 \frac{\partial^2 \psi}{\partial z^2} = 0 \quad \dots \dots \dots (4)$$

If we assume that u, v, w vary as $e^{i\sigma t}$, we find

$$u = \frac{i\sigma \frac{\partial \psi}{\partial x} + 2\omega \frac{\partial \psi}{\partial y}}{\sigma^2 - 4\omega^2}, \quad v = \frac{-2\omega \frac{\partial \psi}{\partial x} + i\sigma \frac{\partial \psi}{\partial y}}{\sigma^2 - 4\omega^2}, \quad w = \frac{i}{\sigma} \frac{\partial \psi}{\partial z}, \quad \dots (5)$$

and therefore from (3), or immediately from (4),

$$\frac{\partial^2 \psi}{\partial x^2} + \frac{\partial^2 \psi}{\partial y^2} + \left(1 - \frac{4\omega^2}{\sigma^2}\right) \frac{\partial^2 \psi}{\partial z^2} = 0. \quad \dots \dots \dots (6)$$

If we write
$$1 - \frac{4\omega^2}{\sigma^2} = \tau^2, \quad z = \tau z', \quad \dots \dots \dots (7)$$

this takes the form
$$\frac{\partial^2 \psi}{\partial x^2} + \frac{\partial^2 \psi}{\partial y^2} + \frac{\partial^2 \psi}{\partial z'^2} = 0 \quad \dots \dots \dots (8)$$

If the equation of the undisturbed ellipsoid be

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} + \frac{z^2}{c^2} = 1, \quad \dots \dots \dots (9)$$

the appropriate solutions of (8) are those which involve the ellipsoidal harmonics corresponding to the surface

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} + \frac{z'^2}{c^2/\tau^2} = 1, \quad \dots \dots \dots (10)$$

which is obtained from (9) by homogeneous strain*.

At the surface (9) we must have $p = \text{const}$, and therefore

$$\psi = \Omega - \frac{1}{2} \omega^2 (x^2 + y^2) \quad \dots \dots \dots (11)$$

The potential Ω of the disturbed form depends on the normal displacement (ξ) at the surface, this is connected with ψ by a relation of the form

$$lu + mv + nw = \frac{\partial \xi}{\partial t} = i\sigma \xi, \quad \dots \dots \dots (12)$$

where the surface-values of u, v, w are to be taken from (5).

The procedure is then as follows. Assuming that ξ is an ellipsoidal surface-harmonic relative to (9), the surface-value of Ω is calculated, and substituted in (11). The resulting surface-value of ψ is then expressed in

* It appears that for some types of free oscillation τ is imaginary, and the surface (9) consequently a hyperboloid.

terms of harmonics relative to the auxiliary surface (10); the corresponding expression of ψ in the interior can then be written down in ellipsoidal solid harmonics. The condition (12) then gives an equation to determine σ , it appears that this equation is always algebraic.

In the case of Maclaurin's ellipsoid the process is somewhat simplified, the harmonics involved being of the types studied in Arts. 104, 107. This problem has been fully worked out by Bryan*, who has in particular completed Riemann's investigation by shewing that the equilibrium is 'ordinarily' stable for *all* types of disturbance so long as the eccentricity of the meridian is less than 9529.

Dirichlet's Ellipsoids

356 The motion of a liquid mass under its own gravitation, with a *varying* ellipsoidal surface, was first studied by Dirichlet†. Adopting the Lagrangian method of Art. 13, he proposes as the subject of investigation the whole class of motions in which the displacements are linear functions of the coordinates. This was carried further, on the same lines, by Dedekind‡ and Riemann§. More recently, it has been shewn by Greenhill|| and others that the problem can be treated with some advantage by the Eulerian method.

We will take first the case where the ellipsoid does not change the directions of its axes, and the internal motion is irrotational. This is interesting as an example of *finite* oscillation of a liquid mass about the spherical form.

The expression for the velocity-potential has been given in Art. 110; viz. we have

$$\phi = -\frac{1}{2} \left(\frac{\dot{a}}{a} x^2 + \frac{\dot{b}}{b} y^2 + \frac{\dot{c}}{c} z^2 \right), \quad \dots \dots \dots (1)$$

with the condition of constant volume

$$\frac{a}{a} + \frac{b}{b} + \frac{\dot{c}}{c} = 0 \quad \dots \dots \dots (2)$$

* "The Waves on a Rotating Liquid Spheroid of Finite Ellipticity," *Phil. Trans. A*, t. clxxx. p. 187 (1888).
† "Untersuchungen über ein Problem der Hydrodynamik," *Gott. Abh.*, t. viii p. 3 (1860); *Crelle*, t. lvi p. 181 [*Werke*, t. ii p. 263]. The paper was posthumous, and was edited and amplified by Dedekind.
‡ *Crelle*, t. lvi p. 217 (1861).
§ *loc. ante* p. 619.
|| "On the Rotation of a liquid Ellipsoid about its Mean Axis," *Proc. Camb. Phil. Soc.*, t. iii p. 233 (1879), "On the general Motion of a liquid Ellipsoid under the Gravitation of its own parts," *Proc. Camb. Phil. Soc.*, t. iv p. 4 (1880).

The pressure is then given by

$$\frac{p}{\rho} = \frac{\partial \phi}{\partial t} - \Omega - \frac{1}{2} Q^2 + F(t), \quad \dots \quad (3)$$

by Art. 20 (4), and substituting the value of Ω from Art 347 we find

$$\frac{p}{\rho} = -\frac{1}{2} \left(\frac{a}{a} x^2 + \frac{b}{b} y^2 + \frac{c}{c} z^2 \right) - \pi \rho (\alpha_0 x^2 + \beta_0 y^2 + \gamma_0 z^2) + F(t). \quad \dots \quad (4)$$

The conditions that the pressure may be uniform over the external surface

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} + \frac{z^2}{c^2} = 1, \quad \dots \quad (5)$$

are therefore

$$\left(\frac{a}{a} + 2\pi\rho\alpha_0 \right) a^2 = \left(\frac{b}{b} + 2\pi\rho\beta_0 \right) b^2 = \left(\frac{c}{c} + 2\pi\rho\gamma_0 \right) c^2. \quad \dots \quad (6)$$

These equations, with (2), determine the variations of a, b, c . If we multiply the three terms of (2) by the three equal magnitudes in (6), we obtain

$$\dot{a}a + \dot{b}b + \dot{c}c + 2\pi\rho(\alpha_0 a\dot{a} + \beta_0 b\dot{b} + \gamma_0 c\dot{c}) = 0 \quad \dots \quad (7)$$

If we substitute the values of $\alpha_0, \beta_0, \gamma_0$ from Art 347, this has the integral

$$a^2 + b^2 + c^2 - 4\pi\rho abc \int_0^\infty \frac{d\lambda}{\Delta} = \text{const.} \quad \dots \quad (8)$$

It has already been proved that the potential energy is

$$V = \text{const} - \frac{8}{15} \pi^2 \rho^2 a^2 b^2 c^2 \int_0^\infty \frac{d\lambda}{\Delta}, \quad \dots \quad (9)$$

and it easily follows from (1) that the kinetic energy is

$$T = \frac{2}{15} \pi \rho abc (a^2 + b^2 + c^2). \quad \dots \quad (10)$$

Hence (8) is recognized as the equation of energy

$$T + V = \text{const} \quad \dots \quad (11)$$

When the ellipsoid is of revolution ($a = b$), the equation (8), with $a^2 c = R^2$, is sufficient to determine the motion. We find

$$\frac{2}{15} \pi \rho R^3 \left(1 + \frac{R^2}{2c^2} \right) \dot{c}^2 + V = \text{const} \quad \dots \quad (12)$$

The character of the motion depends on the total energy. If this be less than the potential energy in the state of infinite diffusion, the ellipsoid will oscillate regularly between the prolate and oblate forms, with a period depending on the amplitude, whilst if the energy exceed this limit it will not oscillate, but will tend to one or other of two extreme forms, viz an

infinite line of matter coinciding with the axis of z , or an infinite film coincident with the plane xy *

If, in the case of an ellipsoid of revolution, we superpose on the irrotational motion given by (1) a uniform rotation ζ about the axis of z , the component velocities (relative to fixed axes) are

$$u = \frac{a}{a}x - \zeta y, \quad v = \frac{a}{a}y + \zeta x, \quad w = \frac{c}{c}z \quad (13)$$

The Eulerian equations (Art 6 (2)) then reduce to

$$\left. \begin{aligned} \frac{a}{a}x - \zeta y - 2\frac{a}{a}\zeta y - \zeta^2 x &= -\frac{1}{\rho} \frac{\partial p}{\partial x} - \frac{\partial \Omega}{\partial x}, \\ \frac{a}{a}y + \zeta x + 2\frac{a}{a}\zeta x - \zeta^2 y &= -\frac{1}{\rho} \frac{\partial p}{\partial y} - \frac{\partial \Omega}{\partial y}, \\ \frac{c}{c}z &= -\frac{1}{\rho} \frac{\partial p}{\partial z} - \frac{\partial \Omega}{\partial z} \end{aligned} \right\} \quad (14)$$

The first two equations give, by cross-differentiation,

$$\frac{\zeta}{\zeta} + 2\frac{a}{a} = 0, \quad . \quad . \quad . \quad . \quad . \quad (15)$$

or

$$\zeta a^2 = \zeta_0 a_0^2, \quad . \quad . \quad . \quad . \quad . \quad (16)$$

which is simply the expression of von Helmholtz' theorem that the 'strength' of a vortex is constant (Art. 146). In virtue of (15), the equations (14) have the integral

$$\frac{p}{\rho} = -\frac{1}{2} \left(\frac{a}{a} - \zeta^2 \right) (x^2 + y^2) - \frac{1}{2} \frac{c}{c} z^2 - \Omega + \text{const} \quad (17)$$

Introducing the value of Ω from Art 347 (4), we find that the pressure will be constant over the surface

$$\frac{x^2 + y^2}{a^2} + \frac{z^2}{c^2} = 1, \quad . \quad . \quad (18)$$

provided

$$\left(\frac{a}{a} + 2\pi\rho a_0 - \zeta^2 \right) a^2 = \left(\frac{c}{c} + 2\pi\rho\gamma_0 \right) c^2 \quad . \quad . \quad (19)$$

In virtue of the relation (15), and of the condition of constancy of volume

$$2\frac{a}{a} + \frac{c}{c} = 0, \quad . \quad (20)$$

this may be put in the form

$$2aa + c + 2(\zeta^2 aa + \zeta\zeta a^2) + 4\pi\rho a_0 aa + 2\pi\rho\gamma_0 cc = 0, \quad (21)$$

whence

$$2a^2 + c^2 + 2\zeta^2 a^2 - 4\pi\rho a^2 c \int_0^\infty \frac{d\lambda}{(a^2 + \lambda)(c^2 + \lambda)^{\frac{1}{2}}} = \text{const} \quad (22)$$

This, again, may be identified as the equation of energy

In terms of c as dependent variable, (22) may be written

$$4\pi^2 \rho R^3 \left\{ \left(1 + \frac{R^3}{2c^3} \right) c^2 + \frac{2\zeta_0^2 a_0^4}{R^3} c \right\} + V = \text{const} \quad (23)$$

* Dirichlet, *l c* When the amplitude of oscillation is small, the period must coincide with that obtained by putting $n=2$ in the formula (10) of Art 259. This has been verified by Hicks, *Proc Camb Phil Soc.*, t iv p 309 (1883)

If the initial circumstances be favourable, the surface will oscillate regularly between two extreme forms. Since, for a prolate ellipsoid, V increases with c , it is evident that, whatever the initial conditions, there is a limit to the elongation in the direction of the axis which the rotating ellipsoid can attain. On the other hand, we may have an indefinite spreading out in the equatorial plane*

357 For the further study of the motion of a fluid mass bounded by a varying ellipsoidal surface we must refer to the paper by RIEMANN already quoted, and to other memoirs cited below†. We may, however, briefly notice the case where the ellipsoidal boundary is invariable in form, but rotates about a principal axis (Oz)‡.

If u, v, w denote the velocities relative to axes x, y rotating in their own plane with constant angular velocity ω , the equations of motion are, by Art 206,

$$\left. \begin{aligned} \frac{Du}{Dt} - 2\omega v - \omega^2 x &= -\frac{1}{\rho} \frac{\partial p}{\partial x} - \frac{\partial \Omega}{\partial x}, \\ \frac{Dv}{Dt} + 2\omega u - \omega^2 y &= -\frac{1}{\rho} \frac{\partial p}{\partial y} - \frac{\partial \Omega}{\partial y}, \\ \frac{Dw}{Dt} &= -\frac{1}{\rho} \frac{\partial p}{\partial z} - \frac{\partial \Omega}{\partial z}. \end{aligned} \right\} \dots \dots \dots (1) \S$$

If the fluid have an angular velocity ζ about lines parallel to z , the actual velocities parallel to the instantaneous positions of the axes will be

$$\left. \begin{aligned} u - \omega y &= \frac{a^2 - b^2}{a^2 + b^2} (\omega - \zeta) y - \zeta y, \\ v + \omega x &= \frac{a^2 - b^2}{a^2 + b^2} (\omega - \zeta) x + \zeta x, \\ w &= 0, \end{aligned} \right\} \dots \dots \dots (2)$$

since the conditions are evidently satisfied by the superposition of the irrotational motion which would be produced by the revolution of a rigid ellipsoidal envelope with angular velocity $\omega - \zeta$ on the uniform rotation ζ (cf. Art 110). Hence

$$u = \frac{2a^2}{a^2 + b^2} (\omega - \zeta) y, \quad v = -\frac{2b^2}{a^2 + b^2} (\omega - \zeta) x, \quad w = 0 \quad \dots \quad (3)$$

* Dirichlet, *l. c.*

† Brioschi, "Développements relatifs au § 3 des Recherches de Dirichlet sur un problème d'Hydrodynamique," *Crelle*, t. lxx p. 63 (1861), Lipschitz, "Reduction der Bewegung eines flüssigen homogenen Ellipsoids auf das Variationsproblem eines einfachen Integrals," *Crelle*, t. lxxviii p. 245 (1874); Greenhill, *l. c. ante* p. 621, Basset, "On the Motion of a Liquid Ellipsoid under the Influence of its own Attraction," *Proc. Lond. Math. Soc.*, t. xvii p. 255 (1886) [*Hydrodynamics*, c. xv.]; Tedone, *Il moto di un ellissoide fluido secondo l'ipotesi di Dirichlet*, Pisa, 1894.

‡ Greenhill, "On the Rotation of a Liquid Ellipsoid about its Mean Axis," *Proc. Camb. Phil. Soc.*, t. iii p. 233 (1879).

§ A more general system of equations relative to moving axes was given by Greenhill, *Proc. Camb. Phil. Soc.*, t. iv p. 4 (1880).

Substituting in (1), and integrating, we find

$$\frac{\rho}{\rho} = \frac{2a^2b^2}{(a^2+b^2)^2} (\omega - \xi)^2 (x^2 + y^2) + \frac{1}{2} \omega^2 (x^2 + y^2) - \frac{2(b^2x^2 + a^2y^2)}{a^2 + b^2} \omega (\xi - \omega) - \Omega + \text{const} \dots (4)$$

Hence the conditions for a free surface are

$$\left\{ \frac{2a^2b^2}{(a^2+b^2)^2} (\omega - \xi)^2 + \frac{1}{2} \omega^2 - \frac{2b^2}{a^2+b^2} \xi (\omega - \xi) - \pi\rho\alpha_0 \right\} a^2 \\ \left\{ \frac{2a^2b^2}{(a^2+b^2)^2} (\omega - \xi)^2 + \frac{1}{2} \omega^2 - \frac{2a^2}{a^2+b^2} \xi (\omega - \xi) - \pi\rho\beta_0 \right\} b^2 \\ \pi\rho\gamma_0 a^2 \dots \dots \dots \dots \dots \dots \dots \dots \dots (5)$$

This includes a number of interesting cases.

1°. If we put $\omega = \xi$, we get the conditions of Jacobi's ellipsoid (Art. 349)

2°. If we put $\omega = 0$, so that the external boundary is stationary in space, we get

$$\left\{ \pi\rho\alpha_0 - \frac{2a^2b^2}{(a^2+b^2)^2} \xi^2 \right\} a^2 - \left\{ \pi\rho\beta_0 - \frac{2a^2b^2}{(a^2+b^2)^2} \xi^2 \right\} b^2 - \pi\rho\gamma_0 a^2 \dots \dots \dots (6)$$

These conditions are equivalent to

$$(\alpha_0 - \beta_0) a^2 b^2 + \gamma_0 a^2 (a^2 - b^2) = 0, \dots \dots \dots (7)$$

and

$$\frac{\xi^2}{2\pi\rho} \left\{ \frac{(a^2 + b^2)^2}{a^2 b^2} - \frac{a^2 \alpha_0 - b^2 \beta_0}{a^2 - b^2} \right\} \dots \dots \dots (8)$$

It is evident, on comparison with Art. 349, that c must be the least axis of the ellipsoid, and that the value (8) of $\omega^2/2\pi\rho$ is positive.

The paths of the particles are determined by

$$\dot{x} = \frac{2a^2}{a^2 + b^2} \xi y, \quad \dot{y} = \frac{2b^2}{a^2 + b^2} \xi x, \quad \dot{z} = 0, \dots \dots \dots (9)$$

whence

$$x = ka \cos(\sigma t + \epsilon), \quad y = kb \sin(\sigma t + \epsilon), \quad z = 0, \dots \dots \dots (10)$$

if

$$\sigma = \frac{2ab}{a^2 + b^2} \xi, \dots \dots \dots (11)$$

and k, ϵ are arbitrary constants.

These results are due to Dedekind*. It is remarked by Prof. Love that as regards the external form the series of Dedekind's and of Jacobi's ellipsoids are identical.

3°. Let $\xi = 0$, so that the motion is irrotational. The conditions (5) reduce to

$$\left\{ \alpha_0 - \frac{(a^2 - b^2)(a^2 + 3b^2)}{(a^2 + b^2)^2} \frac{\omega^2}{2\pi\rho} \right\} a^2 - \left\{ \beta_0 - \frac{(b^2 - a^2)(3a^2 + b^2)}{(a^2 + b^2)^2} \frac{\omega^2}{2\pi\rho} \right\} b^2 - \gamma_0 a^2 \dots \dots \dots (12)$$

These may be replaced by

$$\{ \alpha_0 (3a^2 + b^2) + \beta_0 (3b^2 + a^2) \} a^2 b^3 - \gamma_0 (a^4 + 6a^2 b^2 + b^4) a^2 = 0, \dots \dots \dots (13)$$

and

$$\frac{\omega^2}{2\pi\rho} \left\{ \frac{(a^2 + b^2)^2}{a^4 + 6a^2 b^2 + b^4} - \frac{\alpha_0 a^2 - \beta_0 b^2}{a^2 - b^2} \right\} \dots \dots \dots (14)$$

The equation (13) determines c in terms of a, b . Let us suppose that $a > b$. Then the left-hand side is easily seen to be positive for $c = a$, and negative for $c = b$. Hence

* *L.c. ante* p. 621. See also Love, "On Dedekind's Theorem,..." *Phil. Mag.* (5), t. xxv p. 40 (1888).

there is some real value of c , *between* a and b , for which the condition is satisfied; and the value of ω given by (14) is then real, for the same reason as in Art. 349.

4° In the case of an elliptic cylinder rotating about its axis (Art. 349), the condition (5) takes the form

$$\omega^2 + \frac{4a^2b^2}{(a^2+b^2)^2}(\omega - \zeta)^2 = \frac{4\pi\rho ab}{(a+b)^2}. \quad \dots\dots\dots (15)^*$$

If we put $\omega = \zeta$, we get the case of Art. 349 (8).

If $\omega = 0$, so that the external boundary is stationary, we have

$$\zeta^2 = \pi\rho \frac{(a^2+b^2)^2}{ab(a+b)^2} \quad \dots\dots\dots (16)$$

If $\zeta = 0$, i.e. the motion is irrotational, we have

$$\omega^2 = 4\pi\rho \frac{ab(a^2+b^2)^2}{(a+b)^2(a^4+6a^2b^2+b^4)} \quad \dots\dots\dots (17)$$

* Greenhill, *loc. ante* p. 621

LIST OF AUTHORS CITED.

The numbers refer to the pages

- | | |
|---|---|
| Abraham, M., 32 | Darwin, Sir G. H., 265, 316, 322, 323, 324, 342, 343, 581, 608, 611, 617, 618 |
| Airy, Sir G. B., 244, 252, 257, 261, 265, 323, 324, 327, 349, 524, 526, 569 | Dedekind, R., 621, 625 |
| Aitken, J., 570 | Delannay, C., 527 |
| d'Alembert, J. le R., 605 | De Morgan, A., 279, 382 |
| Allen, H. S., 554 | De Vries, G., 402 |
| Ampère, A. M., 202 | Dirichlet, P. L., 115, 297, 381, 382, 554, 621, 623, 624 |
| Barnes, H. T., 592 | Drude, P., 516 |
| Baquet, A. B., 126, 149, 174, 219, 225, 566, 584, 611, 616, 619, 624 | Dyson, F. W., 149, 232 |
| Beltrami, E., 79, 84, 141 | Earnshaw, S., 462 |
| Bernoulli, D., 19, 21, 342 | Edwardes, D., 556 |
| Bertrand, J., 176 | Ekman, V. W., 354, 392, 417 |
| Bessel, F. W., 128 | Encke, J. F., 560 |
| Bjerknes, C. A., 141, 182 | Euler, L., 2, 481 |
| Bolyeff, D., 95, 541 | Fawcett, Miss, 170, 174 |
| Boltzmann, L., 100, 191 | Ferrel, W., 327, 528 |
| Borchardt, C. W., 549, 550 | Ferrers, N. M., 102, 140 |
| Borda, J. C., 23 | Forsyth, A. R., 64, 65, 86, 233, 276, 387, 541 |
| Boussinesq, J., 398, 401, 516 | Fourier, J. B., 481 |
| Brionchi, F., 624 | Franklin, B., 354 |
| Bromwich, T. J. P. A., 338 | Frost, P., 37 |
| Bryan, G. H., 110, 173, 621 | Froude, R. E., 414, 415 |
| Burkhardt, H., 59 | Froude, W., 20, 23, 414, 415, 594 |
| Burnside, W., 356, 373 | |
| Byerly, W. E., 102 | |
| Carshaw, H. S., 233, 516 | Gauss, C. F., 37, 96, 105 |
| Cauchy, A., 15, 16, 29, 195, 364, 408, 409 | Gerstner, F. J. von, 395, 397 |
| Cayley, A., 222, 223, 226 | Glaisher, J. W. L., 107, 382, 480, 560 |
| Chree, C., 482 | Gouy, L. G., 361 |
| Christoffel, E. B., 77, 80, 498 | Graham, T., 24 |
| Chrystal, G., 261 | Gray and Mathews, 128, 271, 276 |
| Clebsch, A., 102, 148, 161, 233, 487, 497, 574 | Green, G., 43, 58, 115, 147, 257, 348, 349 |
| Clement, S. B., 592 | Greenhill, A. G., 76, 83, 164, 168, 216, 356, 358, 419, 545, 621, 624 |
| Coker, E. G., 592 | Grobh, W., 216, 228 |
| Colladon and Sturm, 455 | Guthrie, F., 182 |
| Coulomb, C. A., 561 | Gwyther, R. F., 402 |
| Craig, T., 161 | |
| Darey, H., 593 | Hadamard, J., 337, 466 |

- Hadley, G., 293
 Hagen, G. H. L., 592, 594
 Hamilton, Sir W. R., 176, 177
 Hankel, H., 32, 276, 279
 Hanlon, G. O., 23
 Hansen, P. A., 128
 Hayward, R. B., 153
 Heaviside, O., 201, 282
 Heine, E., 102, 132, 278, 479, 487, 505
 Helmholtz, H. von, 20, 52, 70, 85, 87, 99, 177, 185, 193, 199, 201, 205, 265, 335, 357, 392, 403, 405, 455, 474, 475, 586, 557, 558, 578
 Herman, R. A., 126
 Hicks, W. M., 83, 126, 141, 149, 182, 215, 233, 623
 Hilbert, D., 235
 Hill, M. J. M., 221, 231, 233
 Hobson, E. W., 130, 407
 Hough, S., 328, 329, 332, 333, 334, 563, 566
 Hugoniot, A., 24, 466

 Jacobi, C. G. J., 112, 142, 607
 Jeans, J. H., 619

 Kelland, P., 241, 424
 Kelvin, Lord, 7, 30, 32, 33, 36, 45, 99, 112, 153, 157, 170, 173, 174, 182, 187, 190, 191, 192, 193, 198, 201, 214, 218, 226, 232, 233, 301, 304, 316, 319, 327, 329, 334, 342, 358, 386, 389, 390, 391, 413, 415, 417, 428, 429, 436, 437, 439, 445, 528, 569, 593, 597
 Knechhoff, G., 37, 38, 52, 77, 85, 91, 93, 94, 99, 100, 101, 150, 157, 164, 169, 191, 196, 217, 219, 419, 420, 472, 473, 477, 485, 547, 554, 583, 584, 586, 587, 589, 591
 Klein, F., 338
 Knibbs, G. H., 594
 Koch, S., 537
 Korteweg, D. J., 338, 402, 455, 557
 Kowalewski, Mme Sophie, 611

 Lagrange, J. L., 2, 3, 8, 15, 61, 65, 176, 198, 230, 242
 Lamé, G., 142, 144
 Laplace, P. S., 104, 112, 291, 312, 314, 327, 328, 337, 339, 342, 456, 480, 520, 605, 610
 Larmor, J., 59, 162, 170, 185, 192, 229, 475, 477, 511
 Legendre, A. M., 107, 487
 Levi-Civita, T., 281
 Lewis, T. C., 229
 Lapounoff, A., 337
 Liouville, J., 471, 607
 Lipschitz, R., 130, 279, 624
 Lodge, A., 107, 304
 Lommel, E., 128, 366
 Lorentz, H. A., 600

 Love, A. E. H., 97, 182, 221, 228, 233, 338, 356, 477, 497, 498, 574, 619, 625

 McCowan, J., 241, 265, 401, 402
 Macdonald, H. M., 292, 426
 MacLaurin, C., 293, 605
 McMahon, J., 271
 Mallock, A., 594
 Margules, M., 520
 Marnner, W. W., 418
 Mathews, G. B., *see* Gray and Mathews
 Matthiessen, L., 610, 611
 Maxwell, J. C., 23, 32, 38, 103, 141, 155, 191, 201, 204, 223, 226, 433, 439, 514, 536, 537, 539, 561, 586, 589, 598
 Mehler, F. G., 128, 277
 Meissel, E., 128
 Merian, J. R., 418
 Meyn, C. O., 607
 Meyer, O. E., 581
 Mitchell, J. H., 97, 415
 Minchin, G. M., 223
 Morrow, J., 593
 Murphy, R., 107

 Nagaoka, H., 223, 225
 Nanson, E. J., 196, 197, 198
 Navier, C. L. M. II., 538
 Neumann, C., 63, 126, 127, 149, 187
 Newton, Sir I., 456, 546
 Nielsen, N., 128
 Niven, C., 497
 Niven, W. D., 140

 Oberbeck, A., 550, 555
 Ostrogradsky, M. A., 418

 Perry, J., 107
 Piotrowski, G. von, 545
 Planck, M., 86
 Pockels, F., 474
 Pocklington, H. C., 233
 Poincaré, H., 140, 298, 334, 611, 612, 616, 617, 618, 619
 Poiseuille, J. L. M., 544
 Poisson, S. D., 16, 126, 272, 279, 353, 364, 374, 408, 409, 418, 463, 471, 472, 485, 486, 518, 538
 Popoff, A., 378

 Rankine, W. J. M., 61, 77, 121, 395, 463, 466, 593
 Rayleigh, Lord, 37, 76, 91, 93, 94, 95, 109, 128, 129, 130, 285, 289, 246, 247, 258, 267, 271, 272, 273, 279, 287, 291, 292, 299, 304, 336, 351, 356, 358, 359, 361, 363, 366, 378, 392, 395, 398, 418, 420, 422, 433, 436, 438, 445, 446, 449, 451, 457, 460, 465, 468, 469,

- 472, 474, 481, 482, 485, 487, 488, 491, 493,
496, 503, 504, 506, 508, 516, 519, 521, 528,
548, 553, 554, 556, 557, 560, 569, 591, 593,
594, 597
- Réthy, M , 95
- Reusch, E , 228
- Reynolds, O , 20, 24, 229, 363, 519, 536, 570,
592, 597
- Riecke, E , 214
- Riemann, B , 52, 262, 460, 619, 621
- Routh, E J , 185, 186, 216, 235, 239, 290,
297, 521, 531
- Russell, J Scott, 360, 398, 445, 448, 569
- Saint-Venant, B de, 23, 539
- Sampson, R A , 118, 556
- Schlömilch, O , 382
- Schwarz, H A , 77, 86
- Schwerd, 481
- Sharpe, F R , 601
- Shaw, H J S Hele, 80, 542
- Simpson, T , 605
- Smith, B. A , 278
- Smoluchowski, M , 99
- Sommerfeld, A , 59, 338, 474, 516
- Stearn, H T , 119, 535
- Stokes, Sir G G , 15, 28, 32, 83, 115, 117,
118, 121, 124, 196, 198, 199, 202, 230, 231,
244, 270, 279, 356, 361, 392, 394, 395, 397,
401, 403, 422, 424, 457, 463, 464, 468, 480,
483, 484, 505, 537, 539, 541, 542, 546, 548,
552, 554, 558, 564, 569, 584, 586, 587, 594
- Sylvester, J J , 104
- Tait, P G , 228, 567
- Tarleton, R A , 215
- Tedone, O , 624
- Thomson, J , 23
- Thomson, J J., 77, 208, 210, 211, 232
- Thomson, Sir W , *see* Kelvin
- Thomson and Tait, 32, 44, 45, 82, 102, 104,
105, 112, 127, 150, 155, 159, 164, 174, 180,
185, 192, 225, 235, 292, 294, 298, 335, 340,
342, 365, 521, 550, 554, 605, 608, 616, 617,
618, 619
- Tisserand, F , 612
- Todhunter, I , 102, 330
- Tomlinson, H , 537
- Topler, A , 100
- Tornicelli, E , 22
- Turner, H H , 342
- Unwin, W C , 593
- Wangerin, A , 102, 111, 140
- Webb, R R , 451
- Weber, H , 14, 128, 130, 131, 278, 460, 466,
474, 503
- Whetham, W C. D , 545
- Whittaker, E T , 102, 112, 176, 185, 186, 235,
239, 279, 330
- Wien, W , 390, 392
- Yarrow, H , 418
- Young, T , 238, 252, 255
- Zoppritz, K , 563

INDEX.

The numbers refer to the pages

- Air-waves, plane, 454, 457, spherical, 466, general, 470, in two dimensions, 499
- due to a vibrating sphere or cylinder, 483, 485, 504
- of finite amplitude, 459
- effect of viscosity and heat-conduction on, 587, 589
- incidence of, on narrow obstacles, or on screens with narrow apertures, 486, 491, 493, 505
- Annulus, liquid, rotating, 610
- Apertures, irrotational flow of a liquid through rectilinear, circular, and elliptic, 69, 130, 137, 145
- transmission of sound-waves through small, 492, 507
- Atmospheric oscillations, 516
- Basin, tidal oscillations in a circular, 268, 275
- tides in a rotating, 304, 310
- Bessel's Functions, 126, 128, 268, 450, 503, of the 'second kind,' 276, 503
- Bifurcation, forms of, 613, 617
- Bolyeff's problem, 95
- Borda's mouthpiece, 23, 87
- Bubble, vibrations of a, 453, 581
- Canal, uniform, theory of 'long' waves in, 239, 244, 248, waves of finite amplitude, 261, effect of friction, 524
- of variable section, 257
- Canal-theory of the tides, 252, effect of friction, 524
- Capillarity, 433
- Capillary waves, 434
- Circular sheet of water, tidal oscillations in, 268, case of variable depth, 274, influence of rotation, 304, 310
- Circulation, defined, 30, constancy of, in moving circuit, 195
- Clebsch's transformation, 233
- Coaxial circles, flow in, 67
- Complex variable, 64
- Conduction of heat, effect on sound-waves, 589
- Confocal conics, flow in, 69
- Continuity, general equation of (Eulerian), 4, (Lagrangian), 13, in cylindrical coordinates, 118; in spherical polar coordinates, 104, in general orthogonal coordinates, 142, in ellipsoidal coordinates, 144
- Critical velocity in turbulent motion, 592, 601
- Curved stratum of liquid, irrotational flow, 100
- Curvilinear coordinates, 78, 141
- Cyclic motion in multiply-connected spaces, 48
- Cylinder (circular) moving in a frictionless liquid, without and with circulation round it, 72, 75; rotating in viscous liquid, 546
- (elliptic) moving in frictionless liquid, translation and rotation, 78, 84
- Cylindrical harmonics, 126, 128, expansions in terms of, 127
- Dead-water resistance, 354, 392
- Dedekind's ellipsoid, 625
- Determinateness, conditions of, 39, 198, 473
- Diffraction or scattering of sound-waves, 486, 491, 505, 509, 514
- Dirichlet's ellipsoids, 621
- Discontinuities at wave fronts, 498
- Discontinuous motions, 97; instability of, 353, obliterated in a viscous fluid, 560
- Disk (circular), moving in a frictionless liquid, 131, 137, steady motion of, in a viscous liquid, 556
- (elliptic) moving in a frictionless liquid, 147
- Dissipation a minimum in slow steady motion of viscous liquid, 556
- Dissipation-function, 528, 541

- Dissipation of energy by viscosity, 540, 556, 586
 Dissipative systems, general theory of, 521, 528
 Distortion of a fluid element, 29
 Divergence of a vector-field, 42

 Eddies, 592
 Edge-waves, 423
 Efflux, of liquids, 21, of gases, 23
 Elasticity of volume, 454
 Electromagnetic analogies, 191, 209
 Electromagnetic rotation, 27
 Ellipsoid, Maclaurin's, 604, Jacobi's, 607, Dirichlet's, 621, Dedekind's, 625
 Ellipsoid moving in a frictionless liquid, 134, 135, 137, 139, 140, 146, 148, in a viscous liquid, 554
 Ellipsoidal harmonics, 132, 136, 140
 Ellipsoidal mass of liquid rotating under its own gravitation, 604
 Ellipsoidal shell, irrotational motion of liquid in a rotating, 140
 Elliptic coordinates, 78
 Elliptic cylinder in frictionless liquid, circulation round, 69
 motion due to an, 78, 84
 Energy, equation of, 8, 19, dissipation of, 540, 556, 586
 Energy, of rotationally moving liquid, 44, 54; of long waves, 246, of vortex-systems of surface waves, 351, of air-waves, 458, 468, 472
 dissipation of, *see* Dissipation
 Equation of continuity, *see* Continuity
 Equations of motion, of frictionless fluid, 3, 12, of viscous fluid, 538
 of solids in a frictionless liquid, 157, 176, 185, 187
 Equilibrium (relative) of a rotating mass of liquid, 602
 Exchange of stabilities, 614
 Expansion, defined, 5
 and rotation, velocities expressed in terms of, 199
 Expansion, waves of, *see* Air-waves

 Finite amplitude, waves of, on water, 261, 392, 395, 398, 402, in air, 459
 Finite oscillations of a liquid mass about the spherical form, 621
 Fish-line problem, 445
 Flapping of sails and flags, 359
 Flow, defined, 30
 Flux, defined, 36
 Forced oscillations, 237, of a rotating system, 299
 Fourier's theorem, 364

 Free oscillations, 236, of a rotating system, 298
 Friction, effect of, on tides, 524

 Generalized coordinates, 174
 Gerstner's waves, 395
 Globe, oscillations of a liquid, 428
 Globule, vibrations of a, 451, with friction, 581
 Grating, reflection and transmission of sound-waves by a, 509, 514
 Green's theorem, 41, Kelvin's extension to cyclic regions, 52, Helmholtz' extension to sound vibrations, 474
 Group-velocity (of waves), 360, 363, 435, 438
 Gyrostatic systems, equations of motion of, 186, small oscillations of, 294; with friction, 508

 Hamiltonian principle, 177
 Harmonic analysis of tidal observations, 342
 Harmonics, spherical, 102, cylindrical, 126, ellipsoidal, 132, 136
 Helicoidal solid moving in frictionless liquid, 163, 169
 Highest waves on water, 394
 Hydrokinetic symmetry, 161

 Ignorance of coordinates, 185
 Image, of a double source, in a sphere, 120, of a vortex-ring, 229
 Impulse, of a solid moving in a frictionless liquid, 152, 155
 of a vortex-system, 208
 Impulsive motion, 11, 16, 113
 Inertia-coefficients, of a cylinder, 72; of a sphere, 115, of an ellipsoid, 147, general, 154, in cases of symmetry, 161
 Instability, of surfaces of discontinuity, 358, of linear flow of a liquid in a pipe, 592
 Irreducible circuits, 47
 Irrotational motion, general theory of, 28, 32, in cyclic spaces, 48, in two dimensions, 62
 of a liquid mass with a free ellipsoidal boundary, 625

 Jacobi's ellipsoid, 607
 Jets, theory of, in two dimensions, 85
 capillary phenomena of, 448, 449

 Kelvin's theorem of minimum energy, 45, 54
 Kinematic coefficient of viscosity, 536
 Kinetic energy, of an irrotationally moving liquid, 44, 54, 63, 118, of a solid moving through a liquid, 155, 172, 183, of a vortex-system, 208, 210, 217, 225

- Kinetic stability, 298, 337
 Kineto-statics, 188, 190
 Kirchhoff's integral of the general equation of sound, 477

 Lagrangian equations in generalized coordinates, 176, 182
 Lagrangian equations of fluid motion, 12
 Lamina, impact of a frictionless stream on a, 91, 93, 95
 Laminar motion, 29, in viscous liquids, 558, 560, 561
 Laplace's tidal problem, 312
 Limiting form of relative equilibrium of a rotating liquid, 613
 Limiting velocity, 21
 Lines of motion, *see* Stream-lines

 Maclaurin's ellipsoid, 604
 Minimum energy, Kelvin's theorem of, 45, 54
 Minimum velocity of water-waves, 437
 Modulus of decay, 522, of water-waves, 564, 566; of air-waves, 589
 Moving axes, motion of a solid referred to, 157, 170
 Multiply-connected regions, 47

 Newtonian velocity of sound, 456
 Normal modes of oscillation, 237, of water in rectangular and circular tanks, 418, in a channel of uniform section, 419, 421, 422, 424, of air in a spherical or cylindrical envelope, 480, 503

 Obstacles, scattering of sound-waves by, 486, 491, 507
 Oil, effect of a thin film of, on water-waves, 570
 Orbits of particles in water-waves, 346, 349, 396
 Ordinary stability, 298, 337
 Orthogonal coordinates, 141
 Orthomorphic projection, 65, 100
 Oscillating plane in viscous fluid, 560
 Oscillations, *see* Small oscillations, *and* Waves

 Pear-shaped figure of equilibrium of a rotating liquid mass, 618
 Pendulum, oscillating in air, 485, 497, impact of air-waves on, 486, in viscous liquid, 583
 Periodic motions in a viscous fluid, 558
 Periphractic regions, 38
 Permanent type, waves of, on water, 398, 402, in air, 460, 463
 Physical equations, 6, 433, 589
 Pipe, flow of viscous liquid in, 543, 545; turbulent motion in, 592

 Poiseuille's experiments, 544
 Pressure-equation in irrotational motion, 18; in steady irrotational motion, 19
 Pressures on solid moving through a frictionless liquid, 158
 Prismatic vessel, irrotational motion of a liquid in a rotating, 81
 Progressive waves, tidal, 242, on deep water, 347, in air, 455

 Reflection of water waves, 247
 and transmission of air-waves by a grating, 509, 514
 Relative equilibrium, general conditions of, 615, linear series of configurations of, 615
 Resistance, hydrodynamic, in a frictionless liquid, 93, 94, in a viscous fluid, 553 due to the generation of waves, 391, 418
 Retardation and acceleration of tides by inertia, 334, by friction, 524
 Revolution, solid of, moving in frictionless liquid, 164, 167, 168
 Ring moving in frictionless liquid, 173
 Ripples and waves, 437
 Rotating liquid, 24, 25
 Rotating dynamical system, small oscillations of a, 293
 Rotating sheet of water, tides on, 301
 Rotation of a fluid element, 29
 Rotation of a liquid mass under its own attraction, 602
 Rotational motion, 193

 Scattering of air-waves by spherical and other obstacles, 486, 491, 505, 506
 Schwarz' method of conformal representation, 86
 Secular stability, 297, 615
 Ship-waves, 412, 416
 Simple source of sound, 474
 Simply-connected regions, 35
 Skin-resistance, 594
 Slipping, resistance to, at the surface of a solid, 537, 544
 Small oscillations, 235; of a gyrostatic system, 298, of a dissipative system, 529 of a rotating ellipsoidal mass of liquid, 619
 Smoke-rings, 228
 Solids, moving in frictionless liquid, 150, with cycloids, 170
 Solitary wave, Scott Russell's, 398
 Sound, velocity of, 456
 Sound-waves, *see* Air-waves
 Sources and sinks, in irrotational motion, 55, 119
 Sources of sound, simple, and double, 474
 Speed of an oscillation, defined, 237

- Sphere moving in frictionless liquid, 114, 130,
 inertia coefficient of, 115
 in viscous fluid, steady motion, 552, oscil-
 latory motion, 582
- Spheres, motion of two, in frictionless liquid,
 122, 124, 181
- Spherical globe of liquid, free and forced os-
 cillations, 428, 431, influence of vis-
 cosity, 579
- Spherical sheet of water, tidal oscillations of,
 286, 290
- Spherical harmonics, 102, zonal, 105, tesseral
 and sectorial, 110, conjugate property
 of, 110, expansions in terms of, 111,
 486
 application of to sound-waves, 478, 496, to
 steady and periodic motions of a viscous
 fluid, 548, 571
- Spherical vortex, Hill's, 231
- Stability, theory of ordinary and secular, 297,
 337
 of a solid moving in frictionless liquid, 159,
 167, 168, of a cylindrical vortex, 218,
 of a jet, 450, 451
 of the ocean, 386
 of a rotating mass of liquid, 615, of a
 rotating annulus, 611; of Maclaurin's
 and Jacob's ellipsoids, 616, 617
- Standing waves on deep water, 346; *see also*
 Normal modes
- Steady motion of a frictionless liquid, 18, with
 a free surface, 85, general conditions
 for, 229
 of a viscous fluid, 542, 546, 548
 of a solid in a frictionless liquid, possible
 types of, 158, 159, 168; stability of,
 159, 167, 168
 of a solid of revolution, 168
- Stokes' theorem, 117
- Stream-function, Lagrange's, 60, Stokes', 117,
 119
- Stream-lines, 17, in two dimensions, 61
 of a circular cylinder, 73, 74, 75, of an
 elliptic cylinder, translation and rota-
 tion, 79, of a sphere, 121, of a circular
 disk, 138, of a vortex-pair, 214, of a
 vortex-ring, 224, of a spherical vortex,
 232, of standing waves on deep water,
 347, of a sphere in viscous liquid,
 553
- Stresses in a viscous fluid, 532
- Surface-conditions, 7, 433
- Surface-distributions of sources, 56, 58, 575
- Surface-disturbance of a stream, 378, 379, 386,
 440
- Surface-energy and surface-tension, 433
- Surfaces of discontinuity, *see* Discontinuous
 motions
- Surface-waves, 344
 due to a localized disturbance, 364, 371,
 due to a local periodic pressure, 374, 410,
 due to a progressive disturbance, 378,
 379, 386, 412, 442, 445
 of finite height, 392, 395, 398, 402
- Symmetry, hydrokinetic, 161
- Tangential stress, 533
- Tension, surface-, *see* Capillarity and Surface
 tension
- Terminal velocity of sphere falling in viscous
 fluid, 554
- Tidal waves, defined, 235
 in uniform canal, 239, 244, 248, in canal
 of variable section, 257, on open sheets
 of water, 265, 267, on a spherical ocean,
 286, 290
 on a rotating sheet of water, 301
 of finite height, 261
- Tide-generating forces, 339
- Tides, diurnal, 323, 332, semi-diurnal, 324,
 332, long-period, 315, 319, 329, spring-
 and neap-, 335, of second order, 265
 equilibrium theory of, 340
 on a rotating globe, 312, Laplace's theory,
 314, Hough's theory, 329
 effect of friction on, 524
- Torsional oscillations of a sphere in viscous
 fluid, 582
- Trochoidal waves, 393, 397
- Tube, flow of viscous fluid in a, 543, 545,
 critical velocity, 592
- Turbulent motion, 591, critical velocity in a
 pipe, 592, theory of Reynolds, 597
- Vectors, polar and axial, 32
- Velocity-potential, defined, 15, kinematical
 property of, 17, persistence of, in
 frictionless fluids, 15, 33, mean value
 of, over a spherical surface, 37, 474; in
 simply and multiply connected spaces,
 35, 49
 of an isolated vortex, 202
- Vena contracta, 22, 89, 91
- Viscosity, 532, stresses due to, 533, coefficient
 of, 535
 of gases, 586, effect on sound-waves, 587
- Viscous fluid, equations of motion of, 538
 steady motion of, 551, periodic motion of,
 553, 571, 584
 flow between parallel plates, 542, through
 a narrow tube, 543, 545
 steady motions of a sphere and of an el-
 lipsoid in, 551, 554
 pendulum oscillating in, 533
- Vortex-lines and filaments, 193, vortex-sheet, 204
- Vortex-pair, 213

- Vortex-rings, 221; mutual influence of, 228
 Vortices, motion due to isolated, 201, 202
 persistence of, in frictionless liquid, 195
 rectilinear, 211; cylindrical, 218, 219, 231,
 circular, 221; spherical, 231

 Water-waves, effect of viscosity on, 563, 564;
 effect of oil on, 570
 see also Capillary waves, Surface-waves,
 Tidal waves

 Wave-patterns, due to a progressive disturb-
 ance, 412, 416
 Wave-propagation in one, two, and three di-
 mensions, 241, 276, 279, 347, 406, 409,
 455, 471, 500
 Wave-resistance, 391, 418
 Waves, *see* Air-waves and Water-waves
 Weber's transformation, 13
 Wind, action of, in generating water-waves,
 568